

FACILITY SCHEDULE NO. 44

1. **Name:** **Laguna**
2. **Location:** The Laguna Substation is located in Corpus Christi, Texas in Nueces County. There are two Points of Interconnection at the Laguna Substation. One is at the termination of the 69 kV transmission line from the Naval Base Substation and the other is at the termination of the 69 kV transmission line from the Airline Substation. Both Points of Interconnection are at the point where the jumper conductors from the substation equipment physically contact the connectors on the 69 kV transmission line conductors.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

 AEP owns the following facilities:
 - Laguna Substation, including all the substation facilities within it
 - jumper conductors from the station facilities to the Point(s) of Interconnection
 - substation deadend structures that terminate all transmission lines into the station
 - a four-wire RTU communication circuit from the station to the AEP control center
 - any under-built distribution voltage circuits attached to the transmission lines that terminate into the station
 LCRA owns the following facilities:
 - insulators and hardware on the deadend structures that terminate the 69 kV transmission lines from the Naval Base and Airline stations
 - the following transmission line(s) comprised of easements, structures, conductors, insulators, and connecting hardware:
 - Laguna to Airline 69 kV transmission line
 - Laguna to Naval Base 69 kV transmission line
7. **Facility Operation Responsibilities of the Parties:**
 - AEP controls and operates the Laguna Substation, including all facilities within it.
 - AEP controls and operates all transmission lines that terminate into the station.


- AEP coordinates, directs, and performs all control center and field operation activities on the transmission line(s) owned by AEP and LCRA. These activities shall include, but are not limited to, switching, clearances, and outages for planned maintenance and operations, emergency service restoration, and overall coordination of such activities with ERCOT.
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions:

- AEP will poll the AEP RTU installed inside the substation and LCRA will have access to the RTU data via a direct Inter-control Center Communications Protocol (ICCP) communication circuit between the Parties' control centers. The Parties will coordinate the analog and digital point list and communications protocol issues.



FACILITY SCHEDULE NO. 45

1. **Name:** **Kenedy Switching Station**
2. **Location:** The Kenedy Switching Station is located at 3508 FM 719 in Kenedy, Texas, in Karnes County. There are two Points of Interconnection at the Kenedy Switching Station. One is at the termination of the 69 kV transmission line from the Runge Substation and the other is at the termination of the 69 kV transmission line from the AEP Nixon Substation. Both Points of Interconnection are at the point where the jumper conductors from the substation equipment physically contact the connectors on the 69 kV transmission line conductors.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- insulators and hardware on the deadend structures that terminate the 69 kV transmission lines from the Runge and AEP Nixon substations
- the following transmission lines comprised of structures easements, conductors, insulators, and connecting hardware:
 - Kenedy Switching Station to Runge 69 kV transmission line
 - Kenedy Switching Station to AEP Nixon 69 kV transmission line

AEP owns the following facilities:

- the Kenedy Switching Station including all the facilities within it
- the jumpers from the 69 kV buses to the 69 kV transmission lines to the Runge and AEP Nixon substations
- the following transmission line(s) comprised of structures, easements, conductors, insulators, connecting hardware:
 - Kenedy Switching Station to Pleasanton 138 kV transmission line
 - Kenedy Switching Station to Coletto Creek 138 kV transmission line
 - Kenedy Switching Station to Falls City (CPSB) 138 kV transmission line
 - Kenedy Switching Station to Kenedy 69 kV transmission line
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station


7. Facility Operation and Maintenance Responsibilities of the Parties:

- AEP controls and operates the Kenedy Switching Station, including all facilities within it.
- AEP will control and operate the following facilities until LCRA takes over operational control:
 - 69 kV transmission line to AEP Nixon, via Magnolia Tap
 - 69 kV transmission line to Runge
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None



FACILITY SCHEDULE NO. 46

1. **Name:** **Runge**
2. **Location:** The Runge Substation is located off of Highway 81, 1.2 miles south of Highway 72 in Runge, Texas, in Karnes County. The Point of Interconnection at the Runge station is located at the top connectors on the jumpers that connect the 69 kV high bus to the 69 kV low bus.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- transmission line dead-end insulator strings and termination hardware
- the following facilities inside the Runge Substation:
 - 69 kV transmission line switches 823 and 827
 - 69 kV high-bus, including conductors, insulators and termination hardware
 - jumpers from switches 823 and 827 to the lines and to the 69 kV high-bus
- the following transmission lines comprised of structures easements, conductors, insulators, and connecting hardware:
 - Runge to Kenedy Switching Station 69 kV transmission line
 - Runge to Nordheim 69 kV transmission line

AEP owns the following facilities:

- the Runge Substation including all the facilities within it, except for those facilities owned by LCRA
- the 69 kV low bus and jumpers to high bus inside the Runge Substation
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station


7. **Facility Operation and Maintenance Responsibilities of the Parties:**
 - AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV switch 823 and associated 69 kV transmission line to Kenedy

- Switching Station
 - 69 kV switch 827 and associated 69 kV transmission line to Nordheim
- AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 664 and 825
 - all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8 Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None



FACILITY SCHEDULE NO. 47

1. **Name:** **Nordheim 69**
2. **Location:** The Nordheim Substation is located off of FM 239 2 miles south of Highway 72 in Nordheim, Texas in DeWitt County. There is one Point of Interconnection at the Nordheim Substation. The Points of Interconnection are located at the top connectors on the jumpers that connect the 69 kV high bus to the 69 kV low bus.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- transmission lines, dead-end insulator strings and termination hardware
- the following facilities inside the Nordheim Substation:
 - 69 kV transmission line switches 5207 and 707
 - high-bus 69 kV sectionalizing switch 2584
 - 69 kV high-buses, including conductors, insulators and termination hardware
 - jumpers from switches 5207 and 707 to the lines and to the high-buses
 - jumpers from sectionalizing switch 2584 to the high-buses
- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - Nordheim to Runge 69 kV transmission line
 - Nordheim to Yorktown 69 kV transmission line

AEP owns the following facilities:

- the Nordheim Substation including all the facilities within it, except for those facilities owned by LCRA
- the 69 kV low bus and jumpers to high bus inside the Nordheim Substation
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station


7. **Facility Operation and Maintenance Responsibilities of the Parties:**

- AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV switch 5207 and associated 69 kV transmission line to Runge
 - 69 kV switch 2584
 - 69 kV switch 707 and associated 69 kV transmission line to Yorktown
- AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 227
 - all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None



FACILITY SCHEDULE NO. 48

1. **Name:** **Yorktown 69**
2. **Location:** The Yorktown Substation is located at 43 FM 240, Yorktown, TX, in DeWitt County. There are two Points of Interconnection at the Yorktown Substation. The Points of interconnection are located at the top connectors on the jumpers that connect the 69 kV high buses to the 69 kV low buses.
- 3 **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- transmission lines, dead-end insulator strings and termination hardware
- the following facilities inside the Yorktown Substation:
 - 69 kV transmission line switches 2524 and 2523 with interrupter and motor operator for 2523
 - high-buses 69 kV sectionalizing switch 9157
 - 69 kV high-buses, including conductors, insulators and termination hardware
 - jumpers from switches 2524 and 2523 to the lines and to the high-buses
 - jumpers from sectionalizing switch 9157 to the high-buses
- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - Yorktown to Nordheim 69 kV transmission line
 - Yorktown to Cuero (Hydro) 69 kV transmission line

AEP owns the following facilities:

- the Yorktown Substation including all the facilities within it, except for those facilities owned by LCRA
- the 69 kV low buses and jumpers to high buses inside the Yorktown Substation
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station

7. **Facility Operation and Maintenance Responsibilities of the Parties:**

- AEP will control and operate the following equipment until LCRA takes over

Attachments – Page 57


operational control:

- 69 kV switch 2523 and associated 69 kV transmission line to Nordheim
- 69 kV switch 9157
- 69 kV switch 2524 and associated 69 kV transmission line to Cuero (Hydro)
- AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 658, 2527, and 9267
 - all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None



FACILITY SCHEDULE NO. 49

1. Name: **Hochheim**
2. Location: The Hochheim Substation is located on Highway 183, 11.4 miles north of Hospital Drive, Cuero, Texas, in DeWitt County. The Point of Interconnection is located where the AEP jumper conductors from the substation equipment physically contact the connectors on the 69 kV tap transmission line conductors.
3. Delivery Voltage: 69 kV
4. Normal Operation of Interconnection: Closed
5. One-Line Diagram Attached: Yes
6. Facility Ownership Responsibilities of the Parties:

LCRA owns the following facilities:

- transmission line dead-end insulator strings and termination hardware
- the following transmission lines comprised of structures, easements, switches, conductors, insulators, and connecting hardware:
 - Cuero (Hydro) to Luling City 69 kV transmission line
 - two 69 kV line switches 1393 and 1813 and any associated attachments
- transmission tap line from the tap in the Cuero (Hydro) – Luling City 69 kV transmission line to the Hochheim Substation

AEP owns the following facilities:

- the Hochheim Substation including all the facilities within it
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station

7. Facility Operation and Maintenance Responsibilities of the Parties:
 - AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV switch 1813 and associated 69 kV transmission line to Cuero (Hydro)
 - 69 kV switch 1393 and associated 69 kV transmission line to Luling City
 - 69 kV tap line from Hochheim Tap to the Hochheim Substation
 - AEP controls and operates all other equipment in the station including the following:


Attachments – Page 60

- 69 kV switch 2265
- all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None



FACILITY SCHEDULE NO. 50

1. **Name:** **Malone**
2. **Location:** The Malone Substation is located at 16 Darst Field Road, Luling, Texas in Guadalupe County. The Point of Interconnection is located at the top connectors on the jumpers that connect the 69 kV high bus to the 69 kV low bus.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- transmission line dead-end insulator strings and termination hardware
- the following facilities inside the Malone Substation:
 - 69 kV transmission line switches 2236 and 2234
 - 69 kV high-bus, including conductors, insulators and termination hardware
 - jumpers from switches 2236 and 2234 to the lines and to the high-bus
- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - Malone to Luling City 69 kV transmission line
 - Malone to Darst 69 kV transmission line

AEP owns the following facilities:

- the Malone Substation including all the facilities within it, , except for those facilities owned by LCRA
- the 69 kV low bus and jumpers to high bus inside the Malone Substation
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station

7. **Facility Operation and Maintenance Responsibilities of the Parties:**
 - AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV switch 2236 and associated 69 kV transmission line to Luling City
 - 69 kV switch 2234 and associated 69 kV transmission line to Darst

- AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 2237
 - all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None

FACILITY SCHEDULE NO. 51

1. **Name:** **Darst**
2. **Location:** The Darst Substation is located at 1001 Red Rock Road, Kingsbury, Texas in Guadalupe County. There are two Points of Interconnection at the Darst Substation. The Points of Interconnection are located at the top connectors on the jumpers that connect the 69 kV high buses to the 69 kV low buses.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- transmission line dead-end insulator strings and termination hardware
- the following facilities inside the Darst Substation:
 - 69 kV transmission line switches 496 and 655
 - high-buses 69 kV sectionalizing switch 495
 - 69 kV high-buses, including conductors, insulators and termination hardware
 - jumpers from switches 496 and 655 to the lines and to the high-buses
 - jumpers from sectionalizing switch 495 to the high-buses
- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - Darst to Malone 69 kV transmission line
 - Darst to LCRA Nixon 69 kV transmission line

AEP owns the following facilities:

- the Darst Substation including all the facilities within it, except for those facilities owned by LCRA
- the 69 kV low buses and jumpers to high buses inside the Darst Substation
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station

7. **Facility Operation and Maintenance Responsibilities of the Parties:**

- AEP will control and operate the following equipment until LCRA takes over

operational control:


- 69 kV switch 496 and associated 69 kV transmission line to Malone
- 69 kV switch 495
- 69 kV switch 655 and associated 69 kV transmission line to LCRA Nixon
- AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 418, 464 and 2686
 - all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions:

- LCRA will provide AEP with MV-90 master file information and dial-up access to net meter at LCRA Nixon for AEP net metering purposes.



FACILITY SCHEDULE NO. 52

1. **Name:** **AEP Nixon**
2. **Location:** The AEP Nixon Substation is located at 1739 County Road 173 (10th Street) Nixon, Texas in Gonzales County. There are two Points of Interconnection at the AEP Nixon Substation. The Points of Interconnection are located at the top connectors on the jumpers that connect the 69 kV high buses to the 69 kV low buses.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- transmission lines dead-end insulator strings and termination hardware
- the following facilities inside the AEP Nixon Substation:
 - 69 kV high-buses, including bus relaying, conductors, insulators and termination hardware
 - high-buses 69 kV sectionalizing switch 2626
 - 69 kV circuit breaker 9310, breaker foundation and associated 69 kV switches 9309, 9311, 9312
 - panel 9310 line relaying, local controls and carrier equipment including wave trap, coupling capacitor, carrier equipment stand and foundation, and associated equipment
 - 69 kV circuit breaker 815, breaker foundation and associated 69 kV switches 814, 816
 - panel 815 line relaying and local controls
 - jumpers from switches to the lines, circuit breakers and to the high-buses
 - 3 – 69 kV bus potential transformers, PT stands and foundations, fused disconnect switches and jumpers
 - 1 – 69 kV line potential transformer, PT stand and foundation
 - associated jumpers, junction boxes, manifolds, conduits, cables, and ground straps
- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - AEP Nixon to Kenedy Switching Station 69 kV transmission line

- AEP Nixon to LCRA Nixon 69 kV transmission line

AEP owns the following facilities:

- the AEP Nixon Substation including all the facilities within it, except for those facilities owned by LCRA
- the 69 kV low buses and jumpers to high buses inside the AEP Nixon Substation
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station

7. Facility Operation and Maintenance Responsibilities of the Parties:


- AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV breaker 815, associated switches 814, 816 and associated 69 kV transmission line to Kenedy SS via Magnolia Tap
 - 69 kV switch 2626
 - 69 kV breaker 9310, associated switches 9309, 9311, 9312 and associated 69 kV transmission line to LCRA Nixon
- AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 2617, 2625 and 2773
 - all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions:

- LCRA will provide AEP with MV-90 master file information and dial-up access to net meter at LCRA Nixon for AEP net metering purposes..



Attachments – Page 71

Interconnection Agreement Amendment
Doc #378393

FACILITY SCHEDULE NO. 53

1. **Name:** **Magnolia**
2. **Location:** The Magnolia Substation is located 0.5 miles from FM 2724, 4.6 miles north of the junction of FM 2724 and FM 81, in Karnes County, Texas. The Point of Interconnection is located where the AEP jumper conductors from the station equipment physically contact the connectors on the 69 kV tap transmission line conductors.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- transmission line dead-end insulator strings and termination hardware
- the following transmission lines comprised of structures, easements, switches, conductors, insulators, and connecting hardware:
 - Kenedy Switching Station to AEP Nixon 69 kV transmission line
 - transmission tap line from the tap in the AEP Nixon-Kenedy Switching Station 69 kV transmission line to the Magnolia station
 - two 69 kV line switches 2593 and 2594, and 69 kV line tap switch 2595 and any associated attachments

AEP owns the following facilities:

- the Magnolia Substation including all the facilities within it
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station

7. **Facility Operation and Maintenance Responsibilities of the Parties:**

- AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV switch 2593 and associated 69 kV transmission line to Kenedy SS,
 - 69 kV switch 2594 and associated 69 kV transmission line to AEP Nixon,
 - 69 kV switch 2595, and associated 69 kV transmission line to Magnolia
- AEP controls and operates all other equipment in the station including the


following:

- 69 kV switch 2477
- all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None



FACILITY SCHEDULE NO. 54

1. **Name:** **Columbus**
2. **Location:** The Columbus Substation is located at Harbert and Live Oak Streets in Columbus, Texas, in Colorado County. There are two Points of Interconnection at the Columbus Substation. The Points of Interconnection are located where the jumpers from the 69 kV transformer switches connect to the 69 kV bus conductors.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- transmission line dead-end insulator strings and termination hardware
- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - Columbus to Glidden 69 kV transmission line
 - Columbus to Stafford Hill 69 kV transmission line
- the following facilities within the Columbus Substation:
 - 69 kV transmission line switches 695 and 183 with local controls, associated interrupters and motor operator for switch 183
 - 69 kV bus sectionalizing switch 1803
 - 69 kV buses, both 69 kV high buses and 69 kV low-buses, including conductors, jumpers between buses, insulators and termination hardware
 - jumpers from transmission line switches to the lines and to the 69 kV high-buses
 - jumpers from sectionalizing switch to the 69 kV high-buses

AEP owns the following facilities:

- the Columbus Substation and all other facilities within it, except for those facilities owned by LCRA
- the 69 kV transformer switches and jumpers that connect to the 69 kV bus conductors inside the Columbus Substation
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station

7. Facility Operation and Maintenance Responsibilities of the Parties:


- AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV switch 695 and associated 69 kV transmission line to Glidden
 - 69 kV switch 1803
 - 69 kV switch 183, and associated 69 kV transmission line to Stafford Hill
- AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 153, 474, and 2667
 - all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions:

- LCRA will provide AEP with MV-90 master file information and dial-up access to net meter at Glidden for the 69 kV line to Columbus.



FACILITY SCHEDULE NO. 55

1. **Name:** **Stafford Hill**
2. **Location:** The Stafford Hill Substation is located 3.5 miles south of the town of Columbus, Texas, on Highway 71 in Colorado County. The Point of Interconnection is located at the top connectors on the jumpers that connect the 69 kV high bus to the 69 kV low bus.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- transmission lines dead-end insulator strings and termination hardware
- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - Stafford Hill to Columbus 69 kV transmission line
 - Stafford Hill to Altair 69 kV transmission line
- the following facilities within the Stafford Hill Substation:
 - 69 kV transmission line switches 1556 and 1557
 - 69 kV high-bus, including conductors, insulators and termination hardware
 - jumpers from the two 69 kV transmission line switches to the lines and to the high-bus

AEP owns the following facilities:

- the Stafford Hill Substation including all facilities within it, except for those facilities owned by LCRA
- the 69 kV low bus and jumpers to high bus inside the Stafford Hill Substation
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station

7. **Facility Operation and Maintenance Responsibilities of the Parties:**

- AEP will control and operate the following equipment until LCRA takes over operational control:

- 69 kV switch 1556 and associated 69 kV transmission line to Columbus
- 69 kV switch 1557, and associated 69 kV transmission line to Altair
- AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 1553, and 1554
 - all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None

FACILITY SCHEDULE NO. 56

1. **Name:** **Riverside Pump**
2. **Location:** The Riverside Pump Substation is located approximately 4 miles west of Eagle Lake, Texas in Colorado County. Point of Interconnection is located where the AEP jumper conductors from the station equipment physically contact the connectors on the 69 kV tap transmission line conductors.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- transmission line dead-end insulator strings and termination hardware
- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - Altair to Eagle Lake 69 kV transmission line
- 69 kV transmission line switch 756, located near the tap point in the Altair to Eagle Lake 69 kV line
- 69 kV transmission tap line from the station to the Altair to Eagle Lake 69 kV transmission line
- associated equipment, structures and jumpers

AEP owns the following facilities:

- the Riverside Pump Substation including all the facilities within it
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station


7. **Facility Operation and Maintenance Responsibilities of the Parties:**
 - AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV switch 756 and associated 69 kV transmission line to Altair
 - 69 kV transmission tap line from the Altair to Eagle Lake 69 kV line to the Riverside Pump Substation

- AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 195
 - all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None



FACILITY SCHEDULE NO. 57

- 1 Name: **Prairie Pump**
2. Location: The Prairie Pump Substation is located 2.5 miles west of Eagle Lake, Texas, on Hwy 102, Texas in Colorado County. The Point of Interconnection is located where the AEP jumper conductors from the station equipment physically contact the connectors on the 69 kV tap transmission line conductors.
3. Delivery Voltage: 69 kV
4. Normal Operation of Interconnection: Closed
5. One-Line Diagram Attached: Yes
6. Facility Ownership Responsibilities of the Parties:

LCRA owns the following facilities:

- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - Altair to Eagle Lake 69 kV transmission line
- transmission line dead-end insulator strings and termination hardware
- 69 kV transmission tap line from the station to the Altair to Eagle Lake 69 kV transmission line

AEP owns the following facilities:

- the Prairie Pump Station including all facilities within it
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station


7. Facility Operation and Maintenance Responsibilities of the Parties:
 - AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV transmission tap line from the Altair to Eagle Lake 69 kV line to the Prairie Pump station
 - AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 156
 - all distribution equipment in the station

- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None



FACILITY SCHEDULE NO. 58

- 1 Name: **Parker**
2. Location: The Parker Substation is located 2.4 miles south of Highway 90A on Calhoun Road in the town of Eagle Lake, Texas in Colorado County. The Point of Interconnection is located where the AEP jumper conductors from the station equipment physically contact the connectors on the 69 kV tap transmission line conductors.
3. Delivery Voltage: 69 kV
4. Normal Operation of Interconnection: Closed
5. One-Line Diagram Attached: Yes
6. Facility Ownership Responsibilities of the Parties:

LCRA owns the following facilities:

- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - Altair to Eagle Lake 69 kV transmission line
- transmission line dead-end insulator strings and termination hardware
- 69 kV transmission tap line from the station to the Altair to Eagle Lake 69 kV transmission line including the in-line switch 1438 at the Parker Tap
- transmission line dead-end insulator strings and termination hardware at Parker Tap
- associated equipment, structures and jumpers at Parker Tap

AEP owns the following facilities:

- the Parker Substation including all facilities within it
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station


7. Facility Operation and Maintenance Responsibilities of the Parties:
 - AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV transmission tap line from the Altair to Eagle Lake 69 kV line to the Parker station
 - 69 kV switch 1438 located in the Altair to Eagle Lake 69 kV line

- AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 1477
 - all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None



FACILITY SCHEDULE NO. 59

1. Name: **Eagle Lake**
2. Location: The Eagle Lake Substation is located in Eagle Lake, Texas on FM 102, ½ mile south of Highway 90A, in Colorado County. There are two Points of Interconnection at the Eagle Lake Substation. The Points of interconnection are located where the jumpers from the 69 kV transformer switches connect to the 69 kV bus conductors.
3. Delivery Voltage: 69 kV
4. Normal Operation of Interconnection: Closed
5. One-Line Diagram Attached: Yes
6. Facility Ownership Responsibilities of the Parties:

LCRA owns the following facilities:

- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - Eagle Lake to Altair 69 kV transmission line
 - Eagle Lake to Matthews 69 kV transmission line
- transmission lines dead-end insulator strings and termination hardware
- 69 kV buses, including bus relaying, conductors, insulators and termination hardware
- 69 kV circuit breakers 7640, breaker foundation, and associated 69 kV switches 7639, 7641, and 7642
- panel 7640 line relaying, local controls and carrier equipment including wave trap, coupling capacitor, carrier equipment stand and foundation, and associated equipment
- 69 kV circuit breaker 7650, breaker foundation, and associated 69 kV switches 7649, 7651
- panel 7650 line relaying and local controls
- jumpers from 69 kV switches to the lines, to the 69 kV circuit breakers and from the 69 kV circuit breakers to the 69 kV buses
- 3 – 69 kV bus potential transformers, PT stands and foundations, fused disconnect switches and jumpers
- 2 – 69 kV line potential transformers, PT stands and foundations
- associated jumpers, junction boxes, manifolds, conduits, cables and ground straps

Attachments – Page 90

AEP owns the following facilities:

- the Eagle Lake Substation including all facilities within it, except for those facilities owned by LCRA
- the 69 kV transformer switches and jumpers that connect to the 69 kV bus conductors inside the Eagle Lake Substation
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station


7. Facility Operation and Maintenance Responsibilities of the Parties:

- AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV circuit breaker 7640, associated switches 7639, 7641, 7642, and associated 69 kV transmission line to Altair
 - 69 kV circuit breaker 7650, associated switches 7649, 7651, and associated 69 kV transmission line to El Campo via Matthews, etc.
- AEP controls and operates all other equipment in the station including the following:
 - 69 kV switches 1127 and 8603
 - all distribution equipment in the station
- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None



FACILITY SCHEDULE NO. 60

1. **Name:** **Lakeside Pump**
2. **Location:** The Lakeside Pump Substation is located 1.9 miles south of the town of Eagle Lake, Texas, 3/10 mile east of FM 102 in Colorado of the County. The Point of Interconnection is located where the AEP jumper from the 69 kV transformer switch connects to the 69 kV tap transmission line.
3. **Delivery Voltage:** 69 kV
4. **Normal Operation of Interconnection:** Closed
5. **One-Line Diagram Attached:** Yes
6. **Facility Ownership Responsibilities of the Parties:**

LCRA owns the following facilities:

- the following transmission lines comprised of structures, easements, conductors, insulators, and connecting hardware:
 - Eagle Lake to Matthews 69 kV transmission line
- transmission line dead-end insulator strings and termination hardware
- transmission line tap from the station to the 69 kV Eagle Lake – Matthews line

AEP owns the following facilities:

- the Lakeside Pump Substation including all facilities within it
- the 69 kV transmission tap line surge arresters
- any under-built distribution voltage circuits attached to the 69 kV transmission lines that terminate into the station

7. **Facility Operation and Maintenance Responsibilities of the Parties:**
 - AEP will control and operate the following equipment until LCRA takes over operational control:
 - 69 kV transmission tap line from the Eagle Lake to Matthews 69 kV line to the Lakeside Pump Substation
 - AEP controls and operates all other equipment in the station including the following:
 - 69 kV switch 197
 - all distribution equipment in the station

- Each Party maintains the facilities it owns that are provided for in this Facility Schedule. Maintenance of the facilities, including circuit breaker relays, that are owned by one Party that protect the facilities owned by the other Party, will be subject to review and approval by the other Party.

8. Cost Responsibilities of the Parties:

- Each Party will be fully responsible for the costs and liabilities related to the facilities it owns.
- Each Party will be responsible for all costs it incurs in connection with the establishment and maintenance of the Point of Interconnection in accordance with this Facility Schedule.

9. Other Terms and Conditions: None