



Control Number: 35077



Item Number: 57

Addendum StartPage: 0

PUC Project No. 35077

RECEIVED
2008 OCT -9 PM 4:16
PUBLIC UTILITIES DIVISION
FILING CLERK

First Amendment to Interconnection Agreement

Between

the City of Weimar

and

LCRA Transmission Services Corporation

October 7, 2008

**FIRST AMENDMENT TO
INTERCONNECTION AGREEMENT**

This First Amendment ("Amendment") to the Interconnection Agreement, dated June 27, 2008 between The City of Weimar ("City") and the LCRA Transmission Services Corporation ("Corporation") (the "Agreement") is made and entered into this 7th day of October, 2008, between the City and the Corporation, collectively referred to hereinafter as the Parties. In consideration of the mutual promises and undertakings herein set forth, the Parties agree to amend the Agreement as follows:

1. Exhibit "A" attached to the Agreement is deleted in its entirety and the Exhibit "A" attached to this First Amendment is hereby added to the Agreement in lieu thereof.

2. Facility Schedule No. 1 (including the diagrams attached thereto) is deleted in its entirety and Facility Schedule No. 1 attached to this First Amendment is hereby added to the Agreement in lieu thereof.

3. Facility Schedule No. 1 (including the diagrams attached thereto) attached to this First Amendment will become effective upon execution of this First Amendment by the Parties.

Except as otherwise expressly provided for herein, the Agreement will continue in full force and effect in accordance with its terms.

IN WITNESS WHEREOF, the Parties have caused this First Amendment to be executed in several counterparts, each of which shall be deemed an original but all shall constitute one and the same instrument.

CITY OF WEIMAR

By: 

Name: Randal W. Jones

Title: City Manager

Date: 9/22/08

LCRA TRANSMISSION SERVICES
CORPORATION

By: 

Name: Ray Pfefferkorn, P.E.

Title: LCRA Transmission Engineering
Manager

Date: 10/7/08



EXHIBIT A

[illegible]

FACILITY SCHEDULE NO. 1

1. **Name:** Weimar Substation
2. **Facility Location:** The Weimar Substation is located at 1103 CR 240, Weimar, Colorado County, Texas 78962.
3. **Points of Interconnection:** There are twelve (12) Points of Interconnection in the Weimar Substation generally described as:
 - where the incoming distribution line jumper connects to the line terminal of switch WE-33 at breaker WE-30.
 - where the incoming distribution line jumper connects to the line terminal of switch WE-31 at breaker WE-30.
 - where the jumper from breaker WE-30, passing through CT-3, connects to the 4 hole pad on switch WE-29.
 - where the jumper from breaker WE-30 connects to the 4 hole pad on switch WE-31.
 - where the incoming distribution line jumper connects to the line terminal of switch WE-41 at breaker WE-40.
 - where the incoming distribution line jumper connects to the line terminal of switch WE-43 at breaker WE-40.
 - where the jumper from breaker WE-40, passing through CT-4, connects to the 4 hole pad on switch WE-39.
 - where the jumper from breaker WE-40 connects to the 4 hole pad on switch WE-41.
 - where the incoming distribution line jumper connects to the line terminal of switch WE-51 at breaker WE-50.
 - where the incoming distribution line jumper connects to the line terminal of switch WE-53 at breaker WE-50.
 - where the jumper from breaker WE-50, passing through CT-2, connects to the 4 hole pad on switch WE-49.
 - where the jumper from breaker WE-50 connects to the 4 hole pad on switch WE-51.
4. **Transformation Services Provided by LCRA TSC:** Yes
5. **Metering Services Provided by LCRA TSC:** Yes
6. **Delivery Voltage:** 12.5 kV

7. **Metered Voltage and Location:** The metered voltage is 12.5 kV. The metering current transformers are located in each feeder bay. The metering potential transformers are located on the 12.5 kV operating bus.

8. **One Line Diagram Attached:** Yes

9. **Description of Facilities Owned by Each Party:**

City of Weimar owns:

- Three (3) distribution circuits including dead-end insulators, dead-end clamps, connectors, jumpers, and associated hardware that attach the three (3) circuits to the steel structures
- Three (3) distribution circuit breakers WE-30, WE-40 and WE-50, and associated foundations, jumpers, relaying, control panel, and cabling

LCRA TSC owns:

The Weimar Substation including, but not limited to, the following items:

- One (1) circuit switcher CS-2755
- One (1) power transformer PWT-1, T-1 with associated surge arresters
- Three (3) distribution bays including A-frames, trusses, insulators, disconnect switches, surge arresters, 12.5 kV operating bus, bus potential transformers, and metering current transformers
- Underfrequency relay panel
- Station Service equipment
- Control house with battery

10. **Operational Responsibilities of Each Party:**

- The City will be responsible for the operation of the three (3) distribution circuit breakers serving the City feeders.
- LCRA TSC will be responsible for the operation from the low voltage bus through the power transformer to the high voltage equipment.

11. **Maintenance Responsibilities of Each Party:** Each Party will be fully responsible for the maintenance of the equipment it owns.

12. **Other Terms and Conditions:**

- The City and LCRA TSC are to share access to the substation by LCRA TSC locks in the gate and in the control house doors.

WEIMAR ONE-LINE DIAGRAM

