



Control Number: 41089



Item Number: 195

Addendum StartPage: 0

Utility's Project Number	Project Name	Location (City/County)	Description	Estimated (or Actual) Start Date	Finish Date (Construction Complete)	Date Energized (If Applicable)	Initial Estimated Project Cost (\$)	Final Estimated Project Cost (\$)	Final Actual Project Cost (\$)	Variance %	Percent Complete	Existing Voltage (kV)	Upgraded or New Voltage (kV)	Circuit Length (Miles)	Conductor Type & Size & Bundling	Structure Type(s)	Existing ROW Width (Feet)	New ROW Width (Feet)	New ROW Length (Miles)	Rule Section or PUC Control Number	Comments
11766908, 11766912, 11766928, 11766900, 11766907, 11766507	Ochilene Substation to Lipscomb Substation	Ochilene County, Lipscomb County	Construct approximately 19.27 miles of new 115 kV transmission line from Ochilene Substation to the new Lipscomb Substation	01/01/14	12/31/15		17,276,318 - T-Line, 3,307,791 Substation					115	115	19-27	397.5 kcmil, ACSR, 267 stranded code name IBIS	Single-circuit, single pole self supporting steel structures, drilled pier foundations for corners & angle structures with some possible H-frame steel structures	NA	70	19-27	41334	
10941122, 11313775, 11313767, 11342429, 11342437	TUCO to Texas-Oklahoma Interconnect 345 kV Project	Hale, Floyd, Motley, Cottle, Bliscoe, Hall, Childress, Donley, Collingsworth, Wheeler	Construct approximately 201 miles of 345 kV transmission line from TUCO Substation to a designated point in Adams County, Oklahoma	01/01/13			150,609,087 - T-Line, 21,617,719 Substation				40%	345	345	130	795 kcmil, ACSR, 267 stranded code name Drake	Two-pole steel H-frame steel structures	NA	150-250	180-205	36877	
11350161, 11350178, 11350184, 11350246, 11350254, 11350255, 11350460, 11350688, 11351095, 11352406	Rolling Hills Substation to Hastings Substation	Potter	Construct approximately 3.5 to 7 miles of new 115 kV transmission line from the proposed new Rolling Hills Substation to Hastings Substation	09/01/12			4,377,274 - T-Line, 11,923,334 - Substation				70%	115	115	3.5 to 7	477 kcmil, ACSR, 267 stranded code name IBIS	Single-pole double-circuit steel poles	NA	70	3.5 to 7	39467	
11557274, 11351104, 11351243, 11351271,	Newhart Substation to Kress Substation	Castro, Swisher	Construct approximately 20 miles of new 115 kV transmission line from Newhart Substation to existing Kress Substation				12,923,519 - T-Line, 15,759,906 - Substation				30%	115	115	18 to 20	397.5 kcmil, ACSR, 267 stranded code name IBIS	Single-circuit, single pole self supporting steel structures, drilled pier foundations for corners & angle structures with some possible H-frame steel structures	NA	70	18 to 20	39798	
11350078, 11557172, 11351227, 11351252,	Newhart Substation to Castro Substation	Castro	Construct approximately 24 miles of 115 kV transmission line from Newhart Substation to the existing Castro Substation				13,698,544 - T-Line, 10,790,750 Substation				50%	115	115	23-25	397.5 kcmil, ACSR, 267 stranded code name IBIS	Single-circuit, single pole self supporting steel structures, drilled pier foundations for corners & angle structures with some possible H-frame steel structures	NA	70	23-25	39873	
11350485, 11351098, 11488936, 11351177, 11351290, 11351294, 11351299, 11351303, 11351309, 11351313, 11351315, 11352430, 11352430, 11352432, 11352446	Kiser Substation to Kress Substation	Hale, Swisher	Construct approximately 27 miles of 115 kV transmission line from the existing Kress Substation to Kiser Substation				19,254,306 - T-Line, 10,072,725 - Substation				25%	115	115	23-30	397.5 kcmil, ACSR, 267 stranded code name IBIS	Single-circuit, single pole self supporting steel structures, drilled pier foundations for corners & angle structures with some possible H-frame steel structures	NA	70	23-30	40125	
11351245, 11351274, 11352127, 11352152	Newhart Substation to Swisher Substation	Castro, Swisher	Construct approximately 22 miles of 230 kV transmission line from Newhart Substation to the existing Swisher Substation				16,071,804 - T-Line, 13,069,889 Substation				5%	230	230	21-24	795 kcmil, ACSR, 267 stranded code name Drake	Single-circuit, single pole self supporting steel structures, drilled pier foundations for corners & angle structures with some possible H-frame steel structures	NA	90	21-24	39862	2013 SEP 13 PM 4:42
11557276, 11351120, 11351234, 11351268, 11351280, 11351239	Newhart Substation to Lamton Substation	Lamb, Castro, Hale	Construct approximately 23-30 miles of 115 kV transmission line from Newhart Substation to the existing Lamton Substation				15,498,074 - T-Line, 13,069,889 Substation				5%	115	115	23-30	397.5 kcmil, ACSR, 267 stranded code name IBIS	Single-circuit, single pole self supporting steel structures, drilled pier foundations for corners & angle structures with some possible H-frame steel structures	NA	70	23-30	40193	

195

