



## 11.2.8 30 TAC Chapter 217 Subchapter C Requirements

Table 11-3: High Point TAC Requirements

| Requirement           | Reference | Satisfied (Yes/No)                           |
|-----------------------|-----------|--|
| Site Requirements     | §217.59   | No: lacks access roadway, no perimeter fence |
| Design Considerations | §217.60   | No: lacks ventilation                        |
| Pumps                 | §217.61   | Yes  |
| Pipes                 | §217.62   | Yes  |
| Emergency Provisions  | §217.63   | No: lacks back-up generator, no signage      |

## 11.3 Conclusions

The following conclusions were developed from the evaluation of the High Point lift station:

- The station has poor security as indicated by the lack of perimeter fencing, gates, and signage.
- Site area itself is not well-kept; overgrown grass is evident
- There is no access roadway
- Drainage problems are evident from the pools of accumulated rainwater
- Groundwater infiltration is present in the wet well as reported by City staff
- Upgraded control panel will be installed in the coming weeks
- Site lacks back-up power capabilities
- Ventilation is required

## 11.4 Recommendations

- Install SCADA interface for alarms and run-status indicators
- Equip site with back-up power capability
- Construct access roadway
- Install perimeter fencing along with associated barbed wire and signage
- Landscaping is recommended to improve site area
- Install ventilation pipe

## 11.5 OPCC

The site and facility improvements are estimated to cost \$56,900.



## Water/Wastewater System Improvements – Lift Stations Evaluation

Table 11-4: High Point OPCC

| Item Description                                 | Quantity | Unit | Unit Cost | Total Cost |
|--|----------|------|-----------|------------|
| High Point                                       |          |      |           |            |
| SCADA  | 1        | EA   | \$ 35,000 | \$ 35,000  |
| Generator connection                             | 1        | EA   | \$ 2,000  | \$ 2,000   |
| Access roadway                                   | 1        | LS   | \$ 7,300  | \$ 7,300   |
| Ventilation pipe                                 | 1        | EA   | \$ 500    | \$ 500     |
| Misc. (fence, barbed wire, signage, landscaping) | 1        | LS   | \$ 12,100 | \$ 12,100  |
| Total  |          |      |           | \$ 56,900  |



## 12.0 Carter Ranch Phase II Lift Station

### 12.1 Lift Station Overview

The Carter Ranch Phase II Lift Station was constructed in 2004 and consists of a control panel, three Flygt model MP 3127 pumps, and the physical lift station structure. This lift station will be placed offline in the near future with a CIP project. The lift station services the surrounding neighborhood, which includes approximately 930 houses. It pumps to the Upper Trinity Regional Water District Doe Branch Interceptor.

### 12.2 Condition Assessment

#### 12.2.1 Security

The site is located off of Preston Road and is enclosed by a chain-link perimeter fence. The fence does not contain barbed wire nor does it have signs to prevent trespassing. The access gate is secured with a padlock to restrict access and can easily accommodate a vehicle. The control panel is also secured with a padlock and a remote alarm.



Figure 12-1: Site Perimeter at Carter Ranch LS

#### 12.2.2 Civil

The perimeter fence appears to be good condition with no signs of corrosion. The access roadway is constructed with concrete and appears to have drainage problems. This is indicated in Figure 12-2. Inside the perimeter fence, the ground is covered with grass and large aggregate. There appears to be drainage problems as indicated by the pools of rainwater and algae near the access gate.



Figure 12-2: Access Gate at Carter Ranch LS



Figure 12-3: Site Interior at Carter Ranch LS

### 12.2.3 Access

The site has sufficient access for maintenance as indicated by the concrete roadway, large width of the access gate, and ample space within the perimeter fence. It can easily accommodate a work truck and provide access to the wet wells. The hatch access to the top of the wet well is an aluminum hatch. It is fastened to the top of the wet well with hinges, providing adequate access to the pumps.





Figure 12-4: Site Access at Carter Ranch LS

#### 12.2.4 Pumping and Mechanical

The lift station is comprised of three Flygt model MP 3127 pumps, two with 7.5 HP motors and one with a 10 HP motor. The piping and associated supports appear to be in good condition with no major signs of rust or leakage.



Figure 12-5: Pump Controls at Carter Ranch LS





Figure 12-6: Valve Boxes at Carter Ranch LS

#### 12.2.5 Controls and Instrumentation

The lift station pumps are controlled by a series of mercury floats that pump the lift station wet well down according to set elevations. The floats terminate into the control panel where they activate a motor contactor to start and stop the pumps. The control panel has the following switches present: a master on/off, run status indicators, elapsed time meters, and hand/off/auto. The control panel is not connected to SCADA, thus a SCADA interface is required for alarms and run-status indicators. A red alarm beacon is present, providing a 360 degree visual check of alarm condition.

The controls are in good working condition and operate as designed and intended. The panel is secured with a padlock to ensure security. The site lacks back-up generator capabilities.




Figure 12-7: Control Panel at Carter Ranch LS



## Water/Wastewater System Improvements – Lift Stations Evaluation

## 12.2.6 Condition Assessment

Table 12-1: Carter Ranch Phase II Condition Assessment Ratings

| Aspect                       | Rating |
|------------------------------|--------|
| Site Security                | Fair   |
| Site Civil                   | Fair   |
| Access                       | Good   |
| Pumping and Mechanical       | Good   |
| Controls and Instrumentation | Good   |

Based on the summary above, the overall condition is determined to have an average rating of good.

## 12.2.7 Lift Station Design Data

Table 12-2: Carter Ranch Phase II Design Data

| Lift Station                       | Carter Ranch Phase II |
|------------------------------------|-----------------------|
| Address                            | 4100 S Preston Road   |
| Year Constructed                   | 2004                  |
| Recent Improvements                | NA                    |
| Capacity one pump, gpm             | 133                   |
| Capacity two pumps, gpm            | 200 (est)             |
| Rated Total Dynamic Head (TDH), ft | NA                    |
| Type of Pump                       | Submersible           |
| Manufacturer                       | Flygt                 |
| Model                              | MP 3127               |
| Volts/Ph/Hz                        | 480/3/60              |
| Motor HP                           | 7.5 (two); 10 (one)   |

## 12.2.8 30 TAC Chapter 217 Subchapter C Requirements

Table 12-3: Carter Ranch Phase II TAC Requirements

| Requirement           | Reference | Satisfied (Yes/No)                         |
|-----------------------|-----------|--|
| Site Requirements     | §217.59   | No: lacks barbed wire                      |
| Design Considerations | §217.60   | No: lacks ventilation                      |
| Pumps                 | §217.61   | Yes  |
| Pipes                 | §217.62   | Yes  |
| Emergency Provisions  | §217.63   | No: lacks back-up generator, lacks signage |





### 12.3 Conclusions

The following conclusions were developed from the evaluation of the Carter Ranch Phase II lift station:

- The station is relatively well maintained
- Perimeter fencing is present; however lacks barbed wire
- Access gate can easily accommodate work truck and provide access to wet well
- Drainage problems are evident due to pools of rainwater and algae
- Control panel is in good operating condition and has not posed any problems for the City staff
- Site lacks back-up power capabilities
- Site lacks ventilation

### 12.4 Recommendations

- Install gravity bypass and upon completion of future CIP project, decommission lift station
- Demolish lift station

### 12.5 OPCC

Demolition is estimated to cost \$25,000.

**Table 12-4: Carter Ranch Phase II OPCC**

| Item Description      | Quantity | Unit | Unit Cost | Total Cost |
|-----------------------|----------|------|-----------|------------|
| Carter Ranch Phase II |          |      |           |            |
| Demolition            | 1        | LS   | \$ 25,000 | \$ 25,000  |
| Total                 |          |      |           | \$ 25,000  |



### 13.0 Willock Hill Lift Station

#### 13.1 Lift Station Overview

The Willock Hill lift station consists of a control panel, two Hydromatic model S4M750 M4-4 pumps, and the physical lift station structure. The lift station services the surrounding neighborhood.

#### 13.2 Condition Assessment

##### 13.2.1 Security

The site is located off of South Hillside Street. The lift station is enclosed by a chain-link perimeter fence with three strands of barbed wire. It also includes signage with emergency contact information. The access gate is secured with a padlock, but cannot accommodate a vehicle within the perimeter area. The wet well access hatch does not fully close, thereby rendering the security lock useless. This is indicated in Figure 13-3. The control panel is secured with a padlock and is equipped with a remote alarm.



Figure 13-1: Site Perimeter at Willock Hill LS



**Figure 13-2: Fencing at Willock Hill LS**

### 13.2.2 Civil

The perimeter fence appears to be in good condition with minor signs of corrosion. However, the site area itself is in poor condition as indicated by the overgrown grass, overhung vines, and lack of landscaping. The lift station rests on a concrete pad that appears to be in fair condition. Additionally, the site area is not particularly well graded.



**Figure 13-3: Wet Well at Willock Hill LS**

### 13.2.3 Access

The site has poor access due to the lack of paved roadway leading to the lift station. The site area itself can accommodate a work truck and provided access to the wet well. However, the work truck cannot enter past the perimeter fence, and as previously mentioned, an access roadway is not present. This is indicated in Figure 13-4. The access hatch to top of the wet wall is an aluminum hatch and is elevated approximately 4 feet on a concrete pad. It is fastened to the top of the wet well with hinges and remains partially open at all times. It provides adequate access to the pumps. However, the access hatch is in poor condition as it remains partially open, thereby allowing rainfall, debris, and wildlife to enter the wet well.





**Figure 13-4: Site Access at Willock Hill LS**

#### 13.2.4 Pumping and Mechanical

The lift station is comprised of two Hydromatic model S4M750 M4-4 pumps each with a 7.5 HP motor. During the inspection, one of the pumps was not in service. A valve box cover is not provided. The piping and associated supports appear to be in fair condition as indicated by Figure 13-3 and Figure 13-5.



**Figure 13-5: Pump Controls at Willock Hill LS**





Figure 13-6: Valve Box at Willock Hill LS

#### 13.2.5 Controls and Instrumentation

The lift station pumps are controlled by a series of mercury floats that pump the lift station wet well down according to set elevations. The floats terminate into the control panel where they activate a motor contactor to start and stop the pumps. The control panel is not connected to SCADA, thus a SCADA interface is preferred for alarms and run-status indicators. A red alarm beacon is present, providing a 360 degree visual check of alarm condition.

The controls are in fair condition. The panel is secured with a padlock to restrict access. However, there is no standby generator capability.




Figure 13-7: Control Panel Interior at Willock Hill LS



## Water/Wastewater System Improvements – Lift Stations Evaluation

## 13.2.6 Condition Assessment

Table 13-1: Willock Hill Condition Assessment Ratings

| Aspect                       | Rating |
|------------------------------|--------|
| Site Security                | Good   |
| Site Civil                   | Poor   |
| Access                       | Poor   |
| Pumping and Mechanical       | Good   |
| Controls and Instrumentation | Good   |

Based on the summary above, the overall condition is determined to have an average rating of fair.

## 13.2.7 Lift Station Design Data

Table 13-2: Willock Hill Design Data

| Lift Station                       | Willock Hill  |
|------------------------------------|---|
| Address                            | 131 S Hillside Street   |
| Recent Improvements                | Upgraded control panel; generator connection; replaced pumps and valves |
| Capacity one pump, gpm             | 156   |
| Capacity two pumps, gpm            | NA  |
| Rated Total Dynamic Head (TDH), ft | 31  |
| Type of Pump                       | Submersible   |
| Manufacturer                       | Hydromatic  |
| Model                              | S4M750 M4-4   |
| Volts/Ph/Hz                        | 480/3/60  |
| Motor HP                           | 7.5   |

## 13.2.8 30 TAC Chapter 217 Subchapter C Requirements

Table 13-3: Willock Hill TAC Requirements

| Requirement           | Reference | Satisfied (Yes/No)       |
|-----------------------|-----------|--------------------------|
| Site Requirements     | §217.59   | No: lacks access roadway |
| Design Considerations | §217.60   | No: lacks ventilation    |
| Pumps                 | §217.61   | Yes                      |
| Pipes                 | §217.62   | Yes                      |
| Emergency Provisions  | §217.63   | Yes                      |





### 13.3 Conclusions

The following conclusions were developed from the evaluation of the Willock Hill lift station:

- The station is in fair condition
- Perimeter fencing is present along with barbed wire and proper signage
- The site area is not well-kept as indicated by the overgrown grass
- Access roadway is not present
- The wet well access hatch remains partially open at all times
- There is no cover on the valve box
- Ventilation is required

### 13.4 Recommendations

- Install SCADA interface for alarms and run-status indicators
- Improve gravel roadway
- Rehabilitate wet well access hatch
- Improve site area landscaping
- Install ventilation pipe
- Install gravity flow bypass and upon completion of future interceptor, decommission lift station

### 13.5 OPCC

The site and facility improvements are estimated to cost \$53,000.

Table 13-4: Willock Hill OPCC

| Item Description    | Quantity | Unit | Unit Cost | Total Cost |
|---------------------|----------|------|-----------|------------|
| Willock Hill        |          |      |           |            |
| SCADA               | 1        | EA   | \$ 35,000 | \$ 35,000  |
| Gravel roadway      | 1        | LS   | \$ 7,500  | \$ 7,500   |
| Rehab access hatch  | 1        | LS   | \$ 5,000  | \$ 5,000   |
| Ventilation pipe    | 1        | EA   | \$ 500    | \$ 500     |
| Misc. (landscaping) | 1        | LS   | \$ 5,000  | \$ 5,000   |
| Total               |          |      |           | \$ 53,000  |





## 14.0 Tolleson

### 14.1 Lift Station Overview

The Tolleson lift station consists of a control panel, pumps, and the physical lift station structure. The lift station services the surrounding neighborhood. City staff reported the lift station would be decommissioned in the near future. Therefore, a detailed site assessment was not conducted.

### 14.2 Conclusion/Recommendation

A field inspection for this site was not conducted. However, based on staff input, it is recommended to demolish the Tolleson lift station.

### 14.3 OPCC

Demolition is estimated to cost \$25,000.

Table 14-1: Tolleson OPCC

| Item Description | Quantity | Unit | Unit Cost | Total Cost |
|------------------|----------|------|-----------|------------|
| Tolleson         |          |      |           |            |
| Demolition       | 1        | LS   | \$ 25,000 | \$ 25,000  |
| Total            |          |      |           | \$ 25,000  |



## 15.0 Summary of Condition

Table 15-1 presents a summary of the description, size, and overall condition of the ten lift stations that were assessed.

**Table 15-1: Overall Condition Summary**

| Lift Station  | Description and Size                                      | Overall Condition |
|---|---|-------------------|
| Winn Road   | Flygt (two) MP 3068 with 3.8 HP motors                    | Fair              |
| Parkside  | Flygt (two) MP 3068 with 10 HP motors                     | Good              |
| Old Celina Park   | Hydromatic (two) HPG-200 with 2 HP motors                 | Good              |
| Lucy's  | Hydromatic (two) HPG-200 with 2 HP motors                 | Poor              |
| Business 298 #1   | Hydromatic (two) HPGH-750 PC with 7.5 HP motors           | Fair              |
| Shawnee Trail #1  | Dayton (two) with 2 HP motors                             | Fair              |
| Shawnee Trail #2  | Hydromatic (two) with 2 HP motors                         | Fair              |
| High Point  | Hydromatic (two) with 7.5 HP motors                       | Poor              |
| Carter Ranch Phase II   | Flygt Pumps (three) with 7.5 (two) and 10 (one) HP motors | Good              |
| Willock Hill  | Flygt Pump (two) with 7.5 HP motors                       | Fair              |
| Tolleson  | NA (Tolleson was not inspected)                           | NA                |
| General Physical Condition Rating Guidelines:<br>Good: no immediate attention required.<br>Fair: requires some initial repair to remain in adequate working condition.<br>Poor: requires replacement or reconstruction in the immediate future. |   |                   |





## 16.0 Summary of Recommendations

Table 16-1 and Table 16-2 present the recommendations and cost for each of the lift stations.

**Table 16-1: Summary of Recommendations**

| Lift Station     | Recommendations   | Cost     |
|------------------|---|----------|
| Winn Road        | <ul style="list-style-type: none"><li>• Install SCADA interface</li><li>• Install perimeter fencing with barbed wire and signage</li><li>• Install ventilation pipe</li><li>• Install gravity flow bypass and upon completion of future CIP project, decommission lift station</li></ul>  | \$45,500 |
| Parkside         | <ul style="list-style-type: none"><li>• Install SCADA interface</li><li>• Equip site with back-up power capabilities</li><li>• Install barbed wire and signage on perimeter wall</li><li>• Widen driveway</li><li>• Install chain to pull pumps</li></ul>   | \$54,600 |
| Old Celina Park  | <ul style="list-style-type: none"><li>• Install SCADA interface</li><li>• Equip site with back-up generator capabilities</li><li>• Install ventilation pipe</li><li>• Install signage</li><li>• Trim back overhanging tree limbs away from control panel</li></ul>  | \$42,600 |
| Lucy's           | <ul style="list-style-type: none"><li>• Install SCADA interface</li><li>• Upgrade control panel</li><li>• Equip site with back-up power capabilities</li><li>• Install perimeter fence with barbed wire and signage</li><li>• Improve roadway accessibility</li><li>• Replace existing manhole cover with wet well access hatch</li><li>• Install ventilation pipe</li><li>• Consider abandoning lift station due to the condition of the site area and location of the lift station</li><li>• Install gravity flow bypass and upon completion of future CIP project, decommission lift station</li></ul> | \$82,100 |
| Business 298 #1  | <ul style="list-style-type: none"><li>• Install SCADA interface</li><li>• Upgrade control panel</li><li>• Equip site with back-up generator capability</li><li>• Construct access roadway</li><li>• Rehabilitate concrete slab and general landscaping</li><li>• Install signage</li><li>• Install ventilation pipe</li></ul>   | \$75,300 |
| Shawnee Trail #1 | <ul style="list-style-type: none"><li>• Install SCADA interface</li><li>• Equip site with back-up generator capabilities</li><li>• Install barbed wire on perimeter fence</li><li>• Install ventilation pipe</li></ul>  | \$39,500 |

(Continued on following page)



## Water/Wastewater System Improvements – Lift Stations Evaluation

Table 16-2: Summary of Recommendations (Continued)

| Lift Station     | Recommendations   | Cost             |
|------------------|---|------------------|
| Shawnee Trail #2 | <ul style="list-style-type: none"><li>• Install SCADA interface</li><li>• Equip site with back-up power capability</li><li>• Rehabilitate concrete pad and install slab supports</li><li>• Extend access roadway</li><li>• Add hinges to wet well access hatch</li><li>• Install barbed wire on perimeter fence</li><li>• Install ventilation pipe</li><li>• Landscaping to clean up area</li></ul> | \$46,400         |
| High Point       | <ul style="list-style-type: none"><li>• Install SCADA interface</li><li>• Equip site with back-up power capability</li><li>• Construct access roadway</li><li>• Install perimeter fencing with barbed wire and signage</li><li>• Install ventilation pipe</li><li>• Landscaping to improve site area</li></ul>  | \$56,900         |
| Carter Ranch II  | <ul style="list-style-type: none"><li>• Install gravity flow bypass and upon completion of future CIP project, decommission lift station</li><li>• Demolish lift station</li></ul>  | \$25,000         |
| Willock Hill     | <ul style="list-style-type: none"><li>• Install SCADA interface</li><li>• Construct access roadway</li><li>• Rehabilitate wet well access hatch</li><li>• Install ventilation pipe</li><li>• Landscaping</li><li>• Install gravity flow bypass and upon completion of future interceptor, decommission lift station</li></ul>   | \$53,000         |
| Tolleson         | <ul style="list-style-type: none"><li>• Demolish lift station</li></ul>   | \$25,000         |
| <b>Total</b>     |   | <b>\$545,900</b> |



# **Appendix C**


---

## **Water & Wastewater System Improvements Water Capital Improvements Plan**

**City of Celina, Texas**



Prepared by:



3010 Gaylord Parkway  
Suite 190  
Frisco, TX 75034

September 2017

Garver Project No.: 16088050



## 1.0 Executive Summary

This Water Capital Improvements Plan utilizes the model criteria and simulations detailed in the Water and Wastewater Modeling Improvements to develop proposed projects from the recommended improvements. These improvements are identified for a 5-year planning horizon (2017 – 2022 fiscal years).

A summary of all proposed project costs and schedules is displayed on Page 4, while a proposed schedule is located on Page 5. Project descriptions are in order based on priority ranking following this summary.

### 1.1 Identification and Ranking

Each project will be initiated based on regulatory, capacity, fire flow, condition, City-directed, or operational triggers. As these triggers activated a project, alphabetical project groupings were developed in localized areas to address that need. These were then ranked numerically based on the criticality of the project and service area impacted. Project triggers are described below:

#### 1.1.1 Capacity

This trigger is activated if a section or area of the system is unable to provide modeled flow or elevated storage needed for all meters within that portion of the system.

#### 1.1.2 Regulatory

This trigger is activated if TCEQ regulations (e.g., minimum residual pressure, storage capacity per connection, etc.) would not be met.

#### 1.1.3 Fire Flow

This trigger is activated if a portion of the system is unable to meet minimum required flow rates during the fire flow modeling scenario.

#### 1.1.4 Condition

This trigger would be activated based on deteriorating conditions of existing infrastructure, as identified during field investigations.

#### 1.1.5 City-Directed

This trigger is activated when City staff have indicated that items will be replaced, are required as part of upcoming policy changes, or are needed to manage growth.

#### 1.1.6 Operational

This trigger is activated when an improvement will provide an operational benefit. An example would be looping and dead end requirements that would improve water quality and minimize flushing.





## 1.2 Timeline

This priority was then applied to an overall timeline, in order to meet a 5-year planning horizon. Each project has also been assigned a flexibility rating of low, medium, or high. Projects with higher flexibility can be extended later in the planning horizon, depending on the City's available funding or changing system conditions which may impact the need for the project (such as unexpected delays in development that delay the need for capacity improvements).

The project priority and the City's expected timeline for development dictates the trigger date. Projects with higher priority will trigger sooner than those with lower priority. The trigger date is then utilized to capture anticipated costs for the life of the project, by escalating the total estimated 2017 costs at a rate of 3% to the trigger date for the engineering and construction items.

The trigger date can also be expressed as a number of residential lots constructed. In the event that development occurs at rate faster or slower than anticipated, the City can track number of lots constructed relative to the estimated number of constructed lots as of May 2017 (4,879). For example, projects triggered in October 2018 could also be triggered by construction on 1,526 new residential lots, for a total of 6,405 constructed lots. Projects triggered in October 2019 would be triggered by construction on 3,233 residential lots (8,112 lots total).

## 1.3 Cost Development

Costs estimates were prepared for each individual project, based on industry standards and the 2017 bidding environment. These costs are an estimate, and should be re-evaluated as each project nears the trigger date. Each project has the following costs associated with the total OPCC:

### 1.3.1 Construction Costs

This cost is the estimated cost once the project has been designed and is ready for the bid phase to begin. It represents a combination of the estimated total construction costs, and includes a 20% contingency.

Costs for tanks and pumps were developed from manufacturer and contractor quotations. Pipeline installation costs were developed from a combination of recent neighboring city water and sewer project bid tabulations. Individual bid items are described as follows.

### 1.3.2 Engineering

The engineering estimate includes all professional services needed to bid each project, including survey, deed research (as needed), preliminary, and final design of all improvements. This cost is 20% of the estimated construction costs, including contingency. This does not include construction observation or start-up services.

### 1.3.3 Bid Item Descriptions:

*General Improvements:* Anticipated sitework, backfill, erosion control, rehabilitation of existing structures, testing, easements, and contractor overhead costs.




*Pipe Installation:* Material and labor costs associated with pipe installation by open cut on a linear footage basis, depending on line size.

*Bored Pipe Installation:* Anticipated material, labor, sitework, backfill, erosion control, testing, easements, and contractor overhead costs associated with bored pipe installation on a lump sum basis. These costs are dependent on line size, length of boring, and location of boring.

*Valves and Fittings:* Cost for anticipated service connections and connections to existing pipes, including isolation valves.

A proposed spending schedule follows. Further refinement of this spending schedule and associated project trigger dates is available, depending upon City funding timeframes.



Proposed Spending Schedule for Water CIP





#### **1.4 Project Descriptions**

A summary of water CIP items, schedule, and individual project descriptions are provided in the following pages.



Table 1: Water CIP Summary

| Project Identification |          |  |                   |             |                 |                   | Schedule     |              |                  |                     |                               |                        | 2017 Costs (\$1,000)                 |              | Forecasted Cost (\$1,000) |          |  |  |
|------------------------|----------|--|-------------------|-------------|-----------------|-------------------|--------------|--------------|------------------|---------------------|-------------------------------|------------------------|--------------------------------------|--------------|---------------------------|----------|--|--|
| Project                | Grouping | Description  | Location          | Flexibility | Primary Trigger | Secondary Trigger | Trigger Lots | Trigger Date | Project Complete | Engineering /Design | Bld/ Construction             | Total Project Duration | OPCC                                 | Construction | Professional Services     | OPCC     |  |  |
| 1                      | B        | Downtown EST shutdown and SCADA switchover                         | Low Plane         | Low         | Regulatory      | Capacity          | 0            | Feb-17       | Mar-17           | 0                   | 1                             | 1                      | \$0                                  | \$0          | \$0                       | \$0      |  |  |
| 2                      | A        | Capacity upgrades to CRPS and installation of 4 new pumps          | CRPS              | Low         | Capacity        | Regulatory        | 0            | Feb-17       | Jul-18           | 8                   | 9                             | 17                     | \$6,305                              | \$5,412      | \$1,051                   | \$6,463  |  |  |
| 3                      | H        | Capacity upgrades to DTPS and installation of 3 new pumps          | DTPS              | Low         | Capacity        | Operational       | 0            | Feb-17       | Jul-18           | 8                   | 9                             | 17                     | \$5,173                              | \$4,440      | \$862                     | \$5,302  |  |  |
| 4                      | E        | 12" line and valves to switch LPP to HPP                           | Low to High Plane | Low         | Regulatory      | Fire Flow         | 0            | Oct-17       | Oct-18           | 6                   | 6                             | 12                     | \$171                                | \$147        | \$29                      | \$176    |  |  |
| 5                      | F        | 18", 30" and 36" line along Celina Road from CRPS                  | CRPS; Low Plane   | Low         | Capacity        | Regulatory        | 0            | Oct-17       | Oct-19           | 12                  | 12                            | 24                     | \$7,939                              | \$7,019      | \$1,363                   | \$8,382  |  |  |
| 6                      | G        | 24" and 30" lines to Downtown GST                                  | Low Plane         | Low         | Capacity        | Regulatory        | 0            | Oct-17       | Oct-19           | 12                  | 12                            | 24                     | \$5,588                              | \$4,940      | \$959                     | \$5,899  |  |  |
| 7                      | J        | 24" and 30" discharge lines from DTPS                              | High Plane        | Low         | Capacity        | Regulatory        | 0            | Oct-17       | Oct-19           | 12                  | 12                            | 24                     | \$3,490                              | \$3,086      | \$599                     | \$3,685  |  |  |
| 8                      | D        | 18" and 24" line to Morgan Lake area                               | High Plane        | Medium      | Regulatory      | Capacity          | 1,526        | Oct-18       | Jul-20           | 9                   | 12                            | 21                     | \$4,730                              | \$4,307      | \$836                     | \$5,143  |  |  |
| 9                      | C        | 18" line east of Light Farm EST along Cypress Creek Way            | Low Plane         | Medium      | Capacity        | Regulatory        | 1,526        | Oct-18       | May-19           | 3                   | 4                             | 7                      | \$312                                | \$276        | \$54                      | \$329    |  |  |
| 10                     | L        | Additional capacity upgrades to CRPS                               | CRPS; Low Plane   | Low         | Capacity        | Regulatory        | 1,526        | Oct-18       | Oct-19           | 6                   | 6                             | 12                     | \$536                                | \$474        | \$95                      | \$568    |  |  |
| 11                     | Z        | New 6 MG GST at CRPS   | Low Plane         | Medium      | Operational     | Capacity          | 1,526        | Oct-18       | Jul-20           | 9                   | 12                            | 21                     | \$7,619                              | \$6,938      | \$1,347                   | \$8,285  |  |  |
| 12                     | R        | Additional capacity upgrades to DTPS                               | DTPS              | Low         | Capacity        | Regulatory        | 2,370        | Oct-18       | Oct-19           | 6                   | 6                             | 12                     | \$556                                | \$491        | \$98                      | \$589    |  |  |
| 13                     | K        | Decommission Morgan Lake facilities                                | High Plane        | Medium      | Operational     | Capacity          | 2,226        | Mar-19       | Aug-19           | 2                   | 3                             | 5                      | \$145                                | \$127        | \$27                      | \$154    |  |  |
| 14                     | AB       | SCADA improvements   | System Wide       | High        | Operational     | None              | 3,233        | Oct-19       | Apr-21           | 9                   | 9                             | 18                     | \$312                                | \$262        | \$79                      | \$341    |  |  |
| 15                     | AA       | 8" line upgrades in Downtown area                                  | System Wide       | Medium      | Operational     | City-directed     | 3,233        | Oct-19       | Oct-21           | 12                  | 12                            | 24                     | \$22,390                             | \$21,000     | \$4,078                   | \$25,078 |  |  |
| 16                     | M        | 12" line along Settlers Ridge                                      | Low Plane         | Medium      | Capacity        | Regulatory        | 3,233        | Oct-19       | Oct-21           | 12                  | 12                            | 24                     | \$3,308                              | \$3,102      | \$602                     | \$3,705  |  |  |
| 17                     | Q        | Additional capacity upgrades to CRPS                               | CRPS              | Low         | Capacity        | Regulatory        | 3,233        | Oct-19       | Oct-20           | 6                   | 6                             | 12                     | \$556                                | \$506        | \$101                     | \$607    |  |  |
| 18                     | AC       | 2020 5-year Master Plan  | System Wide       | Medium      | Operational     | City-directed     | 4,894        | Oct-20       | Oct-21           | 12                  | 0                             | 12                     | \$200                                | \$0          | \$225                     | \$225    |  |  |
| 19                     | P        | 8", 12", and 18" line from Morgan Lake to DC Ranch                 | High Plane        | Medium      | Capacity        | Regulatory        | 3,233        | Oct-19       | Jul-21           | 9                   | 12                            | 21                     | \$5,119                              | \$4,802      | \$932                     | \$5,734  |  |  |
| 20                     | O        | 24" line to increase capacity in the Low Pressure Plane            | Low Plane         | Medium      | Capacity        | Regulatory        | 4,894        | Oct-20       | Jul-22           | 9                   | 12                            | 21                     | \$5,340                              | \$5,158      | \$1,002                   | \$6,160  |  |  |
| 21                     | T        | 18" and 24" lines along Hwy. 455                                   | High Plane        | High        | Fire flow       | Operational       | 4,894        | Oct-20       | Jul-22           | 9                   | 12                            | 21                     | \$2,387                              | \$2,306      | \$448                     | \$2,754  |  |  |
| 22                     | S        | 18" and 24" lines along Legacy Drive                               | Low Plane         | High        | Operational     | Capacity          | 6,504        | Oct-21       | Jul-23           | 9                   | 12                            | 21                     | \$3,353                              | \$3,336      | \$648                     | \$3,984  |  |  |
| 23                     | X        | 8" and 24" lines to connect Preston Lakes to Preston Road Corridor | Low Plane         | High        | Fire flow       | Operational       | 6,504        | Oct-21       | Jul-23           | 9                   | 12                            | 21                     | \$4,175                              | \$4,154      | \$807                     | \$4,961  |  |  |
| 24                     | W        | 8" and 12" line along E. Malone St. and Preston Road               | High Plane        | High        | Fire flow       | Operational       | 4,894        | Oct-20       | Oct-21           | 6                   | 6                             | 12                     | \$612                                | \$574        | \$115                     | \$689    |  |  |
| 25                     | V        | 8" lines in the Low Pressure Plane                                 | Low Plane         | High        | Fire flow       | Operational       | 4,894        | Oct-20       | Oct-21           | 6                   | 6                             | 12                     | \$547                                | \$513        | \$103                     | \$616    |  |  |
| 26                     | Y        | 18" line from the Parks at Wilson Creek to Lakes at Mustang Ranch  | Low Plane         | High        | Fire flow       | Operational       | 6,504        | Oct-21       | Jul-23           | 9                   | 12                            | 21                     | \$2,939                              | \$2,924      | \$568                     | \$3,492  |  |  |
| 27                     | U        | 12" line from Preston Road to Morgan Lake Estates                  | High Plane        | High        | Fire flow       | Operational       | 6,504        | Oct-21       | Oct-22           | 6                   | 6                             | 12                     | \$342                                | \$330        | \$66                      | \$396    |  |  |
|                        |          |  |                   |             |                 |                   |              |              |                  |                     | Total 2017 OPCC: \$94,141,277 |                        | Total Forecasted OPCC: \$103,716,670 |              |                           |          |  |  |





Table 2: Development Driven Projects

| Project Identification |          |   |                   |             |                 |                   |              | Schedule     |                  |                     |                   | 2017 Costs (\$1,000)   |              | Forecasted Cost (\$1,000) |                        |         |              |  |
|------------------------|----------|---|-------------------|-------------|-----------------|-------------------|--------------|--------------|------------------|---------------------|-------------------|------------------------|--------------|---------------------------|------------------------|---------|--------------|--|
| Project                | Grouping | Description   | Location          | Flexibility | Primary Trigger | Secondary Trigger | Trigger Lots | Trigger Date | Project Complete | Engineering /Design | Bld/ Construction | Total Project Duration | OPCC         | Construction              | Professional Services  | OPCC    |              |  |
| 1                      | B        | Downtown EST shutdown and SCADA switchover                | Low Plane         | Low         | Regulatory      | Capacity          | 0            | Feb-17       | Mar-17           | 0                   | 1                 | 1                      | 0            | \$0                       | \$0                    | \$0     |              |  |
| 2                      | A        | Capacity upgrades to CRPS and installation of 4 new pumps | CRPS              | Low         | Capacity        | Regulatory        | 0            | Feb-17       | Jul-18           | 8                   | 9                 | 17                     | \$6,305      | \$5,412                   | \$1,051                | \$6,463 |              |  |
| 3                      | H        | Capacity upgrades to DTPS and installation of 3 new pumps | DTPS              | Low         | Capacity        | Operational       | 0            | Feb-17       | Jul-18           | 8                   | 9                 | 17                     | \$5,173      | \$4,440                   | \$862                  | \$5,302 |              |  |
| 4                      | E        | 12" line and valves to switch LPP to HPP                  | Low to High Plane | Low         | Regulatory      | Fire Flow         | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$171        | \$147                     | \$29                   | \$176   |              |  |
| 5                      | F        | 18", 30" and 36" line along Celina Road from CRPS         | CRPS; Low Plane   | Low         | Capacity        | Regulatory        | 0            | Oct-17       | Oct-19           | 12                  | 12                | 24                     | \$7,939      | \$7,019                   | \$1,363                | \$8,382 |              |  |
| 6                      | G        | 24" and 30" lines to Downtown GST                         | Low Plane         | Low         | Capacity        | Regulatory        | 0            | Oct-17       | Oct-19           | 12                  | 12                | 24                     | \$5,588      | \$4,940                   | \$959                  | \$5,899 |              |  |
| 7                      | J        | 24" and 30" discharge lines from DTPS                     | High Plane        | Low         | Capacity        | Regulatory        | 0            | Oct-17       | Oct-19           | 12                  | 12                | 24                     | \$3,490      | \$3,086                   | \$599                  | \$3,685 |              |  |
| 8                      | D        | 18" and 24" line to Morgan Lake area                      | High Plane        | Medium      | Regulatory      | Capacity          | 1,526        | Oct-18       | Jul-20           | 9                   | 12                | 21                     | \$4,730      | \$4,307                   | \$836                  | \$5,143 |              |  |
| 9                      | C        | 18" line east of Light Farm EST along Cypress Creek Way   | Low Plane         | Medium      | Capacity        | Regulatory        | 1,526        | Oct-18       | May-19           | 3                   | 4                 | 7                      | \$312        | \$276                     | \$54                   | \$329   |              |  |
| 10                     | L        | Additional capacity upgrades to CRPS                      | CRPS; Low Plane   | Low         | Capacity        | Regulatory        | 1,526        | Oct-18       | Oct-19           | 6                   | 6                 | 12                     | \$536        | \$474                     | \$95                   | \$568   |              |  |
| 11                     | Z        | New 6 MG GST at CRPS                                      | Low Plane         | Medium      | Operational     | Capacity          | 1,526        | Oct-18       | Jul-20           | 9                   | 12                | 21                     | \$7,619      | \$6,938                   | \$1,347                | \$8,285 |              |  |
| 12                     | R        | Additional capacity upgrades to DTPS                      | DTPS              | Low         | Capacity        | Regulatory        | 2,370        | Oct-18       | Oct-19           | 6                   | 6                 | 12                     | \$556        | \$491                     | \$98                   | \$589   |              |  |
| 16                     | M        | 12" line along Settlers Ridge                             | Low Plane         | Medium      | Capacity        | Regulatory        | 3,233        | Oct-19       | Oct-21           | 12                  | 12                | 24                     | \$3,308      | \$3,102                   | \$602                  | \$3,705 |              |  |
| 17                     | Q        | Additional capacity upgrades to CRPS                      | CRPS              | Low         | Capacity        | Regulatory        | 3,233        | Oct-19       | Oct-20           | 6                   | 6                 | 12                     | \$556        | \$506                     | \$101                  | \$607   |              |  |
| 18                     | AC       | 2020 5-year Master Plan                                   | System Wide       | Medium      | Operational     | City-directed     | 4,894        | Oct-20       | Oct-21           | 12                  | 0                 | 12                     | \$200        | \$0                       | \$225                  | \$225   |              |  |
| 19                     | P        | 8", 12", and 18" line from Morgan Lake to DC Ranch        | High Plane        | Medium      | Capacity        | Regulatory        | 3,233        | Oct-19       | Jul-21           | 9                   | 12                | 21                     | \$5,119      | \$4,802                   | \$932                  | \$5,734 |              |  |
| 20                     | O        | 24" line to increase capacity in the Low Pressure Plane   | Low Plane         | Medium      | Capacity        | Regulatory        | 4,894        | Oct-20       | Jul-22           | 9                   | 12                | 21                     | \$5,340      | \$5,158                   | \$1,002                | \$6,160 |              |  |
|                        |          |   |                   |             |                 |                   |              |              |                  |                     | Total 2017 OPCC:  |                        | \$56,940,272 |                           | Total Forecasted OPCC: |         | \$61,253,106 |  |

Table 3: Operational Projects

| Project Identification |          |                                      |             |             |                 |                   | Schedule     |              |                  |                     |                   | 2017 Costs (\$1,000)   |          | Forecasted Cost (\$1,000) |                       |                        |  |              |  |
|------------------------|----------|--------------------------------------|-------------|-------------|-----------------|-------------------|--------------|--------------|------------------|---------------------|-------------------|------------------------|----------|---------------------------|-----------------------|------------------------|--|--------------|--|
| Project                | Grouping | Description                          | Location    | Flexibility | Primary Trigger | Secondary Trigger | Trigger Lots | Trigger Date | Project Complete | Engineering /Design | Bld/ Construction | Total Project Duration | OPCC     | Construction              | Professional Services | OPCC                   |  |              |  |
| 13                     |          | Decommission Morgan Lake facilities  | High Plane  | Medium      | Operational     | Capacity          | 2,226        | Mar-19       | Aug-19           | 2                   | 3                 | 5                      | \$145    | \$127                     | \$27                  | \$154                  |  |              |  |
| 14                     | AB       | SCADA improvements                   | System Wide | High        | Operational     | None              | 3,233        | Oct-19       | Apr-21           | 9                   | 9                 | 18                     | \$312    | \$262,254                 | \$79                  | \$341                  |  |              |  |
| 15                     | AA       | 8" line upgrades in Downtown area    | System Wide | Medium      | Operational     | City-directed     | 3,233        | Oct-19       | Oct-21           | 12                  | 12                | 24                     | \$22,390 | \$21,000                  | \$4,078               | \$25,078               |  |              |  |
| 22                     | S        | 16" and 24" lines along Legacy Drive | Low Plane   | High        | Operational     | Capacity          | 6,504        | Oct-21       | Jul-23           | 9                   | 12                | 21                     | \$3,353  | \$3,336                   | \$648                 | \$3,984                |  |              |  |
|                        |          |                                      |             |             |                 |                   |              |              |                  |                     |                   | Total 2017 OPCC:       |          | \$26,199,874              |                       | Total Forecasted OPCC: |  | \$29,556,640 |  |




Table 4: Fire Flow Projects

| Project Identification |          |  |            | Schedule    |                 |                   |              |              |                  |                     |                   | 2017 Costs (\$1,000)   |              | Forecasted Cost (\$1,000) |                       |              |
|------------------------|----------|--|------------|-------------|-----------------|-------------------|--------------|--------------|------------------|---------------------|-------------------|------------------------|--------------|---------------------------|-----------------------|--------------|
| Project                | Grouping | Description  | Location   | Flexibility | Primary Trigger | Secondary Trigger | Trigger Lots | Trigger Date | Project Complete | Engineering /Design | Bld/ Construction | Total Project Duration | OPCC         | Construction              | Professional Services | OPCC         |
| 21                     | T        | 18" and 24" lines along Hwy. 455                                   | High Plane | High        | Fire flow       | Operational       | 4,894        | Oct-20       | Jul-22           | 9                   | 12                | 21                     | \$2,387      | \$2,306                   | \$448                 | \$2,754      |
| 23                     | X        | 8" and 24" lines to connect Preston Lakes to Preston Road Corridor | Low Plane  | High        | Fire flow       | Operational       | 6,504        | Oct-21       | Jul-23           | 9                   | 12                | 21                     | \$4,175      | \$4,154                   | \$807                 | \$4,961      |
| 24                     | W        | 8" and 12" line along E. Malone St. and Preston Road               | High Plane | High        | Fire flow       | Operational       | 4,894        | Oct-20       | Oct-21           | 6                   | 6                 | 12                     | \$612        | \$574                     | \$115                 | \$689        |
| 25                     | V        | 8" lines in the Low Pressure Plane                                 | Low Plane  | High        | Fire flow       | Operational       | 4,894        | Oct-20       | Oct-21           | 6                   | 6                 | 12                     | \$547        | \$512,928                 | \$103                 | \$616        |
| 26                     | Y        | 18" line from the Parks at Wilson Creek to Lakes at Mustang Ranch  | Low Plane  | High        | Fire flow       | Operational       | 6,504        | Oct-21       | Jul-23           | 9                   | 12                | 21                     | \$2,939      | \$2,924                   | \$568                 | \$3,492      |
| 27                     | U        | 12" line from Preston Road to Morgan Lake Estates                  | High Plane | High        | Fire flow       | Operational       | 6,504        | Oct-21       | Oct-22           | 6                   | 6                 | 12                     | \$342        | \$330                     | \$66                  | \$396        |
| Total 2017 OPCC:       |          |  |            |             |                 |                   |              |              |                  |                     |                   |                        | \$11,001,131 | Total Forecasted OPCC:    |                       | \$12,906,925 |





## Proposed 5 Year Water CIP Schedule





## Project 1: Water Group B Capital Improvements

### Project Description

This project includes decommissioning the DT EST and switching SCADA control of the CRPS from the DT EST Level to the Light Farms EST Level. No decommissioning costs are included with this project.

### Justification

The DT EST has reached the end of its useful life and is in need of rehabilitation. In addition, the increasing water demand through the system is resulting in rapid turnover times within the DT EST. However, the Light Farms EST does not turn over because the CRPS is controlled off of the DT EST level. Decommissioning the DT EST and controlling the CRPS using the Light Farms EST level will allow the hydraulic grade line in the Light Farms EST to be raised to 835 ft, increasing pressures in the Low Pressure Plane and providing more stable system operation.

### Unintended Consequences

Water quality will be improved in the Light Farm EST due to increased turnover. The Low Pressure Plane will have slightly less total storage, but will gain operational elevated storage due to the ability to increase the HGL in the Light Farms EST.

### Special Considerations

It will be important to confirm that SCADA control has successfully been switched to control the CRPS based on the Light Farms EST level.

### Potential Alternatives

The DT EST can be demolished or removed at the City's discretion. If the City prefers to maintain the use of the DT EST, extensive rehabilitation and an elevation control valve would be required.

| Project Identification          |                             |                                   |
|---------------------------------|-----------------------------|-----------------------------------|
| Number:                         | 1                           |                                   |
| Location:                       | Low Plane                   |                                   |
| Flexibility:                    | Low                         |                                   |
| Schedule                        |                             |                                   |
| Primary Trigger:                | Regulatory                  |                                   |
| Secondary Trigger:              | Capacity                    |                                   |
| Trigger # of Lots Constructed:  | 0                           |                                   |
| Trigger Date:                   | Feb-2017                    |                                   |
| Project Complete:               | Mar-2017                    |                                   |
| Project Implementation (Months) |                             |                                   |
| Engineering/Design:             | 0                           |                                   |
| Bid/Construction:               | 1                           |                                   |
| Total Project Duration:         | 1                           |                                   |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted Costs<br>(\$ Millions) |
| Construction                    | \$0.00                      | \$0.00                            |
| Professional Services           | \$0.00                      | \$0.00                            |
| Total Project Cost              | \$0.00                      | \$0.00                            |

| Group B                                    |      |          |      |
|--|------|----------|------|
| Description                                | Unit | Quantity | Cost |
| Downtown EST shutdown and SCADA switchover | LS   | 1        | \$ - |
| Subtotal Test                              |      |          | \$ - |
| Contingency (20%)                          |      |          | \$ - |
| Appurtenances (electrical, SCADA, etc.)    |      |          | \$ - |
| Professional Services                      |      |          | \$ - |
| OPCC                                       |      |          | \$ - |





Project 1 – Photographs



Figure 1-1: Existing DT EST, to be decommissioned



## Project 2: Water Group A Capital Improvements

### Project Description

This project consists of capacity upgrades to the CRPS, including installation of four new pumps and the associated piping. Preliminary sizing indicates that each pump should be sized to provide 3,800 gpm at 240 ft of head. Variable frequency drives will be provided for the new pumps to allow efficient operation during periods of lower demands. Three existing spare pump spaces will be utilized, and one existing pump will be demolished during this project so that the existing CRPS footprint will not have to be expanded. Design of the CRPS improvements will also include evaluation of existing chemical storage and feed equipment. Recommendations for these improvements will be made during final design, but placeholder costs have been included below. Design of backup power up to firm capacity to increase the reliability of the City's primary drinking water source will be included. However, this item may be bid as an additive alternative.

### Justification

Figure 1-2 shows the expected pumping capacity needed for the CRPS through 2022. The current system's firm capacity would require approximately 2,700 gpm of additional pumping capacity by the midpoint of 2017, which would increase to approximately 6,900 gpm by 2019 if no new pumps were added. These improvements will provide pumping capacity of 1.3 times the maximum day demand until late 2019, allowing equalization of diurnal peaks without completely draining the elevated storage tanks.

### Unintended Consequences

The increased horsepower of the pumps and associated electrical gear may require specialized electrical maintenance providers. In addition, maintenance will increase due to the addition of new pumps and increased pump sizing.

### Special Considerations

Due to rapid growth in Celina and the limited capacity of the existing elevated storage tanks and pumps, design should start in 2017 so that these improvements can be in place as soon as possible.

### Potential Alternatives

None Identified.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 2                           |                                      |
| Location:                       | CRPS                        |                                      |
| Flexibility:                    | Low                         |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Regulatory                  |                                      |
| Trigger # of Lots Constructed:  | 0                           |                                      |
| Trigger Date:                   | Feb-2017                    |                                      |
| Project Complete:               | Jul-2018                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 8                           |                                      |
| Bid/Construction:               | 9                           |                                      |
| Total Project Duration:         | 17                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$5.25                      | \$5.41                               |
| Professional Services           | \$1.05                      | \$1.05                               |
| Total Project Cost              | \$6.31                      | \$6.46                               |






Figure 1-2: Comparison of Proposed CRPS Capacity and Demand

| Group A                                 |                          |                    |                     |
|---|--------------------------|--------------------|---------------------|
| Description                             | Unit                     | Quantity           | Cost                |
| Demo existing pump                      | LS                       | 1                  | \$ 10,000           |
| Pump with motor                         | EA                       | 4                  | \$ 450,000          |
| Electrical                              | LS                       | 1                  | \$ 100,000          |
| VFDs                                    | EA                       | 4                  | \$ 320,000          |
| Valves and fittings                     | LS                       | 1                  | \$ 100,000          |
| Interconnecting pipes                   | LS                       | 1                  | \$ 75,000           |
| Chemical feed improvements              | LS                       | 1                  | \$ 750,000          |
| Firm capacity backup power              | LS                       | 1                  | \$ 1,305,085        |
| <b>Diameter (in.)</b>                   | <b>Unit Cost (\$/LF)</b> | <b>Length (ft)</b> | <b>Cost</b>         |
| 36                                      | 683                      | 110                | \$ 75,174           |
| <b>Subtotal</b>                         |                          |                    | <b>\$ 3,185,259</b> |
| <b>Contractor's OH&amp;P (18%)</b>      |                          |                    | <b>\$ 573,347</b>   |
| <b>Miscellaneous (SCADA, etc., 20%)</b> |                          |                    | <b>\$ 620,017</b>   |
| <b>Contingency (20%)</b>                |                          |                    | <b>\$ 875,725</b>   |
| <b>Professional Services</b>            |                          |                    | <b>\$ 1,050,869</b> |
| <b>OPCC</b>                             |                          |                    | <b>\$ 6,305,217</b> |





Project 2 Schematic







### Project 3: Water Group H Capital Improvements

#### Project Description

This project consists of capacity upgrades to the DTPS, including installation of three new pumps and the associated piping. The three smallest existing pumps will be demolished during this project so that the existing DTPS footprint will not have to be expanded. Design of the DTPS improvements will also include evaluation of existing chemical storage and feed equipment. Recommendations for these improvements will be made during final design, but placeholder costs have been included below. Design of backup power up to firm capacity to increase the reliability of the High Pressure Plane's primary drinking water source will be included. However, this item may be bid as an additive alternative.

This project also includes installation of new fill and draw lines for the GST. The new fill line will include a level control valve, which will allow automatic filling of the GST. It is preferred to maintain the existing 12-inch fill and draw lines for redundancy. The existing clearwell is unused and will be demolished during this project.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 3                           |                                      |
| Location:                       | DTPS                        |                                      |
| Flexibility:                    | Low                         |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Operational                 |                                      |
| Trigger # of Lots Constructed:  | 0                           |                                      |
| Trigger Date:                   | Feb-2017                    |                                      |
| Project Complete:               | Jul-2018                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 8                           |                                      |
| Bid/Construction:               | 9                           |                                      |
| Total Project Duration:         | 17                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$4.31                      | \$4.44                               |
| Professional Services           | \$0.86                      | \$0.86                               |
| Total Project Cost              | \$5.17                      | \$5.30                               |

#### Justification

Figure 1-3 shows the expected pumping capacity needed for the DTPS through 2022. The current system's firm capacity would require approximately 1,400 gpm of additional pumping capacity by the midpoint of 2017, which would increase to approximately 3,600 gpm by 2019 if no new pumps were added. These improvements will provide pumping capacity of 1.3 times the High Pressure Plane's maximum day demand until late 2019, allowing equalization of diurnal peaks without completely draining the elevated storage tanks.

#### Unintended Consequences

The increased horsepower of the pumps and associated electrical gear may require specialized electrical maintenance providers. In addition, maintenance will increase due to the addition of new pumps and increased pump sizing.

#### Special Considerations

Due to rapid growth in Celina and the limited capacity of the existing elevated storage tanks and pumps, design should start in 2017 so that these improvements can be in place as soon as possible.

#### Potential Alternatives

None identified.




Figure 1-3: Comparison of High Pressure Plane Demands and Proposed Pump Capacity

| Group H                          |      |          |              |
|----------------------------------|------|----------|--------------|
| Description                      | Unit | Quantity | Cost         |
| Demo existing pumps              | LS   | 1        | \$ 25,000    |
| Demo existing clearwell          | LS   | 1        | \$ 50,000    |
| New pumps with motors            | EA   | 3        | \$ 337,500   |
| Electrical                       | LS   | 1        | \$ 100,000   |
| VFDs                             | EA   | 3        | \$ 240,000   |
| Valves and fittings              | LS   | 1        | \$ 100,000   |
| Interconnecting pipes            | LS   | 1        | \$ 150,000   |
| Level control valve with vault   | LS   | 1        | \$ 35,000    |
| Chemical feed improvements       | LS   | 1        | \$ 750,000   |
| Firm capacity backup power       | LS   | 1        | \$ 815,700   |
| Subtotal                         |      |          | \$ 2,603,200 |
| Contractor's OH&P (18%)          |      |          | \$ 468,576   |
| Miscellaneous (SCADA, etc., 20%) |      |          | \$ 520,640   |
| Contingency (20%)                |      |          | \$ 718,483   |
| Professional Services            |      |          | \$ 862,180   |
| OPCC                             |      |          | \$ 5,173,079 |





Project 3 Schematic:







## Project 4: Group E Facilities Improvements

### Project Description

This project includes distribution system modifications to switch portions of downtown from the Low Pressure Plane to the High Pressure Plane. Changes include opening and closing existing isolation valves as well as installing a pressure reducing valve.

### Justification

Low pressure areas have been identified in this portion of downtown. These improvements will result in adequate pressures and fire flows in the area, by utilizing the higher pressures available in the High Pressure Plane. The new pressure reducing valves will allow controlled increase in pressures to limit any adverse impacts of the new system pressure on the existing infrastructure.

### Unintended Consequences

None identified.

### Special Considerations

This change should occur after the DTPS improvements to minimize adjustments to the new pressure reducing valves.

### Potential Alternatives

None identified.


| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 4                           |                                      |
| Location:                       | Low to High Plane           |                                      |
| Flexibility:                    | Low                         |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Regulatory                  |                                      |
| Secondary Trigger:              | Fire Flow                   |                                      |
| Trigger # of Lots Constructed:  | 0                           |                                      |
| Trigger Date:                   | Oct-2017                    |                                      |
| Project Complete:               | Oct-2018                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 6                           |                                      |
| Bid/Construction:               | 6                           |                                      |
| Total Project Duration:         | 12                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$0.14                      | \$0.15                               |
| Professional Services           | \$0.03                      | \$0.03                               |
| Total Project Cost              | \$0.17                      | \$0.18                               |

| Group E                            |                      |                      |                 |            |
|------------------------------------|----------------------|----------------------|-----------------|------------|
| Description                        |                      | Unit                 | Quantity        | Cost       |
| Pressure reducing valve with vault |                      | LS                   | 1               | \$ 25,000  |
| Bored pipe installation            |                      | LS                   | 1               | \$ 50,000  |
| Diameter<br>(in.)                  | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost       |
| 12                                 | Pipe installation    | 180                  | 100             | \$ 18,000  |
|                                    | General improvements | 75                   |                 | \$ 7,500   |
| Subtotal                           |                      |                      |                 | \$ 100,500 |
| Contractor's OH&P (18%)            |                      |                      |                 | \$ 18,090  |
| Contingency (20%)                  |                      |                      |                 | \$ 23,718  |
| Professional Services              |                      |                      |                 | \$ 28,462  |
| OPCC                               |                      |                      |                 | \$ 170,770 |





Project 4 Schematic







## Project 5: Water Group F Capital Improvements

### Project Description

This project includes installation of a new discharge main along Celina Road from the CRPS to connect to an existing 12-inch line running along the railroad tracks, and a future 30-inch line which will be installed as part of Water Group G Improvements. The new 30-inch discharge main will parallel an existing 18-inch line, which will stay in service.

### Justification

This project will reduce system discharge head for the CRPS pumps, resulting in improved pump capacities. This also improves system hydraulics in the downtown area. This pipeline is needed to supply projected flows during this five-year planning period.

### Unintended Consequences

None identified.

### Special Considerations

TxDOT coordination and right-of-way/easement acquisition will likely be necessary for this pipeline. Portions of the alignment from Celina Road to CR 55 may need to be revised during detailed design based on right-of-way and roadway alignments.

Although a 12" line is being installed for the Glen Crossing subdivision, the entire length of the new pipeline must be 30" to keep pipe velocities within the acceptable range.

### Potential Alternatives

The existing 18-inch line could be decommissioned, which would require the proposed 30-inch discharge main to be upsized.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 5                           |                                      |
| Location:                       | CRPS; Low Plane             |                                      |
| Flexibility:                    | Low                         |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Regulatory                  |                                      |
| Trigger # of Lots Constructed:  | 0                           |                                      |
| Trigger Date:                   | Oct-2017                    |                                      |
| Project Complete:               | Oct-2019                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 12                          |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 24                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$6.62                      | \$7.02                               |
| Professional Services           | \$1.32                      | \$1.36                               |
| Total Project Cost              | \$7.94                      | \$8.38                               |






**City of Celina Water and Wastewater System Improvements  
Water Capital Improvements Plan**

| Group F                  |                      |                      |                 |              |
|--------------------------|----------------------|----------------------|-----------------|--------------|
| Diameter<br>(in.)        | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost         |
| 30                       | Pipe installation    | 300                  | 14,520          | \$ 4,356,000 |
|                          | General improvements | 50                   |                 | \$ 726,000   |
| 18                       | Pipe installation    | 225                  | 75              | \$ 16,875    |
|                          | General improvements | 40                   |                 | \$ 3,000     |
| 36                       | Pipe installation    | 375                  | 350             | \$ 131,250   |
|                          | General improvements | 50                   |                 | \$ 17,500    |
| Subtotal                 |                      |                      |                 | \$ 5,250,625 |
| Valves and Fittings (5%) |                      |                      |                 | \$ 262,531   |
| Contingency (20%)        |                      |                      |                 | \$ 1,102,631 |
| Professional Services    |                      |                      |                 | \$ 1,323,158 |
| OPCC                     |                      |                      |                 | \$ 7,938,945 |





Project 5 Schematic







## Project 6: Water Group G Capital Improvements

### Project Description

This project includes addition of a new pipeline running north northeast from the connection point of Water Group F to the DT GST location.

### Justification

This pipeline will result in increased capacity and adequate pressures in the distribution system, specifically for the DTPS area. This project is necessary to provide adequate flows to the High Pressure Plane.

### Unintended Consequences

None identified.

### Special Considerations

The alignment follows the existing 12-inch alignment along the railroad tracks; therefore, additional easements may be necessary to accommodate this pipe. In addition, a bored pipe installation will be needed to cross the railroad tracks near Ash Street.

### Potential Alternatives

None identified.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 6                           |                                      |
| Location:                       | Low Plane                   |                                      |
| Flexibility:                    | Low                         |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Regulatory                  |                                      |
| Trigger # of Lots Constructed:  | 0                           |                                      |
| Trigger Date:                   | Oct-2017                    |                                      |
| Project Complete:               | Oct-2019                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 12                          |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 24                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$4.66                      | \$4.94                               |
| Professional Services           | \$0.93                      | \$0.96                               |
| Total Project Cost              | \$5.59                      | \$5.90                               |

| Group G                  |                      |                   |              |              |
|--------------------------|----------------------|-------------------|--------------|--------------|
| Diameter (in.)           | Description          | Unit Cost (\$/LF) | Length (ft.) | Cost         |
| 30                       | Pipe installation    | 300               | 5,509        | \$ 3,162,166 |
|                          | General improvements | 50                |              | \$ 275,450   |
| 24                       | Pipe installation    | 275               | 523          | \$ 143,825   |
|                          | General improvements | 75                |              | \$ 39,225    |
| Description              |                      | Unit              | Quantity     | Cost         |
| Bored pipe installation  |                      | LS                | 1            | \$ 75,000    |
| Subtotal                 |                      |                   |              | \$ 3,695,666 |
| Valves and Fittings (5%) |                      |                   |              | \$ 184,783   |
| Contingency (20%)        |                      |                   |              | \$ 776,090   |
| Professional Services    |                      |                   |              | \$ 931,308   |
| OPCC                     |                      |                   |              | \$ 5,587,847 |





Project 6 Schematic







## Project 7: Water Group J Capital Improvements

### Project Description

This project consists of installation of new 24- and 30-inch discharge lines from the DTPS connecting to the existing 12-inch line running parallel to Preston Road.

### Justification

This project will provide pipeline capacity needed for projected flows to the High Pressure Plane.

### Unintended Consequences

No unintended consequences are foreseen by the implementation of this project.

### Special Considerations

TxDOT coordination and right-of-way/easement acquisition will likely be necessary for this pipeline. In addition, a bored pipe installation will be needed to cross Preston Road.

### Potential Alternatives

None identified.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 7                           |                                      |
| Location:                       | High Plane                  |                                      |
| Flexibility:                    | Low                         |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Regulatory                  |                                      |
| Trigger # of Lots Constructed:  | 0                           |                                      |
| Trigger Date:                   | Oct-2017                    |                                      |
| Project Complete:               | Oct-2019                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 12                          |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 24                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$2.91                      | \$3.09                               |
| Professional Services           | \$0.58                      | \$0.60                               |
| Total Project Cost              | \$3.49                      | \$3.68                               |

| Group J                   |                      |                   |              |              |
|---------------------------|----------------------|-------------------|--------------|--------------|
| Diameter (in.)            | Description          | Unit Cost (\$/LF) | Length (ft.) | Cost         |
| 24                        | Pipe installation    | 275               | 2,501        | \$ 687,775   |
|                           | General improvements | 50                |              | \$ 125,050   |
| 30                        | Pipe installation    | 300               | 3,259        | \$ 977,700   |
|                           | General improvements | 50                |              | \$ 162,950   |
| Description               |                      | Unit              | Quantity     | Cost         |
| Bored pipe installation   |                      | LS                | 1            | \$ 250,000   |
| Subtotal                  |                      |                   |              | \$ 2,203,475 |
| Valves and Fittings (10%) |                      |                   |              | \$ 220,348   |
| Contingency (20%)         |                      |                   |              | \$ 484,765   |
| Professional Services     |                      |                   |              | \$ 581,717   |
| OPCC                      |                      |                   |              | \$ 3,490,304 |





Project 7 Schematic







## Project 8: Water Group D Capital Improvements

### Project Description

This project includes installation of new pipelines from north of the SE EST to the Morgan Lake area and within the Morgan Lake area.

### Justification

This project provides necessary looping from the SE EST area to the northern portion of the distribution system. The looping is needed to meet projected flow demands for the area to ensure minimum pressures are met.

### Unintended Consequences

None identified.

### Special Considerations

TxDOT coordination may be required for alignments along CR 94 and CR 97. Appropriate placement of the water line along CR 97 (i.e., east vs. west of the roadway) will be determined during detailed design.

### Potential Alternatives

None identified.


| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 8                           |                                      |
| Location:                       | High Plane                  |                                      |
| Flexibility:                    | Medium                      |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Regulatory                  |                                      |
| Secondary Trigger:              | Capacity                    |                                      |
| Trigger # of Lots Constructed:  | 1,526                       |                                      |
| Trigger Date:                   | Oct-2018                    |                                      |
| Project Complete:               | Jul-2020                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 9                           |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 21                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$3.94                      | \$4.31                               |
| Professional Services           | \$0.79                      | \$0.84                               |
| Total Project Cost              | \$4.73                      | \$5.14                               |

| Group D                  |                      |                      |                 |              |
|--------------------------|----------------------|----------------------|-----------------|--------------|
| Diameter<br>(in.)        | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost         |
| 24                       | Pipe installation    | 275                  | 7,892           | \$ 2,170,300 |
|                          | General improvements | 50                   |                 | \$ 394,600   |
| 18                       | Pipe installation    | 225                  | 1,182           | \$ 265,950   |
|                          | General improvements | 40                   |                 | \$ 47,280    |
| Description              | Unit                 | Quantity             | Cost            |              |
| Bored pipe installation  | LS                   | 1                    | \$ 250,000      |              |
| Subtotal                 |                      |                      | \$ 3,128,130    |              |
| Valves and Fittings (5%) |                      |                      | \$ 156,407      |              |
| Contingency (20%)        |                      |                      | \$ 656,907      |              |
| Professional Services    |                      |                      | \$ 788,289      |              |
| OPCC                     |                      |                      | \$ 4,729,733    |              |





Project 8 Schematic







## Project 9: Water Group C Capital Improvements

### Project Description

This project includes installation of a new 18-inch pipeline east of the Light Farms EST. This will connect to larger pipelines in the area.

### Justification

This line will be installed parallel to an existing 8-inch line that currently acts as a bottleneck, resulting in increased capacity and maintenance of adequate system pressures throughout this area.

### Unintended Consequences

None identified.

### Special Considerations

Detailed design should incorporate ongoing development in the proposed alignment.

### Potential Alternatives

None identified.


| Project Identification          |                             |                                   |
|---------------------------------|-----------------------------|-----------------------------------|
| Number:                         | 9                           |                                   |
| Location:                       | Low Plane                   |                                   |
| Flexibility:                    | Medium                      |                                   |
| Schedule                        |                             |                                   |
| Primary Trigger:                | Capacity                    |                                   |
| Secondary Trigger:              | Regulatory                  |                                   |
| Trigger # of Lots Constructed:  | 1,526                       |                                   |
| Trigger Date:                   | Oct-2018                    |                                   |
| Project Complete:               | May-2019                    |                                   |
| Project Implementation (Months) |                             |                                   |
| Engineering/Design:             | 3                           |                                   |
| Bid/Construction:               | 4                           |                                   |
| Total Project Duration:         | 7                           |                                   |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted Costs<br>(\$ Millions) |
| Construction                    | \$0.26                      | \$0.28                            |
| Professional Services           | \$0.05                      | \$0.05                            |
| Total Project Cost              | \$0.31                      | \$0.33                            |

| Group C                   |                      |                      |                 |            |
|---------------------------|----------------------|----------------------|-----------------|------------|
| Diameter<br>(in.)         | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost       |
| 18                        | Pipe installation    | 225                  | 606             | \$ 136,350 |
|                           | General improvements | 100                  |                 | \$ 60,600  |
| Subtotal                  |                      |                      |                 | \$ 196,950 |
| Valves and Fittings (10%) |                      |                      |                 | \$ 19,695  |
| Contingency (20%)         |                      |                      |                 | \$ 43,329  |
| Professional Services     |                      |                      |                 | \$ 51,995  |
| OPCC                      |                      |                      |                 | \$ 311,969 |





Project 9 Schematic







## Project 10: Water Group L Capital Improvements

### Project Description

This project includes installation of a new pump and a new 36-inch common suction line for the CRPS. Preliminary sizing indicates that the new pump should be sized to provide 3,800 gpm at 240 ft of head. A variable frequency drive will be provided for the new pump to allow efficient operation during periods of lower demands. One existing pump will be demolished during this project so that the existing CRPS footprint will not have to be expanded.

### Justification

Figure 1-4 shows the expected pumping capacity needed for the CRPS through 2022. Demand will surpass the added firm capacity provided by the Group A improvements in 2019, leading to a deficiency in firm pumping capacity of approximately 1,100 gpm by 2020. The new pump would be installed in late 2019 and would provide pumping capacity of 1.3 times the maximum day demand through 2020, allowing equalization of diurnal peaks without completely draining the elevated storage tanks.

### Unintended Consequences

Although this project will not change the number of pumps in the CRPS, maintenance cost will increase due to the increased pump sizing.

### Special Considerations

Based on projected growth, this project must begin in 2018 so that the new pump can be installed in late 2019.

### Potential Alternatives

None identified.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 10                          |                                      |
| Location:                       | CRPS; Low Plane             |                                      |
| Flexibility:                    | Low                         |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Regulatory                  |                                      |
| Trigger # of Lots Constructed:  | 1,526                       |                                      |
| Trigger Date:                   | Oct-2018                    |                                      |
| Project Complete:               | Oct-2019                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 6                           |                                      |
| Bid/Construction:               | 6                           |                                      |
| Total Project Duration:         | 12                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$0.45                      | \$0.47                               |
| Professional Services           | \$0.09                      | \$0.09                               |
| Total Project Cost              | \$0.54                      | \$0.57                               |




Figure 1-4: Comparison of Proposed CRPS Capacity and Demand

| Group L                          |      |          |            |
|----------------------------------|------|----------|------------|
| Description                      | Unit | Quantity | Cost       |
| Demo existing pump               | LS   | 1        | \$ 10,000  |
| Pump with motor                  | EA   | 1        | \$ 112,500 |
| Electrical                       | LS   | 1        | \$ 20,000  |
| VFDs                             | EA   | 1        | \$ 80,000  |
| Valves and fittings              | LS   | 1        | \$ 35,000  |
| Interconnecting pipes            | LS   | 1        | \$ 25,000  |
| Subtotal                         |      |          | \$ 282,500 |
| Contractor's OH&P (18%)          |      |          | \$ 50,850  |
| Miscellaneous (SCADA, etc., 20%) |      |          | \$ 56,500  |
| Contingency (20%)                |      |          | \$ 56,500  |
| Professional Services            |      |          | \$ 89,270  |
| OPCC                             |      |          | \$ 535,620 |





Project 10 Schematic







## Project 11: Water Group Z Capital Improvements

### Project Description

This project consists of installation of a new, 6 MG ground storage tank and associated site improvements at the CRPS. Associated site improvements include bypass piping, SCADA level sensor, and security fencing.

### Justification

Ground storage at this location provides a buffer against interruptions in Upper Trinity Regional Water District (UTRWD) water supply. Current demand projections identify a significant reduction in the amount of detention time provided by the existing GST, as shown in Figure 1-5Figure 1-4. This project will provide 16 hours of emergency storage at average day conditions in 2022 in the event of temporary water supply interruptions from UTRWD and provide additional system storage to meet TCEQ requirements. The new tank will provide steady operation of the high service pumps at the UTRWD, and will allow bypass of the existing GST during maintenance activities.

### Unintended Consequences

This tank could lead to increased water age if flow demands do not increase as projected; however, this can be mitigated by controlling the level in the tank.

### Special Considerations

This project will require geotechnical evaluation of the site prior to tank design. Coordination with UTRWD will be needed for tank level SCADA integration.

### Potential Alternatives

A smaller GST could be constructed; however, a smaller tank would result in increased unit costs and would reduce the amount of time the system could operate without the UTRWD supply.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 11                          |                                      |
| Location:                       | Low Plane                   |                                      |
| Flexibility:                    | Medium                      |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Operational                 |                                      |
| Secondary Trigger:              | Capacity                    |                                      |
| Trigger # of Lots Constructed:  | 1,526                       |                                      |
| Trigger Date:                   | Oct-2018                    |                                      |
| Project Complete:               | Jul-2020                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 9                           |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 21                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$6.35                      | \$6.94                               |
| Professional Services           | \$1.27                      | \$1.35                               |
| Total Project Cost              | \$7.62                      | \$8.29                               |







Figure 1-5: Comparison of Available Ground Storage at the CRPS with and without the 6 MG GST

| Group Z                            |      |          |              |
|------------------------------------|------|----------|--------------|
| Description                        | Unit | Quantity | Cost         |
| New 6 MG GST                       | LS   | 1        | \$ 2,668,750 |
| Piping and appurtenances           | LS   | 1        | \$ 150,000   |
| Work area and subgrade preparation | LS   | 1        | \$ 900,000   |
| City standard brick fencing        | LS   | 1        | \$ 450,000   |
| Subtotal                           |      |          | \$ 4,168,750 |
| Contractor's OH&P (18%)            |      |          | \$ 750,375   |
| Miscellaneous (SCADA, etc., 10%)   |      |          | \$ 371,875   |
| Contingency (20%)                  |      |          | \$ 1,058,200 |
| Professional Services              |      |          | \$ 1,269,840 |
| OPCC                               |      |          | \$ 7,619,040 |





Project 11 Schematic







## Project 12: Water Group R Capital Improvements

### Project Description

This project will include installation of a new pump and associated piping at the DTPS. Preliminary sizing indicates that the new pump should be sized to provide 3,200 gpm at 240 ft of head. A variable frequency drive will be provided for the new pump to allow efficient operation during periods of lower demands. The existing Pump 4 will be demolished during this project so that the existing DTPS footprint will not have to be expanded.

### Justification

Figure 1-6 shows the expected pumping capacity needed for the DTPS through 2022. Demand will surpass the added firm capacity provided by the Group H improvements in 2019, leading to a deficiency in firm pumping capacity of approximately 2,800 gpm by 2022. The new pump would be installed in late 2019 and would provide pumping capacity of 1.3 times the High Pressure Plane's maximum day demand through 2022, allowing equalization of diurnal peaks without completely draining the elevated storage tanks.

### Unintended Consequences

None identified.

### Special Considerations

This project must begin in 2018 and be in place by June 2020.

### Potential Alternatives

None identified.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 12                          |                                      |
| Location:                       | DTPS                        |                                      |
| Flexibility:                    | Low                         |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Regulatory                  |                                      |
| Trigger # of Lots Constructed:  | 2,370                       |                                      |
| Trigger Date:                   | Oct-2018                    |                                      |
| Project Complete:               | Oct-2019                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 6                           |                                      |
| Bid/Construction:               | 6                           |                                      |
| Total Project Duration:         | 12                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$0.46                      | \$0.49                               |
| Professional Services           | \$0.09                      | \$0.10                               |
| Total Project Cost              | \$0.56                      | \$0.59                               |




Figure 1-6: Comparison of High Pressure Plane Demands and Proposed Pump Capacity

| Group R                          |      |          |            |
|----------------------------------|------|----------|------------|
| Description                      | Unit | Quantity | Cost       |
| Pump with motor                  | EA   | 1        | \$ 112,500 |
| Electrical                       | LS   | 1        | \$ 20,000  |
| VFDs                             | EA   | 1        | \$ 80,000  |
| Valves and fittings              | LS   | 1        | \$ 35,000  |
| Interconnecting pipes            | LS   | 1        | \$ 25,000  |
| Subtotal                         |      |          | \$ 272,500 |
| Contractor's OH&P (18%)          |      |          | \$ 49,050  |
| Miscellaneous (SCADA, etc., 20%) |      |          | \$ 64,310  |
| Contingency (20%)                |      |          | \$ 77,172  |
| Professional Services            |      |          | \$ 92,606  |
| OPCC                             |      |          | \$ 555,638 |





## **Project 13: Water Group K Capital Improvements**

### **Project Description**

This project includes decommissioning of the Morgan Lake facilities and an engineering study to evaluate the condition and future use of existing groundwater supply facilities.

### **Justification**

Construction of the new SE EST will raise the High Pressure Plane HGL by 15 ft, which will render the Morgan Lake facilities inoperable.

### **Unintended Consequences**

None identified.

### **Special Considerations**

The new SE EST must be online prior to decommissioning Morgan Lake facilities. If the groundwater well is to remain online, additional rehabilitation may be required for the well and chemical disinfection facilities.

### **Potential Alternatives**

These facilities could remain in use if an elevation control valve was installed; however, this would result in high water age in the existing tank. Additional alternatives for groundwater facilities will be evaluated as part of the engineering study.

| Project Identification          |                             |                                   |
|---------------------------------|-----------------------------|-----------------------------------|
| Number:                         | 13                          |                                   |
| Location:                       | High Plane                  |                                   |
| Flexibility:                    | Medium                      |                                   |
| Schedule                        |                             |                                   |
| Primary Trigger:                | Operational                 |                                   |
| Secondary Trigger:              | Capacity                    |                                   |
| Trigger # of Lots Constructed:  | 2,226                       |                                   |
| Trigger Date:                   | Mar-2019                    |                                   |
| Project Complete:               | Aug-2019                    |                                   |
| Project Implementation (Months) |                             |                                   |
| Engineering/Design:             | 2                           |                                   |
| Bid/Construction:               | 3                           |                                   |
| Total Project Duration:         | 5                           |                                   |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted Costs<br>(\$ Millions) |
| Construction                    | \$0.12                      | \$0.13                            |
| Professional Services           | \$0.03                      | \$0.03                            |
| Total Project Cost              | \$0.15                      | \$0.15                            |

| Group K                       |      |          |            |
|-------------------------------|------|----------|------------|
| Description                   | Unit | Quantity | Cost       |
| Tank decommissioning and demo | LS   | 1        | \$ 100,000 |
| Subtotal                      |      |          | \$ 100,000 |
| Contingency (20%)             |      |          | \$ 20,000  |
| Engineering Study             |      |          | \$ 25,000  |
| OPCC                          |      |          | \$ 145,000 |



Project 13 Photographs



Figure 1-7: Existing Morgan Lake facilities, to be decommissioned





## Project 14: Water Group AB Capital Improvements

### Project Description

This project will consist of SCADA improvements identified in the SCADA Master Plan.

### Justification

This project will implement the improvements identified in the SCADA Master Plan and will improve consistency, reliability, and automation of operations.

### Unintended Consequences

None identified.

### Special Considerations

None identified.

### Potential Alternatives

Alternatives will be identified during development of the SCADA Master Plan.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 14                          |                                      |
| Location:                       | System Wide                 |                                      |
| Flexibility:                    | High                        |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Operational                 |                                      |
| Secondary Trigger:              | None                        |                                      |
| Trigger # of Lots Constructed:  | 3,233                       |                                      |
| Trigger Date:                   | Oct-2019                    |                                      |
| Project Complete:               | Apr-2021                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 9                           |                                      |
| Bid/Construction:               | 9                           |                                      |
| Total Project Duration:         | 18                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$0.24                      | \$0.26                               |
| Professional Services           | \$0.07                      | \$0.08                               |
| Total Project Cost              | \$0.31                      | \$0.34                               |

| Group AB                                |      |          |            |
|---|------|----------|------------|
| Description                             | Unit | Quantity | Cost       |
| SCADA improvements - water & wastewater | 1    | LS       | \$ 200,000 |
| Subtotal                                |      |          | \$ 200,000 |
| Contingency (20%)                       |      |          | \$ 40,000  |
| Engineering/Integration                 |      |          | \$ 72,000  |
| OPCC                                    |      |          | \$ 312,000 |



## Project 15: Water Group AA Capital Improvements

### Project Description

This project consists of upsizing all existing lines less than 8-inch in diameter in the Downtown area, in both the High and Low Pressure Planes.

### Justification

These improvements will minimize head loss in the system and prepare the older portion of the system for growth.

### Unintended Consequences

None identified.

### Special Considerations

This project will take place in a developed area. As such, bored pipe installations and significant pavement, sidewalk, and landscaping repairs may be required.

### Potential Alternatives

These lines may be replaced during concurrent street rehabilitation projects, which will significantly reduce the overall general improvements cost.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 15                          |                                      |
| Location:                       | System Wide                 |                                      |
| Flexibility:                    | Medium                      |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Operational                 |                                      |
| Secondary Trigger:              | City-directed               |                                      |
| Trigger # of Lots Constructed:  | 3,233                       |                                      |
| Trigger Date:                   | Oct-2019                    |                                      |
| Project Complete:               | Oct-2021                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 12                          |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 24                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$18.66                     | \$21.00                              |
| Professional Services           | \$3.73                      | \$4.08                               |
| Total Project Cost              | \$22.39                     | \$25.08                              |

| Group AA                 |                      |                      |                 |               |
|--------------------------|----------------------|----------------------|-----------------|---------------|
| Diameter<br>(in.)        | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost          |
| 8                        | Pipe installation    | 150                  | 58,933          | \$ 8,839,950  |
|                          | General improvements | 100                  |                 | \$ 5,893,300  |
| Details                  |                      | Unit Cost            | Quantity        | Cost          |
| Bored pipe installation  |                      | LS                   | 1               | \$ 75,000     |
| Subtotal                 |                      |                      |                 | \$ 14,808,250 |
| Valves and Fittings (5%) |                      |                      |                 | \$ 740,413    |
| Contingency (20%)        |                      |                      |                 | \$ 3,109,733  |
| Professional Services    |                      |                      |                 | \$ 3,731,679  |
| OPCC                     |                      |                      |                 | \$ 22,390,074 |





Project 15 Schematic







## Project 16: Water Group M Capital Improvements

### Project Description

This project includes installation of a 12-inch pipeline around the northwest side of downtown.

### Justification

This project will alleviate low pressures in the areas of the Low Pressure Plane and will result in increased capacity.

### Unintended Consequences

None identified.

### Special Considerations

The proposed pipeline will run alongside a future thoroughfare, and coordination of easements will be required. Also, two bored piping installations will be required.

### Potential Alternatives

None identified.


| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 16                          |                                      |
| Location:                       | Low Plane                   |                                      |
| Flexibility:                    | Medium                      |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Regulatory                  |                                      |
| Trigger # of Lots Constructed:  | 3,233                       |                                      |
| Trigger Date:                   | Oct-2019                    |                                      |
| Project Complete:               | Oct-2021                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 12                          |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 24                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$2.76                      | \$3.10                               |
| Professional Services           | \$0.55                      | \$0.60                               |
| Total Project Cost              | \$3.31                      | \$3.70                               |

| Group M                  |                      |                      |                 |              |
|--------------------------|----------------------|----------------------|-----------------|--------------|
| Diameter<br>(in.)        | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost         |
| 12                       | Pipe installation    | 180                  | 9,489           | \$ 1,708,020 |
|                          | General improvements | 40                   |                 | \$ 379,560   |
| Description              |                      | Unit                 | Quantity        | Cost         |
| Bored pipe installation  |                      | LS                   | 1               | \$ 100,000   |
| Subtotal                 |                      |                      |                 | \$ 2,187,580 |
| Valves and Fittings (5%) |                      |                      |                 | \$ 109,379   |
| Contingency (20%)        |                      |                      |                 | \$ 459,392   |
| Professional Services    |                      |                      |                 | \$ 551,270   |
| OPCC                     |                      |                      |                 | \$ 3,307,621 |





Project 16 Schematic







## Project 17: Water Group Q Capital Improvements

### Project Description

This project consists of installation of one additional pump in the CRPS. Preliminary sizing indicates that the new pump should be sized to provide 3,800 gpm at 240 ft of head. A variable frequency drive will be provided for the new pump to allow efficient operation during periods of lower demands. One existing pump will be demolished during this project so that the existing CRPS footprint will not have to be expanded.

### Justification

Figure 1-8 shows the expected pumping capacity needed for the CRPS through 2022. Demand will surpass the added firm capacity provided by the Group A and L improvements in 2021, and would lead to a deficiency in pumping capacity of approximately 2,300 gpm by 2022. These improvements will provide pumping capacity of 1.3x maximum day demand through 2022, allowing equalization of diurnal peaks without completely draining the elevated storage tanks.

### Unintended Consequences

Although this project will not change the number of pumps in the CRPS, maintenance costs will increase due to the increased pump sizing.

### Special Considerations

This project must begin in 2019 and be in place by August 2020 in preparation for the projected flows.

### Potential Alternatives

None identified.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 17                          |                                      |
| Location:                       | CRPS                        |                                      |
| Flexibility:                    | Low                         |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Regulatory                  |                                      |
| Trigger # of Lots Constructed:  | 3,233                       |                                      |
| Trigger Date:                   | Oct-2019                    |                                      |
| Project Complete:               | Oct-2020                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 6                           |                                      |
| Bid/Construction:               | 6                           |                                      |
| Total Project Duration:         | 12                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$0.46                      | \$0.51                               |
| Professional Services           | \$0.09                      | \$0.10                               |
| Total Project Cost              | \$0.56                      | \$0.61                               |






Figure 1-8: Comparison of Proposed CRPS Capacity and Demand

| Group Q                          |      |          |            |
|----------------------------------|------|----------|------------|
| Description                      | Unit | Quantity | Cost       |
| Pump with motor                  | EA   | 1        | \$ 112,500 |
| Electrical                       | LS   | 1        | \$ 20,000  |
| VFDs                             | EA   | 1        | \$ 80,000  |
| Valves and fittings              | LS   | 1        | \$ 35,000  |
| Interconnecting pipes            | LS   | 1        | \$ 25,000  |
| Subtotal                         |      |          | \$ 272,500 |
| Contractor's OH&P (18%)          |      |          | \$ 49,050  |
| Miscellaneous (SCADA, etc., 20%) |      |          | \$ 64,310  |
| Contingency (20%)                |      |          | \$ 77,172  |
| Professional Services            |      |          | \$ 92,606  |
| OPCC                             |      |          | \$ 555,638 |



## Project 18: Water Group AC Capital Improvements

### Project Description

This project consists of development of a new 5-year Master Plan with associated hydraulic model updates and revisions needed for water quality monitoring plans such as the RTCR sample siting plan, and Nitrification Action Plan.

### Justification

This master plan will evaluate future growth and lead to development of a new CIP.

### Unintended Consequences

None identified.

### Special Considerations

None identified.

### Potential Alternatives

None identified.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 18                          |                                      |
| Location:                       | System Wide                 |                                      |
| Flexibility:                    | Medium                      |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Operational                 |                                      |
| Secondary Trigger:              | City-directed               |                                      |
| Trigger # of Lots Constructed:  | 4,894                       |                                      |
| Trigger Date:                   | Oct-2020                    |                                      |
| Project Complete:               | Oct-2021                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 12                          |                                      |
| Bid/Construction:               | 0                           |                                      |
| Total Project Duration:         | 12                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$0.00                      | \$0.00                               |
| Professional Services           | \$0.20                      | \$0.23                               |
| Total Project Cost              | \$0.20                      | \$0.23                               |

| Group AC                |      |          |            |
|-------------------------|------|----------|------------|
| Description             | Unit | Quantity | Cost       |
| 2020 5-Year Master Plan | LS   | 1        | \$ 200,000 |
|                         |      | OPCC     | \$ 200,000 |





## Project 19: Water Group P Capital Improvements

### Project Description

This project adds an 18-inch line from Morgan Lake running north to connect to the DC Ranch development and west to Preston Road.

### Justification

This project will result in increased capacity and improve pressures in the distribution system. This pipeline is needed to supply projected flows during this five-year planning period.

### Unintended Consequences

None identified.

### Special Considerations

This project will require completion of Water Group D improvements prior to the connection at Morgan Lake. Coordination and right-of-way/easement acquisition will likely be necessary for this pipeline.

### Potential Alternatives

None identified.


| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 19                          |                                      |
| Location:                       | High Plane                  |                                      |
| Flexibility:                    | Medium                      |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Regulatory                  |                                      |
| Trigger # of Lots Constructed:  | 3,233                       |                                      |
| Trigger Date:                   | Oct-2019                    |                                      |
| Project Complete:               | Jul-2021                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 9                           |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 21                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$4.27                      | \$4.80                               |
| Professional Services           | \$0.85                      | \$0.93                               |
| Total Project Cost              | \$5.12                      | \$5.73                               |

| Group P                  |                      |                      |                 |              |
|--------------------------|----------------------|----------------------|-----------------|--------------|
| Diameter<br>(in.)        | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost         |
| 18                       | Pipe installation    | 225                  | 11,453          | \$ 2,576,925 |
|                          | General improvements | 40                   |                 | \$ 458,120   |
| 12                       | Pipe installation    | 180                  | 267             | \$ 48,060    |
|                          | General improvements | 25                   |                 | \$ 6,675     |
| 8                        | Pipe installation    | 150                  | 384             | \$ 57,600    |
|                          | General improvements | 100                  |                 | \$ 38,400    |
| Description              |                      | Unit                 | Quantity        | Cost         |
| Bored pipe installation  |                      | LS                   | 1               | \$ 200,000   |
| Subtotal                 |                      |                      |                 | \$ 3,385,780 |
| Valves and Fittings (5%) |                      |                      |                 | \$ 169,289   |
| Contingency (20%)        |                      |                      |                 | \$ 711,014   |
| Professional Services    |                      |                      |                 | \$ 853,217   |
| OPCC                     |                      |                      |                 | \$ 5,119,299 |





Project 19 Schematic







## Project 20: Water Group O Capital Improvements

### Project Description

This project will add a 24-inch line parallel to the railroad tracks in the Low Pressure Plane. The new 24-inch line will parallel an existing 12-inch line, which will stay in service.

### Justification

This project will result in increased capacity and improve pressures in this area of the distribution system. This pipeline is needed to supply projected flows during this five-year planning period.

### Unintended Consequences

None identified.

### Special Considerations

None identified.

### Potential Alternatives

The existing 12-inch line could be decommissioned; however, this would require the proposed 24-inch line to be upsized.


| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 20                          |                                      |
| Location:                       | Low Plane                   |                                      |
| Flexibility:                    | Medium                      |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Regulatory                  |                                      |
| Trigger # of Lots Constructed:  | 4,894                       |                                      |
| Trigger Date:                   | Oct-2020                    |                                      |
| Project Complete:               | Jul-2022                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 9                           |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 21                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$4.45                      | \$5.16                               |
| Professional Services           | \$0.89                      | \$1.00                               |
| Total Project Cost              | \$5.34                      | \$6.16                               |

| Group O                  |                      |                      |                 |              |
|--------------------------|----------------------|----------------------|-----------------|--------------|
| Diameter<br>(in.)        | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost         |
| 24                       | Pipe installation    | 275                  | 10,866          | \$ 2,988,150 |
|                          | General improvements | 50                   |                 | \$ 543,300   |
| Subtotal                 |                      |                      |                 | \$ 3,531,450 |
| Valves and Fittings (5%) |                      |                      |                 | \$ 176,573   |
| Contingency (20%)        |                      |                      |                 | \$ 741,605   |
| Professional Services    |                      |                      |                 | \$ 889,925   |
| OPCC                     |                      |                      |                 | \$ 5,339,552 |





Project 20 Schematic







## Project 21: Water Group T Capital Improvements

### Project Description

This project includes installation of 18- and 24-inch pipelines along Hwy. 455 to the east of CVS.

### Justification

This project will remove a dead end, improving fire flow in this area.

### Unintended Consequences

The additional looping would improve water quality in this area.

### Special Considerations

The proposed pipeline will run alongside a future thoroughfare, and coordination of easements will be required. Also, a bored pipe installation will be required to connect to the existing 6-inch pipe serving the Preston 455 development

### Potential Alternatives

None identified.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 21                          |                                      |
| Location:                       | High Plane                  |                                      |
| Flexibility:                    | High                        |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Fire flow                   |                                      |
| Secondary Trigger:              | Operational                 |                                      |
| Trigger # of Lots Constructed:  | 4,894                       |                                      |
| Trigger Date:                   | Oct-2020                    |                                      |
| Project Complete:               | Jul-2022                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 9                           |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 21                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$1.99                      | \$2.31                               |
| Professional Services           | \$0.40                      | \$0.45                               |
| Total Project Cost              | \$2.39                      | \$2.75                               |

| Group T                  |                      |                   |              |              |
|--------------------------|----------------------|-------------------|--------------|--------------|
| Diameter (in.)           | Description          | Unit Cost (\$/LF) | Length (ft.) | Cost         |
| 18                       | Pipe installation    | 225               | 3,930        | \$ 884,250   |
|                          | General improvements | 40                |              | \$ 157,200   |
| 24                       | Pipe installation    | 275               | 1422         | \$ 391,050   |
|                          | General improvements | 50                |              | \$ 71,100    |
| Description              |                      | Unit Cost         | Quantity     | Cost         |
| Bored pipe installation  |                      | LS                | 1            | \$ 75,000    |
| Subtotal                 |                      |                   |              | \$ 1,578,600 |
| Valves and Fittings (5%) |                      |                   |              | \$ 78,930    |
| Contingency (20%)        |                      |                   |              | \$ 331,506   |
| Professional Services    |                      |                   |              | \$ 397,807   |
| OPCC                     |                      |                   |              | \$ 2,386,843 |





Project 21 Schematic







## Project 22: Water Group S Capital Improvements

### Project Description

This project includes installation of 18- and 24-inch lines along Legacy Drive.

### Justification

These lines provide a redundant feed to the Creeks of Legacy development with additional looping, improving pressure and flow rates in this area.

### Unintended Consequences

The additional looping will improve water quality in this area.

### Special Considerations

These improvements will require installation of a 24-inch pipe that is part of an ongoing project for the northern connection. TxDOT coordination and right-of-way/easement acquisition will likely be necessary for this pipeline.

### Potential Alternatives

None identified.


| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 22                          |                                      |
| Location:                       | Low Plane                   |                                      |
| Flexibility:                    | High                        |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Operational                 |                                      |
| Secondary Trigger:              | Capacity                    |                                      |
| Trigger # of Lots Constructed:  | 6,504                       |                                      |
| Trigger Date:                   | Oct-2021                    |                                      |
| Project Complete:               | Jul-2023                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 9                           |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 21                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$2.79                      | \$3.34                               |
| Professional Services           | \$0.56                      | \$0.65                               |
| Total Project Cost              | \$3.35                      | \$3.98                               |

| Group S                  |                      |                      |                 |              |
|--------------------------|----------------------|----------------------|-----------------|--------------|
| Diameter<br>(in.)        | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost         |
| 18                       | Pipe installation    | 225                  | 3,364           | \$ 756,900   |
|                          | General improvements | 40                   |                 | \$ 134,560   |
| 24                       | Pipe installation    | 275                  | 4,080           | \$ 1,122,000 |
|                          | General improvements | 50                   |                 | \$ 204,000   |
| Subtotal                 |                      |                      |                 | \$ 2,217,460 |
| Valves and Fittings (5%) |                      |                      |                 | \$ 110,873   |
| Contingency (20%)        |                      |                      |                 | \$ 465,667   |
| Professional Services    |                      |                      |                 | \$ 558,800   |
| OPCC                     |                      |                      |                 | \$ 3,352,800 |





Project 22 Schematic







## Project 23: Water Group X Capital Improvements

### Project Description

This project consists of installation of new 8-inch and 24-inch pipelines to connect the Preston Lakes development to the existing 18-inch line along the Preston Road Corridor. Another 8-inch line will be installed within the development to provide looping.

### Justification

This project will result in added looping for improved fire flow in the Preston Lakes development.

### Unintended Consequences

The added looping will improve water quality in this area.

### Special Considerations

TxDOT coordination and right-of-way/easement acquisition will likely be necessary for this pipeline. In addition, a bored pipe installation will be needed to cross the railroad tracks.

### Potential Alternatives

None identified.


| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 23                          |                                      |
| Location:                       | Low Plane                   |                                      |
| Flexibility:                    | High                        |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Fire flow                   |                                      |
| Secondary Trigger:              | Operational                 |                                      |
| Trigger # of Lots Constructed:  | 6,504                       |                                      |
| Trigger Date:                   | Oct-2021                    |                                      |
| Project Complete:               | Jul-2023                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 9                           |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 21                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$3.48                      | \$4.15                               |
| Professional Services           | \$0.70                      | \$0.81                               |
| Total Project Cost              | \$4.17                      | \$4.96                               |

| Group X                  |                      |                   |              |              |
|--------------------------|----------------------|-------------------|--------------|--------------|
| Diameter (in.)           | Description          | Unit Cost (\$/LF) | Length (ft.) | Cost         |
| 8                        | Pipe installation    | 150               | 3,600        | \$ 540,000   |
|                          | General improvements | 40                |              | \$ 144,000   |
| 24                       | Pipe installation    | 275               | 6,160        | \$ 1,694,000 |
|                          | General improvements | 50                |              | \$ 308,000   |
| Description              |                      | Unit Cost         | Quantity     | Cost         |
| Bored pipe installation  |                      | LS                | 1            | \$ 75,000    |
| Subtotal                 |                      |                   |              | \$ 2,761,000 |
| Valves and Fittings (5%) |                      |                   |              | \$ 138,050   |
| Contingency (20%)        |                      |                   |              | \$ 579,810   |
| Professional Services    |                      |                   |              | \$ 695,772   |
| OPCC                     |                      |                   |              | \$ 4,174,632 |





Project 23 Schematic







## Project 24: Water Group W Capital Improvements

### Project Description

This project includes installation of an 8-inch line along E Malone St. and a 12-inch line along Preston Road to create looping near downtown in the High Pressure Plane.

### Justification

These improvements are designed to improve looping, and thus fire flow.

### Unintended Consequences

The added looping will improve water quality in this area.

### Special Considerations

TxDOT coordination and right-of-way/easement acquisition will likely be necessary for this pipeline.

### Potential Alternatives

None identified.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 24                          |                                      |
| Location:                       | High Plane                  |                                      |
| Flexibility:                    | High                        |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Fire flow                   |                                      |
| Secondary Trigger:              | Operational                 |                                      |
| Trigger # of Lots Constructed:  | 4,894                       |                                      |
| Trigger Date:                   | Oct-2020                    |                                      |
| Project Complete:               | Oct-2021                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 6                           |                                      |
| Bid/Construction:               | 6                           |                                      |
| Total Project Duration:         | 12                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$0.51                      | \$0.57                               |
| Professional Services           | \$0.10                      | \$0.11                               |
| Total Project Cost              | \$0.61                      | \$0.69                               |

| Group W                  |                      |                      |                 |            |
|--------------------------|----------------------|----------------------|-----------------|------------|
| Diameter<br>(in.)        | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost       |
| 8                        | Pipe installation    | 150                  | 1,685           | \$ 252,750 |
|                          | General improvements | 75                   |                 | \$ 126,375 |
| 12                       | Pipe installation    | 180                  | 101             | \$ 18,180  |
|                          | General improvements | 75                   |                 | \$ 7,575   |
| Subtotal                 |                      |                      |                 | \$ 404,880 |
| Valves and Fittings (5%) |                      |                      |                 | \$ 20,244  |
| Contingency (20%)        |                      |                      |                 | \$ 85,025  |
| Professional Services    |                      |                      |                 | \$ 102,030 |
| OPCC                     |                      |                      |                 | \$ 612,179 |





Project 24 Schematic







## Project 25: Water Group V Capital Improvements

### Project Description

This project consists of installation of three 8-inch pipelines in the Low Pressure Plane near downtown.

### Justification

The new 8-inch lines will connect existing pipelines, providing looping to improve fire flow and water quality in the area.

### Unintended Consequences

None identified.

### Special Considerations

A bored pipeline installation and easement coordination will be required.

### Potential Alternatives

None identified.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 25                          |                                      |
| Location:                       | Low Plane                   |                                      |
| Flexibility:                    | High                        |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Fire flow                   |                                      |
| Secondary Trigger:              | Operational                 |                                      |
| Trigger # of Lots Constructed:  | 4,894                       |                                      |
| Trigger Date:                   | Oct-2020                    |                                      |
| Project Complete:               | Oct-2021                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 6                           |                                      |
| Bid/Construction:               | 6                           |                                      |
| Total Project Duration:         | 12                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$0.46                      | \$0.51                               |
| Professional Services           | \$0.09                      | \$0.10                               |
| Total Project Cost              | \$0.55                      | \$0.62                               |

| Group V                 |                      |                      |                           |            |
|-------------------------|----------------------|----------------------|---------------------------|------------|
| Diameter<br>(in.)       | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.)           | Cost       |
| 8                       | Pipe installation    | 150                  | 1,181                     | \$ 177,150 |
|                         | General improvements | 100                  |                           | \$ 118,100 |
| Description             | Unit Cost            | Quantity             | Cost                      |            |
| Bored pipe installation | LS                   | 1                    | \$ 50,000                 |            |
|                         |                      |                      | Subtotal                  | \$ 345,250 |
|                         |                      |                      | Valves and Fittings (10%) | \$ 34,525  |
|                         |                      |                      | Contingency (20%)         | \$ 75,955  |
|                         |                      |                      | Professional Services     | \$ 91,146  |
|                         |                      |                      | OPCC                      | \$ 546,876 |





Project 25 Schematic







## Project 26: Water Group Y Capital Improvements

### Project Description

This project adds an 18-inch line to serve the Lakes at Mustang Ranch development from the Parks at Wilson Creek development.

### Justification

These improvements will improve fire flows in the Lakes at Mustang Ranch development.

### Unintended Consequences

This project would also result in improved water quality in the area.

### Special Considerations

Construction of lines for the Parks at Wilson Creek by developers will be required before this project can be implemented. The proposed pipeline will run alongside a future thoroughfare, and coordination of easements will be required.

### Potential Alternatives

None identified.


| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 26                          |                                      |
| Location:                       | Low Plane                   |                                      |
| Flexibility:                    | High                        |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Fire flow                   |                                      |
| Secondary Trigger:              | Operational                 |                                      |
| Trigger # of Lots Constructed:  | 6,504                       |                                      |
| Trigger Date:                   | Oct-2021                    |                                      |
| Project Complete:               | Jul-2023                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 9                           |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 21                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$2.45                      | \$2.92                               |
| Professional Services           | \$0.49                      | \$0.57                               |
| Total Project Cost              | \$2.94                      | \$3.49                               |

| Group Y                  |                      |                   |              |              |
|--------------------------|----------------------|-------------------|--------------|--------------|
| Diameter (in.)           | Description          | Unit Cost (\$/LF) | Length (ft.) | Cost         |
| 18                       | Pipe installation    | 225               | 7,052        | \$ 1,586,700 |
|                          | General improvements | 40                |              | \$ 282,080   |
| Details                  |                      | Unit Cost         | Quantity     | Cost         |
| Bored pipe installation  |                      | LS                | 1            | \$ 75,000    |
| Subtotal                 |                      |                   |              | \$ 1,943,780 |
| Valves and Fittings (5%) |                      |                   |              | \$ 97,189    |
| Contingency (20%)        |                      |                   |              | \$ 408,194   |
| Professional Services    |                      |                   |              | \$ 489,833   |
| OPCC                     |                      |                   |              | \$ 2,938,995 |





Project 26 Schematic







## Project 27: Water Group U Capital Improvements

### Project Description

This project includes installation of a new 12-inch line from Preston Road to feed the Morgan Lake Estates development.

### Justification

This project will improve fire flows in the Morgan Lake Estates development.

### Unintended Consequences

This project would also result in improved water quality in the area.

### Special Considerations

This pipeline would run through currently undeveloped land and would require coordination of easements. Also, detailed design should incorporate ongoing development in the proposed alignment.

### Potential Alternatives

None identified.

| Project Identification          |                             |                                   |
|---------------------------------|-----------------------------|-----------------------------------|
| Number:                         | 27                          |                                   |
| Location:                       | High Plane                  |                                   |
| Flexibility:                    | High                        |                                   |
| Schedule                        |                             |                                   |
| Primary Trigger:                | Fire flow                   |                                   |
| Secondary Trigger:              | Operational                 |                                   |
| Trigger # of Lots Constructed:  | 6,504                       |                                   |
| Trigger Date:                   | Oct-2021                    |                                   |
| Project Complete:               | Oct-2022                    |                                   |
| Project Implementation (Months) |                             |                                   |
| Engineering/Design:             | 6                           |                                   |
| Bid/Construction:               | 6                           |                                   |
| Total Project Duration:         | 12                          |                                   |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted Costs<br>(\$ Millions) |
| Construction                    | \$0.28                      | \$0.33                            |
| Professional Services           | \$0.06                      | \$0.07                            |
| Total Project Cost              | \$0.34                      | \$0.40                            |

| Group U                  |                      |                      |                 |            |
|--------------------------|----------------------|----------------------|-----------------|------------|
| Diameter<br>(in.)        | Description          | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost       |
| 12                       | Pipe installation    | 180                  | 886             | \$ 159,480 |
|                          | General improvements | 75                   |                 | \$ 66,450  |
| Subtotal                 |                      |                      |                 | \$ 225,930 |
| Valves and Fittings (5%) |                      |                      |                 | \$ 11,297  |
| Contingency (20%)        |                      |                      |                 | \$ 47,445  |
| Professional Services    |                      |                      |                 | \$ 56,934  |
| OPCC                     |                      |                      |                 | \$ 341,606 |





Project 27 Schematic





# **Appendix D**


---

## **Water & Wastewater System Improvements Wastewater Capital Improvements Plan**

**City of Celina, Texas**



Prepared by:



3010 Gaylord Parkway  
Suite 190  
Frisco, TX 75034

September 2017

Garver Project No.: 16088050

City of Celina 6-1b



## **1.0 Executive Summary**

This Wastewater Capital Improvements Plan utilizes the model criteria and simulations detailed in the Water and Wastewater Modeling Improvements, discussions with City staff, and the results of the 2016 Inflow and Infiltration (I/I) Study prepared by Pacheco Koch to develop proposed projects from the recommended improvements. These improvements are identified for a 5-year planning horizon (2017 – 2022 fiscal years).

A summary of all proposed project costs and schedules is displayed on Page 5, while a proposed schedule is located on Page 6. Project descriptions are in order based on priority ranking following this summary.

### **1.1 Identification and Ranking**

Each project will be initiated based on one or more of the triggers described below:

#### **1.1.1 Capacity**

This trigger is activated if a section or segment of sewer is unable to provide the modeled flow during peak demand or is at risk of producing overflows. Trigger limits are a function of the level of expected surcharging and the available cover (i.e., the depth of the pipe).

#### **1.1.2 Condition**

This trigger would be activated if a known condition requires repair or replacement of the infrastructure. City staff input was also solicited to identify known pipe condition issues in the collection system.

#### **1.1.3 Operational**

Operational triggers are activated when an improvement will provided increased operational benefit, such as decommissioning aged infrastructure. This includes any lift station decommissioning.

#### **1.1.4 City-Directed**

This trigger is activated when City staff have indicated that items will be replaced, are required as part of upcoming policy changes, or are needed to manage growth.

In addition to these triggers, areas of the collection system not meeting minimum slope requirements were identified. Replacement of these existing lines was not recommended unless the minimum slope issue resulted in a previously listed trigger.

After triggers were identified, a modeling analysis was conducted to determine the most cost-effective improvements to implement, i.e., improvements that provided the maximum impact with minimal infrastructure for near and long term system growth. Alphabetical project groupings were developed in localized areas to address the identified improvements. The groupings were divided into three levels of flexibility based on the current condition of the need and anticipated criticality of the improvements. All groupings were then ranked numerically, with the most critical, lowest flexibility needs given the highest priority. For capacity triggers, higher priority was given to pipes with significant surcharging and low cover. The resultant project identification and rankings list provides the City with a directory of the most critical needs addressed in near-term and long-term projects.





## 1.2 Cost Development

Costs estimates were prepared for each individual project, based on industry standards and the 2017 bidding environment. These costs are an estimate, and should be re-evaluated as each project nears the trigger date. Each project has the following costs associated with the total OPCC:

### 1.2.1 Construction Costs

This cost is the estimated cost once the project has been designed and is ready for the bid phase to begin. It represents a combination of the estimated total construction costs, and includes a 20% contingency.

### 1.2.2 Engineering

The engineering estimate includes all professional services currently anticipated to bid each project, including survey, deed research (as needed), preliminary, and final design of all improvements. This cost is 20% of the estimated construction costs, including contingency. This does not include construction observation or start-up services.

### 1.2.3 Bid Item Descriptions:

Costs for manhole rehabilitation and pipeline installation costs were developed from a combination of neighboring city water and sewer project bid tabulations. Forecasted project costs are the estimated engineering and construction costs escalated by 3 percent per year to account for inflation between development of the OPCC and the midpoint of design and construction, respectively. Individual bid items are described as follows.

*General Improvements:* Anticipated sitework, backfill, erosion control, rehabilitation of existing structures, testing, easements, and contractor overhead costs.

*Pipe Installation:* Material and labor costs associated with SDR-35 pipe installation by open cut on a linear footage basis, depending on line size. Cost for all manholes, assuming an even distribution of 4-foot and 5-foot diameter installations is included, along with all sewer service wye connections and connections to existing pipes or manholes. The unit cost is also a function of pipe depth, where installations greater than or equal to 20-feet deep are subject to a 1.5x multiplier to reflect additional manhole, trench safety, and site improvements needed for the larger trenches required.

*Bored Pipe Installation:* Anticipated material, labor, sitework, backfill, erosion control, testing, easements, and contractor overhead costs associated with installation of pipe where boring is required, on a lump sum basis. These costs are dependent on line size, length and depth of boring, and location of boring.

A summary of pipe installation costs and typical associated general improvements is provided in Table 1. Table 1 was produced as a function of pipe diameter size and used to calculate the unit costs in \$/LF. General improvements were assessed on a site-specific basis and the typical unit costs were used unless a specific project required a greater amount of general improvements. The unit price increase for pipe installation at a depth greater than 20-feet utilizing the 1.5x multiplier is also included in the table.




Table 1 - Pipe Installation Costs

| Size (in.) | \$/LF     |                      |          |                                 |                       |
|------------|-----------|----------------------|----------|---------------------------------|-----------------------|
|            | PVC Sewer | General Improvements | Subtotal | Unit Price Increase, Depth >20' | Depth >20' Unit Price |
| 6          | \$125.0   | \$75.0               | \$200.0  | \$62.5                          | \$187.5               |
| 8          | \$150.0   | \$75.0               | \$225.0  | \$75.0                          | \$225.0               |
| 10         | \$185.0   | \$75.0               | \$260.0  | \$92.5                          | \$277.5               |
| 12         | \$195.0   | \$75.0               | \$270.0  | \$97.5                          | \$292.5               |
| 15         | \$210.0   | \$100.0              | \$310.0  | \$105.0                         | \$315.0               |
| 18         | \$225.0   | \$100.0              | \$325.0  | \$112.5                         | \$337.5               |
| 21         | \$240.0   | \$100.0              | \$340.0  | \$120.0                         | \$360.0               |
| 24         | \$255.0   | \$100.0              | \$355.0  | \$127.5                         | \$382.5               |
| 27         | \$270.0   | \$100.0              | \$370.0  | \$135.0                         | \$405.0               |
| 30         | \$275.0   | \$150.0              | \$425.0  | \$137.5                         | \$412.5               |
| 36         | \$305.0   | \$150.0              | \$455.0  | \$152.5                         | \$457.5               |
| 42         | \$335.0   | \$150.0              | \$485.0  | \$167.5                         | \$502.5               |
| 48         | \$365.0   | \$150.0              | \$515.0  | \$182.5                         | \$547.5               |
| 54         | \$400.0   | \$150.0              | \$550.0  | \$200.0                         | \$600.0               |
| 60         | \$425.0   | \$150.0              | \$575.0  | \$212.5                         | \$637.5               |

A proposed spending schedule is provided in . Further refinement of this spending schedule and associated project trigger dates is possible, depending upon City funding timeframes.





Proposed Spending Schedule for Wastewater CIP

### 1.3 Project Descriptions and Legend

A summary of Wastewater CIP items, schedule, and individual project descriptions and schematics are provided in the following pages.



Table 2: Wastewater CIP Summary

| Project Identification |          |  |          |             | Schedule        |                   |              |              |                  |                     |                   |                        | Forecasted Cost (\$1,000) |                        |                       |              |
|------------------------|----------|--|----------|-------------|-----------------|-------------------|--------------|--------------|------------------|---------------------|-------------------|------------------------|---------------------------|------------------------|-----------------------|--------------|
| Project                | Grouping | Description  | Location | Flexibility | Primary Trigger | Secondary Trigger | Trigger Lots | Trigger Date | Project Complete | Engineering /Design | Bid/ Construction | Total Project Duration | OPCC                      | Construction           | Professional Services | OPCC         |
| 1                      | AC       | WWTP expansion to 0.75 MGD   | WWTP     | Low         | Capacity        | Regulatory        | 0            | Oct-17       | Oct-18           | 12                  | 12                | 12                     | \$8,300                   | \$8,169                | \$618                 | \$8,787      |
| 2                      | B        | 12" line to replace Carter Ranch LS  | South    | Medium      | Operational     | Capacity          | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$1,502                   | \$1,289                | \$258                 | \$1,547      |
| 3                      | P        | 6" line to replace Lucy's LS   | Downtown | High        | Operational     | Capacity          | 0            | Oct-17       | Jun-18           | 4                   | 4                 | 8                      | \$120                     | \$103                  | \$20                  | \$123        |
| 4                      | Q        | 8" and 10" line to replace Shawnee Trail No. 1 LS  | South    | High        | Operational     | Capacity          | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$1,172                   | \$1,006                | \$201                 | \$1,207      |
| 5                      | C        | 8" line to replace Winn Road LS  | Downtown | High        | Operational     | Capacity          | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$486                     | \$417                  | \$83                  | \$501        |
| 6                      | R        | 10" and 12" line to provide additional capacity for the addition of the Chalk Hill LS                                | North    | Medium      | Capacity        | Operational       | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$915                     | \$785                  | \$157                 | \$943        |
| 7                      | AA       | Manhole rehabilitation from PK I/I study   | Downtown | Medium      | Condition       | Operational       | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$422                     | \$362                  | \$72                  | \$434        |
| 8                      | AB       | Pipeline rehabilitation from PK I/I study  | Downtown | Medium      | Condition       | Operational       | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$761                     | \$653                  | \$131                 | \$784        |
| 9                      | O        | 12" line replacement to increase capacity to Heritage  | North    | High        | Capacity        | Operational       | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$1,244                   | \$1,068                | \$214                 | \$1,281      |
| 10                     | A        | 24" line replacement to increase capacity along Light Farms  | South    | High        | Capacity        | Operational       | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$1,362                   | \$1,169                | \$234                 | \$1,403      |
| 11                     | AD       | WWTP expansion to 0.95 MGD   | WWTP     | Low         | Capacity        | Regulatory        | 1,526        | Oct-18       | Oct-20           | 12                  | 12                | 24                     | \$3,000                   | \$2,950                | \$318                 | \$3,269      |
| 12                     | N        | New 30", 36", 42", and 60" interceptor from Downtown WWTP to future WWTP; 8" interceptor to replace Willock Hills LS | South    | Low         | Capacity        | Operational       | 3,233        | Oct-19       | Oct-22           | 24                  | 12                | 36                     | \$43,144                  | \$41,680               | \$7,857               | \$49,537     |
| 13                     | T        | 18" line replacement to increase capacity Downtown   | Downtown | High        | Capacity        | Operational       | 3,233        | Oct-19       | Oct-20           | 6                   | 6                 | 12                     | \$3,066                   | \$2,792                | \$558                 | \$3,351      |
| 14                     | U        | 15" line along FM 455 across Preston Rd  | South    | High        | Capacity        | Operational       | 3,233        | Oct-19       | Oct-20           | 6                   | 6                 | 12                     | \$734                     | \$668                  | \$134                 | \$802        |
| Total 2017 OPCC:       |          |  |          |             |                 |                   |              |              |                  |                     |                   |                        | \$66,227,007              | Total Forecasted OPCC: |                       | \$73,967,030 |





Table 3: Development Driven Projects

| Project Identification |          |  |          |             | Schedule        |                   |              |              |                  |                     |                   |                        | Forecasted Cost (\$1,000) |                        |                       |          |
|------------------------|----------|--|----------|-------------|-----------------|-------------------|--------------|--------------|------------------|---------------------|-------------------|------------------------|---------------------------|------------------------|-----------------------|----------|
| Project                | Grouping | Description  | Location | Flexibility | Primary Trigger | Secondary Trigger | Trigger Lots | Trigger Date | Project Complete | Engineering /Design | Bid/ Construction | Total Project Duration | OPCC                      | Construction           | Professional Services | OPCC     |
| 1                      | AC       | WWTP expansion to 0.75 MGD   | WWTP     | Low         | Capacity        | Regulatory        | 0            | Oct-17       | Oct-18           | 12                  | 12                | 12                     | \$8,300                   | \$8,169                | \$618                 | \$8,787  |
| 6                      | R        | 10" and 12" line to provide additional capacity for the addition of the Chalk Hill LS                                | North    | Medium      | Capacity        | Operational       | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$915                     | \$785                  | \$157                 | \$943    |
| 10                     | A        | 24" line replacement to increase capacity along Light Farms  | South    | High        | Capacity        | Operational       | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$1,362                   | \$1,169                | \$234                 | \$1,403  |
| 11                     | AD       | WWTP expansion to 0.95 MGD   | WWTP     | Low         | Capacity        | Regulatory        | 1,526        | Oct-18       | Oct-20           | 12                  | 12                | 24                     | \$3,000                   | \$2,950                | \$318                 | \$3,269  |
| 12                     | N        | New 30", 36", 42", and 60" interceptor from Downtown WWTP to future WWTP; 8" interceptor to replace Willock Hills LS | South    | Low         | Capacity        | Operational       | 3,233        | Oct-19       | Oct-22           | 24                  | 12                | 36                     | \$43,144                  | \$41,680               | \$7,857               | \$49,537 |
| Total 2017 OPCC:       |          |  |          |             |                 |                   |              |              |                  |                     |                   |                        | \$56,720,948              | Total Forecasted OPCC: | \$63,938,025          |          |

Table 4: Operational Projects


| Project Identification |          |   |          |             | Schedule        |                   |              |              |                  |                     |                   |                        | Forecasted Cost (\$1,000) |                        |                       |         |
|------------------------|----------|---|----------|-------------|-----------------|-------------------|--------------|--------------|------------------|---------------------|-------------------|------------------------|---------------------------|------------------------|-----------------------|---------|
| Project                | Grouping | Description                                       | Location | Flexibility | Primary Trigger | Secondary Trigger | Trigger Lots | Trigger Date | Project Complete | Engineering /Design | Bid/ Construction | Total Project Duration | OPCC                      | Construction           | Professional Services | OPCC    |
| 2                      | B        | 12" line to replace Carter Ranch LS               | South    | Medium      | Operational     | Capacity          | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$1,502                   | \$1,289                | \$258                 | \$1,547 |
| 3                      | P        | 6" line to replace Lucy's LS                      | Downtown | High        | Operational     | Capacity          | 0            | Oct-17       | Jun-18           | 4                   | 4                 | 8                      | \$120                     | \$103                  | \$20                  | \$123   |
| 4                      | Q        | 8" and 10" line to replace Shawnee Trail No. 1 LS | South    | High        | Operational     | Capacity          | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$1,172                   | \$1,006                | \$201                 | \$1,207 |
| 5                      | C        | 8" line to replace Winn Road LS                   | Downtown | High        | Operational     | Capacity          | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$486                     | \$417                  | \$83                  | \$501   |
| Total 2017 OPCC:       |          |   |          |             |                 |                   |              |              |                  |                     |                   |                        | \$3,279,312               | Total Forecasted OPCC: | \$3,377,092           |         |

Table 5: I/I Projects

| Project Identification |          |   |          |             | Schedule        |                   |              |              |                  |                     |                   |                        | Forecasted Cost (\$1,000) |                        |                       |         |
|------------------------|----------|---|----------|-------------|-----------------|-------------------|--------------|--------------|------------------|---------------------|-------------------|------------------------|---------------------------|------------------------|-----------------------|---------|
| Project                | Grouping | Description   | Location | Flexibility | Primary Trigger | Secondary Trigger | Trigger Lots | Trigger Date | Project Complete | Engineering /Design | Bid/ Construction | Total Project Duration | OPCC                      | Construction           | Professional Services | OPCC    |
| 7                      | AA       | Manhole rehabilitation from PK I/I study              | Downtown | Medium      | Condition       | Operational       | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$422                     | \$362                  | \$72                  | \$434   |
| 8                      | AB       | Pipeline rehabilitation from PK I/I study             | Downtown | Medium      | Condition       | Operational       | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$761                     | \$653                  | \$131                 | \$784   |
| 9                      | O        | 12" line replacement to increase capacity to Heritage | North    | High        | Capacity        | Operational       | 0            | Oct-17       | Oct-18           | 6                   | 6                 | 12                     | \$1,244                   | \$1,068                | \$214                 | \$1,281 |
| 13                     | T        | 18" line replacement to increase capacity Downtown    | Downtown | High        | Capacity        | Operational       | 3,233        | Oct-19       | Oct-20           | 6                   | 6                 | 12                     | \$3,066                   | \$2,792                | \$558                 | \$3,351 |
| 14                     | U        | 15" line along FM 455 across Preston Rd               | South    | High        | Capacity        | Operational       | 3,233        | Oct-19       | Oct-20           | 6                   | 6                 | 12                     | \$734                     | \$668                  | \$134                 | \$802   |
| Total 2017 OPCC:       |          |   |          |             |                 |                   |              |              |                  |                     |                   |                        | \$6,226,747               | Total Forecasted OPCC: | \$6,651,913           |         |



### Proposed 5 Year Wastewater CIP Schedule







## Project 1: Sewer Group AC Downtown WWTP Phase I Improvements

### Project Description

This ongoing project involves conversion of the Downtown WWTP from a flow-through SBR and oxidation ditch plant to a conventional activated sludge plant as part of an expansion to 0.75 MGD. This project also includes upgrades to the headworks and construction of new disinfection facilities. Engineering of the improvements began in 2017.

### Justification

The Downtown WWTP is currently operating at or above its permitted capacity, and flows from new developments will overwhelm the plant's capacity in the near future. These improvements will provide capacity needed for the Downtown WWTP to remain in compliance with its discharge permit.

### Unintended Consequences

None identified.

### Special Considerations

None identified.

### Potential Alternatives


The City could proceed with a package WWTP until a regional WWTP is available to take flow from the Downtown WWTP.

| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 1                           |                                      |
| Grouping:                       | AC                          |                                      |
| Location:                       | WWTP                        |                                      |
| Flexibility:                    | Low                         |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Capacity                    |                                      |
| Secondary Trigger:              | Regulatory                  |                                      |
| Trigger # of Lots Constructed   | 0                           |                                      |
| Trigger Date:                   | Oct-2017                    |                                      |
| Project Complete:               | Oct-2018                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 12                          |                                      |
| Bid/Construction:               | 12                          |                                      |
| Total Project Duration:         | 12                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$7.70                      | \$8.17                               |
| Professional Services           | \$0.60                      | \$0.62                               |
| Total Project Cost              | \$8.30                      | \$8.79                               |

| AC                           |           |          |              |
|------------------------------|-----------|----------|--------------|
| Description                  | Unit Cost | Quantity | Cost         |
| WWTP improvements (0.75 MGD) | LS        | 1        | \$ 7,700,000 |
| Subtotal                     |           |          | \$ 7,700,000 |
| Professional Services        |           |          | \$ 600,000   |
| OPCC                         |           |          | \$ 8,300,000 |



Project 1 Schematic







## Project 2: Sewer Group B Line Improvements

### Project Description

The project includes installation of 12-inch pipe to eliminate the need for the Carter Ranch Lift Station.

### Justification

This project allows decommissioning of the Carter Ranch Lift Station and provides for gravity rather than pumped flow.

### Unintended Consequences

The lift station currently pumps north, then flows across Preston in a gravity sewer interceptor. That interceptor would see additional capacity by the decommissioning of the lift station, while the line interceptor that feeds the SE Sector LS will see increased flow.

### Special Considerations

A bored pipe installation will be required to cross Preston Road.

### Potential Alternatives

If this project is not constructed, the Carter Ranch Lift Station must remain online. Alternative alignments are also possible, depending on the development plans for the undeveloped area.


| Project Identification          |                             |                                      |
|---------------------------------|-----------------------------|--------------------------------------|
| Number:                         | 2                           |                                      |
| Grouping:                       | B                           |                                      |
| Location:                       | South                       |                                      |
| Flexibility:                    | Medium                      |                                      |
| Schedule                        |                             |                                      |
| Primary Trigger:                | Operational                 |                                      |
| Secondary Trigger:              | Capacity                    |                                      |
| Trigger # of Lots Constructed   | 0                           |                                      |
| Trigger Date:                   | Oct-2017                    |                                      |
| Project Complete:               | Oct-2018                    |                                      |
| Project Implementation (Months) |                             |                                      |
| Engineering/Design:             | 6                           |                                      |
| Bid/Construction:               | 6                           |                                      |
| Total Project Duration:         | 12                          |                                      |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted<br>Costs<br>(\$ Millions) |
| Construction                    | \$1.25                      | \$1.29                               |
| Professional Services           | \$0.25                      | \$0.26                               |
| Total Project Cost              | \$1.50                      | \$1.55                               |

| Group B                 |                      |               |                      |                |              |
|-------------------------|----------------------|---------------|----------------------|----------------|--------------|
| Diameter<br>(in.)       | Description          | Depth<br>(ft) | Unit Cost<br>(\$/LF) | Length<br>(ft) | Cost         |
| 12                      | Pipe installation    | <20           | 195                  | 3,400          | \$ 663,000   |
|                         | General improvements |               | 75                   |                | \$ 255,000   |
| Description             |                      |               | Unit                 | Quantity       | Cost         |
| Bored pipe installation |                      |               | LS                   | 1              | \$ 125,000   |
| Subtotal                |                      |               |                      |                | \$ 1,043,000 |
| Contingency (20%)       |                      |               |                      |                | \$ 208,600   |
| Professional Services   |                      |               |                      |                | \$ 250,320   |
| OPCC                    |                      |               |                      |                | \$ 1,501,920 |





Project 2 Schematic







### Project 3: Sewer Group P Improvements

#### Project Description

This project involves replacement of the existing Lucy's Lift Station force main with a 6-inch gravity collector.

#### Justification

This project will allow the Lucy's Lift Station to be decommissioned.

#### Unintended Consequences

None identified.

#### Special Considerations

Utility easements may be needed in this area and the alignment may need to shift during detailed design to accommodate property lines and easements. General improvements costs have been increased due to the location of the proposed pipeline.

#### Potential Alternatives

If this project is not completed, Lucy's Lift Station would remain in service. The continued use of Lucy's Lift Station as a manhole versus installation of a new manhole and connection of existing services should be evaluated during the design of this project.


| Project Identification          |                             |                                   |
|---------------------------------|-----------------------------|-----------------------------------|
| Number:                         | 3                           |                                   |
| Grouping:                       | P                           |                                   |
| Location:                       | Downtown                    |                                   |
| Flexibility:                    | High                        |                                   |
| Schedule                        |                             |                                   |
| Primary Trigger:                | Operational                 |                                   |
| Secondary Trigger:              | Capacity                    |                                   |
| Trigger # of Lots Constructed   | 0                           |                                   |
| Trigger Date:                   | Oct-2017                    |                                   |
| Project Complete:               | Jun-2018                    |                                   |
| Project Implementation (Months) |                             |                                   |
| Engineering/Design:             | 4                           |                                   |
| Bid/Construction:               | 4                           |                                   |
| Total Project Duration:         | 8                           |                                   |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted Costs<br>(\$ Millions) |
| Construction                    | \$0.10                      | \$0.10                            |
| Professional Services           | \$0.02                      | \$0.02                            |
| Total Project Cost              | \$0.12                      | \$0.12                            |

| Group P               |                      |               |                      |                 |            |
|-----------------------|----------------------|---------------|----------------------|-----------------|------------|
| Diameter<br>(in.)     | Description          | Depth<br>(ft) | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost       |
| 6                     | Pipe installation    | <20           | 125                  | 370             | \$ 46,250  |
|                       | General improvements |               | 100                  |                 | \$ 37,000  |
| Subtotal              |                      |               |                      |                 | \$ 83,250  |
| Contingency (20%)     |                      |               |                      |                 | \$ 16,650  |
| Professional Services |                      |               |                      |                 | \$ 19,980  |
| OPCC                  |                      |               |                      |                 | \$ 119,880 |





Project 3 Schematic







## Project 4: Sewer Group Q Improvements

### Project Description

This project involves installation of new 8- and 10-inch gravity lines along Doe Branch, just south of FM 455.

### Justification

This project will allow the Shawnee Trail No. 1 Lift Station to be decommissioned.

### Unintended Consequences

None identified.

### Special Considerations

This pipeline crosses an undeveloped area and easement acquisition is likely required. Bored pipe installation may be required to cross FM 455. The alignment is flexible and should be optimized during design to minimize the necessary installation depth. The alignment shown has an approximate depth of 10-ft, relative to the 30-ft depth required if the pipe follows the alignment of FM 455.

### Potential Alternatives

If this project is not completed, Shawnee Trail No. 1 Lift Station would remain in service.

| Project Identification          |                             |                                   |
|---------------------------------|-----------------------------|-----------------------------------|
| Number:                         | 4                           |                                   |
| Grouping:                       | Q                           |                                   |
| Location:                       | South                       |                                   |
| Flexibility:                    | High                        |                                   |
| Schedule                        |                             |                                   |
| Primary Trigger:                | Operational                 |                                   |
| Secondary Trigger:              | Capacity                    |                                   |
| Trigger # of Lots Constructed   | 0                           |                                   |
| Trigger Date:                   | Oct-2017                    |                                   |
| Project Complete:               | Oct-2018                    |                                   |
| Project Implementation (Months) |                             |                                   |
| Engineering/Design:             | 6                           |                                   |
| Bid/Construction:               | 6                           |                                   |
| Total Project Duration:         | 12                          |                                   |
|                                 | 2017 Costs<br>(\$ Millions) | Forecasted Costs<br>(\$ Millions) |
| Construction                    | \$0.98                      | \$1.01                            |
| Professional Services           | \$0.20                      | \$0.20                            |
| Total Project Cost              | \$1.17                      | \$1.21                            |

| Group Q                 |                      |               |                      |                 |              |
|-------------------------|----------------------|---------------|----------------------|-----------------|--------------|
| Diameter<br>(in.)       | Description          | Depth<br>(ft) | Unit Cost<br>(\$/LF) | Length<br>(ft.) | Cost         |
| 8                       | Pipe installation    | <20           | 150                  | 470             | \$ 70,500    |
|                         | General improvements |               | 75                   |                 | \$ 35,250    |
| 10                      | Pipe installation    | <20           | 185                  | 2,530           | \$ 468,050   |
|                         | General improvements |               | 75                   |                 | \$ 189,750   |
| Description             |                      |               | Unit                 | Quantity        | Cost         |
| Bored pipe installation |                      |               | LS                   | 1               | \$ 50,000    |
| Subtotal                |                      |               |                      |                 | \$ 813,550   |
| Contingency (20%)       |                      |               |                      |                 | \$ 162,710   |
| Professional Services   |                      |               |                      |                 | \$ 195,252   |
| OPCC                    |                      |               |                      |                 | \$ 1,171,512 |





Project 4 Schematic

