Control Number: 51415

Item Number: 393

Addendum StartPage: 0

PUBLIC UTILITY COMMISSION OF TEXAS
RECEIVED
APR 2 3 2021
BY
FILING CLERK

SOAH DOCKET NO. 473-21-0538

PUC DOCKET NO. 51415

PUBLIC UTILITY COMMISSION OF TEXAS

APPLICATION OF

SOUTHWESTERN ELECTRIC POWER COMPANY

FOR AUTHORITY TO CHANGE RATES

REBUTTAL TESTIMONY OF

DANIEL R. BOEZIO

FOR

SOUTHWESTERN ELECTRIC POWER COMPANY

APRIL 23, 2021

TESTIMONY INDEX

SECTION		PAGE
I.	INTRODUCTION	1
II.	PURPOSE OF REBUTTAL TESTIMONY	1
III.	TRANSMISSION OUTAGE EVENT	1

EXHIBITS

DRB-1R	SWEPCO's responses to CARD RFI 1-17 (Attachment 4) and to Staff RFI 2-13 (Attachment 1)
DRB-2R	SWEPCO's response to CARD 9-18 (Attachment 3)

I. INTRODUCTION

Q. PLEASE STATE YOUR NAME, POSITION AND BUSINESS ADDRESS.

A. My name is Daniel R. Boezio. My business address is 539 North Carancahua, Corpus Christi, Texas 78401. I am Vice President, Transmission Field Services for American Electric Power Service Corporation (AEPSC), a subsidiary of American Electric Power Company, Inc. (AEP).

Q. DID YOU FILE DIRECT TESTIMONY IN THIS CASE?

A. Yes.

II. PURPOSE OF REBUTTAL TESTIMONY

Q. WHAT IS THE PURPOSE OF YOUR REBUTTAL TESTIMONY?

A. The purpose of my rebuttal testimony is to respond to the testimony of Staff witness John Poole recommending that SWEPCO's return on equity be reduced in this case due to an outage that occurred on August 18, 2019. My testimony demonstrates that the Company makes reasonable efforts to prevent interruption of service, consistent with 16 Texas Administrative Code (TAC) § 25.52(b)(1), and that Mr. Poole's proposal is unjustified.

III. TRANSMISSION OUTAGE EVENT

Q. ON PAGE 5 OF HIS TESTIMONY, MR. POOLE ASSERTS THAT A SINGLE TRANSMISSION OUTAGE EVENT SHOULD RESULT IN NON-COMPLIANCE

1 WITH PUBLIC UTILITY REGULATORY ACT (PURA) § 36.052 AND 16 TAC §
2 25.52(b)(1). HOW DO YOU RESPOND?
3 A. Mr. Poole references 16 TAC § 25.52(b)(1), which states in part: "Every utility shall
4 make all reasonable efforts to prevent interruptions of service . . . " A reasonable effort
5 to prevent interruptions of service does not imply that an interruption of service to the
6 transmission system will never occur. On the contrary, interruptions of service do
7 occur, but the Company constantly strives to minimize any event or condition that
8 would lead to an interruption of service. The oversight and maintenance programs
9 performed by SWEPCO do contribute to the quality of services and operations as
10 referenced by Mr. Poole in PURA §36.052.
11 Q. DOES MR. POOLE'S TESTIMONY ACCURATELY DESCRIBE THE DURATION
12 OF THE OUTAGE?
13 A. No. Mr. Poole states that the outage lasted approximately 12 hours and that load was
14 not restored until 4 AM.[1] However, page 6 of Attachment JP-6 to Mr. Poole's
15 testimony confirms the outage lasted 7 hours and power was restored to all load by 11
16 PM.
17 Q. DOES MR. POOLE'S TESTIMONY EXAMINE SWEPCO'S EFFORTS TO
18 PREVENT INTERRUPTION OF SERVICE?
19 A. Not really, although he refers to that standard in 16 TAC § 25.52(b)(1) as a basis for
20 his recommendation. He appears to conclude that SWEPCO's efforts to prevent

[1] Direct Testimony of John Poole at 6 and 8.

interruption of service were unreasonable based largely on the fact that the outage occurred rather than on examining the Company's efforts to prevent interruptions.

Q. HOW DOES SWEPCO TRANSMISSION IMPLEMENT REASONABLE EFFORTS TO PREVENT INTERRUPTION OF SERVICE?

A. Some of SWEPCO's efforts to prevent service interruptions are discussed in the Attachments to Mr. Poole's testimony. For example, AEP Transmission Forestry conducts two aerial vegetation inspection patrols each year for all lines greater than 200kV and AEP Transmission Field Services (TFS) performs one patrol each year for all lines, including those less than 200kV.[2] All forestry issues discovered by the AEP TFS patrols are forwarded to AEP Transmission Forestry. Transmission Forestry uses the data from these inspections to determine reactive and proactive vegetation management strategies for SWEPCO.[3] The reactive strategies target removal of immediate threats, while the proactive strategy uses the identified vegetation conditions as an input in managing future work plans and determining frequency of maintenance.[4] Each of the lines involved in the August outage had been inspected between April and June of that year,[5] only a few months before the outage. As discussed below, the spring season before the outage experienced high rainfall that resulted in vegetation growth far beyond normal.

In my direct testimony, Section V, SWEPCO Transmission O&M Programs, pages 10 through 14, I provide an extensive discussion on the operation and

[2] Direct Testimony of John Poole at Attachment JP-4 at 13-14.
[3] *Id.* at 14.
[4] *Id.* at 6.
[5] *Id.* at 26

1 maintenance programs the Company performs to minimize and prevent interruptions
2 of service. These programs are reasonable and based on industry standards.
3 Specifically, on page 13, line 12 through page 14, line 11, I provide details on how the
4 Company provides reasonable efforts to manage vegetation on the transmission Rights-
5 of-Way (ROW) to minimize or prevent interruptions of service.

6 In addition, SWEPCO has an ongoing program to rebuild aging transmission
7 lines and equipment. Mr. Poole acknowledges that SWEPCO has rebuilt transmission
8 lines,[6] but does not recognize the full extent of SWEPCO's program, which is described
9 in Company witness Wayman L. Smith's direct testimony and in two RFI responses
10 provided by the Company that are attached as Exhibit DRB-1R.[7] In another RFI
11 response, included with this testimony as Exhibit DRB-2R, the Company provided the
12 planning criteria and guidelines for identifying assets that are near end-of-life.

13 As Company witness Smith discusses in his direct testimony, SWEPCO has
14 spent over $636.7 million on transmission investment since its last rate case, including
15 over $270 million on asset improvement projects to replace aging transmission
16 infrastructure.[8] Mr. Poole does not consider whether this is a reasonable effort to
17 prevent interruptions of service, other than to remark that overall system reliability did
18 not appreciably increase following the rebuilds, suggesting that not all issues have been
19 addressed.[9] However, it is undisputed that SWEPCO has an ongoing, significant,

---

[6] Direct Testimony of John Poole at 10.
[7] See Direct Testimony of Wayman L. Smith at 15-16. My Exhibit DRB-1R contains Attachment 4 to the Company's response to CARD RFI 1-17 and Attachment 1 to the Company's response to Staff RFI 2-13.
[8] Direct Testimony of Wayman L. Smith at 13 (Table 1), 14-20.
[9] Direct Testimony of John Poole at 10.

multi-year program to upgrade older transmission infrastructure, which demonstrates the Company is using reasonable efforts to prevent service interruptions.

One other example of the Company's reasonable efforts to prevent interruptions of service is its request in this case to increase distribution vegetation management funding by $5 million above the test year level. As Company witness Drew Seidel explains in his direct testimony, increasing funding for distribution vegetation management will lead to improvements in service reliability.

Q. HAVE THE COMPANY'S EXPENDITURES FOR TRANSMISSION VEGETATION MANAGEMENT AND REBUILDING OF AGING TRANSMISSION INFRASTRUCTURE BEEN INCREASING IN RECENT YEARS?

A. Yes. As shown in Figure 1, SWEPCO's O&M expenditures for transmission vegetation management in Texas have progressively increased over the last five years.

Figure 1 – SWEPCO Texas Transmission Vegetation O&M Expenses

Cost Description	O&M Expense
2016	$2,856,663
2017	$2,630,679
2018	$4,175,288
2019	$6,498,320
2020	$6,135,522
Grand Total	**$22,296,473**

As discussed above, SWEPCO Transmission has spent over $270 million in asset improvements since the last base case, which was four and a half years, ago. That is approximately $60 million per year in capital additions for the rebuilding of aging transmission infrastructure.

Q. MR. POOLE DISMISSES THE COMPANY'S EXPLANATION THAT UNUSUALLY HIGH RAINFALL AND WARM TEMPERATURES IN 2019 CAUSED VEGETATION TO GROW INTO THE LINES. (POOLE AT PAGE 9). DO YOU AGREE?

A. No. In fact, Mr. Poole's Attachment JP-4 shows that rainfall in 2019 was significantly above average.[10] This was especially true during the spring months that also are the prime growing months for trees and vines. National Oceanic and Atmospheric Administration (NOAA) data[11] in Figure 2 below shows that the Longview, TX area received ten inches of rain in April, twelve inches in May and another ten inches in June 2019.

Figure 2 – SWEPCO TEXAS 2019 Precipitation in Inches

Month	Inches	10yr-Avg	Variance
Jan	6.0	4.4	1.6
Feb	4.0	4.8	-0.8
Mar	4.0	5.7	-1.7
Apr	10.0	6.4	3.6
May	12.0	6.8	5.2
Jun	10.0	5.1	4.9
Jul	4.0	3.1	0.9
Aug	4.0	3.3	0.7
Sep	3.0	3.7	-0.7
Oct	8.0	5.8	2.2
Nov	1.0	5.3	-4.3
Dec	2.0	5.9	-3.9

This rainfall not only contributed to abnormal levels of vegetation growth prior to the August outage, but also hindered the Company's efforts to access flooded or

[10] Direct Testimony of John Poole at Attachment JP-4 at 10.
[11] National Oceanic and Atmospheric Administration, https://www.noaa.gov/

1 impassable ROW to manage the growing vegetation. In one instance, the Company
2 even had to use a barge to access and address vegetation growth during this period.
3 While Mr. Poole argues that it would have taken a number of years for trees to
4 reach the height of the power lines, the initial vegetation contact for the August outage
5 was a vine that had been specifically monitored in the aerial inspection several months
6 earlier. The inspection noted greater than 25 feet of clearance between the vine and the
7 conductor, which is not considered to be a threat. Between the April inspection and
8 the August outage, abnormal growing conditions allowed the vine to grow to an
9 unanticipated height.[12]
10 The SWEPCO area also has species of fast-growing trees that grew more than
11 anticipated due to the abnormal rainfall. For example, Poplar trees grow an average of
12 5-8 feet per year, and the Lombardy Poplar can grow as much as 10 feet in a single season.
13 Red and Silver maples under ideal conditions can grow up to 5 feet in a season. There are
14 many other fast growing species, such as American Elm, Linden, Green Ash, Willow Oak,
15 Sweetgum, Sycamore, Pin Oak, and Leyland Cypress, all which can grow more than 2 feet
16 in a season. SWEPCO takes these average growth rates into account in planning its
17 vegetation management.
18 Several months before the August outage SWEPCO actively monitored
19 vegetation conditions near its lines following its standard procedure and responded
20 appropriately. However, abnormal rainfall in the subsequent months caused abnormal
21 vegetation growth and also hindered SWEPCO's efforts to address that growth.

[12] Direct Testimony of John Poole at Attachment JP-6 at 12.

1 SWEPCO undertook reasonable efforts to prevent interruptions of service, and Mr.
2 Poole has not shown otherwise.
3 Q. ARE ENTITIES OTHER THAN SWEPCO INVOLVED IN THE PLANNING,
4 OPERATION, AND OVERSIGHT OF THE SWEPCO TRANSMISSION SYSTEM?
5 A. Yes. NERC (North American Electric Reliability Corporation) has Federal oversight
6 to develop and define the NERC Reliability Standards,[13] which are the reliability
7 requirements for planning and operating the North American bulk power system.
8 SWEPCO uses these standards for operation and maintenance of the Company's
9 transmission system. In addition and as a member of the Southwest Power Pool (SPP),
10 SWEPCO coordinates and complies with SPP requirements. SPP conducts and
11 provides planning studies for the SPP multi-state region, which includes the SWEPCO
12 Transmission System, to ensure the reliability of the transmission system and that the
13 system can withstand and recover from outage events. On page 5, line 6, of my direct
14 testimony, I describe how the SWEPCO Transmission System is planned, constructed,
15 operated, and maintained.
16 Q. IS IT POSSIBLE TO ELIMINATE ALL TRANSMISSION OUTAGE EVENTS?
17 A. No, but it is possible to minimize the number of outage events and minimize the impact
18 of outage events to customers through reasonable efforts. Some outage events are
19 caused by severe weather such as tornadoes or hurricanes and are largely unavoidable.
20 Other outage events such as those caused by tree contact inside the ROW can be
21 minimized through the vegetation management program. Other outage events caused

[13] NERC Reliability Standards, https://www.nerc.com/pa/stand/Pages/default.aspx

by tree contact from trees outside the ROW are much more difficult to reduce or even minimize as they require the permission of the property owner in order for us to trim or remove. In 2017, SWEPCO's total company spend was approximately $5.6 million in O&M for the transmission vegetation management program, then the spend was approximately $8.4 million in 2018, and $9.1 million in 2019. Even with this reasonable effort, the Company will still continue to experience some outages due to vegetation contact.

Q. ON PAGE 11 OF HIS TESTIMONY, MR. POOLE RECOMMENDS THE COMMISSION REDUCE SWEPCO'S ROE BY APPROXIMATELY $1.13 MILLION. DOES THE COMPANY AGREE WITH THIS RECOMMENDATION?

A. No. Mr. Poole has identified only one instance, which was not related to transmission, in which the Commission has ever taken such action against an electric utility. The reduction proposed by Mr. Poole, based on his analysis of SWEPCO's spending on vegetation management as a result of the singular outage event, would be applied to SWEPCO's ongoing annual revenue requirement. This means SWEPCO's base rate revenue would be reduced by $1.13 million each and every year until SWEPCO's next base rate case. However, a reduction in revenue only exacerbates the issue of limited funding for transmission vegetation management. Reducing the availability of funds does not improve the situation. The Company uses a reliability-based approach, which is a balance approached, to address vegetation issues as a subset of all transmission issues that can impact reliability.

1 Q. HAS SWEPCO TAKEN REASONABLE STEPS TO INVESTIGATE THE CAUSE
2 OF THE OUTAGE EVENT THAT OCCURRED ON AUGUST 18, 2019?
3 A. Yes. This was a singular outage event, the likes of which has not occurred before or
4 since on SWEPCO's system. As such, the Company has completed an internal
5 investigation into the events surrounding the August 18, 2019 outage. SWEPCO
6 reviewed the conditions that existed before and after the outage event to determine if
7 the transmission grid performed as designed. The Company coordinated with NERC
8 and SPP during the investigation to develop a comprehensive review to understand the
9 series of unexpected outages and forced load shed. As previously stated, the
10 transmission system is a complex grid that has many dependencies. A comprehensive
11 investigation with all stakeholders was necessary to ensure the continued reliability of
12 the transmission system and reduce the risk for similar events.
13 Q. HAS THE COMPANY PREVIOUSLY PROVIDED A REPORT TO THE
14 COMMISSION TO EXPLAIN THE EVENTS THAT OCCURRED ON AUGUST 18,
15 2019?
16 A. Yes. After the August 18 outage event occurred, the Company cooperated with an
17 investigation by the Commission Staff. SWEPCO responded to numerous RFIs from
18 Staff, including those attached as exhibits to Mr. Poole's testimony. In November of
19 2019, SWEPCO representatives met with the Commission and provided a detailed
20 presentation of the event timelines, the affected stations and lines, and the Company's
21 response.
22 Q. ON PAGE 11 OF HIS TESTIMONY, MR. POOLE RECOMMENDS THE
23 COMMISSION ORDER SWEPCO TO HIRE AN INDEPENDENT CONTRACTOR

TO CONDUCT A COMPREHENSIVE REVIEW OF SWEPCO'S TRANSMISSION SYSTEM. DOES THE COMPANY AGREE WITH THIS RECOMMENDATION?

A. No. Such action is not justified for the reasons discussed above. In addition, SWEPCO does not believe hiring an independent advisor would be the best use of limited funds. Funds used to hire an independent contractor could be better used to directly address outage prevention, for example on vegetation management. As previously stated, NERC and SPP are independent entities that periodically review SWEPCO's performance and have been involved with the review and investigation of the August 18, 2019 outage events. The Company has the responsibility to operate and maintain the transmission grid in accordance with established NERC standards and RTO requirements.

Q. DOES THIS CONCLUDE YOUR REBUTTAL TESTIMONY?

A. Yes, it does.

Transmission plant capital project descriptions having a cost in excess of $2 million

SWEPCO Line Rebuild Program - This program consists of multiple projects completed over a period of several years as part of an ongoing initiative to improve the SWEPCO Transmission System reliability and dependability. It consists of replacing deteriorated and poorly performing transmission lines and switch facilities with identified conditions that include, but are not limited to: broken, split and rotting poles, cross-arms and braces, bending of poles and cross-arms, missing hardware, broken conductor strands, woodpecker damage, etc. The lines rebuilt under this program include all or portions of the following:

- Hughes Springs to Jenkins Tap 69 kV (4.8 miles)
- Greenland to Van Buren Interconnect (VBI) North 69 kV (36.8 miles)
- North Huntington to Waldron West 69 kV (18.7 miles)
- Mt. Pleasant to New Boston 69 kV (42.1 miles)
- Clarendon to Northwest Memphis 69 kV (25.2 miles)
- Northwest Memphis to West Childress 69 kV (33.3 miles)
- Arsenal Hill to Longwood 138 kV (16.3 miles)
- Bann to Sugar Hill 69 kV (1.1 miles)
- Jenkins Tap to Lone Star Power Plant 69 kV (9.0 miles)

Inspections indicate the transmission lines and associated components continue to degrade. As transmission lines are inspected, the number of structures that do not meet the AEP guidelines due to rot, deterioration, and woodpecker damage, continue to increase. The AEP guidelines are built upon the National Electrical Safety Code, which specifies the necessary structural integrity and physical condition of a line to be maintained. On several lines, these numbers have increased to the point where a complete rebuild of the transmission line is warranted. A significant portion of

these lines are over 50 years old, with some facilities approaching 90 years old. As physical deterioration continues on the lines, the performance of the circuits will continue to degrade, and the number of momentary and permanent outages will increase. The increased outage frequencies and duration of the deteriorated lines jeopardize service reliability to customers and the reliability of surrounding areas. An increasing number of outages will have a negative reliability impact on customers served from the affected circuit, and may have a negative power quality impact on customers served from nearby circuits as well. Routine inspection and an increasing number of emergency callouts indicate that the lines and switches are frequently failing to meet AEP specifications. When these conditions are observed, corrective action must be taken to remedy the failed components by emergency replacement or repair. These unplanned activities typically result in higher than normal expenditures.

SWEPCo Station Proactive Rehab Program - This program includes projects to proactively renew transmission assets based on performance, equipment condition, and risk of failure. In light of Asset Health Center reports and field inspections, AEP Transmission determined it necessary to proactively replace equipment at multiple SWEPCO stations to prevent substantial failures that would result in lengthy outages. Among the improvements, the program will replace thirty-two aging transmission circuit breakers and seven transmission transformers at the following stations: Bann, Diana, Dyess, Northwest Texarkana, Patterson, Whitney, and Wilkes. The program also includes smaller station work such as relaying upgrades and capacitor bank replacements at the following stations: Flint Creek, Hyland, Shamrock, Siloam Springs, South Fayetteville, Southwest Shreveport, and Texarkana.

Transmission Asset Replace/Refurbish Program - These projects were part of an ongoing program to improve system reliability and dependability by replacing failed equipment and aging

station equipment that had reached the end of its serviceable life or could no longer be properly maintained due to non-availability of spare parts. This program also included projects to proactively replace deteriorating transmission structures, foundations, poles, cross-arms, conductors, insulators and associated hardware that were identified through inspections.

2013/2014 Asset Replacement Program - The projects under this program were part of an ongoing, multiyear effort to improve system reliability and dependability by replacing failed equipment and strategically replacing selected, obsolete station equipment that had reached the end of its serviceable life and could no longer be properly maintained due to non-availability of parts. In addition, the program was used to selectively replace obsolete and deteriorated transmission structures, foundations, poles, cross-arms, conductors, insulators, and associated hardware.

SWEPCo Region Failure Program - This two year program addressed failures in the Southwestern Electric Power Company (SWEPCo) region. This program only addressed station and line equipment that were indicated as failures.

Cass Tap to Roach – North Texas Electric Cooperative (NTEC) requested a new delivery point and upgrades to the existing Munz City Station. The new delivery point was connected from the West Atlanta to IPC Domino 138 kV line. AEP purchased land and constructed a new 138 kV box bay, Cass Tap Switching Station, consisting of two breakers, one tap switch, and 138 kV metering units. Munz City Station was reconfigured with the installation of two circuit breakers, a new meter and 138 kV metering transformers.

Leaside Way – This project involved the construction of a new 138/69 kV station with a four breaker 138 kV ring bus, 138/69 kV auto transformer, and a single 69 kV line exit. The new

Leaside Way Station eliminates two, three-terminal line arrangements that create relaying difficulties. The mitigation to the difficulties is to delay tripping to allow proper operation, causing longer fault clearing times. These long clearing times resulted in power quality issues for local industrial customers, causing their equipment to trip off. Completion of this project allowed the relay schemes to operate normally providing for faster clearing times and no disruption to the customers.

East Fayetteville - Arkansas Electric Cooperative Corporation (AECC) requested to expand the East Fayetteville delivery point to allow them to convert their 69 kV system in NW Arkansas to 161 kV. To accomplish this request, AEP constructed the East Fayetteville switching station on the Hyland to Osburn 161 kV line to connect to AECC's East Fayetteville Substation. AECC constructed a new AECC East Fayetteville 161 kV switching station and two 161 kV transmission lines from AECC East Fayetteville 161 kV switching station to AEP terminals in the new East Fayetteville switching station.

Hill Lake - Enterprise Products Operating LLC requested service for approximately 14 MW of new load. As a result Southwestern Electric Power Company (SWEPCO) acquired right of way (ROW) to construct a new 1/4 mile double circuit Hill Lake 138 kV Line Extension and 138 kV high side in/out switching Hill Lake Station with supervisory control and data acquisition (SCADA) switches.

Hallsville South Tap - North Texas Electric Cooperative (NTEC) requested a new delivery point. The new delivery point, Hallsville South Tap, is supplied from the Pirkey-Whitney 138 kV Line. AEP constructed a new 138 kV box bay station with a meter and 138 kV meter transformers. AEP also provided a terminal for NTEC's 138 kV line to NTEC's Gum Springs Station. An initial load

of 10 MW was projected.

Wedington Tap - Arkansas Electric Cooperative Corporation (AECC) requested a new delivery point on the Chamber Springs - South Fayetteville line. AEP installed Wedington Tap Station, including a 161 kV box bay structure on the Chamber Springs - South Fayetteville 161 kV Line. AEP provided a terminal for AECC's 161 kV line to its station. Load at the new delivery point was 6 MW.

Morton Saline Sub - SWEPCO constructed a greenfield substation called Morton Station in Grand Saline, Texas. Morton Salt was served from Grand Saline Station (#988). Grand Saline Station is comprised of two non-Load Tap Changing (non-LTC) transformers operated in parallel with a total max capacity of 19.69 Mega Volt-Amp (MVA). These transformers were forecasted to have a load of 19.39 MVA in 2016, which was 98.5% of their rated capacity. This forecast loading was due primarily to the Morton Salt facility adding equipment to increase their salt production capability at their facility in Grand Saline, Texas. The facility manager at Morton Salt sent a letter to SWEPCO requesting that a new substation be constructed in order to serve their future load. Morton Salt signed a new ten-year contract for their anticipated load. Morton Salt transferred the necessary land and easements to SWEPCO for the construction of this new Morton Station (#1169). Morton Station consists of two 25 MVA transformers. One transformer is dedicated service to Morton Salt and the other transformer serves a SWEPCO distribution feeder that will tie back into Grand Saline Circuit 967110 at Texas Highway 110. The combination of this dedicated service to Morton Salt and the distribution feeder tie to Circuit 967110 effectively reduced the loading on the Grand Saline Station to approximately 10 MVA, which would be 50.8% of the rated capacity of the station.

SWEPCo Forestry ROW Widening - This program was for danger tree removal and widening the rights-of-way for SWEPCo Transmission Lines. The NERC standard FAC 003 applies to vegetation management on transmission lines operating at 200 kV and above, plus other, lower voltage lines deemed critical by the Regional Entity to reliable operation of the transmission system. To comply with this standard, AEP Transmission implemented a multi-year plan to widen these reportable facilities to the full easement width.

Transmission Capital Blanket - This program covered projects such as transmission line work, station asset replacements due to failures, public relocation changes made mandatory by the alteration, construction, reconstruction, or relocation of all public projects carried out by a governmental body, and storm recovery costs for minor storm events. These were all projects that individually cost less than $500,000.

Welsh HVDC Tie - When the Welsh HVDC was originally constructed, both the ERCOT and SPP transmission systems in the Welsh area were tightly regulated by large base load generating plants. However, due to changes in the generation supply curve and the corresponding economic dispatch of the system, this is no longer the case. This lack of tight voltage regulation led to high voltage conditions around the Welsh HVDC and the reduction in local on-line generation also contributed to issues with 5th harmonics, leading to trips of the HVDC. In order to alleviate these conditions, SWEPCo installed reactive compensation and a 5th harmonic filter at the Welsh Station. The Welsh HVDC control system computers and software were also outdated, resulting in maintenance and functionality challenges that reduced the reliability of the HVDC under the existing and future conditions. Those systems were also replaced.

Telecom Fiber Buildout Program - This project is part of an on-going program to provide AEP

Transmission with a strong fiber based telecommunications network with the following key benefits:

- Fiber based protective relaying schemes with diverse communication paths to stations 138kV and higher;
- Fiber based Remote Terminal Unit communication paths (AEP owned and controlled; no leased circuits and associated reliability issues and monthly O&M costs);
- Bandwidth required to backhaul Phasor Measurement Unit data;
- Bandwidth required to backhaul Asset Health data (breakers, transformers, switches, etc.)
- Bandwidth required to backhaul video from multiple security cameras at a station
- North American Electric Reliability Corporation-Critical Infrastructure Protection (NERC CIP) security information (card readers, keypads, sensors, etc.) over AEP controlled telecommunications systems;
- Move AEP microwave radio based backbone telecommunication systems from primary to secondary transport systems;
- Telecommunications transport equipment vendors have been evolving away from microwave to fiber based platforms putting AEP in a position to take advantage of this evolution;
- Microwave based transport systems offer a very small fraction of the bandwidth provided by a fiber optic based system;
- Microwave based transport systems are subject to reoccurring outages due to interference and weather conditions that do not affect fiber based systems;
- Fiber based systems offer additional capacity to meet AEP's future strategic telecommunications requirements; and
- Efficient and reliable operation of the Transmission (and Distribution) systems of the future

will require the bandwidth and resiliency that only a fiber optic based telecommunications system can provide.

SWEPCO Region Major Equipment/Spares Program - The Transmission sparing strategy is based on a probabilistic model that predicts failures based on AEP specific transformer data, historical failure rates and material lead times across every operating company. This strategy creates a required target for spares for each operating company based on current inventory, kV class, and failure rates, among other things. This three-year program (2017-2019) consists of specific asset replacement projects, replacement of failed equipment, and the purchase of major spare and mobile equipment. The program is part of an ongoing effort to improve system reliability and dependability by replacing equipment that has reached the end of its serviceable life, and by purchasing long-lead-time equipment that will become system spares. The equipment purchased will mainly consist of capital spare transformers, spare reactors, spare circuit breakers, mobile transformer stations, and spare transmission line towers. A three-year program allows SWEPCo to secure equipment contracts to leverage our purchases and obtain the best prices for the needed equipment. Having these spares on hand will improve reliability to customers by enabling a quicker restoration in the event of a service interruption, either through the use of a mobile transformer or more timely replacement of failed equipment. For long-lead-time equipment, this can be particularly important as a failure can leave the transmission system in a vulnerable state until new equipment is installed.

Telecom Upgrades - This project was a multi-year effort to replace obsolete equipment that is no longer supported by telecommunication companies by replacing analog leased lines, frame relay circuits (obsolete digital leased line), and tone telemetry installations (obsolete 2-point system alarms). Telecom providers phased out these older technologies, which they will no longer

support, and which AEP Transmission will no longer be able to support due to lack of expertise and unavailability of parts. These upgrades also required the replacement of related station equipment such as older model RTUs that will not support newer technology, and in the case of obsolete tone telemetry, RTUs had to be added to support the newer Telecom technology.

Chamber Springs 345 kV Reactor -. The Chambers Spring reactor was needed to maintain voltage within the allowable range through all seasons in the Northwest Arkansas area but is most heavily needed in spring and fall. In periods of off peak loading Flint Creek generator was unable to maintain its voltage schedule. During these periods the generation unit was consuming max VARs and is still unable to maintain proper voltage. To remedy this, the Flint Creek – Brookline 345kV line had to be taken out of service under these conditions. Installation of the reactor allows SWEPCo to maintain a full intact system including this 345kV tie line and still maintain proper voltage. In order to alleviate the voltage issue, a 345 kV reactor bank and circuit breaker were added at Chamber Spring Substation. The station was expanded on AEP property in order to accommodate the reactor bank.

Valliant to Northwest Texarkana 345 kV Line - This project was mandated by the SPP RTO as a part of their "High Priority Projects" Study and subsequent recommendations. This project provides reliability and economic benefits to the region by increasing west – east transfer capability and enabling more efficient operation of the region's generation supply.

The Longview Heights to Marshall 69 kV Line - The SPP identified the Longview Heights - Marshall 69 kV line overloaded under contingency conditions. The project received an NTC (Notification to Construct) and was mandatory for regional reliability network upgrades. To remediate the overload condition, this project rebuilt 17.8 miles of the 69 kV line from Longview

Heights – Marshall.

The Brownlee Road to North Market 69 kV Line - The SPP identified and mandated a reliability project to rebuild approximately 4.7 miles of 69 kV transmission line from Brownlee Road to North Market. The existing line overloaded during contingency outage conditions. In addition to the line rebuild, upgrades were completed at the Brownlee Road and North Market Stations.

Evenside to Northwest Henderson 69 kV Line - This is a SPP mandated reliability project needed to address a single contingency overload for the outage of the Northwest (NW) Henderson to Poynter 69 kV line. The project involved the rebuild of the Evenside to Northwest Henderson 69 kV line.

Chamber Springs to Farmington 161 kV Line - This is an SPP mandated reliability project needed to address a single contingency thermal overload. The project involves a rebuild of the 11.1 miles of 161 kV line from Chamber Springs to Farmington. In addition to the line rebuild, terminal equipment was upgraded at the Chamber Springs and South Fayetteville stations.

Broadmoor - Fort Humbug 69 kV - The Southwest Power Pool identified and mandated a reliability project to rebuild approximately 1.7 miles of 69 kV transmission line from Broadmoor to Fort Humbug. The existing line overloaded during contingency outage conditions. In addition to the line rebuild, upgrades were completed at the Broadmoor and Fort Humbug stations.

Ellerbe Road – Lucas 69 kV - This project was mandated by SPP to address the overload of the Ellerbe Road - Lucas 69 kV line for the outage of the South Shreveport - Wallace Lake 138 kV line. To alleviate the overload, AEP rebuilt approximately 3 miles of 69 kV line from Ellerbe Road Station to Lucas Station. Ellerbe Road Station scope included the replacement of the existing

69 kV breaker, installation of a three-phase set of capacitor voltage transformers (CCVT's), and replacement of both arresters and line/breaker relays. Lucas Station scope included the addition of arresters to the 69 kV circuit to Ellerbe Road Station and conduit for fiber from the dead-end structure to the pre-cast cable trench.

Siloam- W Siloam 161kV Rebuild - Southwest Power Pool (SPP) identified in the 2017 SPP Integrated Transmission Planning (ITP) assessment that the Siloam Springs-Siloam Springs City 161 kV will experience overloads during the outage of the Flint Creek-Tonnece 345 kV line. To remediate the overload condition, this project rebuilt 2.1 miles of the 161 kV line from Siloam Springs-West Siloam Springs and remote end work at Siloam Springs Station was required.

Linwood - South Shreveport Line - This project was to rebuild the Linwood to South Shreveport 138 kV transmission line as part of a SPP mandatory project to address the overload that will occur on the line during the outage of the Arsenal Hill to Fort Humbug 69 kV transmission line. During this project, 2.42 miles of the 138 kV line from Linwood to South Shreveport was rebuilt with Aluminum Composite Steel Reinforced (ACSR) conductor wire. Circuit breakers, switches, jumpers and relays were upgraded to at least 2000A at Linwood Station and South Shreveport Station.

Brooks Street - Edwards Street 69 kV Line - This is a SPP mandatory project to address the overload of the Brooks Street - Edwards Street 69 kV line for the outage of the Arsenal Hill - Fort Humbug 138 kV line. The overload was addressed by rebuilding approximately one mile from Brooks Street - Edwards Street. Additionally, Brooks Street Station and Edwards Street Station were upgraded with jumpers, switches, relays, and a new drop in control module was installed at each station.

Daingerfield - Jenkins Tap 69 kV Line - This is a SPP mandatory project for regional reliability network upgrades. SWEPCo rebuilt 1.3 miles of the Daingerfield to Jenkins 69 kV transmission line. The rebuild was needed to address the overload of the Daingerfield to Jenkins transmission line caused by the outage of the Lone Star South to Pittsburgh 138 kV or Welsh Reserve to Wilkes 138 kV.

Messick 500/230kV Station - The Southwest Power Pool has identified and mandated a 2012 Integrated Transmission Planning Near-Term (ITPNT) project to build a new 500/230kV station at Messick. The new station addresses the overload of IP Mansfield to Wallace Lake 138 kV line, which overloads to 108% for the loss of the Dolet Hills to South Shreveport 345 kV line.

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR100043S	DR100043S South Fayetteville Station	42955421SWP	FAYETTEVILLE - SOUTH FAYETTEVILLE (T)	35300 - Station Equipment	12/01/2019	15,066
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR100043S	DR100043S South Fayetteville Station	42955421SWP	FAYETTEVILLE SOUTH FAYETTEVILLE (T)	35316 - Station Equipment-SmartGrid	12/01/2019	27,326
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190033S	DR190033S Dequeen Station	42961760SWP	DEQUEEN STATION	35300 - Station Equipment	03/01/2020	20,136
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190033S	DR190033S Dequeen Station	42961760SWP	DEQUEEN STATION	35316 - Station Equipment-SmartGrid	03/01/2020	10,258
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190045S	DR190045S DyessStation	42955435SWP	DYESS - NORTH FAYETTEVILLE (T)	35300 - Station Equipment	12/01/2019	10,910
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190873S	DR190873S Rogers Station	42955443SWP	ROGERS SUBSTATION (T)	35300 - Station Equipment	11/01/2019	36,167
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190873S	DR190873S Rogers Station	42955443SWP	ROGERS SUBSTATION (T)	35316 - Station Equipment-SmartGrid	11/01/2019	24,458
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190892S	DR190892S South Springdale Station	42955456SWP	SOUTH SPRINGDALE SUBSTATION (T)	35300 - Station Equipment	12/01/2019	9,209
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190892S	DR190892S South Springdale Station	42955456SWP	SOUTH SPRINGDALE SUBSTATION (T)	35316 - Station Equipment SmartGrid	12/01/2019	348
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190922S	DR190922S Springdale Station	42955487SWP	SPRINGDALE SUBSTATION (T)	35300 - Station Equipment	12/01/2019	14,502
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190958S	DR190958S Hyland Station	42955485SWP	HYLAND SUBSTATION (T)	35300 Station Equipment	11/01/2019	42,312
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190958S	DR190958S Hyland Station	42955485SWP	HYLAND SUBSTATION (T)	35316 - Station Equipment-SmartGrid	11/01/2019	18,650
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190959S	DR190959S Airline Station	42954867SWP	AIRLINE SUBSTATION	35300 Station Equipment	12/01/2019	16,944
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190959S	DR190959S Airline Station	42954867SWP	AIRLINE SUBSTATION	35316 - Station Equipment-SmartGrid	12/01/2019	20,784
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190976S	DR190976S Tenaha Station	42954885SWP	TENAHA SUBSTATION (T)	35300 - Station Equipment	11/01/2019	29,437
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR190976S	DR190976S Tenaha Station	42954885SWP	TENAHA SUBSTATION (T)	35316 - Station Equipment-SmartGrid	11/01/2019	11,958
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR191113S	DR191113S Kingston Station	42953881SWP	KINGSTON STATION (T)	35300 - Station Equipment	11/01/2019	22,089
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR191113S	DR191113S Kingston Station	42953881SWP	KINGSTON STATION (T)	35316 - Station Equipment-SmartGrid	11/01/2019	12,006
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0033	DR19T0033 DEQUEEN STATION	42961760	DEQUEEN STATION	35300 - Station Equipment	03/01/2020	39,254
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0033	DR19T0033 DEQUEEN STATION	42961760	DEQUEEN STATION	35316 - Station Equipment-SmartGrid	03/01/2020	19,997
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0043	DR19T0043 SOUTH FAYETTEVILLE STATION	42955421	FAYETTEVILLE - SOUTH FAYETTEVILLE (T)	35300 - Station Equipment	12/01/2019	30,177
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0043	DR19T0043 SOUTH FAYETTEVILLE STATION	42955421	FAYETTEVILLE - SOUTH FAYETTEVILLE (T)	35316 - Station Equipment-SmartGrid	12/01/2019	54,732
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0045	DR19T0045 DYESS STATION	42955435	DYESS NORTH FAYETTEVILLE (T)	35300 - Station Equipment	12/01/2019	21,732
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0873	DR19T0873 ROGERS STATION	42955443	ROGERS SUBSTATION (T)	35300 - Station Equipment	11/01/2019	71,502
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0873	DR19T0873 ROGERS STATION	42955443	ROGERS SUBSTATION (T)	35316 - Station Equipment-SmartGrid	11/01/2019	48,353
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0892	DR19T0892 SOUTH SPRINGDALE STATION	42955456	SOUTH SPRINGDALE SUBSTATION (T)	35300 - Station Equipment	12/01/2019	18,424
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0892	DR19T0892 SOUTH SPRINGDALE STATION	42955456	SOUTH SPRINGDALE SUBSTATION (T)	35316 - Station Equipment-SmartGrid	12/01/2019	696
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0922	DR19T0922 SPRINGDALE STATION	42955487	SPRINGDALE SUBSTATION (T)	35300 - Station Equipment	12/01/2019	29,333
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0958	DR19T0958 HYLAND STATION	42955485	HYLAND SUBSTATION (T)	35300 - Station Equipment	11/01/2019	83,627
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0958	DR19T0958 HYLAND STATION	42955485	HYLAND SUBSTATION (T)	35316 - Station Equipment SmartGrid	11/01/2019	36,861
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0959	DR19T0959 AIRLINE STATION	42954867	AIRLINE SUBSTATION	35300 - Station Equipment	12/01/2019	33,357
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0959	DR19T0959 AIRLINE STATION	42954867	AIRLINE SUBSTATION	35316 - Station Equipment SmartGrid	12/01/2019	40,917
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0976	DR19T0976 TENAHA STATION	42954885	TENAHA SUBSTATION (T)	35300 - Station Equipment	11/01/2019	57,508
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T0976	DR19T0976 TENAHA STATION	42954885	TENAHA SUBSTATION (T)	35316 - Station Equipment SmartGrid	11/01/2019	23,360
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T1113	DR19T1113 KINGSTON STATION	42953881	KINGSTON STATION (T)	35300 Station Equipment	11/01/2019	43,313
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR19T1113	DR19T1113 KINGSTON STATION	42953881	KINGSTON STATION (T)	35316 - Station Equipment-SmartGrid	11/01/2019	23,542
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR200791S	DR200791S Western Electric T-station sha	T10037867SWP	Western Electric T station - DR20T0791	35300 - Station Equipment	12/01/2019	212
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR200914S	DR200914S North Rogers T-station shadow	T10071438SWP	North Rogers Station - T	35300 - Station Equipment	01/01/2020	205
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR200917S	DR200917S Dogwood T-station shadow	T10071415SWP	Dogwood Station - T	35300 - Station Equipment	12/01/2019	44
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR200924S	DR200924S Lowell T-station shadow	T10037877SWP	Dixieland T-station - DR20T096	35300 - Station Equipment	12/01/2019	404
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR200961S	DR200961S Dixieland T-station shadow	T10037879SWP	Dixieland T-station - DR20T096	35300 - Station Equipment	12/01/2019	436
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR20T0791	DR20T0791 Western Electric T-station	T10037867	Western Electric T-station - DR20T0791	35300 - Station Equipment	12/01/2019	413
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR20T0914	DR20T0914 North Rogers T-Station	T10071438	North Rogers Station T	35300 - Station Equipment	01/01/2020	398
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR20T0917	DR20T0917 Dogwood T-station	T10071415	Dogwood Station - T	35300 - Station Equipment	12/01/2019	85
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR20T0924	DR20T0924 Lowell T-station	T10037877	Dixieland T-station - DR20T096	35300 Station Equipment	12/01/2019	787
DR18S0001	DR18S0001 SWEPCO Modernization Program	DR20T0961	DR20T0961 Dixieland T-station	T10037879	Dixieland T-station DR20T096	35300 - Station Equipment	12/01/2019	849
	DR18S0001 SWEPCO Modernization Program Total							1,023,077
PPBSWEPCO	PPBSWEPCO Production Plant Blkt SWEPCo	ARS6TOOLC	ARS6TOOLC ARS6 TOOLS OVER 1K	42782167	06 ABB MV REMOTE RACKING TOOL	35300 - Station Equipment	12/01/2017	40,407
PPBSWEPCO	PPBSWEPCO Production Plant Blkt -SWEPCo	ARSUSANUN	ARSUSANUN ANNUNCIATOR REPLACEMENT	42601282	ARS U5 ALARM ANNUNCIATOR SYSTEM REPLACEMENT	35300 - Station Equipment	12/01/2016	210,087
PPBSWEPCO	PPBSWEPCO Production Plant Blkt -SWEPCo	FLCU10384	FLCU10384 Replace 8 GSU Pump and Bearing	42468408	REPLACE B GSU PUMPS AND LOW SIDE BUSHINGS	35300 - Station Equipment	05/01/2016	490
PPBSWEPCO	PPBSWEPCO Production Plant Blkt SWEPCo	KXLU5PPBO	KXLU5PPBO Unit 5 PPB Outage Combined	40940300	U5 REPLACE 5A GSU	35300 - Station Equipment	06/01/2007	(131)
PPBSWEPCO	PPBSWEPCO Production Plant Blkt -SWEPCo	WLKC00004	WLKC00004 Miscellaneous Tools and Equip	42787982	U1-REPLACE 1"A" GSU OIL PUMPS	35300 Station Equipment	08/01/2018	52,384
PPBSWEPCO	PPBSWEPCO Production Plant Blkt -SWEPCo	WSX111023	WSX111023 Dolet Hills-Ppb Other Producti	W0026662	DOLET HILLS 345KV BREAKER REPL	35300 - Station Equipment	02/01/2017	(43,101)
	PPBSWEPCO Production Plant Blkt -SWEPCo Total							260,136
STARP0910	STARP0910 2009-2010 Station Rehab Prog	000016677	000016677 TS/SWEP/AR/Replace&Refurbish	T0115280	MURFREESBORO WEST REPLACE KD4 LINE RELAYS ON ALL 3 CKTS	35300 - Station Equipment	07/01/2016	247,710
STARP0910	STARP0910 2009-2010 Station Rehab Prog	000016677	000016677 TS/SWEP/AR/Replace&Refurbish	T0149841	MURFREESBORO WEST INSTALL CONTROL HOUSE	35300 - Station Equipment	09/01/2016	168,547
STARP0910	STARP0910 2009-2010 Station Rehab Prog	000016681	000016681 TS/SWEP/AR/Assoc w/WO000016677	T0115280SWP	MURFREESBORO WEST REPLACE KD4 LINE RELAYS ON ALL 3 CKTS	35300 - Station Equipment	07/01/2016	126,532
STARP0910	STARP0910 2009-2010 Station Rehab Prog	000016681	000016681 TS/SWEP/AR/Assoc w/WO000016677	T0149841SWP	MURFREESBORO WEST INSTALL CONTROL HOUSE	35300 - Station Equipment	09/01/2016	83,562
	STARP0910 2009-2010 Station Rehab Prog Total							626,350
TA2012102	TA2012102 Purchase/Rebuild Maj Eqp Trans	A12102038	A12102038 T/SW/LongviewOpsReserv-PurchCB	42507015	LONGVIEW OPS RESERVE SPARE BREAKER CID 500080854	35300 - Station Equipment	12/01/2016	52,434
TA2012102	TA2012102 Purchase/Rebuild Maj Eqp Trans	A12102039	A12102039 T/SW/Shadow for A12102038	42507015SWP	LONGVIEW OPS RESERVE SPARE BREAKER CID 500080854	35300 - Station Equipment	12/01/2016	26,939
TA2012102	TA2012102 Purchase/Rebuild Maj Eqp Trans	A12102040	A12102040 T/SW/LonviewOpsResrv-PurchCBs	42507060	LONGVIEW SP 2-BREAKERS CID 500080853	35300 - Station Equipment	12/01/2016	(2,519)
TA2012102	TA2012102 Purchase/Rebuild Maj Eqp Trans	A12102041	A12102041 T/SW/Shadow for A12102040	42507060SWP	LONGVIEW SP 2-BREAKERS CID 500080853	35300 - Station Equipment	12/01/2016	(1,294)
TA2012102	TA2012102 Purchase/Rebuild Maj Eqp Trans	A12102518	A12102518 Pirkey Reserve Spare 90MVA 13	42228785	PIRKEY RES SP 90MVA 138/69/13 8KV W/30MVA TV	35300 - Station Equipment	09/01/2016	749,618
TA2012102	TA2012102 Purchase/Rebuild Maj Eqp Trans	A12102519	A12102519 T/SW/Shadow for A12102518	42228785SWP	PIRKEY RES SP 90MVA 138/69/13 8KV W/30MVA TV	35300 - Station Equipment	09/01/2016	378,734
TA2012102	TA2012102 Purchase/Rebuild Maj Eqp Trans	A12102559	A12102559 T/SW/LongviewOpsRsrv-Purchase	T0154683	LONGVIEW OPS RESERVE TWO (2) SP CB CID 070000670	35300 - Station Equipment	09/01/2016	135,547
TA2012102	TA2012102 Purchase/Rebuild Maj Eqp Trans	A12102560	A12102560 T/SW/Shadow for A12102559	T0154683SWP	LONGVIEW OPS RESERVE TWO (2) SP CB CID 070000670	35300 - Station Equipment	09/01/2016	69,265
	TA2012102 Purchase/Rebuild Maj Eqp Trans Total							1,408,724
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006002	A13006002 T/SW/NORTH NEW BOSTON Replace	T0144510	NORTH NEW BOSTON REPLACE FAILED EAST 138/69KV AUTOTRANSFORM	35300 - Station Equipment	09/01/2016	133,875
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006055	A13006055 Logansport Replace Failed RTU	T0145041	LOGANSPORT REPLACE FAILED RTU	35300 - Station Equipment	09/01/2016	156,642
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006059	A13006059 Rock Hill Replace line relay	T0146747	ROCK HILL REPLACE LINE RELAY ON 138 KV KNOX LEE LINE	35300 - Station Equipment	07/01/2016	100,892

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006064	A13006064 SOUTHWEST SHTREVEPORT Replac	42318807	SOUTHWEST SHREVEPORT INSTALL TERTIARY REACTOR & PANELS	35300 - Station Equipment	03/01/2016	745,358
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006064	A13006064 SOUTHWEST SHTREVEPORT Replac	T0146920	SOUTHWEST SHREVEPORT RPLC FAILED AUTOTRF P345 36 SN C0607351	35300 - Station Equipment	12/01/2014	278,535
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006085	A13006085 T/SW/AbbottTee-Waldron69kV-Ref	42436743	ABBOTT TEE - WALDRON REPLACE INSULATORS & GROUNDS LINE 142	35500 - Poles and Fixtures	07/01/2016	234,792
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006502	A13006502 T/SW/Assoc with A13006002	T0144510SWP	NORTH NEW BOSTON REPLACE FAILED EAST 138/69KV AUTOTRANSFORM	35300 - Station Equipment	09/01/2016	66,480
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006555	A13006555 Logansport Replace Failed RTU	T0145041SWP	LOGANSPORT REPLACE FAILED RTU	35300 - Station Equipment	09/01/2016	79,240
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006559	A13006559 Rock Hill Replace line relay	T0146747SWP	ROCK HILL REPLACE LINE RELAY ON 138 KV KNOX LEE LINE	35300 - Station Equipment	07/01/2016	50,690
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006562	A13006562 T/SW/Shadow for A13006A62	T0150666SWP	CLARKSVILLE 345KV NERC CIP VER 5 CP WO CAPITAL PROJE	35300 - Station Equipment	07/01/2016	15,471
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006562	A13006562 T/SW/Shadow for A13006A62	T0150674SWP	DIANA NERC CIP VER 5 CP WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	12,717
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006562	A13006562 T/SW/Shadow for A13006A62	T0150677SWP	FLINT CREEK SUB NERC CIP VER 5 CP WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	13,933
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006562	A13006562 T/SW/Shadow for A13006A62	T0150685SWP	LONGWOOD (SW) NERC CIP VER 5 CP WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	12,309
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006562	A13006562 T/SW/Shadow for A13006A62	T0150695SWP	PATTERSON NERC CIP VER 5 CP WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	25,936
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006562	A13006562 T/SW/Shadow for A13006A62	T0150706SWP	WELSH NERC CIP VER 5 CP WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	20,790
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006562	A13006562 T/SW/Shadow for A13006A62	T0153595SWP	NORTHWEST TEXARKANA NERC CIP VER 5 WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	20,537
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006564	A13006564 SOUTHWEST SHTREVEPORT Replac	42318807SWP	SOUTHWEST SHREVEPORT INSTALL TERTIARY REACTOR & PANELS	35300 - Station Equipment	03/01/2016	380,091
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006564	A13006564 SOUTHWEST SHTREVEPORT Replac	T0146920SWP	SOUTHWEST SHREVEPORT RPLC FAILED AUTOTRF P345 36 SN C0607351	35300 - Station Equipment	12/01/2014	31,054
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006569	A13006569 T/SW/Shadow for A13006A69	42349732SWP	LYDIA-NERC CIP V5 UPGRADES	35300 - Station Equipment	12/01/2015	28
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006573	A13006573 T/SEP/Shadow for A1306A73	T0150568SWP	WILKES REPLACE FAILED 138KV CCVT AND LINE TRAP	35300 - Station Equipment	09/01/2016	20,746
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006576	A13006576 T/SW/Shadow for A13006A76	42391161SWP	T/SW/ARSENALLHILL-LONGWOOD 138KV	35010 - Land Rights	11/01/2015	2
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006576	A13006576 T/SW/Shadow for A13006A76	42391161SWP	T/SW/ARSENALLHILL LONGWOOD 138KV	35500 - Poles and Fixtures	11/01/2015	121
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006576	A13006576 T/SW/Shadow for A13006A76	42391161SWP	T/SW/ARSENALLHILL-LONGWOOD 138KV	35600 - Overhead Conductors, Device	11/01/2015	52
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006578	A13006578 T/SW/Shadow for A13006A78	42334785SWP	NASHVILLE 69KV STATION REPL FAILED CIRCUIT SWITCHER 10810	35300 - Station Equipment	07/01/2017	60,084
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006579	A13006579 T/SW/Shadow for A13006A79	42337691SWP	WELSH STATION REPLACE FAILED V SWITCH 10633 ON CB 10630	35300 - Station Equipment	11/01/2016	62,786
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006581	A13006581 T/SW/Shadow for A13006A81	42400435SWP	T/SW/S W SHREVEPORT - RELAY REPLACEMENT	35300 - Station Equipment	05/01/2016	6,299
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006585	A13006585 T/SW/Shadow for A13006A85	42373070SWP	SE FAYETTEVILLE REPL GCBS820 W/DEAD TANK HVB HS170 FROM RESV	35300 - Station Equipment	07/01/2016	106,453
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006586	A13006586 T/SW/Shadow for A13006A86	42374520SWP	MINEOLA - REPL FAILED 69KV CAPACITOR BANK	35300 Station Equipment	08/01/2016	75,072
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006589	A13006589 lled T/SW/Shadow for A13006A89	42384089SWP	MIDWAY UPGRADE 69KV TERM REPL CB 8310 SW PT CCVT ARR CA RELA	35300 - Station Equipment	02/01/2016	456
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006589	A13006589 lled T/SW/Shadow for A13006A89	42384102SWP	MIDWAY UPGRADE 69KV TERM REPL CB 8320 SW PT CCVT ARR CA RELA	35300 - Station Equipment	07/01/2016	421,494
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006590	A13006590 T/SW/shadow for A13006A90	42470146SWP	HARDY STREET RPL 69KV CB, CCVT, ETC CONTINUE 42384553	35300 - Station Equipment	07/01/2016	9,232
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006590	A13006590 T/SW/shadow for A13006A90	42482055SWP	HARDY STREET RPL 69KV CB PT CCVT ARR RELAY SW TO MIDWAY	35300 - Station Equipment	02/01/2016	1
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006591	A13006591 T/SW/Shadow for A13006A91	42384567SWP	S SHREVEPORT RPL 69KV CB7210 PT CCVT ARR RELAY SW TO MWY/SMM	35300 - Station Equipment	09/01/2016	144,629
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006592	A13006592 T/SW/Shadow for A13006A92	42384679SWP	SUMMER GROVE UPGRADE 69KV TERM TO S SHREVEPORT/MIDWAY	35300 - Station Equipment	09/01/2016	113,681
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006593	A13006593 T/SW/Shadow for A13006A93	42385912SWP	CEDAR GROVE REPL CAPACITOR BANK - ALL CANS	35300 - Station Equipment	07/01/2016	61,899
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006595	A13006595 T/SW/Shadow for A13006A95	42389478SWP	NORTHWEST TEXARKANA REPL FAILED 138KV CB 11050	35300 Station Equipment	11/01/2016	32,976
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006597	A13006597 T/SEP/Shadow for A13006A97	42403834SWP	FARMINGTON AECC REPLACE FAILED SWITCH 5894, 8839	35300 - Station Equipment	11/01/2016	45,977
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006598	A13006598 T/SEP/Shadow for A13006A98	42408273SWP	HACKETT AECC-REPLACE FAILED SWITCH 11108, 10499	35300 - Station Equipment	01/01/2018	34,088
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006599	A13006599 T/SEP/Shadow for A13006A99	42454453SWP	T/SEP/EASTEXSW REPLFAILEDRLYS	35300 Station Equipment	04/01/2016	2,641
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006603	A13006603 T/SW/Shadow for A13006B03	42415562SWP	MURFREESBORO WEST RPLC KD4 LINE RELAYS ALL 3 CKTS (T0115280)	35300 - Station Equipment	12/01/2016	26,737
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006685	A13006685 T/SW/Shadow for A13006B05	42436743SWP	ABBOTT TEE - WALDRON REPLACE INSULATORS & GROUNDS LINE 142	35500 Poles and Fixtures	07/01/2016	120,316
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A03	A13006A03 Knox Lee Replace line relay o	T0146745	KNOX LEE REPLACE LINE RELAY ON 138 KV ROCK HILL LINE	35300 Station Equipment	07/01/2016	199,824
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A04	A13006A04 Knox Lee Replace line relay o	T0146745SWP	KNOX LEE REPLACE LINE RELAY ON 138 KV ROCK HILL LINE	35300 Station Equipment	07/01/2016	98,179
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A62	A13006A62 NERC CIP V5 UPGRADES SWEPCO	T0150666	CLARKSVILLE 345KV NERC CIP VER 5 CP WO CAPITAL PROJE	35300 Station Equipment	07/01/2016	29,981
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A62	A13006A62 NERC CIP V5 UPGRADES - SWEPCO	T0150674	DIANA NERC CIP VER 5 CP WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	24,945
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A62	A13006A62 NERC CIP V5 UPGRADES SWEPCO	T0150677	FLINT CREEK SUB NERC CIP VER 5 CP WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	27,852
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A62	A13006A62 NERC CIP V5 UPGRADES SWEPCO	T0150685	LONGWOOD (SW) NERC CIP VER 5 CP WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	23,955
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A62	A13006A62 NERC CIP V5 UPGRADES SWEPCO	T0150695	PATTERSON NERC CIP VER 5 CP WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	51,615
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A62	A13006A62 NERC CIP V5 UPGRADES - SWEPCO	T0150706	WELSH NERC CIP VER 5 CP WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	40,632
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A62	A13006A62 NERC CIP V5 UPGRADES - SWEPCO	T0153595	NORTHWEST TEXARKANA NERC CIP VER 5 WO CAPITAL PROJECT	35300 - Station Equipment	07/01/2016	40,314
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A69	A13006A69 Lydia - NERC CIP V5 Upgrades	42349732	LYDIA-NERC CIP V5 UPGRADES	35300 - Station Equipment	12/01/2015	54
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A73	A13006A73 T/SW/Wilses-Repl CCVT&LinTrap	T0150568	WILKES REPLACE FAILED 138KV CCVT AND LINE TRAP	35300 - Station Equipment	09/01/2016	41,467
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A76	A13006A76 T/SW/ArsenalHill-Longwood138kV	42391161	T/SW/ARSENALLHILL-LONGWOOD 138KV	35010 Land Rights	11/01/2015	4
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A76	A13006A76 T/SW/ArsenalHill-Longwood138kV	42391161	T/SW/ARSENALLHILL LONGWOOD 138KV	35500 - Poles and Fixtures	11/01/2015	237
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A76	A13006A76 T/SW/ArsenalHill-Longwood138kV	42391161	T/SW/ARSENALLHILL-LONGWOOD 138KV	35600 - Overhead Conductors, Device	11/01/2015	101
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A78	A13006A78 T/SW/Nashville69kV-ReplCS10810	42334785	NASHVILLE 69KV STATION REPL FAILED CIRCUIT SWITCHER 10810	35300 - Station Equipment	07/01/2017	121,145
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A79	A13006A79 T/SW/Welsh-Repl Sw 10633	42337691	WELSH STATION REPLACE FAILED V SWITCH 10633 ON CB 10630	35300 - Station Equipment	11/01/2016	123,631
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A81	A13006A81 T/SW/S W Shreveport-Repl Rlys	42400435	T/SW/S W SHREVEPORT - RELAY REPLACEMENT	35300 - Station Equipment	05/01/2016	12,490
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A85	A13006A85 T/SW/SEFayettville-ReplCB5820	42373070	SE FAYETTEVILLE REPL GCBS820 W/DEAD TANK HVB HS170 FROM RESV	35300 - Station Equipment	07/01/2016	214,501
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A86	A13006A86 T/SW/Mineola-ReplFailedCapBank	42374520	MINEOLA - REPL FAILED 69KV CAPACITOR BANK	35300 - Station Equipment	08/01/2016	151,153
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A89	A13006A89 T/SW/Midway(SW)-Repl69KVCBs	42384089	MIDWAY UPGRADE 69KV TERM REPL CB 8310 SW PT CCVT ARR CA RELA	35300 - Station Equipment	02/01/2016	896
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A89	A13006A89 T/SW/Midway(SW) Repl69KVCBs	42384102	MIDWAY UPGRADE 69KV TERM REPL CB 8320 SW PT CCVT ARR CA RELA	35300 - Station Equipment	07/01/2016	830,885
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A90	A13006A90 T/SW/HardySt-Repl	42470146	HARDY STREET RPL 69KV CB, CCVT, ETC CONTINUE 42384553	35300 - Station Equipment	07/01/2016	17,990
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A90	A13006A90 T/SW/HardySt-Repl	42482055	HARDY STREET RPL 69KV CB PT CCVT ARR RELAY SW TO MIDWAY	35300 - Station Equipment	02/01/2016	1
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A91	A13006A91 T/SW/S Shreveport-Repl69kVCB	42384567	S SHREVEPORT RPL 69KV CB7210 PT CCVT ARR RELAY SW TO MWY/SMM	35300 - Station Equipment	09/01/2016	283,640
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A92	A13006A92 T/SW/SummerGrove-UpgradeTerm	42384679	SUMMER GROVE UPGRADE 69KV TERM TO S SHREVEPORT/MIDWAY	35300 - Station Equipment	09/01/2016	222,326
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A93	A13006A93 T/SW/CedarGrove-ReplCapBank	42385912	CEDAR GROVE REPL CAPACITOR BANK ALL CANS	35300 - Station Equipment	07/01/2016	121,088
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A95	A13006A95 T/SW/N W Texarkana-ReplCB11050	42389478	NORTHWEST TEXARKANA REPL FAILED 138KV CB 11050	35300 - Station Equipment	11/01/2016	65,105
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A97	A13006A97 T/SEP/FARMINGTON-AECC Repl	42403834	FARMINGTON AECC REPLACE FAILED SWITCH 5894, 8839	35300 Station Equipment	11/01/2016	92,208
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A98	A13006A98 T/SEP/HACKETT AECC=Repl SWs	42408273	HACKETT AECC-REPLACE FAILED SWITCH 11108, 10499	35300 - Station Equipment	01/01/2018	68,360
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006A99	A13006A99 T/SEP/EastexSw-ReplFailedRlys	42454453	T/SEP/EASTEXSW-REPLFAILEDRLYS	35300 - Station Equipment	04/01/2016	5,314
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006B03	A13006B03 T/SW/MurfreesboroWest-ReplRlys	42415562	MURFREESBORO WEST RPLC KD4 LINE RELAYS ALL 3 CKTS (T0115280)	35300 - Station Equipment	12/01/2016	59,863
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006B52	A13006B52 T/SW/S Fayettevill ReplCB10480	42481658	SO FAYETTEVILLE STA REPLACE FAILED 161 KV CB 10480	35300 - Station Equipment	02/01/2017	15,319
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006B53	A13006B53 T/SW/Shadow for A13006B52	42481658SWP	SO FAYETTEVILLE STA REPLACE FAILED 161 KV CB 10480	35300 - Station Equipment	02/01/2017	7,740

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006B60	A13006B60 Shadow SWEPCO for A13006B57	42565206SWP	EAST ROGERS REPLACE THE DLP RELAYS 161 KV BEAVER DAM	35200 - Structures and Improvements	12/01/2016	2,702
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006B60	A13006B60 Shadow SWEPCO for A13006B57	42565206SWP	EAST ROGERS REPLACE THE DLP RELAYS 161 KV BEAVER DAM	35300 - Station Equipment	12/01/2016	201,224
TA2013006	TA2013006 2013/2014 Asset Replacement	A13006B61	A13006B61 SHADOW for SWEPCO A13006B54	42593741SWP	TENASKA-REPLACE LCB11 RELAYS	35300 - Station Equipment	05/01/2017	56,209
	TA2013006 2013/2014 Asset Replacement Total							6,978,060
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216033	A13216033 Bonanza - Telecom Legacy Circu	42564707	BONANZA - TELECOM RPA WORK	35300 - Station Equipment	12/01/2016	13,739
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216058	A13216058 T/SWEPCO/Raines - Telecom Lega	42179095	RAINES - TELECOM LEGACY CIRCUIT UPGRADES, TELECOM ONLY	35300 - Station Equipment	01/01/2018	1,473
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216063	A13216063 T/SWEPCO/Superior (SW) Telec	42234353	SUPERIOR (SW) - TELECOM LEGACY CIRCUIT UPGRADES	35300 - Station Equipment	01/01/2016	0
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216514	A13216514 T/SEP/Shadow for A13216A14	42396100SWP	STONEWALL STATION-LEGACY TELECOM CIRCUIT UPGRADES	35300 - Station Equipment	04/01/2017	41,062
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216533	A13216533 Shadow for A13216033	42564707SWP	BONANZA - TELECOM RPA WORK	35300 - Station Equipment	12/01/2016	6,950
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216536	A13216536 T/SW/Shadow for A13216A36	42545999SWP	DEQUEEN -TELECOM LEGACY	35200 Structures and Improvements	02/01/2019	9,729
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216536	A13216536 T/SW/Shadow for A13216A36	42545999SWP	DEQUEEN -TELECOM LEGACY	35300 - Station Equipment	02/01/2019	217,553
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216558	A13216558 T/SWEPCO-TX/Shadow for A132160	42179095SWP	RAINES - TELECOM LEGACY CIRCUIT UPGRADES, TELECOM ONLY	35300 Station Equipment	01/01/2018	821
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216563	A13216563 shadow for A13216063	42234353SWP	SUPERIOR (SW) - TELECOM LEGACY CIRCUIT UPGRADES	35300 - Station Equipment	01/01/2016	0
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A04	A13216A04 Powell Street-Telecom Legacy C	42245150	POWELL STREET-TELECOM LEGACY CIRCUIT UPGRADES	35300 - Station Equipment	12/01/2015	118,927
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A05	A13216A05 Shed Road-Telecom Legacy Circu	42251048	SHED ROAD-TELECOM LEGACY CIRCUIT UPGRADES	35300 - Station Equipment	12/01/2015	305
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A08	A13216A08 shadow for A13216A04	42245150SWP	POWELL STREET-TELECOM LEGACY CIRCUIT UPGRADES	35300 Station Equipment	12/01/2015	60,717
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A09	A13216A09 Shadow for A13216A05	42251048SWP	SHED ROAD-TELECOM LEGACY CIRCUIT UPGRADES	35300 - Station Equipment	12/01/2015	157
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A14	A13216A14 STONEWALL STATION - Telecom Le	42396100	STONEWALL STATION-LEGACY TELECOM CIRCUIT UPGRADES	35300 - Station Equipment	04/01/2017	80,510
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A23	A13216A23 Danville (AP&L)(AR) Telecom Le	42608119	DANVILLE (AP&L)(AR) TELECOM LE	35200 - Structures and Improvements	02/01/2018	8,772
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A23	A13216A23 Danville (AP&L)(AR) Telecom Le	42608119	DANVILLE (AP&L)(AR) TELECOM LE	35300 - Station Equipment	02/01/2018	267,593
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A31	A13216A31 Huntington (AR) Telecom Legacy	42603975	HUNTINGTON (AR) TELECOM LEGACY	35300 - Station Equipment	11/01/2017	137,641
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A31	A13216A31 Huntington (AR) Telecom Legacy	42603975	HUNTINGTON (AR) TELECOM LEGACY	35316 - Station Equipment SmartGrid	11/01/2017	41,848
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A32	A13216A32 Ashdown West (AR) Telecom Lega	42626733	ASHDOWN WEST (AR) STATION - TELECOM LEGACY CIRCUIT UPGRADES	35200 - Structures and Improvements	10/01/2017	7,435
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A32	A13216A32 Ashdown West (AR) Telecom Lega	42626733	ASHDOWN WEST (AR) STATION - TELECOM LEGACY CIRCUIT UPGRADES	35300 - Station Equipment	10/01/2017	201,158
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A36	A13216A36 DeQueen -Telecom Legacy	42545999	DEQUEEN -TELECOM LEGACY	35200 - Structures and Improvements	02/01/2019	18,996
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A36	A13216A36 DeQueen Telecom Legacy	42545999	DEQUEEN -TELECOM LEGACY	35300 - Station Equipment	02/01/2019	424,795
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A42	A13216A42 Branch Telecom Legacy Circuit	42626729	BRANCH TELECOM LEGACY CIRCUIT	35200 - Structures and Improvements	02/01/2018	7,897
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A42	A13216A42 Branch Telecom Legacy Circuit	42626729	BRANCH TELECOM LEGACY CIRCUIT	35300 - Station Equipment	02/01/2018	264,823
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A44	A13216A44 McWillie TelecomLegacyFiber Ca	42633523	MCWILLIE TELECOM LEGACY FIBER	35700 - Underground Conduit	08/01/2017	1,224
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A44	A13216A44 McWillie TelecomLegacyFiber Ca	42633523	MCWILLIE TELECOM LEGACY FIBER	35816 - Ug Cond-Dev-Smart Grid	08/01/2017	408
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A46	A13216A46 Trichel-Arsenal Hill TelLegFib	42632499	TRICHEL-ARSENAL HILL TELLEGFIBER	35616 - OVH Cond-Dev-Smart Grid	09/01/2018	801,582
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A46	A13216A46 Trichel-Arsenal Hill TelLegFib	42632499	TRICHEL-ARSENAL HILL - TELLEGFIBER	35700 - Underground Conduit	09/01/2018	8,181
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A46	A13216A46 Trichel-Arsenal Hill TelLegFib	42632499	TRICHEL-ARSENAL HILL - TELLEGFIBER	35816 - Ug Cond-Dev-Smart Grid	09/01/2018	8,181
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A47	A13216A47 Whitehurst - Trichel TelLegFib	42632501	WHITEHURST-TRICHEL - TELLEGFIBER	35616 - OVH Cond-Dev-Smart Grid	09/01/2018	197,542
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A47	A13216A47 Whitehurst - Trichel TelLegFib	42632501	WHITEHURST-TRICHEL - TELLEGFIBER	35700 - Underground Conduit	09/01/2018	2,016
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A47	A13216A47 Whitehurst - Trichel TelLegFib	42632501	WHITEHURST TRICHEL TELLEGFIBER	35816 - Ug Cond-Dev-Smart Grid	09/01/2018	2,016
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A48	A13216A48 T/SW/Shadow for A13216A31	42603975SWP	HUNTINGTON (AR) TELECOM LEGACY	35300 - Station Equipment	11/01/2017	70,479
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A48	A13216A48 T/SW/Shadow for A13216A31	42603975SWP	HUNTINGTON (AR) TELECOM LEGACY	35316 - Station Equipment-SmartGrid	11/01/2017	21,429
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A50	A13216A50 SE Longview-Whitney TelLegFibe	42578391	SE LONGVIEW-WHITNEY TELLEG FIBER	35616 - OVH Cond-Dev-Smart Grid	11/01/2018	303,316
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A50	A13216A50 SE Longview-Whitney TelLegFibe	42578391	SE LONGVIEW-WHITNEY TELLEG FIBER	35700 - Underground Conduit	11/01/2018	3,091
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A50	A13216A50 SE Longview-Whitney TelLegFibe	42578391	SE LONGVIEW-WHITNEY TELLEG FIBER	35816 - Ug Cond-Dev-Smart Grid	11/01/2018	3,091
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A52	A13216A52 Linwood-SW Shreveport TeLegFib	42632506	LINWOOD-SW SHREVEPORT - TELLEGFIBER	35616 - OVH Cond-Dev Smart Grid	09/01/2018	415,932
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A52	A13216A52 Linwood-SW Shreveport TeLegFib	42632506	LINWOOD-SW SHREVEPORT - TELLEGFIBER	35700 - Underground Conduit	09/01/2018	4,244
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A52	A13216A52 Linwood SW Shreveport TeLegFib	42632506	LINWOOD-SW SHREVEPORT TELLEGFIBER	35816 Ug Cond Dev-Smart Grid	09/01/2018	4,244
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A58	A13216A58 Domtar Telecom Legacy Cir	42611245	DOMTAR (NEKOOSA) - TELECOM LEGACY	35200 - Structures and Improvements	11/01/2017	10,954
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A58	A13216A58 Domtar Telecom Legacy Cir	42611245	DOMTAR (NEKOOSA) - TELECOM LEGACY	35300 - Station Equipment	11/01/2017	269,483
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A66	A13216A66 Shadow for A13216A42 Tele Lega	42626729SWP	BRANCH TELECOM LEGACY CIRCUIT	35200 - Structures and Improvements	02/01/2018	4,053
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A66	A13216A66 Shadow for A13216A42 Tele Lega	42626729SWP	BRANCH TELECOM LEGACY CIRCUIT	35300 - Station Equipment	02/01/2018	135,919
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A68	A13216A68 Shadow for A132176S2	42594781SWP	JEFFERSON IPC TELLEGFIB	35616 - OVH Cond-Dev-Smart Grid	08/01/2017	29,029
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A68	A13216A68 Shadow for A132176S2	42594781SWP	JEFFERSON IPC TELLEGFIB	35700 - Underground Conduit	08/01/2017	296
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A68	A13216A68 Shadow for A132176S2	42594781SWP	JEFFERSON IPC TELLEGFIB	35816 - Ug Cond-Dev-Smart Grid	08/01/2017	296
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A69	A13216A69 Shadow for A13216A23	42608119SWP	DANVILLE (AP&L)(AR) TELECOM LE	35200 - Structures and Improvements	02/01/2018	4,497
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A69	A13216A69 Shadow for A13216A23	42608119SWP	DANVILLE (AP&L)(AR) TELECOM LE	35300 - Station Equipment	02/01/2018	137,176
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A70	A13216A70 Shadow for A13216A58	42611245SWP	DOMTAR (NEKOOSA) - TELECOM LEGACY	35200 - Structures and Improvements	11/01/2017	5,621
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A70	A13216A70 Shadow for A13216A58	42611245SWP	DOMTAR (NEKOOSA) - TELECOM LEGACY	35300 - Station Equipment	11/01/2017	138,282
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A71	A13216A71 Shadow for A13216A32	42626733SWP	ASHDOWN WEST (AR) STATION - TELECOM LEGACY CIRCUIT UPGRADES	35200 - Structures and Improvements	10/01/2017	3,810
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A71	A13216A71 Shadow for A13216A32	42626733SWP	ASHDOWN WEST (AR) STATION - TELECOM LEGACY CIRCUIT UPGRADES	35300 - Station Equipment	10/01/2017	103,090
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A74	A13216A74 Shadow for A13216A44	42633523SWP	MCWILLIE TELECOM LEGACY FIBER	35700 - Underground Conduit	08/01/2017	617
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A74	A13216A74 Shadow for A13216A44	42633523SWP	MCWILLIE TELECOM LEGACY FIBER	35816 - Ug Cond-Dev-Smart Grid	08/01/2017	206
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A76	A13216A76 Shadow for A13216A46	42632499SWP	TRICHEL-ARSENAL HILL - TELLEGFIBER	35616 - OVH Cond-Dev-Smart Grid	09/01/2018	413,107
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A76	A13216A76 Shadow for A13216A46	42632499SWP	TRICHEL-ARSENAL HILL - TELLEGFIBER	35700 - Underground Conduit	09/01/2018	4,216
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A76	A13216A76 Shadow for A13216A46	42632499SWP	TRICHEL-ARSENAL HILL - TELLEGFIBER	35816 - Ug Cond-Dev-Smart Grid	09/01/2018	4,216
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A77	A13216A77 Shadow for A13216A47	42632501SWP	WHITEHURST-TRICHEL - TELLEGFIBER	35616 - OVH Cond-Dev-Smart Grid	09/01/2018	101,739
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A77	A13216A77 Shadow for A13216A47	42632501SWP	WHITEHURST-TRICHEL - TELLEGFIBER	35700 - Underground Conduit	09/01/2018	1,038
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A77	A13216A77 Shadow for A13216A47	42632501SWP	WHITEHURST-TRICHEL - TELLEGFIBER	35816 - Ug Cond-Dev Smart Grid	09/01/2018	1,038
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A78	A13216A78 Shadow for A13216A52	42632506SWP	LINWOOD SW SHREVEPORT TELLEGFIBER	35616 - OVH Cond-Dev-Smart Grid	09/01/2018	214,453
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A78	A13216A78 Shadow for A13216A52	42632506SWP	LINWOOD-SW SHREVEPORT - TELLEGFIBER	35700 - Underground Conduit	09/01/2018	2,188
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A78	A13216A78 Shadow for A13216A52	42632506SWP	LINWOOD-SW SHREVEPORT - TELLEGFIBER	35816 - Ug Cond-Dev-Smart Grid	09/01/2018	2,188
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A82	A13216A82 Shadow for A13216A50	42578391SWP	SE LONGVIEW-WHITNEY TELLEG FIBER	35616 - OVH Cond-Dev-Smart Grid	11/01/2018	156,219
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A82	A13216A82 Shadow for A13216A50	42578391SWP	SE LONGVIEW-WHITNEY TELLEG FIBER	35700 - Underground Conduit	11/01/2018	1,592
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A82	A13216A82 Shadow for A13216A50	42578391SWP	SE LONGVIEW WHITNEY TELLEG FIBER	35816 - Ug Cond-Dev-Smart Grid	11/01/2018	1,592

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A84	A13216A84 Van Buren Inter Telecom Legacy	42751538	VAN BUREN INTER TELECOM LEGACY	35300 - Station Equipment	06/01/2018	312,027
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A85	A13216A85 West Siloam Springs Telecom Le	42751516	WEST SILOAM SPRINGS TELECOM LE	35300 - Station Equipment	06/01/2018	299,098
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A86	A13216A86 Shadow for A13216A84 No WOs!	42751538SWP	VAN BUREN INTER TELECOM LEGACY	35300 - Station Equipment	06/01/2018	147,019
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13216A87	A13216A87 Shadow for A13216A85 No WOs!	42751516SWP	WEST SILOAM SPRINGS TELECOM LE	35300 - Station Equipment	06/01/2018	153,319
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13217652	A13217652 Jefferson IPC TelLegFib	42594781	JEFFERSON IPC TELLEGFIB	35616 - OVH Cond-Dev-Smart Grid	08/01/2017	56,501
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13217652	A13217652 Jefferson IPC TelLegFib	42594781	JEFFERSON IPC TELLEGFIB	35700 - Underground Conduit	08/01/2017	576
TA2013216	TA2013216 T/SW/Telecom Upgrades	A13217652	A13217652 Jefferson IPC TelLegFib	42594781	JEFFERSON IPC TELLEGFIB	35816 - Ug Cond Dev-Smart Grid	08/01/2017	576
	TA2013216 T/SW/Telecom Upgrades Total							6,495,906
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A13006B57	A13006B57 EAST ROGERS Replace the DLP	42565206	EAST ROGERS REPLACE THE DLP RELAYS 161 KV BEAVER DAM	35200 - Structures and Improvements	12/01/2016	5,392
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A13006B57	A13006B57 EAST ROGERS Replace the DLP	42565206	EAST ROGERS REPLACE THE DLP RELAYS 161 KV BEAVER DAM	35300 - Station Equipment	12/01/2016	401,572
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706001	A15706001 East Rogers UF Islanding	42549265	EAST ROGERS UF ISLANDING -REPL CB 1T20 CONTROL RELAY	35300 - Station Equipment	07/01/2018	12
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706501	A15706501 Shadow for A15706001	42549265SWP	EAST ROGERS UF ISLANDING REPL CB 1T20 CONTROL RELAY	35300 Station Equipment	07/01/2018	(3)
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706503	A15706503 T/SEP/GRANDSALINE-MINEOLA69KV	42607358	2016 REHAB GRAND SALINE - MINEOLA 69KV, REPL BAD POLES/ARMS	35500 - Poles and Fixtures	04/01/2017	99,193
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706506	A15706506 T/SEP/HOSSTN BLOOMBURG69KV(AR)	42611588	2016 REHAB HOSSTON - BLOOMBURG (AR), REPL POLES & ARMS	35500 - Poles and Fixtures	12/01/2016	300,317
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706507	A15706507 T/SEP/BOONEVILLE-BRANCH69KV	42519246	2016 REHAB BOONEVILLE - BRANCH TL162 2 POLES & CROSS ARMS	35500 - Poles and Fixtures	07/01/2016	193,567
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706510	A15706510 North Huntington UF Islanding	42549271	NORTH HUNTINGTON UF ISLANDING -REPLACE CB 2130 CONTROL RELAY	35300 - Station Equipment	10/01/2016	21,680
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706511	A15706511 Siloam Springs UF Islanding	42549275	SILOAM SPRINGS UF ISLANDING - REPLACE CB 10460 CONTROL RELAY	35300 - Station Equipment	11/01/2016	19,693
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706512	A15706512 South Nashville UF Relaying	42549593	SOUTH NASHVILLE UF RELAYING - REPLACE CB 12170 CONTROL RELAY	35300 - Station Equipment	01/01/2017	36,847
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706513	A15706513 SWEPCO Shadow for A15706507	42519246SWP	2016 REHAB BOONEVILLE - BRANCH TL162 2 POLES & CROSS ARMS	35500 Poles and Fixtures	07/01/2016	99,413
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706516	A15706516 Shadow for SWEPCO A15706506	42611588SWP	2016 REHAB HOSSTON - BLOOMBURG (AR), REPL POLES & ARMS	35500 - Poles and Fixtures	12/01/2016	154,296
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706538	A15706538 Welsh Relay Repl on Wilkes 345	42677293	WELSH HVDC EAST TIE 345KV SUBSTATION	35200 - Structures and Improvements	04/01/2018	17,412
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706538	A15706538 Welsh Relay Repl on Wilkes 345	42677293	WELSH HVDC EAST TIE 345KV SUBSTATION	35300 - Station Equipment	04/01/2018	451,935
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706538	A15706538 Welsh Relay Repl on Wilkes 345	42677293	WELSH HVDC EAST TIE 345KV SUBSTATION	35316 - Station Equipment-SmartGrid	04/01/2018	23,460
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706540	A15706540 Shadow SWEPCO A15706510	42549271SWP	NORTH HUNTINGTON UF ISLANDING -REPLACE CB 2130 CONTROL RELAY	35300 - Station Equipment	10/01/2016	10,988
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706541	A15706541 Shadow SWEPCO A15706511	42549275SWP	SILOAM SPRINGS UF ISLANDING - REPLACE CB 10460 CONTROL RELAY	35300 - Station Equipment	11/01/2016	9,623
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706542	A15706542 Shadow SWEPCO A15706512	42549593SWP	SOUTH NASHVILLE UF RELAYING - REPLACE CB 12170 CONTROL RELAY	35300 - Station Equipment	01/01/2017	17,544
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706543	A15706543 SW Shreveport Rpl Fail Air Co	42570926	SW SHREVEPORT REPL FAILED SHUNT REACTORS ON MIDDLE AUTO	35300 - Station Equipment	06/01/2018	696,300
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706545	A15706545 T/SEP/DIANA-PLILERRD/STR REPLA	42573588	WHITNEY-PLILER-DIANA-LONE STAR SOUTH REPL 2 FAILED STRUCT	35500 - Poles and Fixtures	06/01/2017	601,273
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706549	A15706549 Shadow SWEPCO A15706545	42573588SWP	WHITNEY-PLILER-DIANA-LONE STAR SOUTH REPL 2 FAILED STRUCT	35500 - Poles and Fixtures	06/01/2017	308,468
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706550	A15706550 Shadow, A15706543, RPL Shunt R	42570926SWP	SW SHREVEPORT REPL FAILED SHUNT REACTORS ON MIDDLE AUTO	35300 - Station Equipment	05/01/2018	354,414
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706558	A15706558 South Shreveport Station Rehab	42645078	SOUTH SHREVEPORT STATION REHAB	35200 - Structures and Improvements	12/01/2017	36,495
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706558	A15706558 South Shreveport Station Rehab	42645078	SOUTH SHREVEPORT STATION REHAB	35300 - Station Equipment	12/01/2017	682,567
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706558	A15706558 South Shreveport Station Rehab	42645078	SOUTH SHREVEPORT STATION REHAB	35316 - Station Equipment-SmartGrid	12/01/2017	5,302
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706559	A15706559 Grand Saline Breaker Rep	42645081	GRAND SALINE STATION WORK	35300 - Station Equipment	03/01/2020	722
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706595	A15706595 LMABean-2017GEUpgrade	T0179279	2017 GEUPGRADE BEAN STA_1 RELAY	35316 Station Equipment-SmartGrid	11/01/2017	15,952
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706596	A15706596 EastCenterton-2017GEUpgrade	T0179277	2017 GEUPGRADE EAST CENTERTON STA_1 RELAY	35316 - Station Equipment-SmartGrid	06/01/2018	17,773
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706597	A15706597 Lieberman-2017GEUpgrade	T0179276	2017 GEUPGRADE LIEBERMAN STA_1 RELAY	35316 - Station Equipment-SmartGrid	12/01/2017	12,495
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706598	A15706598 Lonestar(SEP)-2017GEUpgrade	T0179274	2017 GEUPGRADE LONE STAR (SEP) STA_2 RELAYS	35316 - Station Equipment-SmartGrid	06/01/2018	17,816
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706599	A15706599 Longwood(SW)-2017GEUpgrade	T0179273	2017 GEUPGRADE LONGWOOD (SW) STA_1 RELAY	35316 - Station Equipment-SmartGrid	06/01/2018	11,184
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706600	A15706600 Okay-2017GEUpgrade	T0179272	2017 GEUPGRADE OKAY STA_3 RELAYS	35316 - Station Equipment-SmartGrid	11/01/2017	28,435
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706601	A15706601 Pirkey-2017GEUpgrade	T0179271	2017 GEUPGRADE PIRKEY STA_1 RELAY	35316 - Station Equipment-SmartGrid	12/01/2018	8,400
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706602	A15706602 Pittsburg(SW)-2017GEUpgrade	T0179270	2017 GEUPGRADE PITTSBURG (SW) STA_1 RELAY	35316 - Station Equipment-SmartGrid	11/01/2017	15,761
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706603	A15706603 PortRobson-2017GEUpgrade	T0179269	2017 GEUPGRADE PORT ROBSON STA_3 RELAYS	35316 - Station Equipment-SmartGrid	11/01/2017	26,175
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706604	A15706604 SouthShreveport-2017GEUpgrade	T0179268	2017 GEUPGRADE SOUTH SHREVEPORT STA_1 RELAY	35316 - Station Equipment-SmartGrid	12/01/2017	11,056
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706605	A15706605 Tontitown 2017GEUpgrade	T0179265	2017 GEUPGRADE TONTITOWN STA_3 RELAYS	35316 - Station Equipment-SmartGrid	10/01/2018	37,437
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706606	A15706606 Turk-2017GEUpgrade	T0179297	2017 GEUPGRADE TURK STA_9 RELAYS	35316 - Station Equipment-SmartGrid	06/01/2018	98,311
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706607	A15706607 Whitney-2017GEUpgrade	T0179262	2017 GEUPGRADE WHITNEY STA_1 RELAY	35316 - Station Equipment-SmartGrid	11/01/2017	14,613
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706608	A15706608 Shadow for A15706595-2017GEUpg	T0179279SWP	2017 GEUPGRADE BEAN STA_1 RELAY	35316 - Station Equipment-SmartGrid	11/01/2017	8,122
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706609	A15706609 Shadow for A15706596-2017GEUpg	T0179277SWP	2017 GEUPGRADE EAST CENTERTON STA_1 RELAY	35316 - Station Equipment-SmartGrid	06/01/2018	9,037
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706610	A15706610 Shadow for A15706597-2017GEUpg	T0179276SWP	2017 GEUPGRADE LIEBERMAN STA_1 RELAY	35316 - Station Equipment-SmartGrid	12/01/2017	6,383
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706611	A15706611 Shadow for A15706598-2017GEUpg	T0179274SWP	2017 GEUPGRADE LONE STAR (SEP) STA_2 RELAYS	35316 - Station Equipment-SmartGrid	06/01/2018	9,034
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706612	A15706612 Shadow for A15706599-2017GEUpg	T0179273SWP	2017 GEUPGRADE LONGWOOD (SW) STA_1 RELAY	35316 - Station Equipment-SmartGrid	06/01/2018	5,740
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706613	A15706613 Shadow for A15706600-2017GEUpg	T0179272SWP	2017 GEUPGRADE OKAY STA_3 RELAYS	35316 Station Equipment-SmartGrid	11/01/2017	14,323
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706614	A15706614 Shadow for A15706601-2017GEUpg	T0179271SWP	2017 GEUPGRADE PIRKEY STA_1 RELAY	35316 - Station Equipment-SmartGrid	12/01/2018	4,301
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706615	A15706615 Shadow for A15706602-2017GEUpg	T0179270SWP	2017 GEUPGRADE PITTSBURG (SW) STA_1 RELAY	35316 - Station Equipment-SmartGrid	11/01/2017	7,899
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706616	A15706616 Shadow for A15706603-2017GEUpg	T0179269SWP	2017 GEUPGRADE PORT ROBSON STA_3 RELAYS	35316 Station Equipment-SmartGrid	11/01/2017	13,330
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706617	A15706617 Shadow for A15706604-2017GEUpg	T0179268SWP	2017 GEUPGRADE SOUTH SHREVEPORT STA_1 RELAY	35316 - Station Equipment-SmartGrid	12/01/2017	5,646
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706618	A15706618 Shadow for A15706605-2017GEUpg	T0179265SWP	2017 GEUPGRADE TONTITOWN STA_3 RELAYS	35316 - Station Equipment-SmartGrid	10/01/2018	19,003
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706619	A15706619 Shadow for A15706606-2017GEUpg	T0179297SWP	2017 GEUPGRADE TURK STA_9 RELAYS	35316 - Station Equipment-SmartGrid	06/01/2018	49,872
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706620	A15706620 Shadow for A15706607-2017GEUpg	T0179262SWP	2017 GEUPGRADE WHITNEY STA_1 RELAY	35316 Station Equipment SmartGrid	11/01/2017	7,469
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706622	A15706622 Shadow SWEPCO A15706503	42607358SWP	2016 REHAB GRAND SALINE - MINEOLA 69KV, REPL BAD POLES/ARMS	35500 - Poles and Fixtures	04/01/2017	50,183
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706623	A15706623 Vernon Main CB 122	42707036	VERNON MAIN STEET 138KV SUBSTATION	35200 Structures and Improvements	05/01/2019	49,008
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706623	A15706623 Vernon Main CB 122	42707036	VERNON MAIN STEET 138KV SUBSTATION	35300 - Station Equipment	05/01/2019	546,540
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706623	A15706623 Vernon Main CB 122	42707036	VERNON MAIN STEET 138KV SUBSTATION	35316 Station Equipment-SmartGrid	05/01/2019	84
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706624	A15706624 Clarendon - Jericho 69kV strs	42657647	2017 WP/ CLARENDON - JERICHO 69KV REHAB (STEEL REPLACEMENT)	35500 - Poles and Fixtures	11/01/2018	727,403
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706625	A15706625 shadow for A15706624	42657647SWP	2017 WP/ CLARENDON - JERICHO 69KV REHAB (STEEL REPLACEMENT)	35500 Poles and Fixtures	11/01/2018	372,316
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706630	A15706630 Shadow for A15706559	42645081SWP	GRAND SALINE STATION WORK	35300 - Station Equipment	03/01/2020	692
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706728	A15706728 Shadow for A15706538	42677293SWP	WELSH HVDC EAST TIE 345KV SUBSTATION	35200 - Structures and Improvements	04/01/2018	8,922
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706728	A15706728 Shadow for A15706538	42677293SWP	WELSH HVDC EAST TIE 345KV SUBSTATION	35300 - Station Equipment	04/01/2018	231,575
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706728	A15706728 Shadow for A15706538	42677293SWP	WELSH HVDC EAST TIE 345KV SUBSTATION	35316 Station Equipment-SmartGrid	04/01/2018	12,021
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706730	A15706730 Shadow for A15706623	42707036SWP	VERNON MAIN STEET 138KV SUBSTATION	35200 Structures and Improvements	05/01/2019	25,143

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706730	A15706730 Shadow for A15706623	42707036SWP	VERNON MAIN STEET 138KV SUBSTATION	35300 - Station Equipment	05/01/2019	280,396
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706730	A15706730 Shadow for A15706623	42707036SWP	VERNON MAIN STEET 138KV SUBSTATION	35316 - Station Equipment-SmartGrid	05/01/2019	43
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C02	A15706C02 SEP-East Leesville Hicks-Rehab	42644366	2017 REHAB E LEESVILLE-HICKS 69 KV SEPTL347	35500 - Poles and Fixtures	07/01/2017	388,248
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C03	A15706C03 SHADOW for A15706C02	42644366SWP	2017 REHAB E LEESVILLE-HICKS 69 KV SEPTL347	35500 - Poles and Fixtures	07/01/2017	199,174
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706C08	A15706C08 Shadow for A15706558	42645078SWP	SOUTH SHREVEPORT STATION REHAB	35200 - Structures and Improvements	12/01/2017	18,731
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C08	A15706C08 Shadow for A15706558	42645078SWP	SOUTH SHREVEPORT STATION REHAB	35300 - Station Equipment	12/01/2017	350,323
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C08	A15706C08 Shadow for A15706558	42645078SWP	SOUTH SHREVEPORT STATION REHAB	35316 - Station Equipment-SmartGrid	12/01/2017	2,721
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C15	A15706C15 SEP-WILKES-NNEWBOSTON-RHB	42650846	2017 REHAB WILKES-NORTH NEW BOSTON SEPTL246	35500 - Poles and Fixtures	06/01/2017	353,921
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C16	A15706C16 Shadow for A15706C15	42650846SWP	2017 REHAB WILKES-NORTH NEW BOSTON SEPTL246	35500 - Poles and Fixtures	06/01/2017	181,069
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C19	A15706C19 T/SWEPCO/NWTEX OCB10770 FAIL	42665151	NORTHWEST TEXARKANA REPLACE FAILED 138KV OCB 10770	35300 - Station Equipment	11/01/2017	56,495
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C23	A15706C23 SEP-CARTHAGE-CB2560 RHB	42660819	CARTHAGE - MURVAUL REC TAP 69KV REPLACE POLES & ARMS	35500 - Poles and Fixtures	08/01/2018	109,576
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C24	A15706C24 Shadow for A15706C23	42660819SWP	CARTHAGE - MURVAUL REC TAP 69KV REPLACE POLES & ARMS	35500 - Poles and Fixtures	08/01/2018	55,757
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C27	A15706C27 SEP-TaylorSt-ThirtyNinthSt-RHB	42673502	2017 REHAB TAYLOR ST 39TH ST TEXAS TLN194 0213N	35500 - Poles and Fixtures	06/01/2017	137,880
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706C27	A15706C27 SEP-TaylorSt-ThirtyNinthSt-RHB	42673502	2017 REHAB TAYLOR ST - 39TH ST TEXAS TLN194 0213N	35600 - Overhead Conductors, Device	06/01/2017	26,263
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C28	A15706C28 Shadow For A15706C27 SEP	42673502SWP	2017 REHAB TAYLOR ST 39TH ST TEXAS TLN194 0213N	35500 - Poles and Fixtures	06/01/2017	70,788
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C28	A15706C28 Shadow For A15706C27 SEP	42673502SWP	2017 REHAB TAYLOR ST - 39TH ST TEXAS TLN194 0213N	35600 - Overhead Conductors, Device	06/01/2017	13,483
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C31	A15706C31 SEP-Diana-Pliler REHAB	42668026	2017 REHAB DIANA-PLILER SEPTL249A REPL STR 150-178	35500 - Poles and Fixtures	04/01/2017	197,067
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706C32	A15706C32 Shadow For A15706C31	42668026SWP	2017 REHAB DIANA-PLILER SEPTL249A REPL STR 150-178	35500 - Poles and Fixtures	04/01/2017	101,156
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C33	A15706C33 SEP NLeesville Hornbeck REHAB	42694057	2017 REHAB 69KV N LEESVILLE-HORNBECK REPL 34 POLES 150 XARM	35500 - Poles and Fixtures	07/01/2017	576,759
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C34	A15706C34 Shadow For A15706C33	42694057SWP	2017 REHAB 69KV N LEESVILLE-HORNBECK REPL 34 POLES 150 XARM	35500 - Poles and Fixtures	07/01/2017	296,197
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706C39	A15706C39 SEP-RedPoint-DeanPoint-RHB	42704592	2017 REHAB 138KV LIEBERMAN RED POINT 132 3 REPL 100+ STR	35500 - Poles and Fixtures	10/01/2017	1,524,987
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C40	A15706C40 Shadow For A15706C39	42704592SWP	2017 REHAB 138KV LIEBERMAN-RED POINT 132 3 REPL 100+ STR	35500 - Poles and Fixtures	10/01/2017	782,478
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706C41	A15706C41 SEP Arsenal Hill-ShedRoad-RHB	42690455	2017 REHAB ARSENAL HILL - SHED RD 69KV REPL 14 STRUCTURES	35500 - Poles and Fixtures	06/01/2017	318,660
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C42	A15706C42 Shadow For A15706C41	42690455SWP	2017 REHAB ARSENAL HILL - SHED RD 69KV REPL 14 STRUCTURES	35500 - Poles and Fixtures	06/01/2017	163,532
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C43	A15706C43 SEP Blanchard-NorthMarket-RHB	42716999	2017 REHAB - 69KV BLANCHARD - N MARKET REPL 125 WOOD W STEEL	35500 - Poles and Fixtures	09/01/2018	1,854,284
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C44	A15706C44 Shadow For A15706C43	42716999SWP	2017 REHAB - 69KV BLANCHARD - N MARKET REPL 125 WOOD W STEEL	35500 - Poles and Fixtures	09/01/2018	956,667
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C53	A15706C53 SEP-MurfWest-Dierks-RHB	42683366	2017 REHAB MURFREESBORO WEST - REPL POLES/ARMS/STRUCTURES	35500 - Poles and Fixtures	06/01/2017	84,135
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C54	A15706C54 Shadow For A15706C53	42683366SWP	2017 REHAB MURFREESBORO WEST - REPL POLES/ARMS/STRUCTURES	35500 - Poles and Fixtures	06/01/2017	43,221
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C55	A15706C55 SEP-Dierks-Mena-RHB	42675934	2017 REHAB 69KV DIERKS - MENA REPL 14 POLES/ARMS	35500 - Poles and Fixtures	07/01/2017	110,007
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C56	A15706C56 Shadow For A15706C55	42675934SWP	2017 REHAB 69KV DIERKS - MENA REPL 14 POLES/ARMS	35500 - Poles and Fixtures	07/01/2017	56,446
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706C57	A15706C57 SEP-PrairieGrove-SiloamSpr-RHB	42684637	2017 REHAB SILOAM SPRINGS - PRAIRIE GROVE REPL 46 STRUCTURES	35500 - Poles and Fixtures	07/01/2017	540,743
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C58	A15706C58 Shadow For A15706C57	42684637SWP	2017 REHAB SILOAM SPRINGS - PRAIRIE GROVE REPL 46 STRUCTURES	35500 - Poles and Fixtures	07/01/2017	277,821
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C63	A15706C63 SEP-Dyess-Springdale1-RHB	42705364	2017 REHAB SPRINGDALE-DYESS #1 LINE 154	35500 - Poles and Fixtures	02/01/2018	1,334,299
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C64	A15706C64 Shadow For A15706C63	42705364SWP	2017 REHAB SPRINGDALE-DYESS #1 LINE 154	35500 - Poles and Fixtures	02/01/2018	685,456
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C71	A15706C71 SEP-GrandSaline-Quitman-RHB	42696060	2017 REHAB GRAND SALINE - QUITMAN REPL 120 STRUCTURES 214B	35500 - Poles and Fixtures	06/01/2018	391,150
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706C72	A15706C72 Shadow For A15706C71	42696060SWP	2017 REHAB GRAND SALINE QUITMAN REPL 120 STRUCTURES 214B	35500 - Poles and Fixtures	05/01/2018	200,445
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706C73	A15706C73 SEP Winnsboro-Pittsburg-RHB	42706999	2018 REHAB WINNSBORO - PITTSBURG LINE 229 C/O 70 STR	35500 - Poles and Fixtures	08/01/2018	200,251
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C74	A15706C74 Shadow For A15706C73	42706999SWP	2018 REHAB WINNSBORO - PITTSBURG LINE 229 C/O 70 STR	35500 - Poles and Fixtures	08/01/2018	100,435
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706C95	A15706C95 SEP Sugarhill-Ashdown-RHB	42703649	2017 REHAB 12TH ST SUGAR HILL-ASHDOWN C/O MULT STR	35500 - Poles and Fixtures	01/01/2018	611,594
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C96	A15706C96 Shadow For A15706C95	42703649SWP	2017 REHAB 12TH ST SUGAR HILL-ASHDOWN C/O MULT STR	35500 - Poles and Fixtures	01/01/2018	313,575
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706C97	A15706C97 SEP-Nashville-WMurfreesbro-RHB	42706996	2017 REHAB NASHVILLE-MURFREESBORO W LINE 152D C/O 65 ST	35500 - Poles and Fixtures	01/01/2018	223,764
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706C98	A15706C98 Shadow For A15706C97	42706996SWP	2017 REHAB NASHVILLE-MURFREESBORO W LINE 152D C/O 65 ST	35500 - Poles and Fixtures	01/01/2018	114,860
TA2015706	TA2015706 Replace/Refurbish SWEPCo	A15706D02	A15706D02 SEP-Nashville-Okay-RHB	42706994	2017 REHAB NASHVILLE - OKAY LINE 153 C/O 60 STR	35500 - Poles and Fixtures	01/01/2018	513,532
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706D03	A15706D03 Shadow For A15706D02	42706994SWP	2017 REHAB NASHVILLE - OKAY LINE 153 C/O 60 STR	35500 - Poles and Fixtures	01/01/2018	263,492
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706D07	A15706D07 Shadow for A15706C19	42665151SWP	NORTHWEST TEXARKANA REPLACE FAILED 138KV OCB 10770	35300 - Station Equipment	11/01/2017	27,622
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706D10	A15706D10 T/SWEPCO/W_ATL W AUTO FAIL	42680737	WEST ATLANTA PURCHASE TRANSFORMER TO REPLACE FAILED UNIT	35300 - Station Equipment	12/01/2017	1,150,004
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706D12	A15706D12 T/SWEPCO/Chambers XFMR Failure	42694037	CHAMBER SPRINGS 345KV XFMR FAILURE REPLACEMENT	35200 - Structures and Improvements	10/01/2017	4,958
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706D12	A15706D12 T/SWEPCO/Chambers XFMR Failure	42694037	CHAMBER SPRINGS 345KV XFMR FAILURE REPLACEMENT	35300 - Station Equipment	10/01/2017	421,815
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706D12	A15706D12 T/SWEPCO/Chambers XFMR Failure	42694037	CHAMBER SPRINGS 345KV XFMR FAILURE REPLACEMENT	35316 - Station Equipment-SmartGrid	10/01/2017	251
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706D13	A15706D13 Shadow for A15706D10	42680737SWP	WEST ATLANTA - PURCHASE TRANSFORMER TO REPLACE FAILED UNIT	35300 - Station Equipment	12/01/2017	588,134
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706D14	A15706D14 Shadow for A15706D12	42694037SWP	CHAMBER SPRINGS 345KV XFMR FAILURE REPLACEMENT	35200 Structures and Improvements	10/01/2017	1,288
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706D14	A15706D14 Shadow for A15706D12	42694037SWP	CHAMBER SPRINGS 345KV XFMR FAILURE REPLACEMENT	35300 - Station Equipment	10/01/2017	109,578
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	A15706D14	A15706D14 Shadow for A15706D12	42694037SWP	CHAMBER SPRINGS 345KV XFMR FAILURE REPLACEMENT	35316 - Station Equipment-SmartGrid	10/01/2017	65
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14138004	P14138004 Brooks St Station Work	42572769	BROOKS STREET STATION WORK	35200 - Structures and Improvements	12/01/2017	127,936
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14138004	P14138004 Brooks St Station Work	42572769	BROOKS STREET STATION WORK	35300 - Station Equipment	12/01/2017	587,583
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14138005	P14138005 Edwards St Station Work	42572788	EDWARDS STREET STATION WORK	35200 - Structures and Improvements	12/01/2017	82,278
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14138005	P14138005 Edwards St Station Work	42572788	EDWARDS STREET STATION WORK	35300 - Station Equipment	12/01/2017	440,784
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14138006	P14138006 SHADOW P14138004	42572769SWP	BROOKS STREET STATION WORK	35200 - Structures and Improvements	12/01/2017	65,107
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14138006	P14138006 SHADOW P14138004	42572769SWP	BROOKS STREET STATION WORK	35300 - Station Equipment	12/01/2017	299,022
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14138007	P14138007 SHADOW for P14138005	42572788SWP	EDWARDS STREET STATION WORK	35200 - Structures and Improvements	12/01/2017	41,825
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14138007	P14138007 SHADOW for P14138005	42572788SWP	EDWARDS STREET STATION WORK	35300 - Station Equipment	12/01/2017	224,067
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14139003	P14139003 Linwood Station work	42589268	LINWOOD STATION WORK	35200 - Structures and Improvements	06/01/2018	3
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14139003	P14139003 Linwood Station work	42589268	LINWOOD STATION WORK	35300 - Station Equipment	06/01/2018	417,114
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14139004	P14139004 South Shreveport Station work	42589299	SOUTH SHREVEPORT STATION	35200 - Structures and Improvements	06/01/2018	1
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14139004	P14139004 South Shreveport Station work	42589299	SOUTH SHREVEPORT STATION	35300 - Station Equipment	06/01/2018	654,503
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14139503	P14139503 Linwood Station work *SHADOW*	42589268SWP	LINWOOD STATION WORK	35200 - Structures and Improvements	05/01/2018	1
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14139503	P14139503 Linwood Station work *SHADOW*	42589268SWP	LINWOOD STATION WORK	35300 - Station Equipment	05/01/2018	212,125
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14139504	P14139504 S Shreveport Station *SHADOW*	42589299SWP	SOUTH SHREVEPORT STATION	35200 - Structures and Improvements	05/01/2018	1
TA2015706	TA2015706 Replace/Refurbish - SWEPCo	P14139504	P14139504 S Shreveport Station *SHADOW*	42589299SWP	SOUTH SHREVEPORT STATION	35300 - Station Equipment	05/01/2018	334,748
	TA2015706 Replace/Refurbish - SWEPCo Total							27,920,634
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15706D20	A15706D20 Texarkana Plant-SE Texar Fiber	42755615	SOUTHEAST TEXARKANA STATION TEXARKANA PLANT STATION FIBER	35600 - Overhead Conductors, Device	12/01/2017	3,669

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15706D20	A15706D20 Texarkana Plant-SE Texar Fiber	42755615	SOUTHEAST TEXARKANA STATION TEXARKANA PLANT STATION FIBER	35616 - OVH Cond-Dev-Smart Grid	12/01/2017	6,492
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15706D20	A15706D20 Texarkana Plant-SE Texar Fiber	42755615	SOUTHEAST TEXARKANA STATION - TEXARKANA PLANT STATION FIBER	35700 - Underground Conduit	12/01/2017	26,406
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15706D20	A15706D20 Texarkana Plant-SE Texar Fiber	42755615	SOUTHEAST TEXARKANA STATION - TEXARKANA PLANT STATION FIBER	35816 - Ug Cond Dev-Smart Grid	12/01/2017	298
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713001	A15713001 Northwest Texarkana Telecom Mo	42706962	2017 TTMP NW TEXARKANA SUBSTATION WO	35300 - Station Equipment	10/01/2018	2,327
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713001	A15713001 Northwest Texarkana Telecom Mo	42706962	2017 TTMP NW TEXARKANA SUBSTATION WO	35316 - Station Equipment-SmartGrid	10/01/2018	4,239
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713003	A15713003 NW Texarkana Str 12 TelModFi	42679702	TTMP 2017 BANN STA - NORTHWEST TEXARKANA STA FIBER WO	35600 - Overhead Conductors, Device	09/01/2018	41,094
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713003	A15713003 NW Texarkana - Str 12 TelModFi	42679702	TTMP 2017 BANN STA - NORTHWEST TEXARKANA STA FIBER WO	35616 - OVH Cond-Dev Smart Grid	09/01/2018	109,617
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713003	A15713003 NW Texarkana Str 12 TelModFi	42679702	TTMP 2017 BANN STA - NORTHWEST TEXARKANA STA FIBER WO	35700 - Underground Conduit	09/01/2018	51,997
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713003	A15713003 NW Texarkana - Str 12 TelModFi	42679702	TTMP 2017 BANN STA - NORTHWEST TEXARKANA STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	09/01/2018	936
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713009	A15713009 Fayetville - Fayetville LMR Te	42691381	TTMP 2017 FAYETTEVILLE STA - FAYETTEVILLE LMR FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	18,085
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713009	A15713009 Fayetville - Fayetville LMR Te	42691381	TTMP 2017 FAYETTEVILLE STA - FAYETTEVILLE LMR FIBER WO	35616 OVH Cond-Dev-Smart Grid	01/01/2018	73,231
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713009	A15713009 Fayetville - Fayetville LMR Te	42691381	TTMP 2017 FAYETTEVILLE STA - FAYETTEVILLE LMR FIBER WO	35700 - Underground Conduit	01/01/2018	42,666
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713009	A15713009 Fayetville - Fayetville LMR Te	42691381	TTMP 2017 FAYETTEVILLE STA - FAYETTEVILLE LMR FIBER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	782
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713012	A15713012 Knox Lee Telecom Modernization	42703695	2017 TTMP KNOX LEE SUBSTATION WO	35300 - Station Equipment	08/01/2018	9,324
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713012	A15713012 Knox Lee Telecom Modernization	42703695	2017 TTMP KNOX LEE SUBSTATION WO	35316 - Station Equipment-SmartGrid	08/01/2018	17,443
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713013	A15713013 Tatum Telecom Modernization	42704499	2017 TTMP TATUM SUBSTATION WO	35300 - Station Equipment	08/01/2018	17,375
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713013	A15713013 Tatum Telecom Modernization	42704499	2017 TTMP TATUM SUBSTATION WO	35316 - Station Equipment-SmartGrid	08/01/2018	19,800
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713014	A15713014 Rock Hill Telecom Modernizatio	42703707	2017 TTMP ROCK HILL SUBSTATION WO	35300 Station Equipment	08/01/2018	9,311
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713014	A15713014 Rock Hill Telecom Modernizatio	42703707	2017 TTMP ROCK HILL SUBSTATION WO	35316 - Station Equipment-SmartGrid	08/01/2018	17,419
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713020	A15713020 Shadow SWEPCO A15713001	42706962SWP	2017 TTMP NW TEXARKANA SUBSTATION WO	35300 - Station Equipment	10/01/2018	1,181
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713020	A15713020 Shadow SWEPCO A15713001	42706962SWP	2017 TTMP NW TEXARKANA SUBSTATION WO	35316 - Station Equipment-SmartGrid	10/01/2018	2,152
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713022	A15713022 Shadow SWEPCO A15713003	42679702SWP	TTMP 2017 BANN STA - NORTHWEST TEXARKANA STA FIBER WO	35600 - Overhead Conductors, Device	09/01/2018	21,106
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713022	A15713022 Shadow SWEPCO A15713003	42679702SWP	TTMP 2017 BANN STA - NORTHWEST TEXARKANA STA FIBER WO	35616 OVH Cond-Dev-Smart Grid	09/01/2018	56,300
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713022	A15713022 Shadow SWEPCO A15713003	42679702SWP	TTMP 2017 BANN STA - NORTHWEST TEXARKANA STA FIBER WO	35700 Underground Conduit	09/01/2018	26,706
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713022	A15713022 Shadow SWEPCO A15713003	42679702SWP	TTMP 2017 BANN STA - NORTHWEST TEXARKANA STA FIBER WO	35816 Ug Cond-Dev Smart Grid	09/01/2018	480
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713026	A15713026 Shadow SWEPCO A15713009	42691381SWP	TTMP 2017 FAYETTEVILLE STA - FAYETTEVILLE LMR FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	9,285
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713026	A15713026 Shadow SWEPCO A15713009	42691381SWP	TTMP 2017 FAYETTEVILLE STA - FAYETTEVILLE LMR FIBER WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	37,598
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713026	A15713026 Shadow SWEPCO A15713009	42691381SWP	TTMP 2017 FAYETTEVILLE STA - FAYETTEVILLE LMR FIBER WO	35700 - Underground Conduit	01/01/2018	21,906
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713026	A15713026 Shadow SWEPCO A15713009	42691381SWP	TTMP 2017 FAYETTEVILLE STA - FAYETTEVILLE LMR FIBER WO	35816 Ug Cond-Dev-Smart Grid	01/01/2018	401
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713029	A15713029 Shadow SWEPCO A15713012	42703695SWP	2017 TTMP KNOX LEE SUBSTATION WO	35300 - Station Equipment	08/01/2018	4,744
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713029	A15713029 Shadow SWEPCO A15713012	42703695SWP	2017 TTMP KNOX LEE SUBSTATION WO	35316 Station Equipment-SmartGrid	08/01/2018	8,876
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713030	A15713030 Shadow SWEPCO A15713013	42704499SWP	2017 TTMP TATUM SUBSTATION WO	35300 - Station Equipment	08/01/2018	8,878
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713030	A15713030 Shadow SWEPCO A15713013	42704499SWP	2017 TTMP TATUM SUBSTATION WO	35316 Station Equipment-SmartGrid	08/01/2018	10,117
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713031	A15713031 Shadow SWEPCO A15713014	42703707SWP	2017 TTMP ROCK HILL SUBSTATION WO	35300 - Station Equipment	08/01/2018	4,754
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713031	A15713031 Shadow SWEPCO A15713014	42703707SWP	2017 TTMP ROCK HILL SUBSTATION WO	35316 - Station Equipment-SmartGrid	08/01/2018	8,894
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713035	A15713035 Sugar Hill - Turk TelModFib	42678970	TTMP 2017 SUGAR HILL STATION - TURK STATION FIBER CABLE WO	35600 - Overhead Conductors, Device	03/01/2018	81,165
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713035	A15713035 Sugar Hill - Turk TelModFib	42678970	TTMP 2017 SUGAR HILL STATION - TURK STATION FIBER CABLE WO	35616 - OVH Cond-Dev-Smart Grid	03/01/2018	702,438
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713035	A15713035 Sugar Hill - Turk TelModFib	42678970	TTMP 2017 SUGAR HILL STATION - TURK STATION FIBER CABLE WO	35700 - Underground Conduit	03/01/2018	56,303
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713035	A15713035 Sugar Hill - Turk TelModFib	42678970	TTMP 2017 SUGAR HILL STATION - TURK STATION FIBER CABLE WO	35816 - Ug Cond-Dev-Smart Grid	03/01/2018	1,017
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713036	A15713036 39th Street - Taylor TelModFib	42691786	TTMP 2017 39TH STREET STATION - TAYLOR STATION FIBER WO	35600 - Overhead Conductors, Device	06/01/2018	24,921
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713036	A15713036 39th Street - Taylor TelModFib	42691786	TTMP 2017 39TH STREET STATION - TAYLOR STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	06/01/2018	111,397
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713036	A15713036 39th Street - Taylor TelModFib	42691786	TTMP 2017 39TH STREET STATION - TAYLOR STATION FIBER WO	35700 - Underground Conduit	06/01/2018	48,587
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713036	A15713036 39th Street - Taylor TelModFib	42691786	TTMP 2017 39TH STREET STATION - TAYLOR STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	06/01/2018	878
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713039	A15713039 Taylor Texarkana Ops TelModFib	42691795	TTMP 2017 TAYLOR STA - TEXARKANA OP CENTER FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	28,914
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713039	A15713039 Taylor Texarkana Ops TelModFib	42691795	TTMP 2017 TAYLOR STA - TEXARKANA OP CENTER FIBER WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	78,129
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713039	A15713039 Taylor Texarkana Ops TelModFib	42691795	TTMP 2017 TAYLOR STA - TEXARKANA OP CENTER FIBER WO	35700 Underground Conduit	01/01/2018	47,816
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713039	A15713039 Taylor Texarkana Ops TelModFib	42691795	TTMP 2017 TAYLOR STA - TEXARKANA OP CENTER FIBER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	861
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713052	A15713052 Sugar Hill (SW) Telecom Modern	42689413	TTMP 2017 SUGAR HILL 138KV SUBSTATION WO	35200 - Structures and Improvements	12/01/2018	1,288
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713052	A15713052 Sugar Hill (SW) Telecom Modern	42689413	TTMP 2017 SUGAR HILL 138KV SUBSTATION WO	35300 - Station Equipment	12/01/2018	15,697
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713052	A15713052 Sugar Hill (SW) Telecom Modern	42689413	TTMP 2017 SUGAR HILL 138KV SUBSTATION WO	35316 - Station Equipment-SmartGrid	12/01/2018	29,070
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713069	A15713069 Fayettville South Fayetvile	42679708	TTMP 2017 FAYETTEVILLE STA-SOUTH FAYETTEVILLE STA FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	26,539
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713069	A15713069 Fayettville - South Fayetvile	42679708	TTMP 2017 FAYETTEVILLE STA-SOUTH FAYETTEVILLE STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	58,032
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713069	A15713069 Fayettville - South Fayetvile	42679708	TTMP 2017 FAYETTEVILLE STA-SOUTH FAYETTEVILLE STA FIBER WO	35700 - Underground Conduit	01/01/2018	51,741
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713069	A15713069 Fayettville - South Fayetvile	42679708	TTMP 2017 FAYETTEVILLE STA-SOUTH FAYETTEVILLE STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	934
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713070	A15713070 Farmington - South Fayetville	42679698	TTMP 2017 FARMINGTON STA - SOUTH FAYETTVILLE STA FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	22,992
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713070	A15713070 Farmington - South Fayetville	42679698	TTMP 2017 FARMINGTON STA SOUTH FAYETTVILLE STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	87,862
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713070	A15713070 Farmington - South Fayetville	42679698	TTMP 2017 FARMINGTON STA - SOUTH FAYETTVILLE STA FIBER WO	35700 - Underground Conduit	01/01/2018	44,474
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713070	A15713070 Farmington - South Fayetville	42679698	TTMP 2017 FARMINGTON STA SOUTH FAYETTVILLE STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	780
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713071	A15713071 Cherokee Connection - Knox Lee	42679697	TTMP 2017 CHEROKEE CONNECTION STA - KNOX LEE STA FIBER WO	35600 Overhead Conductors, Device	02/01/2018	17,586
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713071	A15713071 Cherokee Connection - Knox Lee	42679697	TTMP 2017 CHEROKEE CONNECTION STA - KNOX LEE STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	02/01/2018	103,806
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713071	A15713071 Cherokee Connection - Knox Lee	42679697	TTMP 2017 CHEROKEE CONNECTION STA - KNOX LEE STA FIBER WO	35700 Underground Conduit	02/01/2018	53,186
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713071	A15713071 Cherokee Connection - Knox Lee	42679697	TTMP 2017 CHEROKEE CONNECTION STA - KNOX LEE STA FIBER WO	35816 Ug Cond-Dev-Smart Grid	02/01/2018	975
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713072	A15713072 Cherokee Connection - Tatum	42679694	TTMP 2017 CHEROKEE CONNECTION STA - TATUM STA FIBER WO	35600 - Overhead Conductors, Device	02/01/2018	26,948
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713072	A15713072 Cherokee Connection - Tatum	42679694	TTMP 2017 CHEROKEE CONNECTION STA - TATUM STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	02/01/2018	195,196
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713072	A15713072 Cherokee Connection - Tatum	42679694	TTMP 2017 CHEROKEE CONNECTION STA - TATUM STA FIBER WO	35700 Underground Conduit	02/01/2018	52,644
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713072	A15713072 Cherokee Connection - Tatum	42679694	TTMP 2017 CHEROKEE CONNECTION STA - TATUM STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	02/01/2018	948
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713073	A15713073 Eastex SW - Knox Lee TelModFib	42679692	TTMP 2017 EASTEX SWITCHING STA - KNOX LEE STA FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	28,791
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713073	A15713073 Eastex SW - Knox Lee TelModFib	42679692	TTMP 2017 EASTEX SWITCHING STA - KNOX LEE STA FIBER WO	35616 OVH Cond-Dev-Smart Grid	01/01/2018	180,269
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713073	A15713073 Eastex SW - Knox Lee TelModFib	42679692	TTMP 2017 EASTEX SWITCHING STA - KNOX LEE STA FIBER WO	35700 - Underground Conduit	01/01/2018	56,245
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713073	A15713073 Eastex SW - Knox Lee TelModFib	42679692	TTMP 2017 EASTEX SWITCHING STA - KNOX LEE STA FIBER WO	35816 - Ug Cond Dev-Smart Grid	01/01/2018	1,012
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713075	A15713075 Rock Hill - Tatum TelModFib	42679689	TTMP 2017 ROCK HILL STATION TATUM STATION FIBER CABLE WO	35600 - Overhead Conductors, Device	01/01/2018	21,409

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713075	A15713075 Rock Hill - Tatum TelModFib	42679689	TTMP 2017 ROCK HILL STATION - TATUM STATION FIBER CABLE WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	153,222
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713075	A15713075 Rock Hill - Tatum TelModFib	42679689	TTMP 2017 ROCK HILL STATION TATUM STATION FIBER CABLE WO	35700 - Underground Conduit	01/01/2018	51,084
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713075	A15713075 Rock Hill - Tatum TelModFib	42679689	TTMP 2017 ROCK HILL STATION - TATUM STATION FIBER CABLE WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	919
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713076	A15713076 Ashdown - Str 158A1-2A TelModF	42679688	TTMP 2017 ASHDOWN STA - STRUCTURE 158A1-2A FIBER CABLE WO	35600 - Overhead Conductors, Device	01/01/2018	41,578
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713076	A15713076 Ashdown - Str 158A1-2A TelModF	42679688	TTMP 2017 ASHDOWN STA - STRUCTURE 158A1-2A FIBER CABLE WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	124,294
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713076	A15713076 Ashdown - Str 158A1-2A TelModF	42679688	TTMP 2017 ASHDOWN STA - STRUCTURE 158A1-2A FIBER CABLE WO	35700 - Underground Conduit	01/01/2018	98,091
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713076	A15713076 Ashdown - Str 158A1-2A TelModF	42679688	TTMP 2017 ASHDOWN STA - STRUCTURE 158A1-2A FIBER CABLE WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	1,798
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713077	A15713077 Ashdown - Str 194 TelModFib	42679687	TTMP 2017 ASHDOWN STATION - SUGAR HILL STATION FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	42,282
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713077	A15713077 Ashdown - Str 194 TelModFib	42679687	TTMP 2017 ASHDOWN STATION - SUGAR HILL STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	425,090
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713077	A15713077 Ashdown - Str 194 TelModFib	42679687	TTMP 2017 ASHDOWN STATION - SUGAR HILL STATION FIBER WO	35700 - Underground Conduit	01/01/2018	47,925
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713077	A15713077 Ashdown - Str 194 TelModFib	42679687	TTMP 2017 ASHDOWN STATION - SUGAR HILL STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	879
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713078	A15713078 Domtar - Str 63 TelModFib	42679685	TTMP 2017 DOMTAR STATION - STRUCTURE 62 FIBER CABLE WO	35600 - Overhead Conductors, Device	03/01/2018	19,251
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713078	A15713078 Domtar - Str 63 TelModFib	42679685	TTMP 2017 DOMTAR STATION - STRUCTURE 62 FIBER CABLE WO	35616 - OVH Cond-Dev-Smart Grid	03/01/2018	68,011
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713078	A15713078 Domtar - Str 63 TelModFib	42679685	TTMP 2017 DOMTAR STATION - STRUCTURE 62 FIBER CABLE WO	35700 - Underground Conduit	03/01/2018	45,416
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713078	A15713078 Domtar - Str 63 TelModFib	42679685	TTMP 2017 DOMTAR STATION - STRUCTURE 62 FIBER CABLE WO	35816 - Ug Cond-Dev-Smart Grid	03/01/2018	833
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713079	A15713079 Chamber Springs - Siloam Sprin	42701951	2018 TTMP CHAMBER SPRINGS STA - SILOAM SPRINGS STA FIBER WO	35600 Overhead Conductors, Device	07/01/2018	13,727
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713079	A15713079 Chamber Springs - Siloam Sprin	42701951	2018 TTMP CHAMBER SPRINGS STA - SILOAM SPRINGS STA FIBER WO	35616 OVH Cond-Dev-Smart Grid	07/01/2018	193,751
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713079	A15713079 Chamber Springs - Siloam Sprin	42701951	2018 TTMP CHAMBER SPRINGS STA - SILOAM SPRINGS STA FIBER WO	35700 - Underground Conduit	07/01/2018	47,577
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713079	A15713079 Chamber Springs - Siloam Sprin	42701951	2018 TTMP CHAMBER SPRINGS STA SILOAM SPRINGS STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	07/01/2018	539
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713080	A15713080 Flint Creek - Siloam Springs T	42702026	2018 TTMP FLINT CREEK STATION - SILOAM SPRINGS STA FIBER WO	35600 - Overhead Conductors, Device	09/01/2018	42,950
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713080	A15713080 Flint Creek - Siloam Springs T	42702026	2018 TTMP FLINT CREEK STATION - SILOAM SPRINGS STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	09/01/2018	385,220
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713080	A15713080 Flint Creek - Siloam Springs T	42702026	2018 TTMP FLINT CREEK STATION - SILOAM SPRINGS STA FIBER WO	35700 Underground Conduit	09/01/2018	70,403
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713080	A15713080 Flint Creek - Siloam Springs T	42702026	2018 TTMP FLINT CREEK STATION - SILOAM SPRINGS STA FIBER WO	35816 - Ug Cond Dev-Smart Grid	09/01/2018	1,289
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713083	A15713083 Red Point - Whitehurst TelModF	42677342	TTMP 2017 RED POINT STA - WHITEHURST STA FIBER CABLE WO	35600 - Overhead Conductors, Device	01/01/2018	46,310
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713083	A15713083 Red Point - Whitehurst TelModF	42677342	TTMP 2017 RED POINT STA - WHITEHURST STA FIBER CABLE WO	35616 OVH Cond-Dev Smart Grid	01/01/2018	220,647
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713083	A15713083 Red Point Whitehurst TelModF	42677342	TTMP 2017 RED POINT STA - WHITEHURST STA FIBER CABLE WO	35700 - Underground Conduit	01/01/2018	84,505
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713083	A15713083 Red Point - Whitehurst TelModF	42677342	TTMP 2017 RED POINT STA - WHITEHURST STA FIBER CABLE WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	1,549
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713088	A15713088 South Fayetteville TTMP	42704451	2017 TTMP SOUTH FAYETTEVILLE SUBSTATION WO	35200 - Structures and Improvements	06/01/2018	806
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713088	A15713088 South Fayetteville TTMP	42704451	2017 TTMP SOUTH FAYETTEVILLE SUBSTATION WO	35300 - Station Equipment	06/01/2018	9,260
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713088	A15713088 South Fayetteville TTMP	42704451	2017 TTMP SOUTH FAYETTEVILLE SUBSTATION WO	35316 - Station Equipment-SmartGrid	06/01/2018	18,320
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713090	A15713090 Red Point TTMP	42704478	2017 TTMP RED POINT SUBSTATION WO	35300 Station Equipment	06/01/2018	656
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713090	A15713090 Red Point TTMP	42704478	2017 TTMP RED POINT SUBSTATION WO	35316 - Station Equipment-SmartGrid	06/01/2018	4,857
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713091	A15713091 Eastex Switching Station TTMP	42697190	TTMP 2017 EASTEX SWITCHING STATION 138KV WO	35300 - Station Equipment	08/01/2018	3,279
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713091	A15713091 Eastex Switching Station TTMP	42697190	TTMP 2017 EASTEX SWITCHING STATION 138KV WO	35316 - Station Equipment-SmartGrid	08/01/2018	24,027
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713092	A15713092 Turk TTMP	42697186	TTMP 2017 TURK 138KV STATION WO	35200 - Structures and Improvements	02/01/2019	2,270
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713092	A15713092 Turk TTMP	42697186	TTMP 2017 TURK 138KV STATION WO	35300 - Station Equipment	02/01/2019	17,725
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713092	A15713092 Turk TTMP	42697186	TTMP 2017 TURK 138KV STATION WO	35316 - Station Equipment-SmartGrid	02/01/2019	34,408
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713093	A15713093 Springdale -East Rogers TelMod	42723613	2018 TTMP - DYESS STATION - EAST ROGERS STATION FIBER WO	35600 - Overhead Conductors, Device	09/01/2019	87,596
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713093	A15713093 Springdale -East Rogers TelMod	42723613	2018 TTMP - DYESS STATION - EAST ROGERS STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	09/01/2019	710,794
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713093	A15713093 Springdale -East Rogers TelMod	42723613	2018 TTMP - DYESS STATION - EAST ROGERS STATION FIBER WO	35700 - Underground Conduit	09/01/2019	171,169
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713093	A15713093 Springdale -East Rogers TelMod	42723613	2018 TTMP - DYESS STATION - EAST ROGERS STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	09/01/2019	1,936
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713094	A15713094 Dyess-Gregg Str TelModFib	42717902	2018 TTMP - DYESS STATION - GREGG STREET STATION FIBER WO	35600 - Overhead Conductors, Device	09/01/2018	55,656
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713094	A15713094 Dyess-Gregg Str TelModFib	42717902	2018 TTMP - DYESS STATION - GREGG STREET STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	09/01/2018	271,310
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713094	A15713094 Dyess-Gregg Str TelModFib	42717902	2018 TTMP - DYESS STATION - GREGG STREET STATION FIBER WO	35700 - Underground Conduit	09/01/2018	94,936
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713094	A15713094 Dyess-Gregg Str TelModFib	42717902	2018 TTMP - DYESS STATION GREGG STREET STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	09/01/2018	1,073
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713095	A15713095 East Fayetteville -Hyland TelM	42717907	2018 TTMP - EAST FAYETTEVILLE STA - HYLAND STA FIBER WO	35600 - Overhead Conductors, Device	12/01/2019	21,584
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713095	A15713095 East Fayetteville -Hyland TelM	42717907	2018 TTMP - EAST FAYETTEVILLE STA - HYLAND STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	12/01/2019	192,309
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713095	A15713095 East Fayetteville -Hyland TelM	42717907	2018 TTMP - EAST FAYETTEVILLE STA - HYLAND STA FIBER WO	35700 - Underground Conduit	12/01/2019	49,366
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713095	A15713095 East Fayetteville -Hyland TelM	42717907	2018 TTMP - EAST FAYETTEVILLE STA - HYLAND STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	12/01/2019	558
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713097	A15713097 FayettevilleLMR-Hyland TelModF	42716389	2018 TTMP - FAYETTEVILLE LMR - HYLAND STATION FIBER WO	35600 - Overhead Conductors, Device	08/01/2019	7,422
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713097	A15713097 FayettevilleLMR-Hyland TelModF	42716389	2018 TTMP - FAYETTEVILLE LMR - HYLAND STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	08/01/2019	46,981
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713097	A15713097 FayettevilleLMR-Hyland TelModF	42716389	2018 TTMP - FAYETTEVILLE LMR - HYLAND STATION FIBER WO	35700 - Underground Conduit	08/01/2019	53,319
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713097	A15713097 FayettevilleLMR-Hyland TelModF	42716389	2018 TTMP - FAYETTEVILLE LMR - HYLAND STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	08/01/2019	603
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713098	A15713098 Gates-Longview Heights TelModF	42719353	2018 TTMP - GATES STATION - LONGVIEW HEIGHTS STA FIBER WO	35600 - Overhead Conductors, Device	07/01/2018	29,386
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713098	A15713098 Gates-Longview Heights TelModF	42719353	2018 TTMP - GATES STATION - LONGVIEW HEIGHTS STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	07/01/2018	94,658
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713098	A15713098 Gates-Longview Heights TelModF	42719353	2018 TTMP - GATES STATION LONGVIEW HEIGHTS STA FIBER WO	35700 - Underground Conduit	07/01/2018	41,759
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713098	A15713098 Gates-Longview Heights TelModF	42719353	2018 TTMP - GATES STATION - LONGVIEW HEIGHTS STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	07/01/2018	766
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713099	A15713099 Greenland-SFayettevilleTelModF	42716968	2018 TTMP - GREENLAND STATION - S FAYETTEVILLE STA FIBER WO	35600 - Overhead Conductors, Device	07/01/2018	19,892
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713099	A15713099 Greenland-SFayettevilleTelModF	42716968	2018 TTMP - GREENLAND STATION - S FAYETTEVILLE STA FIBER WO	35616 - OVH Cond-Dev Smart Grid	07/01/2018	128,713
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713099	A15713099 Greenland-SFayettevilleTelModF	42716968	2018 TTMP GREENLAND STATION - S FAYETTEVILLE STA FIBER WO	35700 - Underground Conduit	07/01/2018	54,842
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713099	A15713099 Greenland-SFayettevilleTelModF	42716968	2018 TTMP - GREENLAND STATION - S FAYETTEVILLE STA FIBER WO	35816 - Ug Cond-Dev Smart Grid	07/01/2018	621
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713100	A15713100 Greggton-Lake Lamond TelModFib	42723614	2018 TTMP - GREGGTON STATION - LAKE LAMOND STATION FIBER WO	35600 - Overhead Conductors, Device	07/01/2018	12,551
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713100	A15713100 Greggton-Lake Lamond TelModFib	42723614	2018 TTMP - GREGGTON STATION - LAKE LAMOND STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	07/01/2018	85,657
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713100	A15713100 Greggton-Lake Lamond TelModFib	42723614	2018 TTMP - GREGGTON STATION - LAKE LAMOND STATION FIBER WO	35700 - Underground Conduit	07/01/2018	58,805
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713100	A15713100 Greggton-Lake Lamond TelModFib	42723614	2018 TTMP - GREGGTON STATION - LAKE LAMOND STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	07/01/2018	664
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713101	A15713101 Greggton - Perdue TelModFib	42724152	2018 TTMP - GREGGTON STATION - PERDUE STATION FIBER WO	35600 - Overhead Conductors, Device	11/01/2018	46,772
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713101	A15713101 Greggton - Perdue TelModFib	42724152	2018 TTMP - GREGGTON STATION - PERDUE STATION FIBER WO	35616 - OVH Cond-Dev Smart Grid	11/01/2018	302,176
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713101	A15713101 Greggton - Perdue TelModFib	42724152	2018 TTMP - GREGGTON STATION - PERDUE STATION FIBER WO	35700 - Underground Conduit	11/01/2018	68,257
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713101	A15713101 Greggton - Perdue TelModFib	42724152	2018 TTMP - GREGGTON STATION - PERDUE STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	11/01/2018	770
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713102	A15713102 Knox Lee - NW Henderson TelMod	42724173	2018 TTMP - KNOX LEE STATION - NWT HENDERSON STA FIBER WO	35600 - Overhead Conductors, Device	09/01/2019	54,232
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713102	A15713102 Knox Lee - NW Henderson TelMod	42724173	2018 TTMP - KNOX LEE STATION - NWT HENDERSON STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	09/01/2019	610,617

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713102	A15713102 Knox Lee - NW Henderson TelMod	42724173	2018 TTMP - KNOX LEE STATION - NWT HENDERSON STA FIBER WO	35700 - Underground Conduit	09/01/2019	99,144
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713102	A15713102 Knox Lee - NW Henderson TelMod	42724173	2018 TTMP - KNOX LEE STATION - NWT HENDERSON STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	09/01/2019	1,084
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713103	A15713103 Longview - Str 19 TelModFib	42853170	2018 TTMP LONGVIEW STATION STRUCTURE 19 FIBER WO	35600 - Overhead Conductors, Device	09/01/2018	29,793
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713103	A15713103 Longview - Str 19 TelModFib	42853170	2018 TTMP - LONGVIEW STATION - STRUCTURE 19 FIBER WO	35616 - OVH Cond-Dev-Smart Grid	09/01/2018	21,298
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713103	A15713103 Longview Str 19 TelModFib	42853170	2018 TTMP - LONGVIEW STATION - STRUCTURE 19 FIBER WO	35700 - Underground Conduit	09/01/2018	25,307
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713103	A15713103 Longview - Str 19 TelModFib	42853170	2018 TTMP - LONGVIEW STATION - STRUCTURE 19 FIBER WO	35816 - Ug Cond-Dev-Smart Grid	09/01/2018	281
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713104	A15713104 Longview - Whitney TelModFib	42724192	2018 TTMP - LONGVIEW STATION - WHITNEY STATION FIBER WO	35600 - Overhead Conductors, Device	03/01/2018	6,533
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713104	A15713104 Longview - Whitney TelModFib	42724192	2018 TTMP - LONGVIEW STATION - WHITNEY STATION FIBER WO	35616 - OVH Cond-Dev Smart Grid	03/01/2018	65,973
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713104	A15713104 Longview - Whitney TelModFib	42724192	2018 TTMP LONGVIEW STATION - WHITNEY STATION FIBER WO	35700 - Underground Conduit	03/01/2018	47,021
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713104	A15713104 Longview - Whitney TelModFib	42724192	2018 TTMP - LONGVIEW STATION - WHITNEY STATION FIBER WO	35816 - Ug Cond Dev-Smart Grid	03/01/2018	531
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713105	A15713105 Osburn - Springdale TelModFib	42725075	2018 TTMP OSBURN STATION - SPRINGDALE STATION FIBER WO	35600 - Overhead Conductors, Device	09/01/2019	9,407
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713105	A15713105 Osburn - Springdale TelModFib	42725075	2018 TTMP - OSBURN STATION - SPRINGDALE STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	09/01/2019	34,201
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713105	A15713105 Osburn - Springdale TelModFib	42725075	2018 TTMP - OSBURN STATION - SPRINGDALE STATION FIBER WO	35700 - Underground Conduit	09/01/2019	44,020
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713105	A15713105 Osburn - Springdale TelModFib	42725075	2018 TTMP - OSBURN STATION - SPRINGDALE STATION FIBER WO	35816 - Ug Cond Dev-Smart Grid	09/01/2019	498
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713106	A15713106 Springdale - Tontitown TelModF	42718252	2018 TTMP - SPRINGDALE STATION - TONTITOWN STATION FIBER WO	35600 - Overhead Conductors, Device	10/01/2018	51,568
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713106	A15713106 Springdale - Tontitown TelModF	42718252	2018 TTMP - SPRINGDALE STATION - TONTITOWN STATION FIBER WO	35616 - OVH Cond-Dev Smart Grid	10/01/2018	317,445
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713106	A15713106 Springdale - Tontitown TelModF	42718252	2018 TTMP - SPRINGDALE STATION - TONTITOWN STATION FIBER WO	35700 - Underground Conduit	10/01/2018	128,928
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713106	A15713106 Springdale Tontitown TelModF	42718252	2018 TTMP - SPRINGDALE STATION - TONTITOWN STATION FIBER WO	35816 Ug Cond-Dev-Smart Grid	10/01/2018	1,458
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713110	A15713110 East Rogers TTMP	42706338	2018 TTMP EAST ROGERS SUBSTATION	35300 - Station Equipment	09/01/2019	2,616
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713110	A15713110 East Rogers TTMP	42706338	2018 TTMP EAST ROGERS SUBSTATION	35316 - Station Equipment-SmartGrid	09/01/2019	20,519
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713116	A15713116 Tontitown Station TTMP	42706235	2018 TTMP TONTITOWN SUBSTATION WO	35300 - Station Equipment	12/01/2018	8,248
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713116	A15713116 Tontitown Station TTMP	42706235	2018 TTMP TONTITOWN SUBSTATION WO	35316 - Station Equipment-SmartGrid	12/01/2018	18,607
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713119	A15713119 Chambers Spring TTMP	42706222	2018 TTMP CHAMBERS SPRING SUBSTATION	35300 Station Equipment	08/01/2018	8,026
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713119	A15713119 Chambers Spring TTMP	42706222	2018 TTMP CHAMBERS SPRING SUBSTATION	35316 - Station Equipment-SmartGrid	08/01/2018	14,898
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713120	A15713120 Siloam Springs TTMP	42706214	2018 TTMP SILOAM SPRINGS SUBSTATION WO	35300 Station Equipment	10/01/2018	2,735
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713120	A15713120 Siloam Springs TTMP	42706214	2018 TTMP SILOAM SPRINGS SUBSTATION WO	35316 - Station Equipment-SmartGrid	10/01/2018	21,509
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713121	A15713121 Flint Creek Station TTMP	42706218	2018 TTMP FLINT CREEK SUBSTATION WO	35300 - Station Equipment	10/01/2018	9,898
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713121	A15713121 Flint Creek Station TTMP	42706218	2018 TTMP FLINT CREEK SUBSTATION WO	35316 - Station Equipment-SmartGrid	10/01/2018	18,378
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713126	A15713126 Perdue Station TTMP	42706208	2018 TTMP PERDUE SUBSTATION WO	35300 - Station Equipment	11/01/2018	9,831
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713126	A15713126 Perdue Station TTMP	42706208	2018 TTMP PERDUE SUBSTATION WO	35316 - Station Equipment-SmartGrid	11/01/2018	25,738
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713151	A15713151 Minden Road TTMP	42773249	2019 TTMP MINDEN ROAD STATION WO	35300 - Station Equipment	10/01/2018	(4)
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713166	A15713166 Longwood Transition Fiber	42935593	TTMP - LONGWOOD STATION ENTRANCE - FIBER - WO	35600 - Overhead Conductors, Device	08/01/2019	8,828
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713166	A15713166 Longwood Transition Fiber	42935593	TTMP - LONGWOOD STATION ENTRANCE - FIBER WO	35700 - Underground Conduit	08/01/2019	63,527
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713166	A15713166 Longwood Transition Fiber	42935593	TTMP - LONGWOOD STATION ENTRANCE - FIBER - WO	35816 - Ug Cond-Dev-Smart Grid	08/01/2019	717
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713168	A15713168 Brush Creek TTMP	42936000	TTMP BRUSH CREEK STATION - WO	35316 - Station Equipment-SmartGrid	01/01/2020	16,445
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713169	A15713169 Shadow for A15713168 No WOs!	42936000SWP	TTMP - BRUSH CREEK STATION - WO	35316 - Station Equipment-SmartGrid	01/01/2020	8,366
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713170	A15713170 Brush Creek TelModFib	42936019	TTMP - BRUSH CREEK STATION - TONTITOWN STATION - FIBER - WO	35600 - Overhead Conductors, Device	12/01/2019	35,511
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713170	A15713170 Brush Creek TelModFib	42936019	TTMP - BRUSH CREEK STATION - TONTITOWN STATION - FIBER - WO	35616 - OVH Cond-Dev-Smart Grid	12/01/2019	135,343
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713170	A15713170 Brush Creek TelModFib	42936019	TTMP - BRUSH CREEK STATION - TONTITOWN STATION - FIBER - WO	35700 - Underground Conduit	12/01/2019	83,230
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713170	A15713170 Brush Creek TelModFib	42936019	TTMP - BRUSH CREEK STATION - TONTITOWN STATION - FIBER - WO	35816 - Ug Cond Dev-Smart Grid	12/01/2019	930
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713171	A15713171 Shadow for A15713170 No WOS	42936019SWP	TTMP BRUSH CREEK STATION - TONTITOWN STATION - FIBER - WO	35600 - Overhead Conductors Device	12/01/2019	18,245
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713171	A15713171 Shadow for A15713170 No WOS	42936019SWP	TTMP - BRUSH CREEK STATION - TONTITOWN STATION - FIBER - WO	35616 - OVH Cond-Dev-Smart Grid	12/01/2019	69,536
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713171	A15713171 Shadow for A15713170 No WOS	42936019SWP	TTMP BRUSH CREEK STATION - TONTITOWN STATION - FIBER - WO	35700 - Underground Conduit	12/01/2019	42,762
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713171	A15713171 Shadow for A15713170 No WOS	42936019SWP	TTMP - BRUSH CREEK STATION - TONTITOWN STATION - FIBER - WO	35816 - Ug Cond-Dev-Smart Grid	12/01/2019	478
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713174	A15713174 Lowell (SEP) TTMP	42936736	SWEPCO TTMP - LOWELL STATION - WO	35300 - Station Equipment	09/01/2019	41,421
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713174	A15713174 Lowell (SEP) TTMP	42936736	SWEPCO TTMP - LOWELL STATION WO	35316 - Station Equipment-SmartGrid	09/01/2019	16,063
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713175	A15713175 Shadow for A15713174 No WOs	42936736SWP	SWEPCO TTMP - LOWELL STATION - WO	35300 - Station Equipment	09/01/2019	20,910
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713175	A15713175 Shadow for A15713174 No WOs	42936736SWP	SWEPCO TTMP - LOWELL STATION - WO	35316 - Station Equipment-SmartGrid	09/01/2019	8,109
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713178	A15713178 Northwest Henderson TTMP	42937118	SWEPCO TTMP - NORTHWEST HENDERSON 138KV SUBSTATION - WO	35300 - Station Equipment	09/01/2019	10,733
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713178	A15713178 Northwest Henderson TTMP	42937118	SWEPCO TTMP - NORTHWEST HENDERSON 138KV SUBSTATION - WO	35316 - Station Equipment-SmartGrid	09/01/2019	11,590
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713179	A15713179 Shadow for A15713178	42937118SWP	SWEPCO TTMP - NORTHWEST HENDERSON 138KV SUBSTATION - WO	35300 - Station Equipment	09/01/2019	5,407
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713179	A15713179 Shadow for A15713178	42937118SWP	SWEPCO TTMP - NORTHWEST HENDERSON 138KV SUBSTATION - WO	35316 - Station Equipment-SmartGrid	09/01/2019	5,838
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713180	A15713180 Osburn Station TTMP	42937188	SWEPCO TTMP - OSBURN STATION - WO	35316 - Station Equipment-SmartGrid	09/01/2019	22,311
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713181	A15713181 Shadow for A15713180 No WOs	42937188SWP	SWEPCO TTMP - OSBURN STATION - WO	35316 - Station Equipment SmartGrid	09/01/2019	11,317
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713197	A15713197 Shadow for A15713166 No WO's!	42935593SWP	TTMP - LONGWOOD STATION ENTRANCE - FIBER - WO	35600 - Overhead Conductors, Device	08/01/2019	4,527
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713197	A15713197 Shadow for A15713166 No WO's!	42935593SWP	TTMP - LONGWOOD STATION ENTRANCE - FIBER - WO	35700 - Underground Conduit	08/01/2019	32,580
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713197	A15713197 Shadow for A15713166 No WO's!	42935593SWP	TTMP - LONGWOOD STATION ENTRANCE - FIBER WO	35816 - Ug Cond Dev-Smart Grid	08/01/2019	368
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713C02	A15713C02 Shadow for A15706D20 No WOs	42755615SWP	SOUTHEAST TEXARKANA STATION - TEXARKANA PLANT STATION FIBER	35600 - Overhead Conductors, Device	12/01/2017	1,881
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713C02	A15713C02 Shadow for A15706D20 No WOs	42755615SWP	SOUTHEAST TEXARKANA STATION - TEXARKANA PLANT STATION FIBER	35616 - OVH Cond-Dev-Smart Grid	12/01/2017	3,328
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713C02	A15713C02 Shadow for A15706D20 No WOs	42755615SWP	SOUTHEAST TEXARKANA STATION - TEXARKANA PLANT STATION FIBER	35700 - Underground Conduit	12/01/2017	13,535
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713C02	A15713C02 Shadow for A15706D20 No WOs	42755615SWP	SOUTHEAST TEXARKANA STATION - TEXARKANA PLANT STATION FIBER	35816 - Ug Cond Dev-Smart Grid	12/01/2017	153
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S02	A15713S02 Shadow for A15713035 No WOs	42678970SWP	TTMP 2017 SUGAR HILL STATION - TURK STATION FIBER CABLE WO	35600 - Overhead Conductors, Device	03/01/2018	41,653
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S02	A15713S02 Shadow for A15713035 No WOs	42678970SWP	TTMP 2017 SUGAR HILL STATION - TURK STATION FIBER CABLE WO	35616 - OVH Cond-Dev-Smart Grid	03/01/2018	360,487
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S02	A15713S02 Shadow for A15713035 No WOs	42678970SWP	TTMP 2017 SUGAR HILL STATION TURK STATION FIBER CABLE WO	35700 - Underground Conduit	03/01/2018	28,895
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S02	A15713S02 Shadow for A15713035 No WOs	42678970SWP	TTMP 2017 SUGAR HILL STATION - TURK STATION FIBER CABLE WO	35816 - Ug Cond-Dev-Smart Grid	03/01/2018	522
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S03	A15713S03 Shadow for A15713036 No WOs	42691786SWP	TTMP 2017 39TH STREET STATION - TAYLOR STATION FIBER WO	35600 - Overhead Conductors, Device	06/01/2018	12,793
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713S03	A15713S03 Shadow for A15713036 No WOs	42691786SWP	TTMP 2017 39TH STREET STATION - TAYLOR STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	06/01/2018	57,185
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S03	A15713S03 Shadow for A15713036 No WOs	42691786SWP	TTMP 2017 39TH STREET STATION - TAYLOR STATION FIBER WO	35700 - Underground Conduit	06/01/2018	24,942
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S03	A15713S03 Shadow for A15713036 No WOs	42691786SWP	TTMP 2017 39TH STREET STATION - TAYLOR STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	06/01/2018	451
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S04	A15713S04 Farmington - Farmington AECCTe	42681593	TTMP 2017 FARMINGTON STATION - FARMINGTON OEC STATION WO	35600 - Overhead Conductors, Device	01/01/2018	16,165
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S04	A15713S04 Farmington Farmington AECCTe	42681593	TTMP 2017 FARMINGTON STATION - FARMINGTON OEC STATION WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	101,073

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S04	A15713S04 Farmington - Farmington AECCTe	42681593	TTMP 2017 FARMINGTON STATION - FARMINGTON OEC STATION WO	35700 Underground Conduit	01/01/2018	68,994
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S04	A15713S04 Farmington Farmington AECCTe	42681593	TTMP 2017 FARMINGTON STATION FARMINGTON OEC STATION WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	1,247
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S05	A15713S05 Gregg Street - Fayettville	42679710	TTMP 2017 GREGG STREET STA - FAYETTVILLE STA FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	15,760
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S05	A15713S05 Gregg Street - Fayettville	42679710	TTMP 2017 GREGG STREET STA - FAYETTVILLE STA FIBER WO	35616 - OVH Cond-Dev Smart Grid	01/01/2018	96,225
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S05	A15713S05 Gregg Street - Fayettville	42679710	TTMP 2017 GREGG STREET STA - FAYETTVILLE STA FIBER WO	35700 - Underground Conduit	01/01/2018	67,262
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713S05	A15713S05 Gregg Street - Fayettville	42679710	TTMP 2017 GREGG STREET STA - FAYETTVILLE STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	1,215
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S06	A15713S06 Gregg Street - Fayettville SC	42679715	TTMP 2017 GREGG STREET STA - FAYETTVILLE SERVICE CENTER WO	35600 - Overhead Conductors, Device	01/01/2018	28,263
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713S06	A15713S06 Gregg Street - Fayettville SC	42679715	TTMP 2017 GREGG STREET STA - FAYETTVILLE SERVICE CENTER WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	15,362
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S06	A15713S06 Gregg Street - Fayettville SC	42679715	TTMP 2017 GREGG STREET STA FAYETTVILLE SERVICE CENTER WO	35700 - Underground Conduit	01/01/2018	66,710
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S06	A15713S06 Gregg Street - Fayettville SC	42679715	TTMP 2017 GREGG STREET STA - FAYETTVILLE SERVICE CENTER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	1,098
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S09	A15713S09 Hardy- Midway Telmodfib	42677368	TTMP 2017 HARDY ST STA MIDWAY SPLICE POINT FIBER WO	35600 - Overhead Conductors, Device	06/01/2017	13,250
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S09	A15713S09 Hardy- Midway Telmodfib	42677368	TTMP 2017 HARDY ST STA - MIDWAY SPLICE POINT FIBER WO	35616 - OVH Cond-Dev Smart Grid	06/01/2017	25,286
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S09	A15713S09 Hardy- Midway Telmodfib	42677368	TTMP 2017 HARDY ST STA MIDWAY SPLICE POINT FIBER WO	35700 - Underground Conduit	06/01/2017	31,615
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713S09	A15713S09 Hardy- Midway Telmodfib	42677368	TTMP 2017 HARDY ST STA - MIDWAY SPLICE POINT FIBER WO	35816 - Ug Cond Dev-Smart Grid	06/01/2017	569
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S12	A15713S12 Shadow for A15713039	42691795SWP	TTMP 2017 TAYLOR STA - TEXARKANA OP CENTER FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	14,853
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S12	A15713S12 Shadow for A15713039	42691795SWP	TTMP 2017 TAYLOR STA - TEXARKANA OP CENTER FIBER WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	40,135
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S12	A15713S12 Shadow for A15713039	42691795SWP	TTMP 2017 TAYLOR STA - TEXARKANA OP CENTER FIBER WO	35700 - Underground Conduit	01/01/2018	24,563
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S12	A15713S12 Shadow for A15713039	42691795SWP	TTMP 2017 TAYLOR STA - TEXARKANA OP CENTER FIBER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	442
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S25	A15713S25 Shadow for A15713052	42689413SWP	TTMP 2017 SUGAR HILL 138KV SUBSTATION WO	35200 - Structures and Improvements	12/01/2018	654
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S25	A15713S25 Shadow for A15713052	42689413SWP	TTMP 2017 SUGAR HILL 138KV SUBSTATION WO	35300 - Station Equipment	12/01/2018	7,967
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S25	A15713S25 Shadow for A15713052	42689413SWP	TTMP 2017 SUGAR HILL 138KV SUBSTATION WO	35316 - Station Equipment-SmartGrid	12/01/2018	14,755
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S31	A15713S31 Shadow for A15713S04	42681593SWP	TTMP 2017 FARMINGTON STATION - FARMINGTON OEC STATION WO	35600 - Overhead Conductors, Device	01/01/2018	8,297
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S31	A15713S31 Shadow for A15713S04	42681593SWP	TTMP 2017 FARMINGTON STATION - FARMINGTON OEC STATION WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	51,875
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S31	A15713S31 Shadow for A15713S04	42681593SWP	TTMP 2017 FARMINGTON STATION - FARMINGTON OEC STATION WO	35700 - Underground Conduit	01/01/2018	35,411
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S31	A15713S31 Shadow for A15713S04	42681593SWP	TTMP 2017 FARMINGTON STATION - FARMINGTON OEC STATION WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	640
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S32	A15713S32 Shadow for A15713S05	42679710SWP	TTMP 2017 GREGG STREET STA - FAYETTVILLE STA FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	8,093
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S32	A15713S32 Shadow for A15713S05	42679710SWP	TTMP 2017 GREGG STREET STA - FAYETTVILLE STA FIBER WO	35616 - OVH Cond Dev-Smart Grid	01/01/2018	49,413
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S32	A15713S32 Shadow for A15713S05	42679710SWP	TTMP 2017 GREGG STREET STA FAYETTVILLE STA FIBER WO	35700 Underground Conduit	01/01/2018	34,540
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S32	A15713S32 Shadow for A15713S05	42679710SWP	TTMP 2017 GREGG STREET STA - FAYETTVILLE STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	624
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S33	A15713S33 Shadow for A15713S06	42679715SWP	TTMP 2017 GREGG STREET STA - FAYETTVILLE SERVICE CENTER WO	35600 - Overhead Conductors, Device	01/01/2018	14,501
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S33	A15713S33 Shadow for A15713S06	42679715SWP	TTMP 2017 GREGG STREET STA - FAYETTVILLE SERVICE CENTER WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	7,882
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S33	A15713S33 Shadow for A15713S06	42679715SWP	TTMP 2017 GREGG STREET STA - FAYETTVILLE SERVICE CENTER WO	35700 - Underground Conduit	01/01/2018	34,227
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S33	A15713S33 Shadow for A15713S06	42679715SWP	TTMP 2017 GREGG STREET STA - FAYETTVILLE SERVICE CENTER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	563
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713S36	A15713S36 Shadow for A15713S09	42677368SWP	TTMP 2017 HARDY ST STA MIDWAY SPLICE POINT FIBER WO	35600 - Overhead Conductors, Device	06/01/2017	6,803
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S36	A15713S36 Shadow for A15713S09	42677368SWP	TTMP 2017 HARDY ST STA - MIDWAY SPLICE POINT FIBER WO	35616 - OVH Cond-Dev-Smart Grid	06/01/2017	12,982
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S36	A15713S36 Shadow for A15713S09	42677368SWP	TTMP 2017 HARDY ST STA - MIDWAY SPLICE POINT FIBER WO	35700 - Underground Conduit	06/01/2017	16,231
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713S36	A15713S36 Shadow for A15713S09	42677368SWP	TTMP 2017 HARDY ST STA - MIDWAY SPLICE POINT FIBER WO	35816 Ug Cond-Dev-Smart Grid	06/01/2017	292
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S37	A15713S37 Shadow for A15713069	42679708SWP	TTMP 2017 FAYETTEVILLE STA-SOUTH FAYETTEVILLE STA FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	13,632
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S37	A15713S37 Shadow for A15713069	42679708SWP	TTMP 2017 FAYETTEVILLE STA-SOUTH FAYETTEVILLE STA FIBER WO	35616 OVH Cond-Dev-Smart Grid	01/01/2018	29,809
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S37	A15713S37 Shadow for A15713069	42679708SWP	TTMP 2017 FAYETTEVILLE STA-SOUTH FAYETTEVILLE STA FIBER WO	35700 - Underground Conduit	01/01/2018	26,577
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S37	A15713S37 Shadow for A15713069	42679708SWP	TTMP 2017 FAYETTEVILLE STA-SOUTH FAYETTEVILLE STA FIBER WO	35816 - Ug Cond-Dev Smart Grid	01/01/2018	480
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S38	A15713S38 Shadow for A15713070	42679698SWP	TTMP 2017 FARMINGTON STA - SOUTH FAYETTVILLE STA FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	11,811
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S38	A15713S38 Shadow for A15713070	42679698SWP	TTMP 2017 FARMINGTON STA - SOUTH FAYETTVILLE STA FIBER WO	35616 OVH Cond-Dev-Smart Grid	01/01/2018	45,133
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S38	A15713S38 Shadow for A15713070	42679698SWP	TTMP 2017 FARMINGTON STA SOUTH FAYETTVILLE STA FIBER WO	35700 - Underground Conduit	01/01/2018	22,846
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S38	A15713S38 Shadow for A15713070	42679698SWP	TTMP 2017 FARMINGTON STA - SOUTH FAYETTVILLE STA FIBER WO	35816 Ug Cond-Dev Smart Grid	01/01/2018	401
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S39	A15713S39 Shadow for A15713071	42679697SWP	TTMP 2017 CHEROKEE CONNECTION STA - KNOX LEE STA FIBER WO	35600 - Overhead Conductors, Device	02/01/2018	9,034
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S39	A15713S39 Shadow for A15713071	42679697SWP	TTMP 2017 CHEROKEE CONNECTION STA - KNOX LEE STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	02/01/2018	53,327
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S39	A15713S39 Shadow for A15713071	42679697SWP	TTMP 2017 CHEROKEE CONNECTION STA KNOX LEE STA FIBER WO	35700 Underground Conduit	02/01/2018	27,322
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S39	A15713S39 Shadow for A15713071	42679697SWP	TTMP 2017 CHEROKEE CONNECTION STA KNOX LEE STA FIBER WO	35816 - Ug Cond-Dev Smart Grid	02/01/2018	501
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S40	A15713S40 Shadow for A15713072	42679694SWP	TTMP 2017 CHEROKEE CONNECTION STA TATUM STA FIBER WO	35600 - Overhead Conductors, Device	02/01/2018	13,845
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S40	A15713S40 Shadow for A15713072	42679694SWP	TTMP 2017 CHEROKEE CONNECTION STA - TATUM STA FIBER WO	35616 OVH Cond-Dev-Smart Grid	02/01/2018	100,285
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S40	A15713S40 Shadow for A15713072	42679694SWP	TTMP 2017 CHEROKEE CONNECTION STA - TATUM STA FIBER WO	35700 - Underground Conduit	02/01/2018	27,047
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S40	A15713S40 Shadow for A15713072	42679694SWP	TTMP 2017 CHEROKEE CONNECTION STA - TATUM STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	02/01/2018	487
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S41	A15713S41 Shadow for A15713073	42679692SWP	TTMP 2017 EASTEX SWITCHING STA - KNOX LEE STA FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	14,792
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S41	A15713S41 Shadow for A15713073	42679692SWP	TTMP 2017 EASTEX SWITCHING STA - KNOX LEE STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	92,618
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S41	A15713S41 Shadow for A15713073	42679692SWP	TTMP 2017 EASTEX SWITCHING STA - KNOX LEE STA FIBER WO	35700 - Underground Conduit	01/01/2018	28,897
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S41	A15713S41 Shadow for A15713073	42679692SWP	TTMP 2017 EASTEX SWITCHING STA - KNOX LEE STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	520
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S43	A15713S43 Shadow for A15713075	42679689SWP	TTMP 2017 ROCK HILL STATION - TATUM STATION FIBER CABLE WO	35600 - Overhead Conductors, Device	01/01/2018	10,999
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S43	A15713S43 Shadow for A15713075	42679689SWP	TTMP 2017 ROCK HILL STATION - TATUM STATION FIBER CABLE WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	78,721
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713S43	A15713S43 Shadow for A15713075	42679689SWP	TTMP 2017 ROCK HILL STATION - TATUM STATION FIBER CABLE WO	35700 - Underground Conduit	01/01/2018	26,245
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S43	A15713S43 Shadow for A15713075	42679689SWP	TTMP 2017 ROCK HILL STATION - TATUM STATION FIBER CABLE WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	472
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S44	A15713S44 Shadow for A15713076	42679688SWP	TTMP 2017 ASHDOWN STA - STRUCTURE 158A1-2A FIBER CABLE WO	35600 - Overhead Conductors, Device	01/01/2018	21,359
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S44	A15713S44 Shadow for A15713076	42679688SWP	TTMP 2017 ASHDOWN STA STRUCTURE 158A1 2A FIBER CABLE WO	35616 - OVH Cond-Dev-Smart Grid	01/01/2018	63,852
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S44	A15713S44 Shadow for A15713076	42679688SWP	TTMP 2017 ASHDOWN STA - STRUCTURE 158A1-2A FIBER CABLE WO	35700 - Underground Conduit	01/01/2018	50,391
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S44	A15713S44 Shadow for A15713076	42679688SWP	TTMP 2017 ASHDOWN STA - STRUCTURE 158A1-2A FIBER CABLE WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	924
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S45	A15713S45 Shadow for A15713077	42679687SWP	TTMP 2017 ASHDOWN STATION - SUGAR HILL STATION FIBER WO	35600 - Overhead Conductors, Device	01/01/2018	21,724
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S45	A15713S45 Shadow for A15713077	42679687SWP	TTMP 2017 ASHDOWN STATION - SUGAR HILL STATION FIBER WO	35616 OVH Cond Dev-Smart Grid	01/01/2018	218,400
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S45	A15713S45 Shadow for A15713077	42679687SWP	TTMP 2017 ASHDOWN STATION - SUGAR HILL STATION FIBER WO	35700 - Underground Conduit	01/01/2018	24,623
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S45	A15713S45 Shadow for A15713077	42679687SWP	TTMP 2017 ASHDOWN STATION - SUGAR HILL STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	451
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713S46	A15713S46 Shadow for A15713078	42679685SWP	TTMP 2017 DOMTAR STATION - STRUCTURE 62 FIBER CABLE WO	35600 - Overhead Conductors, Device	03/01/2018	9,872
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S46	A15713S46 Shadow for A15713078	42679685SWP	TTMP 2017 DOMTAR STATION - STRUCTURE 62 FIBER CABLE WO	35616 - OVH Cond Dev-Smart Grid	03/01/2018	34,877

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S46	A15713S46 Shadow for A15713078	42679685SWP	TTMP 2017 DOMTAR STATION - STRUCTURE 62 FIBER CABLE WO	35700 Underground Conduit	03/01/2018	23,290
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S46	A15713S46 Shadow for A15713078	42679685SWP	TTMP 2017 DOMTAR STATION - STRUCTURE 62 FIBER CABLE WO	35816 - Ug Cond-Dev-Smart Grid	03/01/2018	427
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S47	A15713S47 Shadow for A15713079	42701951SWP	2018 TTMP CHAMBER SPRINGS STA - SILOAM SPRINGS STA FIBER WO	35600 - Overhead Conductors, Device	07/01/2018	7,044
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S47	A15713S47 Shadow for A15713079	42701951SWP	2018 TTMP CHAMBER SPRINGS STA - SILOAM SPRINGS STA FIBER WO	35616 - OVH Cond Dev Smart Grid	07/01/2018	99,416
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S47	A15713S47 Shadow for A15713079	42701951SWP	2018 TTMP CHAMBER SPRINGS STA - SILOAM SPRINGS STA FIBER WO	35700 - Underground Conduit	07/01/2018	24,412
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S47	A15713S47 Shadow for A15713079	42701951SWP	2018 TTMP CHAMBER SPRINGS STA SILOAM SPRINGS STA FIBER WO	35816 Ug Cond Dev-Smart Grid	07/01/2018	276
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S48	A15713S48 Shadow for A15713080	42702026SWP	2018 TTMP FLINT CREEK STATION - SILOAM SPRINGS STA FIBER WO	35600 - Overhead Conductors, Device	09/01/2018	22,058
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S48	A15713S48 Shadow for A15713080	42702026SWP	2018 TTMP FLINT CREEK STATION - SILOAM SPRINGS STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	09/01/2018	197,839
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S48	A15713S48 Shadow for A15713080	42702026SWP	2018 TTMP FLINT CREEK STATION - SILOAM SPRINGS STA FIBER WO	35700 - Underground Conduit	09/01/2018	36,157
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S48	A15713S48 Shadow for A15713080	42702026SWP	2018 TTMP FLINT CREEK STATION - SILOAM SPRINGS STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	09/01/2018	662
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S51	A15713S51 Shadow for A15713083	42677342SWP	TTMP 2017 RED POINT STA - WHITEHURST STA FIBER CABLE WO	35600 - Overhead Conductors, Device	01/01/2018	23,789
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S51	A15713S51 Shadow for A15713083	42677342SWP	TTMP 2017 RED POINT STA - WHITEHURST STA FIBER CABLE WO	35616 - OVH Cond Dev Smart Grid	01/01/2018	113,344
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S51	A15713S51 Shadow for A15713083	42677342SWP	TTMP 2017 RED POINT STA - WHITEHURST STA FIBER CABLE WO	35700 - Underground Conduit	01/01/2018	43,409
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S51	A15713S51 Shadow for A15713083	42677342SWP	TTMP 2017 RED POINT STA - WHITEHURST STA FIBER CABLE WO	35816 - Ug Cond-Dev-Smart Grid	01/01/2018	796
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S55	A15713S55 Shadow for A15713088	42704451SWP	2017 TTMP SOUTH FAYETTEVILLE SUBSTATION WO	35200 - Structures and Improvements	06/01/2018	407
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S55	A15713S55 Shadow for A15713088	42704451SWP	2017 TTMP SOUTH FAYETTEVILLE SUBSTATION WO	35300 - Station Equipment	06/01/2018	4,678
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S55	A15713S55 Shadow for A15713088	42704451SWP	2017 TTMP SOUTH FAYETTEVILLE SUBSTATION WO	35316 - Station Equipment-SmartGrid	06/01/2018	9,255
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S56	A15713S56 Shadow for A15713090	42704478SWP	2017 TTMP RED POINT SUBSTATION WO	35300 - Station Equipment	06/01/2018	338
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S56	A15713S56 Shadow for A15713090	42704478SWP	2017 TTMP RED POINT SUBSTATION WO	35316 Station Equipment-SmartGrid	06/01/2018	2,504
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S57	A15713S57 Shadow for A15713091	42697190SWP	TTMP 2017 EASTEX SWITCHING STATION 138KV WO	35300 - Station Equipment	08/01/2018	1,665
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S57	A15713S57 Shadow for A15713091	42697190SWP	TTMP 2017 EASTEX SWITCHING STATION 138KV WO	35316 Station Equipment-SmartGrid	08/01/2018	12,197
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S58	A15713S58 Shadow for A15713092	42697186SWP	TTMP 2017 TURK 138KV STATION WO	35200 Structures and Improvements	02/01/2019	1,142
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S58	A15713S58 Shadow for A15713092	42697186SWP	TTMP 2017 TURK 138KV STATION WO	35300 Station Equipment	02/01/2019	8,916
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S58	A15713S58 Shadow for A15713092	42697186SWP	TTMP 2017 TURK 138KV STATION WO	35316 - Station Equipment-SmartGrid	02/01/2019	17,310
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S60	A15713S60 Shadow for A15713093 No WO's	42723613SWP	2018 TTMP - DYESS STATION - EAST ROGERS STATION FIBER WO	35600 - Overhead Conductors, Device	09/01/2019	44,986
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S60	A15713S60 Shadow for A15713093 No WO's	42723613SWP	2018 TTMP - DYESS STATION - EAST ROGERS STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	09/01/2019	365,039
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S60	A15713S60 Shadow for A15713093 No WO's	42723613SWP	2018 TTMP - DYESS STATION - EAST ROGERS STATION FIBER WO	35700 - Underground Conduit	09/01/2019	87,907
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S60	A15713S60 Shadow for A15713093 No WO's	42723613SWP	2018 TTMP - DYESS STATION - EAST ROGERS STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	09/01/2019	994
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S61	A15713S61 Shadow for A15713094 No WO's	42717902SWP	2018 TTMP - DYESS STATION - GREGG STREET STATION FIBER WO	35600 - Overhead Conductors, Device	09/01/2018	28,530
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S61	A15713S61 Shadow for A15713094 No WO's	42717902SWP	2018 TTMP - DYESS STATION - GREGG STREET STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	09/01/2018	139,079
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S61	A15713S61 Shadow for A15713094 No WO's	42717902SWP	2018 TTMP - DYESS STATION - GREGG STREET STATION FIBER WO	35700 - Underground Conduit	09/01/2018	48,666
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S61	A15713S61 Shadow for A15713094 No WO's	42717902SWP	2018 TTMP - DYESS STATION - GREGG STREET STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	09/01/2018	550
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S62	A15713S62 Shadow for A15713095 No WO's	42717907SWP	2018 TTMP - EAST FAYETTEVILLE STA - HYLAND STA FIBER WO	35600 - Overhead Conductors, Device	12/01/2019	11,082
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S62	A15713S62 Shadow for A15713095 No WO's	42717907SWP	2018 TTMP - EAST FAYETTEVILLE STA - HYLAND STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	12/01/2019	98,739
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713S62	A15713S62 Shadow for A15713095 No WO's	42717907SWP	2018 TTMP - EAST FAYETTEVILLE STA - HYLAND STA FIBER WO	35700 - Underground Conduit	12/01/2019	25,346
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S62	A15713S62 Shadow for A15713095 No WO's	42717907SWP	2018 TTMP - EAST FAYETTEVILLE STA - HYLAND STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	12/01/2019	286
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S64	A15713S64 Shadow for A15713097 No WO's	42716389SWP	2018 TTMP - FAYETTEVILLE LMR - HYLAND STATION FIBER WO	35600 - Overhead Conductors, Device	08/01/2019	3,922
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S64	A15713S64 Shadow for A15713097 No WO's	42716389SWP	2018 TTMP - FAYETTEVILLE LMR - HYLAND STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	08/01/2019	24,824
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S64	A15713S64 Shadow for A15713097 No WO's	42716389SWP	2018 TTMP - FAYETTEVILLE LMR - HYLAND STATION FIBER WO	35700 - Underground Conduit	08/01/2019	28,174
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S64	A15713S64 Shadow for A15713097 No WO's	42716389SWP	2018 TTMP - FAYETTEVILLE LMR - HYLAND STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	08/01/2019	318
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S65	A15713S65 Shadow for A15713098 No WO's	42719353SWP	2018 TTMP - GATES STATION LONGVIEW HEIGHTS STA FIBER WO	35600 Overhead Conductors, Device	07/01/2018	15,098
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S65	A15713S65 Shadow for A15713098 No WO's	42719353SWP	2018 TTMP GATES STATION - LONGVIEW HEIGHTS STA FIBER WO	35616 OVH Cond-Dev-Smart Grid	07/01/2018	48,631
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S65	A15713S65 Shadow for A15713098 No WO's	42719353SWP	2018 TTMP GATES STATION LONGVIEW HEIGHTS STA FIBER WO	35700 - Underground Conduit	07/01/2018	21,454
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S65	A15713S65 Shadow for A15713098 No WO's	42719353SWP	2018 TTMP - GATES STATION - LONGVIEW HEIGHTS STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	07/01/2018	393
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S66	A15713S66 Shadow for A15713099 No WO's	42716968SWP	2018 TTMP - GREENLAND STATION - S FAYETTEVILLE STA FIBER WO	35600 - Overhead Conductors, Device	07/01/2018	10,214
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S66	A15713S66 Shadow for A15713099 No WO's	42716968SWP	2018 TTMP - GREENLAND STATION - S FAYETTEVILLE STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	07/01/2018	66,087
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S66	A15713S66 Shadow for A15713099 No WO's	42716968SWP	2018 TTMP - GREENLAND STATION - S FAYETTEVILLE STA FIBER WO	35700 - Underground Conduit	07/01/2018	28,158
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S66	A15713S66 Shadow for A15713099 No WO's	42716968SWP	2018 TTMP - GREENLAND STATION - S FAYETTEVILLE STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	07/01/2018	319
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S67	A15713S67 Shadow for A15713100 No WO's	42723614SWP	2018 TTMP - GREGGTON STATION - LAKE LAMOND STATION FIBER WO	35600 Overhead Conductors, Device	07/01/2018	6,444
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S67	A15713S67 Shadow for A15713100 No WO's	42723614SWP	2018 TTMP - GREGGTON STATION - LAKE LAMOND STATION FIBER WO	35616 - OVH Cond Dev Smart Grid	07/01/2018	43,977
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S67	A15713S67 Shadow for A15713100 No WO's	42723614SWP	2018 TTMP - GREGGTON STATION LAKE LAMOND STATION FIBER WO	35700 - Underground Conduit	07/01/2018	30,191
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S67	A15713S67 Shadow for A15713100 No WO's	42723614SWP	2018 TTMP - GREGGTON STATION - LAKE LAMOND STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	07/01/2018	341
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S68	A15713S68 Shadow for A15713101 No WO's	42724152SWP	2018 TTMP - GREGGTON STATION - PERDUE STATION FIBER WO	35600 - Overhead Conductors, Device	11/01/2018	24,000
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S68	A15713S68 Shadow for A15713101 No WO's	42724152SWP	2018 TTMP - GREGGTON STATION - PERDUE STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	11/01/2018	155,052
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713S68	A15713S68 Shadow for A15713101 No WO's	42724152SWP	2018 TTMP - GREGGTON STATION - PERDUE STATION FIBER WO	35700 - Underground Conduit	11/01/2018	35,024
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S68	A15713S68 Shadow for A15713101 No WO's	42724152SWP	2018 TTMP - GREGGTON STATION PERDUE STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	11/01/2018	395
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S69	A15713S69 Shadow for A15713102 No WO's	42724173SWP	2018 TTMP - KNOX LEE STATION - NWT HENDERSON STA FIBER WO	35600 - Overhead Conductors, Device	09/01/2019	27,862
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S69	A15713S69 Shadow for A15713102 No WO's	42724173SWP	2018 TTMP - KNOX LEE STATION NWT HENDERSON STA FIBER WO	35616 - OVH Cond-Dev-Smart Grid	09/01/2019	313,713
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S69	A15713S69 Shadow for A15713102 No WO's	42724173SWP	2018 TTMP - KNOX LEE STATION - NWT HENDERSON STA FIBER WO	35700 - Underground Conduit	09/01/2019	50,937
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S69	A15713S69 Shadow for A15713102 No WO's	42724173SWP	2018 TTMP - KNOX LEE STATION - NWT HENDERSON STA FIBER WO	35816 - Ug Cond-Dev-Smart Grid	09/01/2019	557
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S70	A15713S70 Shadow for A15713103 No WO's	42853170SWP	2018 TTMP - LONGVIEW STATION - STRUCTURE 19 FIBER WO	35600 - Overhead Conductors, Device	09/01/2018	15,052
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S70	A15713S70 Shadow for A15713103 No WO's	42853170SWP	2018 TTMP LONGVIEW STATION - STRUCTURE 19 FIBER WO	35616 - OVH Cond Dev-Smart Grid	09/01/2018	10,760
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S70	A15713S70 Shadow for A15713103 No WO's	42853170SWP	2018 TTMP - LONGVIEW STATION STRUCTURE 19 FIBER WO	35700 - Underground Conduit	09/01/2018	12,786
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S70	A15713S70 Shadow for A15713103 No WO's	42853170SWP	2018 TTMP LONGVIEW STATION STRUCTURE 19 FIBER WO	35816 - Ug Cond-Dev-Smart Grid	09/01/2018	142
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S71	A15713S71 Shadow for A15713104 No Wo's	42724192SWP	2018 TTMP LONGVIEW STATION - WHITNEY STATION FIBER WO	35600 - Overhead Conductors, Device	03/01/2018	3,355
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S71	A15713S71 Shadow for A15713104 No Wo's	42724192SWP	2018 TTMP LONGVIEW STATION - WHITNEY STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	03/01/2018	33,877
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S71	A15713S71 Shadow for A15713104 No Wo's	42724192SWP	2018 TTMP - LONGVIEW STATION - WHITNEY STATION FIBER WO	35700 - Underground Conduit	03/01/2018	24,145
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S71	A15713S71 Shadow for A15713104 No Wo's	42724192SWP	2018 TTMP - LONGVIEW STATION - WHITNEY STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	03/01/2018	273
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S72	A15713S72 Shadow for A15713105 No WO's	42725075SWP	2018 TTMP - OSBURN STATION - SPRINGDALE STATION FIBER WO	35600 - Overhead Conductors, Device	09/01/2019	4,825
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S72	A15713S72 Shadow for A15713105 No WO's	42725075SWP	2018 TTMP - OSBURN STATION - SPRINGDALE STATION FIBER WO	35616 - OVH Cond-Dev-Smart Grid	09/01/2019	17,541
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S72	A15713S72 Shadow for A15713105 No WO's	42725075SWP	2018 TTMP OSBURN STATION - SPRINGDALE STATION FIBER WO	35700 Underground Conduit	09/01/2019	22,577

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S72	A15713S72 Shadow for A15713105 No WO's	42725075SWP	2018 TTMP - OSBURN STATION - SPRINGDALE STATION FIBER WO	35816 - Ug Cond-Dev-Smart Grid	09/01/2019	255
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S73	A15713S73 Shadow for A15713106 No WO's	42718252SWP	2018 TTMP - SPRINGDALE STATION - TONTITOWN STATION FIBER WO	35600 - Overhead Conductors, Device	10/01/2018	26,460
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S73	A15713S73 Shadow for A15713106 No WO's	42718252SWP	2018 TTMP - SPRINGDALE STATION - TONTITOWN STATION FIBER WO	35616 OVH Cond-Dev-Smart Grid	10/01/2018	162,883
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S73	A15713S73 Shadow for A15713106 No WO's	42718252SWP	2018 TTMP SPRINGDALE STATION - TONTITOWN STATION FIBER WO	35700 - Underground Conduit	10/01/2018	66,154
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S73	A15713S73 Shadow for A15713106 No WO's	42718252SWP	2018 TTMP SPRINGDALE STATION - TONTITOWN STATION FIBER WO	35816 - Ug Cond-Dev Smart Grid	10/01/2018	748
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S76	A15713S76 Shadow for A15713110 No WO's	42706338SWP	2018 TTMP EAST ROGERS SUBSTATION	35300 Station Equipment	09/01/2019	1,319
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S76	A15713S76 Shadow for A15713110 No WO's	42706338SWP	2018 TTMP EAST ROGERS SUBSTATION	35316 - Station Equipment-SmartGrid	09/01/2019	10,347
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S78	A15713S78 Shadow for A15713116 No WO's	42706235SWP	2018 TTMP TONTITOWN SUBSTATION WO	35300 - Station Equipment	12/01/2018	4,220
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S78	A15713S78 Shadow for A15713116 No WO's	42706235SWP	2018 TTMP TONTITOWN SUBSTATION WO	35316 - Station Equipment-SmartGrid	12/01/2018	9,521
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S80	A15713S80 Shadow for A15713119 No WO's	42706222SWP	2018 TTMP CHAMBERS SPRING SUBSTATION	35300 - Station Equipment	08/01/2018	4,053
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S80	A15713S80 Shadow for A15713119 No WO's	42706222SWP	2018 TTMP CHAMBERS SPRING SUBSTATION	35316 - Station Equipment-SmartGrid	08/01/2018	7,524
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S81	A15713S81 Shadow for A15713120 No WO's	42706214SWP	2018 TTMP SILOAM SPRINGS SUBSTATION WO	35300 Station Equipment	10/01/2018	1,386
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S81	A15713S81 Shadow for A15713120 No WO's	42706214SWP	2018 TTMP SILOAM SPRINGS SUBSTATION WO	35316 - Station Equipment-SmartGrid	10/01/2018	10,902
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S82	A15713S82 Shadow for A15713121 No WO's	42706218SWP	2018 TTMP FLINT CREEK SUBSTATION WO	35300 Station Equipment	10/01/2018	5,052
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S82	A15713S82 Shadow for A15713121 No WO's	42706218SWP	2018 TTMP FLINT CREEK SUBSTATION WO	35316 - Station Equipment-SmartGrid	10/01/2018	9,380
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S84	A15713S84 Shadow for A15713126 No WO's	42706208SWP	2018 TTMP PERDUE SUBSTATION WO	35300 Station Equipment	11/01/2018	5,002
TA2015713	TA2015713 Telecom Fiber Build Out-SWEPCo	A15713S84	A15713S84 Shadow for A15713126 No WO's	42706208SWP	2018 TTMP PERDUE SUBSTATION WO	35316 - Station Equipment-SmartGrid	11/01/2018	13,095
TA2015713	TA2015713 Telecom Fiber Build Out SWEPCo	A15713S81	A15713S81 Shadow for A15713151 No WO's	42773249SWP	2019 TTMP MINDEN ROAD STATION WO	35300 - Station Equipment	10/01/2018	7
	TA2015713 Telecom Fiber Build Out-SWEPCo Total							15,886,007
TA2016924	TA2016924 SWP Region Major Eq/Spares Pro	A16924008	A16924008 Purchase Spare 138kV Xfer	42926317	PIRKEY RESERVE YARD	35300 - Station Equipment	12/01/2019	595,543
TA2016924	TA2016924 SWP Region Major Eq/Spares Pro	A16924009	A16924009 Purchase Spare 138kV Transform	42926318	LONGVIEW OPS RESERVE	35300 - Station Equipment	12/01/2019	583,579
TA2016924	TA2016924 SWP Region Major Eq/Spares Pro	A16924012	A16924012 Shadow for A16924008 No WO's	42926317SWP	PIRKEY RESERVE YARD	35300 - Station Equipment	12/01/2019	305,876
TA2016924	TA2016924 SWP Region Major Eq/Spares Pro	A16924013	A16924013 Shadow for A16924009	42926318SWP	LONGVIEW OPS RESERVE	35300 - Station Equipment	12/01/2019	299,770
TA2016924	TA2016924 SWP Region Major Eq/Spares Pro	A17031001	A17031001 Tontitown Spare Prchse	42837810	TONTITOWN 345KV PRI/161KV SEC/13 8KV	35300 - Station Equipment	12/01/2019	3,246,563
TA2016924	TA2016924 SWP Region Major Eq/Spares Pro	A17031002	A17031002 Shadow for A17031001	42837810SWP	TONTITOWN 345KV PRI/161KV SEC/13 8KV	35300 - Station Equipment	12/01/2019	1,667,284
TA2016924	TA2016924 SWP Region Major Eq/Spares Pro	A17031005	A17031005 Pirkey Spare Purch 138kV	42838101	PIRKEY SPARE PURCHASE 138KV PRI/66-73 KV SEC Y-Y/< 13 2 KV	35300 Station Equipment	09/01/2019	703,577
TA2016924	TA2016924 SWP Region Major Eq/Spares Pro	A17031006	A17031006 Shadow for A17031005	42838101SWP	PIRKEY SPARE PURCHASE 138KV PRI/66-73 KV SEC Y-Y/< 13 2 KV	35300 - Station Equipment	09/01/2019	361,015
	TA2016924 SWP Region Major Eq/Spares Pro Total							7,763,206
TA2016930	TA2016930 SWEPCO 2016 May Storm - Texark	SELAA1603	SELAA1603 SWEPCO - TX Storm Shadow T	42549597SWP	S/9/16 STRM N W TEXARKANA-LYD	35400 - Towers and Fixtures	06/01/2016	3,401
TA2016930	TA2016930 SWEPCO 2016 May Storm - Texark	SELAA1603	SELAA1603 SWEPCO - TX - Storm Shadow - T	42549604SWP	S/9/16 STRM BANN-N W TEXARKAN	35500 - Poles and Fixtures	06/01/2016	3,566
TA2016930	TA2016930 SWEPCO 2016 May Storm - Texark	SELAA1603	SELAA1603 SWEPCO - TX - Storm Shadow - T	42549609SWP	S/9/16 STRM BANN N W TEX-SUGAR	35500 - Poles and Fixtures	06/01/2016	38
TA2016930	TA2016930 SWEPCO 2016 May Storm - Texark	SELAA1603	SELAA1603 SWEPCO - TX - Storm Shadow - T	42549681SWP	S/9/16 STRM LONGWOOD - WILKES	35400 - Towers and Fixtures	06/01/2016	1,105
TA2016930	TA2016930 SWEPCO 2016 May Storm - Texark	SELAA1603	SELAA1603 SWEPCO - TX - Storm Shadow - T	42575538SWP	5-9-16 STRM N W TEXARKANA-LYDI	35400 - Towers and Fixtures	06/01/2017	288,558
TA2016930	TA2016930 SWEPCO 2016 May Storm - Texark	SETXS1603	SETXS1603 SWEPCO - TX - Storm - Transmis	42549597	S/9/16 STRM N W TEXARKANA-LYD	35400 - Towers and Fixtures	06/01/2016	6,637
TA2016930	TA2016930 SWEPCO 2016 May Storm - Texark	SETXS1603	SETXS1603 SWEPCO - TX - Storm - Transmis	42549604	S/9/16 STRM BANN-N W TEXARKAN	35500 - Poles and Fixtures	06/01/2016	6,941
TA2016930	TA2016930 SWEPCO 2016 May Storm - Texark	SETXS1603	SETXS1603 SWEPCO - TX - Storm - Transmis	42549609	S/9/16 STRM BANN-N W TEX-SUGAR	35500 - Poles and Fixtures	06/01/2016	74
TA2016930	TA2016930 SWEPCO 2016 May Storm - Texark	SETXS1603	SETXS1603 SWEPCO - TX - Storm - Transmis	42549681	S/9/16 STRM LONGWOOD - WILKES	35400 Towers and Fixtures	06/01/2016	2,151
TA2016930	TA2016930 SWEPCO 2016 May Storm - Texark	SETXS1603	SETXS1603 SWEPCO - TX - Storm - Transmis	42575538	5-9-16 STRM N W TEXARKANA-LYDI	35400 - Towers and Fixtures	06/01/2017	562,342
	TA2016930 SWEPCO 2016 May Storm - Texark Total							874,814
TA2017938	TA2017938 Transmission Access Control	A17938023	A17938023 SWEPCO-Tran-SecurityAccSys-Est	42752438	SWEPCO - TRANS STATION LOCKS	35200 - Structures and Improvements	02/01/2019	304,795
TA2017938	TA2017938 Transmission Access Control	A17938059	A17938059 Shadow for A17938023	42752438SWP	SWEPCO - TRANS STATION LOCKS	35200 Structures and Improvements	02/01/2019	155,598
	TA2017938 Transmission Access Control Total							460,393
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210165	2019 GEUPGRADE LAKE PAULINE (SEP) STA_8 RELAYS	35300 - Station Equipment	12/01/2019	1,409
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL GE Checkbook	T0210165	2019 GEUPGRADE LAKE PAULINE (SEP) STA_8 RELAYS	35316 - Station Equipment-SmartGrid	12/01/2019	69,571
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL GE Checkbook	T0210167	2019 GEUPGRADE WILKES STA_3 RELAYS	35300 - Station Equipment	12/01/2019	33
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL GE Checkbook	T0210167	2019 GEUPGRADE WILKES STA_3 RELAYS	35316 - Station Equipment-SmartGrid	12/01/2019	9,821
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210178	2019 GEUPGRADE BRADY SW STA_1 RELAY	35300 - Station Equipment	03/01/2020	2
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210178	2019 GEUPGRADE BRADY SW STA_1 RELAY	35316 - Station Equipment-SmartGrid	03/01/2020	15,812
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210179	2019 GEUPGRADE CARTHAGE POD STA_5 RELAYS	35316 - Station Equipment-SmartGrid	07/01/2019	37,635
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210180	2019 GEUPGRADE CHAMBERS SPRING STA_1 RELAY	35300 - Station Equipment	10/01/2019	2
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210180	2019 GEUPGRADE CHAMBERS SPRING STA_1 RELAY	35316 Station Equipment SmartGrid	10/01/2019	8,770
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210181	2019 GEUPGRADE CLARKSVILLE 345KV (SWEPCO) STA_9 RELAYS	35300 - Station Equipment	03/01/2020	2
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210181	2019 GEUPGRADE CLARKSVILLE 345KV (SWEPCO) STA_9 RELAYS	35316 - Station Equipment-SmartGrid	03/01/2020	61,730
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210188	2019 GEUPGRADE TURK STA_2 RELAYS	35300 - Station Equipment	03/01/2020	2
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210188	2019 GEUPGRADE TURK STA_2 RELAYS	35316 - Station Equipment-SmartGrid	03/01/2020	17,128
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210190	2019 GEUPGRADE TENASKA STA_6 RELAYS	35300 - Station Equipment	03/01/2020	2
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210190	2019 GEUPGRADE TENASKA STA_6 RELAYS	35316 - Station Equipment-SmartGrid	03/01/2020	38,606
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL GE Checkbook	T0210191	2019 GEUPGRADE TENAHA STA_1 RELAY	35300 - Station Equipment	08/01/2019	0
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210191	2019 GEUPGRADE TENAHA STA_1 RELAY	35316 - Station Equipment-SmartGrid	08/01/2019	8,532
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210192	2019 GEUPGRADE SOUTH FAYETTEVILLE STA_1 RELAY	35300 - Station Equipment	10/01/2019	2
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210192	2019 GEUPGRADE SOUTH FAYETTEVILLE STA_1 RELAY	35316 - Station Equipment-SmartGrid	10/01/2019	14,373
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210193	2019 GEUPGRADE SILOAM SPRINGS 161KV STA_1 RELAY	35300 - Station Equipment	10/01/2019	146
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210193	2019 GEUPGRADE SILOAM SPRINGS 161KV STA_1 RELAY	35316 - Station Equipment-SmartGrid	10/01/2019	11,542
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210194	2019 GEUPGRADE ROGERS STA_6 RELAYS	35300 Station Equipment	10/01/2019	276
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210194	2019 GEUPGRADE ROGERS STA_6 RELAYS	35316 - Station Equipment-SmartGrid	10/01/2019	38,661
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210195	2019 GEUPGRADE ROCK HILL STA_3 RELAYS	35300 Station Equipment	03/01/2020	2
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210195	2019 GEUPGRADE ROCK HILL STA_3 RELAYS	35316 - Station Equipment-SmartGrid	03/01/2020	37,694
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210199	2019 GEUPGRADE RED POINT STA_4 RELAYS	35300 - Station Equipment	03/01/2020	2
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL GE Checkbook	T0210199	2019 GEUPGRADE RED POINT STA_4 RELAYS	35316 - Station Equipment-SmartGrid	03/01/2020	36,884
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210206	2019 GEUPGRADE NORTH MINEOLA STA_1 RELAY	35300 - Station Equipment	12/01/2019	152
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL GE Checkbook	T0210206	2019 GEUPGRADE NORTH MINEOLA STA_1 RELAY	35316 - Station Equipment-SmartGrid	12/01/2019	19,389

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210207	2019 GEUPGRADE NORTH MAGAZINE STA_2 RELAYS	35300 - Station Equipment	10/01/2019	2
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210207	2019 GEUPGRADE NORTH MAGAZINE STA_2 RELAYS	35316 - Station Equipment-SmartGrid	10/01/2019	15,727
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210208	2019 GEUPGRADE DYESS STA_6 RELAYS	35300 - Station Equipment	10/01/2019	0
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210208	2019 GEUPGRADE DYESS STA_6 RELAYS	35316 - Station Equipment-SmartGrid	10/01/2019	46,071
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210210	2019 GEUPGRADE GENERAL MOTORS STA_1 RELAY	35300 - Station Equipment	03/01/2020	2
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210210	2019 GEUPGRADE GENERAL MOTORS STA_1 RELAY	35316 - Station Equipment-SmartGrid	03/01/2020	8,347
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210211	2019 GEUPGRADE MENA STA_3 RELAYS	35300 - Station Equipment	12/01/2019	79
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210211	2019 GEUPGRADE MENA STA_3 RELAYS	35316 - Station Equipment-SmartGrid	12/01/2019	17,770
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210213	2019 GEUPGRADE HOPE STA_1 RELAY	35300 - Station Equipment	12/01/2019	102
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210213	2019 GEUPGRADE HOPE STA_1 RELAY	35316 - Station Equipment-SmartGrid	12/01/2019	13,008
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL-GE Checkbook	T0210277	2019 GEUPGRADE ARSENAL HILL STA_1 RELAY	35300 - Station Equipment	03/01/2020	2
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL GE Checkbook	T0210277	2019 GEUPGRADE ARSENAL HILL STA_1 RELAY	35316 - Station Equipment-SmartGrid	03/01/2020	15,581
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL GE Checkbook	T0211728	2019 GEUPGRADE PITTSBURG (SW) STA_6 RELAYS	35300 - Station Equipment	12/01/2019	62
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075001	A18075001 T/SWEPCo/SEL GE Checkbook	T0211728	2019 GEUPGRADE PITTSBURG (SW) STA_6 RELAYS	35316 - Station Equipment-SmartGrid	12/01/2019	26,596
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210165SWP	2019 GEUPGRADE LAKE PAULINE (SEP) STA_8 RELAYS	35300 - Station Equipment	12/01/2019	715
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210165SWP	2019 GEUPGRADE LAKE PAULINE (SEP) STA_8 RELAYS	35316 - Station Equipment-SmartGrid	12/01/2019	35,310
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210167SWP	2019 GEUPGRADE WILKES STA_3 RELAYS	35300 - Station Equipment	12/01/2019	17
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210167SWP	2019 GEUPGRADE WILKES STA_3 RELAYS	35316 - Station Equipment-SmartGrid	12/01/2019	4,996
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210178SWP	2019 GEUPGRADE BRADY SW STA_1 RELAY	35300 - Station Equipment	03/01/2020	1
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210178SWP	2019 GEUPGRADE BRADY SW STA_1 RELAY	35316 - Station Equipment-SmartGrid	03/01/2020	7,945
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210179SWP	2019 GEUPGRADE CARTHAGE POD STA_5 RELAYS	35316 Station Equipment SmartGrid	07/01/2019	18,914
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210180SWP	2019 GEUPGRADE CHAMBERS SPRING STA_1 RELAY	35300 - Station Equipment	10/01/2019	1
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210180SWP	2019 GEUPGRADE CHAMBERS SPRING STA_1 RELAY	35316 - Station Equipment-SmartGrid	10/01/2019	4,288
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210181SWP	2019 GEUPGRADE CLARKSVILLE 345KV (SWEPCO) STA_9 RELAYS	35300 - Station Equipment	03/01/2020	1
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210181SWP	2019 GEUPGRADE CLARKSVILLE 345KV (SWEPCO) STA_9 RELAYS	35316 - Station Equipment-SmartGrid	03/01/2020	31,733
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210188SWP	2019 GEUPGRADE TURK STA_2 RELAYS	35300 - Station Equipment	03/01/2020	1
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210188SWP	2019 GEUPGRADE TURK STA_2 RELAYS	35316 - Station Equipment-SmartGrid	03/01/2020	8,669
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210190SWP	2019 GEUPGRADE TENASKA STA_6 RELAYS	35300 - Station Equipment	03/01/2020	1
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210190SWP	2019 GEUPGRADE TENASKA STA_6 RELAYS	35316 - Station Equipment-SmartGrid	03/01/2020	19,519
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210191SWP	2019 GEUPGRADE TENAHA STA_1 RELAY	35300 - Station Equipment	08/01/2019	0
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210191SWP	2019 GEUPGRADE TENAHA STA_1 RELAY	35316 - Station Equipment-SmartGrid	08/01/2019	4,362
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210192SWP	2019 GEUPGRADE SOUTH FAYETTEVILLE STA_1 RELAY	35300 - Station Equipment	10/01/2019	1
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210192SWP	2019 GEUPGRADE SOUTH FAYETTEVILLE STA_1 RELAY	35316 - Station Equipment-SmartGrid	10/01/2019	7,318
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210193SWP	2019 GEUPGRADE SILOAM SPRINGS 161KV STA_1 RELAY	35300 - Station Equipment	10/01/2019	74
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210193SWP	2019 GEUPGRADE SILOAM SPRINGS 161KV STA_1 RELAY	35316 - Station Equipment-SmartGrid	10/01/2019	5,871
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210194SWP	2019 GEUPGRADE ROGERS STA_6 RELAYS	35300 - Station Equipment	10/01/2019	140
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210194SWP	2019 GEUPGRADE ROGERS STA_6 RELAYS	35316 - Station Equipment-SmartGrid	10/01/2019	19,595
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210195SWP	2019 GEUPGRADE ROCK HILL STA_3 RELAYS	35300 - Station Equipment	03/01/2020	1
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210195SWP	2019 GEUPGRADE ROCK HILL STA_3 RELAYS	35316 - Station Equipment-SmartGrid	03/01/2020	18,931
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210199SWP	2019 GEUPGRADE RED POINT STA_4 RELAYS	35300 - Station Equipment	03/01/2020	1
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210199SWP	2019 GEUPGRADE RED POINT STA_4 RELAYS	35316 - Station Equipment-SmartGrid	03/01/2020	18,766
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210206SWP	2019 GEUPGRADE NORTH MINEOLA STA_1 RELAY	35300 - Station Equipment	12/01/2019	76
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210206SWP	2019 GEUPGRADE NORTH MINEOLA STA_1 RELAY	35316 Station Equipment-SmartGrid	12/01/2019	9,725
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210207SWP	2019 GEUPGRADE NORTH MAGAZINE STA_2 RELAYS	35300 - Station Equipment	10/01/2019	1
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210207SWP	2019 GEUPGRADE NORTH MAGAZINE STA_2 RELAYS	35316 - Station Equipment-SmartGrid	10/01/2019	8,001
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210208SWP	2019 GEUPGRADE DYESS STA_6 RELAYS	35300 - Station Equipment	10/01/2019	0
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210208SWP	2019 GEUPGRADE DYESS STA_6 RELAYS	35316 - Station Equipment-SmartGrid	10/01/2019	23,530
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210210SWP	2019 GEUPGRADE GENERAL MOTORS STA_1 RELAY	35300 - Station Equipment	03/01/2020	1
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210210SWP	2019 GEUPGRADE GENERAL MOTORS STA_1 RELAY	35316 - Station Equipment-SmartGrid	03/01/2020	4,236
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210211SWP	2019 GEUPGRADE MENA STA_3 RELAYS	35300 - Station Equipment	12/01/2019	40
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210211SWP	2019 GEUPGRADE MENA STA_3 RELAYS	35316 - Station Equipment-SmartGrid	12/01/2019	9,061
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210213SWP	2019 GEUPGRADE HOPE STA_1 RELAY	35300 - Station Equipment	12/01/2019	52
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210213SWP	2019 GEUPGRADE HOPE STA_1 RELAY	35316 - Station Equipment-SmartGrid	12/01/2019	6,683
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210277SWP	2019 GEUPGRADE ARSENAL HILL STA_1 RELAY	35300 - Station Equipment	03/01/2020	1
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0210277SWP	2019 GEUPGRADE ARSENAL HILL STA_1 RELAY	35316 - Station Equipment-SmartGrid	03/01/2020	7,948
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0211728SWP	2019 GEUPGRADE PITTSBURG (SW) STA_6 RELAYS	35300 Station Equipment	12/01/2019	31
TA2018075	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr	A18075003	A18075003 Checkbook SHADOW -GE/SEL Relay	T0211728SWP	2019 GEUPGRADE PITTSBURG (SW) STA_6 RELAYS	35316 - Station Equipment-SmartGrid	12/01/2019	13,197
	TA2018075 SWEPCo SEL/GE Relay Upgrade Pr Total							861,283
TA2018806	TA2018806 SWEPCo Region Failure Program	A15706626	A15706626 T/SWEPCO/IPC 138 GCB 7340 Fail	42684227	ICP 138KV ADD 145KV CIRCUIT BREAKER	35200 - Structures and Improvements	12/01/2018	206,421
TA2018806	TA2018806 SWEPCo Region Failure Program	A15706626	A15706626 T/SWEPCO/IPC 138 GCB 7340 Fail	42684227	ICP 138KV ADD 145KV CIRCUIT BREAKER	35300 - Station Equipment	12/01/2018	1,246,531
TA2018806	TA2018806 SWEPCo Region Failure Program	A15706627	A15706627 Shadow for A15706626	42684227SWP	ICP 138KV ADD 145KV CIRCUIT BREAKER	35200 - Structures and Improvements	12/01/2018	105,076
TA2018806	TA2018806 SWEPCo Region Failure Program	A15706627	A15706627 Shadow for A15706626	42684227SWP	ICP 138KV ADD 145KV CIRCUIT BREAKER	35300 - Station Equipment	12/01/2018	634,567
TA2018806	TA2018806 SWEPCo Region Failure Program	A18806013	A18806013 Bann-New Boston Failed Insulat	42943303	BANN-NEW BOSTON REPLACE FAILED INSULATORS	35600 - Overhead Conductors, Device	06/01/2019	507,049
TA2018806	TA2018806 SWEPCo Region Failure Program	A18806014	A18806014 Shadow for A18806013	42943303SWP	BANN-NEW BOSTON REPLACE FAILED INSULATORS	35600 - Overhead Conductors, Device	06/01/2019	260,208
TA2018806	TA2018806 SWEPCo Region Failure Program	A18806031	A18806031 Welsh breaker 11670 failure	TS0221948	WELSH STA REPL CB 11670/SWITCH/OPERATOR	35300 - Station Equipment	02/01/2020	242,399
TA2018806	TA2018806 SWEPCo Region Failure Program	A18806032	A18806032 Shadow for A18806031	TS0221948SWP	WELSH STA REPL CB 11670/SWITCH/OPERATOR	35300 Station Equipment	02/01/2020	120,879
	TA2018806 SWEPCo Region Failure Program Total							3,323,130
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	42347251SWP	CHAMBERS SPRING-TONTITOWN SPECIAL PERMITTING	35010 - Land Rights	10/01/2016	4,084
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	42413705SWP	CONTINUE TONTITOWN 161KV CAPACITOR INSTALL T0127459	35300 - Station Equipment	09/01/2016	54,409
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	42417203SWP	ARMY CORPS OF ENGINEERS NEW TERM EASEMENT	35010 - Land Rights	10/01/2016	5,653
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0149602SWP	PRAIRIE GROVE CB GREENLAND 3820 REPLACE FAILED CABLE	35300 - Station Equipment	08/01/2016	5,226

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0149773SWP	MENA TRF P145 2 REPLACE FAILED FANS	35300 - Station Equipment	11/01/2016	1,273
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0150240SWP	SOUTH FAYETTEVILLE REPLACE FAILED METERS ON TRANSFORMERS	35300 - Station Equipment	07/01/2016	2,338
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0150362SWP	SILOAM SPRINGS 161KV CCVT REPLACE CCVT AND LINE TUNER	35300 - Station Equipment	07/01/2016	7,597
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0151049SWP	POTTER SUB (POD) BCHGR BATTERY CHARGER STA_1 POTTER_SUB_BCHR	35300 - Station Equipment	11/01/2016	712
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0151156SWP	OKAY CAPITAL PROJECT - REPLACE ARRESTERS ON 69KV CCVT	35300 - Station Equipment	03/01/2017	1,548
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0152501SWP	TURK TRF AUTO #2 138/115 KV P141 2 D584570 CAPITAL PROJECT	35300 - Station Equipment	11/01/2016	1,069
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0152698SWP	SOUTHEAST TEXARKANA CAP PROJ -REPL COMPRESSOR CB4720	35300 - Station Equipment	11/01/2016	361
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0152707SWP	NORTH MAGAZINE PT CSIT12035635 - REPLACE FAILED PT WITH CCVT	35300 Station Equipment	11/01/2016	2,576
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0152823SWP	TEXARKANA PLANT CB 12TH ST 4720 137Y4119 CAPITAL PROJECT	35300 - Station Equipment	11/01/2016	803
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0153230SWP	SOUTH FAYETTEVILLE TRF P161 31 REPLACE FAILED 69 KV PT	35300 - Station Equipment	11/01/2016	2,380
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0153581SWP	TURK DFR FAULT RECORDER DFR_1003240251 CAPITAL PROJECT	35300 - Station Equipment	09/01/2017	5,975
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0153868SWP	FLINT CREEK SUB TRF P345 43 REPLACE 345KV SWITCH 11123	35300 - Station Equipment	09/01/2018	13,632
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0154121SWP	EUREKA SPRINGS 161KV - REPLACE FAILED CCVT	35300 - Station Equipment	11/01/2016	4,190
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0154124SWP	DEQUEEN CB MENA 3610 13014 CAPITAL PROJECT	35300 - Station Equipment	12/01/2016	7,677
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0163698SWP	EUREKA SPRINGS 161KV STA EUREKA SPRINGS 161KV CAPITAL PROJE	35300 - Station Equipment	07/01/2016	202
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0163848SWP	TURK TRF P345 51 TB80068412 CAPITAL PROJECT	35300 - Station Equipment	06/01/2018	123,556
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0163977SWP	SOUTHEAST TEXARKANA TRF P145 1 3 70704A CAPITAL PROJECT	35300 - Station Equipment	02/01/2017	1,982
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0165957SWP	OKAY FR N/A DFR_1003709055 CAPITAL PROJECT-SEL 1102 SDR	35300 - Station Equipment	07/01/2018	6,062
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0166269SWP	NASHVILLE 69KV TCC 69 [CB] DEQUEEN 3050 CAPITAL PROJECT	35300 - Station Equipment	02/01/2017	885
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0166343SWP	EAST ROGERS REPLACE STATION BATTERY	35300 - Station Equipment	07/01/2016	6,616
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0166788SWP	FLINT CREEK SUB TRF P345 43 WEST REPLACE SURGE ARRESTERS	35300 - Station Equipment	10/01/2018	7,802
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0166789SWP	FLINT CREEK SUB TRF P345 50 EAST REPLACE SURGE ARRESTERS	35300 Station Equipment	01/01/2018	10,922
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0175506SWP	EAST ROGERS CAP BANK - REPLACE CAPACITOR AND LIMITERS	35300 - Station Equipment	07/01/2016	1,830
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0175831SWP	DEQUEEN STA DEQUEEN CAPITAL PROJECT	35300 - Station Equipment	01/01/2019	4,733
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0176402SWP	WEST BOONEVILLE STA - REPLACE TRANSFER SWITCH	35300 - Station Equipment	06/01/2016	0
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0176865SWP	NASHVILLE 69KV CAPB 69KV CAP BANK 10810 40828 CAPITAL PROJEC	35300 - Station Equipment	12/01/2016	6,286
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0177120SWP	FLINT CREEK SUB STATION - REPLACE TRANSFER SWITCH	35300 - Station Equipment	08/01/2016	2,346
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0177295SWP	SOUTH DIERKS TRF P141 17 C0229752CAPITAL PROJECT/FANS&ASSEC	35300 - Station Equipment	12/01/2016	2,183
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0177384SWP	REA - ELM SPRINGS DYESS 10457 REPLACE FAILED SF6 INTERUPTERS	35300 - Station Equipment	07/01/2019	16,844
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0177502SWP	SOUTH FAYETTEVILLE CAP BANK REPLACE LIMITERS & CAPACITORS	35300 - Station Equipment	12/01/2016	4,668
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0177508SWP	DEQUEEN STA DEQUEEN CAPITAL PROJECT	35300 - Station Equipment	12/01/2016	1,130
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0177511SWP	PATTERSON STA CAPITAL PROJECT/FANS&ACCESSORIES	35300 - Station Equipment	12/01/2016	774
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0177574SWP	EAST ROGERS TRF P161 22 REPLACE 6 COOLING FANS	35300 - Station Equipment	11/01/2017	2,253
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0177590SWP	SUGAR HILL (SW) STA CAPITAL PROJECT/2 TON BARD 208/230V	35300 - Station Equipment	01/01/2017	2,288
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0177860SWP	EUREKA SPRINGS 161KV STA REPLACE FAILED INTERCONNECT METERS	35300 - Station Equipment	06/01/2017	14,366
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0177909SWP	SOUTH SPRINGDALE RTU REPLACE WITH COOPER SG4250	35300 - Station Equipment	10/01/2017	35,649
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0178095SWP	TWELFTH STREET (SW) STA CAPITAL PROJECT/FUTURA METERS	35300 - Station Equipment	02/01/2017	3,012
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0178206SWP	NORTH HUNTINGTON STA REPLACE AC UNIT	35300 - Station Equipment	09/01/2016	3,906
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0178808SWP	PATTERSON STA CAPITAL PROJECT/ETHERNET SWITCH	35300 - Station Equipment	02/01/2017	1,776
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP-Tx/ ASSOC W/SI194ARRE	T0178912SWP	PATTERSON STA PATTERSON CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	3,194
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006319	000006319 T/SEP Tx/ ASSOC W/SI194ARRE	T0178975SWP	TURK TRF P345 51 TB80068412 CAPITAL PROJECT	35300 Station Equipment	10/01/2018	230
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP Tx/ ASSOC W/SI194LARE	42396695SWP	BLANCHARD NTEC 12 KV SUB - REPLACE METER	35300 - Station Equipment	04/01/2018	711
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	42669575SWP	CAMPTI METERING POINT INSTALL TRILLIANT 2G PHONES	35300 Station Equipment	08/01/2017	503
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006321	000006321 T/SEP Tx/ ASSOC W/SI194LARE	42683413SWP	STANLEY NTEC REPLACE FAILED METER	35300 - Station Equipment	04/01/2018	922
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0118446SWP	CEDAR GROVE (SW) PT CAP BNK REP CAPACITORS	35300 - Station Equipment	04/01/2018	1,626
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP Tx/ ASSOC W/SI194LARE	T0149849SWP	LONGWOOD (SW) REPLACE 3 CCVTS - FLOURNOY CIRCUIT	35300 - Station Equipment	03/01/2017	15,908
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0150629SWP	LIEBERMAN CB SUPERIOR 4380 499864 CAPITAL PROJECT	35300 - Station Equipment	03/01/2017	557
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0150949SWP	STONEWALL CB WESTERN ELE/SW SHREV 5590 SURGE ARRESTERS	35300 - Station Equipment	03/01/2017	7,513
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0151125SWP	LONGWOOD (SW) REPL ANNUNCIATOR RELAYS & RADIATOR BRACKETS	35300 - Station Equipment	03/01/2017	8,118
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0152694SWP	FORT HUMBUG CB TRICHEL/ARSENAL HILL 290 510292 CAPITAL PROJE	35300 - Station Equipment	09/01/2017	5,143
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0153008SWP	ARSENAL HILL CB HUMBUG/SOUTH AUTO 7500 21731 CAPITAL PROJECT	35300 - Station Equipment	09/01/2017	12,452
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0153158SWP	SOUTH SHREVEPORT CB 7260 REPL FAILED SURGE ARRESTERS	35300 - Station Equipment	09/01/2017	2,499
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0153693SWP	STONEWALL CB WESTERN ELE/SW SHREV 5590 H14SA2777201 CAPITAL	35300 - Station Equipment	09/01/2017	11,354
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP Tx/ ASSOC W/SI194LARE	T0153694SWP	SOUTHWEST SHREVEPORT CB E AUTO/W ELEC/STWALL 11620 380263 CA	35300 - Station Equipment	09/01/2017	12,308
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0155138SWP	LIEBERMAN - REPLACE FAILED 138 KV SWITCH 3015	35300 - Station Equipment	09/01/2016	12,211
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0165696SWP	FORT HUMBUG STA FORT HUMBUG CAPITAL PROJECT/BATT&CHG	35300 - Station Equipment	08/01/2016	5,421
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0170151SWP	ARSENAL HILL STA ARSENAL HILL CAPITAL PROJECT	35300 - Station Equipment	07/01/2017	1,307
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0171367SWP	SUPERIOR (SW) STA SUPERIOR (SW) CAPITAL PROJECT	35300 - Station Equipment	11/01/2016	3,002
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0175440SWP	SOUTHWEST SHREVEPORT CB E AUTO/DOLET HILLS 11610 0283A790220	35300 - Station Equipment	08/01/2016	108,982
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0175555SWP	STONEWALL CAPITAL PROJECT RELAYS [CB] LOGANSPORT 5580	35300 - Station Equipment	08/01/2016	5,656
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0175586SWP	SOUTHWEST SHREVEPORT STA SOUTHWEST SHREVEPORT CAPITAL PROJE	35300 - Station Equipment	08/01/2016	34,988
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0176333SWP	SOUTHWEST SHREVEPORT STA SOUTHWEST SHREVEPORT CAPITAL PROJE	35300 - Station Equipment	10/01/2018	9,209
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0176462SWP	SOUTH SHREVEPORT STA SOUTH SHREVEPORT CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	580
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0176784SWP	BAYOU PIERRE STA BAYOU PIERRE CAPITAL PROJECT	35300 - Station Equipment	11/01/2016	5,835
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0176870SWP	ELLERBE ROAD STA ELLERBE ROAD CAPITAL PROJECT	35300 - Station Equipment	11/01/2016	3,549
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0177155SWP	LIEBERMAN STA CAPITAL PROJECT/REPLACE SWITCH 6363	35300 Station Equipment	12/01/2016	4,780
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0177199SWP	HAUGHTON STA CAPITAL PROJECT/CULVERTS	35300 - Station Equipment	01/01/2017	8,333
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0177889SWP	ARSENAL HILL BAT MOBILE TRAILER BAT_11202008 CAPITAL PROJECT	35300 - Station Equipment	01/01/2018	1,672
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0178412SWP	LIEBERMAN DSC MOABS 1690CD SW_1690CD CAPITAL PROJECT	35300 - Station Equipment	02/01/2017	10,790
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0178718SWP	FLOURNOY STA CAPITAL PROJECT/69KV BREAKER 9080	35300 - Station Equipment	02/01/2017	23,318
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006321	000006321 T/SEP-Tx/ ASSOC W/SI194LARE	T0179451SWP	SOUTH SHREVEPORT TRF P141 16 E AUTO C0229751 CAPITAL PROJECT	35300 - Station Equipment	10/01/2017	45,466

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	42393085SWP	PITTSBURG CB 6210 - REPLACE FAILED SWITCH 6213	35300 - Station Equipment	08/01/2016	9,310
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42393780SWP	DE KALB 12 5KV REPLACE FAILED METER	35300 - Station Equipment	04/01/2018	127
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	42396672SWP	OAK HILL - 138KV SUB REPLACE METER	35300 - Station Equipment	04/01/2018	718
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42397319SWP	FOREST HILL NTEC 138KV SUB - REPLACE METER	35300 - Station Equipment	04/01/2018	2,333
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42397355SWP	TATUM SUB - RELPACE METER	35300 - Station Equipment	09/01/2018	1,596
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42466046SWP	NTEC DETC CENTER STATION REPLACE FAILED METER	35300 - Station Equipment	04/01/2018	3,176
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	42526820SWP	PERDUE SUBSTATION CHANGE OUT FAILED METER	35300 - Station Equipment	04/01/2018	745
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42531436SWP	JEFFERSON 138KV NTEC SUBSTATION CHANGE OUT METER	35300 - Station Equipment	07/01/2017	813
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42531459SWP	OAKHILL 2 SUBSTATION CHANGE METER	35300 - Station Equipment	07/01/2017	823
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42531464SWP	CENTER SOUTH STATION CHANGE METER	35300 Station Equipment	07/01/2017	784
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42531470SWP	BOND 69KV SUBSTATION CHANGE METER	35300 - Station Equipment	04/01/2018	5
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	42538717SWP	E BURGESS SUBSTATION CHANGE OUT FAILED METER	35300 - Station Equipment	07/01/2017	813
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42574344SWP	WELSH HVDC REPLACE FAILED VALVE MODULE REACTORS	35300 - Station Equipment	11/01/2017	24,032
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	42626692SWP	KILGORE SUBSTATION CHANGE OUT METER	35300 Station Equipment	04/01/2018	663
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42626989SWP	FRIARS SWITCH STATION REPLACE METER	35300 - Station Equipment	04/01/2018	958
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42627012SWP	CARTHAGE SUBSTATION REPLACE METER	35300 - Station Equipment	04/01/2018	790
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	42682350SWP	TATUM SUBSTATION REPLACE ION METERS WITH UPGRADE	35300 - Station Equipment	09/01/2018	839
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0130312SWP	MARSHALL P142 64 - REPLACE 138KV BUSHINGS, 69KV & 138KV LA'S	35300 - Station Equipment	10/01/2016	45,115
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0141539SWP	CARTHAGE POD - REPLACE FAILED CARRIER TUNER IN CCVT	35300 - Station Equipment	05/01/2016	3
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0150479SWP	ROCK HILL CB 1P70 - REPLACE (2) FAILED BUSHINGS	35300 - Station Equipment	12/01/2016	12,711
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	T0151155SWP	BUFORD SURVEY SW MOABS 7625 REPLACE BATTERY	35300 - Station Equipment	11/01/2016	552
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	T0152088SWP	HUGHES SPRINGS CB 1200 CAPITAL PROJ-REPL FAILED SWITCH 1203	35300 - Station Equipment	11/01/2016	5,793
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0152505SWP	MOUNT PLEASANT CB 1860 REPL FAILED SWITCH 1863 CAP	35300 - Station Equipment	11/01/2016	7,716
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	T0153159SWP	CHAPEL HILL (M O LINE SW) SW MOAB WILKES 6333/6331	35300 - Station Equipment	08/01/2016	458
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0153334SWP	NORTHWEST TEXARKANA CB 10690 REP FAILED SW 10693	35300 - Station Equipment	12/01/2016	31,082
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0153604SWP	ANDERSON CREEK CRSET CARRIER SET S1AXNAS12002231 CAPITAL PR	35300 - Station Equipment	02/01/2017	4,443
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0154118SWP	WILKES CB GSU#2/BUS#1 1M00 230975 CAPITAL PROJECT	35300 Station Equipment	02/01/2017	37,032
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0154119SWP	NORTHWEST TEXARKANA CB SUGAR HILL/PATTERSON 10780 388902 CAP	35300 - Station Equipment	09/01/2016	80,842
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0154418SWP	MOUNT PLEASANT CB 1860 - REPLACE FAILED LIGHTNING ARRESTERS	35300 - Station Equipment	09/01/2016	8,696
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0163996SWP	PETTY STA PETTY CAPITAL PROJECT CABLE REPLACEMENT	35300 - Station Equipment	07/01/2018	19,262
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0164235SWP	IPC-JEFFERSON - REPLACE FAILED DLP RELAY WITH SEL 421 RELAY	35300 Station Equipment	10/01/2017	5,323
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0164453SWP	CHILDRESS WEST (SEP) - C/O FAILED 69KV PTS	35300 - Station Equipment	06/01/2017	15,302
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0165135SWP	KNOX LEE - UPGRADE CARRIER ON OVERTON CIRCUIT TO TC10B	35300 Station Equipment	11/01/2017	5,003
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0165136SWP	OVERTON - UPGRADE CARRIER ON KNOX LEE CIRCUIT TO TC10B	35300 - Station Equipment	11/01/2017	3,924
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0165160SWP	CHILDRESS WEST (SEP) - C/O COOLING FAN	35300 Station Equipment	11/01/2016	1,013
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0165629SWP	SCOTTSVILLE (SW) STA SCOTTSVILLE(SW) CAP PROJECT P141 32BUSH	35300 - Station Equipment	11/01/2016	37,489
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0166256SWP	NWTEXARKANA CAPITAL PROJECT RELAYS [PCMIS] P&C STAT/COMPRESS	35300 - Station Equipment	02/01/2017	798
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0166307SWP	MOUNT PLEASANT CB WEST MOUNT PLEASANT 1860 K6566145CM501 CAP	35300 Station Equipment	07/01/2017	52
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0166339SWP	PITTSBURG (SW) TCC 69 [CB] WINNSBORO 9810 CAPITAL PROJECT	35300 - Station Equipment	02/01/2017	1,211
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0166507SWP	NORTHWEST TEXARKANA CAPITAL PROJECT/SWITCH 10692	35300 - Station Equipment	06/01/2017	36,131
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0171759SWP	LAKE PAULINE C/O FAILED DISC SWITCHES	35300 - Station Equipment	09/01/2016	2,216
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0175558SWP	PETTY CB PILGRIMS PRIDE 1L20 0139A4907201 CAPITAL PROJECT	35300 - Station Equipment	08/01/2016	11,559
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0175699SWP	ESTELLINE INSTALL MOBILE C/O ARRESTORS, CUTOUTS, INSULATORS	35300 - Station Equipment	07/01/2016	16,779
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0175827SWP	SCOTTSVILLE - REPLACE FAILED CARRIER WITH A TC10B SET	35300 - Station Equipment	11/01/2017	4,189
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	T0176005SWP	LYDIA STA LYDIA CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	39,793
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0176025SWP	WELSH STA WELSH CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	30,150
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0176277SWP	DIANA CB PIRKEY/SW SHREVEPORT - REPLACE FAILED CB11910	35300 Station Equipment	07/01/2016	69,770
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0176473SWP	WILKES STA WILKES CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	31,351
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0176910SWP	BANN STA BANN CAPITAL PROJECT/138KV GOABS 11432	35300 - Station Equipment	12/01/2016	7,243
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0177398SWP	WELSH - REPLACE FAILED LIGHT FIXTURES	35300 - Station Equipment	12/01/2016	20,912
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0177424SWP	WHITNEY P141 66 NORTH - REPLACE (2) FAILED 24" FANS	35300 - Station Equipment	07/01/2016	454
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	T0177494SWP	DIANA P345 29 CENTER - REPLACE (3) FAILED 24" FANS	35300 - Station Equipment	08/01/2016	230
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0177495SWP	DIANA P345 25 SOUTH - REPLACE (2) FAILED 24" FANS	35300 - Station Equipment	08/01/2016	447
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	T0177690SWP	IPC 138KV STA CAPITAL PROJECT/REPLACE SURGE ARRESTERS	35300 - Station Equipment	11/01/2016	2,604
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0177736SWP	MARSHALL 138KV P142 64 NORTH - REPLACE (1) FAILED 24" FAN	35300 - Station Equipment	08/01/2016	354
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	T0177760SWP	IPC-JEFFERSON - REPLACE CONTROL HOUSE AIR CONDITIONER	35300 - Station Equipment	10/01/2016	660
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	T0177861SWP	SHAMROCK C/O FAILED CAPACITORS	35300 - Station Equipment	08/01/2016	5,018
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	T0177890SWP	LONGVIEW OPS RESERVE BAT BATTERY TRAILER CAPITAL PROJECT	35300 - Station Equipment	07/01/2018	3,500
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP Tx/ ASSOC W/SI194TXRE	T0178034SWP	CHILDRESS WEST (SEP) C/O SEL 387E ON XFMR	35300 - Station Equipment	08/01/2017	8,519
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0178310SWP	KNOX LEE P141 54 - REPLACE (2) FAILED 24" FANS	35300 - Station Equipment	08/01/2016	638
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0178314SWP	MEMPHIS NW DELIVER FUSE TO STATION	35300 Station Equipment	08/01/2016	593
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0178475SWP	JEFFERSON STA CAPITAL PROJECT/RTU COOPER SG4250	35300 Station Equipment	07/01/2017	31,728
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0178645SWP	JEFFERSON SWITCHING - REPLACE CONTROL HOUSE AC	35300 - Station Equipment	09/01/2017	750
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0178672SWP	NORTHWEST HENDERSON P142 66 REPLACE ONE 24" FAN	35300 - Station Equipment	11/01/2016	508
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0178709SWP	LONE STAR (SEP) STA LONE STAR (SEP) CAPITAL PROJECT	35300 - Station Equipment	12/01/2016	32,932
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0178903SWP	PIRKEY TRF P345 40 S AUTO REPLACE 5 24" FANS	35300 - Station Equipment	10/01/2016	1,705
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0178958SWP	IPC-DOMINO STA CAPITAL PROJECT - AC UNIT	35300 Station Equipment	06/01/2017	3,148
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000006322	000006322 T/SEP-Tx/ ASSOC W/SI194TXRE	T0179275SWP	WEST ATLANTA TRF P137 9 EAST 236941 CAPITAL PROJECT	35300 - Station Equipment	12/01/2016	2,058
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	000008301	000008301 TB SEP-Tx ASSOC W SI194LAUN	42253648SWP	IDS UPGRADE- SWEPCO CELLEMETRY	35300 - Station Equipment	09/01/2016	2,164
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	000008302	000008302 TB/SEP-Tx/ ASSOC W/SI194TXUN	42417869SWP	ACCESS CONTROL- LYDIA 345 SS	35200 - Structures and Improvements	05/01/2017	11,661
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	A13006854	A13006854 TENASKA Replace LCB11 relays	42593741	TENASKA-REPLACE LCB11 RELAYS	35300 Station Equipment	05/01/2017	109,844

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	A14013002	A14013002 T/ROW/SEP/BROWNLEE RD-MINDEN R	42329874	2015-BROWNLEE RD-MINDEN RD-ROW RELOCATE TWO STR	35010 - Land Rights	01/01/2017	11,985
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	A14013004	A14013004 T/SEP/Shadow for A14013002	42329874SWP	2015-BROWNLEE RD-MINDEN RD-ROW RELOCATE TWO STR	35010 Land Rights	01/01/2017	6,185
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	A18260001	A18260001 Crockett SDR Replacement	T0206152	SDR CROCKETT FR SDR 1121560254 CAPITAL PROJECT	35300 - Station Equipment	06/01/2019	12,632
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	A18260002	A18260002 Shadow for A18260001 Crockett	T0206152SWP	SDR - CROCKETT FR SDR 1121560254 CAPITAL PROJECT	35300 - Station Equipment	06/01/2019	6,424
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	A18260003	A18260003 Tenaska SDR Replacement	T0206154	SDR - TENASKA FR SDR DFR_1003196859 CAPITAL PROJECT	35300 - Station Equipment	06/01/2019	13,357
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	A18260004	A18260004 Shadow for A18260003 Tenaska	T0206154SWP	SDR - TENASKA FR SDR DFR_1003196859 CAPITAL PROJECT	35300 - Station Equipment	06/01/2019	6,763
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	A18260007	A18260007 Wilkes 138 SDR Replacement	T0206160	SDR - WILKES FR SDR 1140620409_DFR CAPITAL PROJECT	35300 - Station Equipment	12/01/2018	60,170
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	A18260008	A18260008 Shadow for A18260007 Wilkes138	T0206160SWP	SDR - WILKES FR SDR 1140620409_DFR CAPITAL PROJECT	35300 - Station Equipment	12/01/2018	30,622
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	A18260009	A18260009 Stall Unit SDR Replacement	T0206759	SDR - STALL UNIT - AR HLL FR DFR_1003091328 CAPITAL PROJECT	35300 - Station Equipment	01/01/2019	12,168
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	A18260010	A18260010 Shadow for A18260009 Stall	T0206759SWP	SDR - STALL UNIT - AR HLL FR DFR_1003091328 CAPITAL PROJECT	35300 - Station Equipment	01/01/2019	6,224
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	42636603SWP	DEQUEEN - MENA 69KV TLN152 REPLACE INSULATORS & ARMS	35500 - Poles and Fixtures	06/01/2017	22,775
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	42652362SWP	SILOAM SPR - PRAIRIE GR (AR) REPLACE 10 STRUCTURES	35500 - Poles and Fixtures	04/01/2017	91,207
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	42706335SWP	BRANCH-N MAGAZINE LINE 162	35500 - Poles and Fixtures	06/01/2017	17,542
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	42729292SWP	PATTERSON - S NASHVILLE SEPTL181	35500 - Poles and Fixtures	09/01/2017	3,983
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	42769879SWP	DOP 2017 - SWEPCO - CHAMBER SPRINGS-TONTITOWN ST #85	35500 Poles and Fixtures	02/01/2018	2,926
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	42943676SWP	ARKLAHOMA DISSOLUTION ASSET PUR TOTAL SWEPCO	35600 Overhead Conductors, Device	11/01/2019	34,895
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	42997559SWP	DEQUEEN - MENA CP REPLACE 24 H-STRUCTURES	35500 Poles and Fixtures	06/01/2019	54,909
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL0036327SWP	DYESS - SPRINGDALE SOUTH (T) RP 3 HX	35500 Poles and Fixtures	10/01/2019	35,892
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL0036327SWP	DYESS SPRINGDALE SOUTH (T) RP 3 HX	35600 Overhead Conductors, Device	10/01/2019	595
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL0036437SWP	PRAIRIE GROVE - SILOAM SPRINGS (T) CP WO 12 CONDITIONS	35500 - Poles and Fixtures	10/01/2019	50,060
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL0036437SWP	PRAIRIE GROVE SILOAM SPRINGS (T) CP WO 12 CONDITIONS	35600 - Overhead Conductors, Device	10/01/2019	5,564
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL0036471SWP	DYESS - FLINT CREEK RP DAMAGED STR3	35500 Poles and Fixtures	10/01/2019	24,619
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL0036622SWP	WEST BOONEVILLE - NORTH MAGAZINE 2 CONDITIONS	35500 - Poles and Fixtures	10/01/2019	11,363
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL0036622SWP	WEST BOONEVILLE - NORTH MAGAZINE 2 CONDITIONS	35600 - Overhead Conductors, Device	10/01/2019	2,841
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL029915SWP	TEXARKANA P-BLOOMBUR # 204	35500 - Poles and Fixtures	06/01/2017	13,800
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030059SWP	W BOONEVILLE-N MAGAZ CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	4,554
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030063SWP	EAST ROGERS - ROGERS #282-29	35500 - Poles and Fixtures	09/01/2017	18,563
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030064SWP	CRAIG JCT-DEQUEE(OK) CP WO 1 CONDITIONS	35500 - Poles and Fixtures	09/01/2017	2,037
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030169SWP	N HUNTINGTON-WALDRON WEST # 188 & 13	35500 - Poles and Fixtures	09/01/2017	3,072
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030193SWP	U S MOTORS TAP # 11 A-1	35500 - Poles and Fixtures	06/01/2017	3,909
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030404SWP	SOUTH NASHVILLE - SO CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	327
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030469SWP	EAST ROGERS - BEAVER - DANGER TREE PILKINGTON	35600 - Overhead Conductors, Device	08/01/2017	8,186
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030517SWP	HOSSTON BLMBRG (AR) DEAD TREE - DON VICKERS	35600 - Overhead Conductors, Device	12/01/2017	604
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030558SWP	FLINT CREEK - SILOAM CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	2,583
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030567SWP	FLINT CREEK - BROOKL CP WO 1 CONDITIONS	35500 - Poles and Fixtures	11/01/2017	62
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030568SWP	EAST CENTERTON - NOR CP WO 1 CONDITIONS	35500 - Poles and Fixtures	07/01/2017	285
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030590SWP	FLINT CREEK - SILOAM CP A1 POLE # STR100	35500 - Poles and Fixtures	06/01/2017	45,940
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030593SWP	CHAMBERS SPRING FL STR 8 ARM & STR 20 POLE	35500 - Poles and Fixtures	06/01/2017	15,999
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030666SWP	EAST CENTERTON - NOR DANGER TREE - HOBSON	35600 - Overhead Conductors, Device	06/01/2017	1,331
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030705SWP	PATTERSON - SOUTH NASH # 159	35500 - Poles and Fixtures	06/01/2017	14,925
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030815SWP	W BOONEVILLE-N MAGAZ CP WO 1 CONDITIONS	35500 - Poles and Fixtures	07/01/2017	3,137
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030925SWP	DIERKS - MENA CP #455 A-1 INSULATORS	35500 - Poles and Fixtures	09/01/2017	3,688
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL030941SWP	GREENLAND - VBI NORT - TREE ON LINE	35600 - Overhead Conductors, Device	11/01/2018	215
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL031010SWP	GREENLAND - VBI NORT CP WO 2 CONDITIONS	35500 - Poles and Fixtures	11/01/2017	1,538
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL031204SWP	HOSSTON-BLMBRG (AR) - STORM BIDDY	35600 - Overhead Conductors, Device	02/01/2018	770
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL031473SWP	PATTERSON - SOUTH DI HAZARD TREE - BIDDY	35600 - Overhead Conductors, Device	02/01/2018	382
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL031518SWP	ASHDOWN - TWELFTH ST CP WO 1 CONDITIONS	35500 - Poles and Fixtures	01/01/2018	802
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL031661SWP	S FAYETTEV-SE FAYETT RP 4 B/O STRUCTURES	35500 - Poles and Fixtures	10/01/2018	45,266
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL031835SWP	FLINT CREEK - BROOKL CP WO 1 CONDITIONS	35500 - Poles and Fixtures	02/01/2018	10,695
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL031835SWP	FLINT CREEK - BROOKL CP WO 1 CONDITIONS	35600 - Overhead Conductors, Device	02/01/2018	108
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL031912SWP	EAST CENTERTON E ROG B/O INSUATOR	35500 - Poles and Fixtures	01/01/2018	1,895
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032064SWP	SOUTH DIERKS- DIERKS A-1 # 20	35500 - Poles and Fixtures	10/01/2018	2,582
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032097SWP	DYESS EAST ROGERS POLES AND ARMS	35500 - Poles and Fixtures	10/01/2018	113,029
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032480SWP	FLINT CREEK - BROOKL CP WO 2 CONDITIONS	35600 - Overhead Conductors, Device	03/01/2018	3,703
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032502SWP	EUREKA SPRINGS HAR CP WO 1 CONDITIONS	35500 - Poles and Fixtures	05/01/2018	824
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032502SWP	EUREKA SPRINGS - HAR CP WO 1 CONDITIONS	35600 - Overhead Conductors, Device	05/01/2018	2,471
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032503SWP	DYESS-SPRINGDALE #2 REMOVE SW	35500 - Poles and Fixtures	05/01/2018	4,228
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032503SWP	DYESS-SPRINGDALE #2 REMOVE SW	35600 - Overhead Conductors, Device	05/01/2018	12,686
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032875SWP	GREENLAND VBI NORT HOBSON STORM	35600 Overhead Conductors, Device	01/01/2019	682
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032898SWP	PRAIRIE GROVE SILO STR 72 A1	35500 Poles and Fixtures	05/01/2018	277
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032899SWP	EAST CENTERTON - NOR CP WO 1 CONDITIONS	35500 Poles and Fixtures	05/01/2018	106
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032899SWP	EAST CENTERTON - NOR CP WO 1 CONDITIONS	35600 Overhead Conductors, Device	05/01/2018	588
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032962SWP	EAST ROGERS - BEAVER CP WO 1 CONDITIONS	35500 - Poles and Fixtures	11/01/2019	8,307
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032963SWP	DYESS-HYLAND CP WO 3 CONDITIONS	35500 - Poles and Fixtures	04/01/2019	51,740
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL032997SWP	DEQUEEN - MENA CP REPLACE 24 H-STRUCTURES	35500 - Poles and Fixtures	06/01/2019	130,867
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033086SWP	W BOONEVILLE N MAGAZ CP WO 1 CONDITIONS	35600 - Overhead Conductors, Device	06/01/2019	5,955
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033206SWP	BOONEVILLE - BRANCH GROUNDING LINE - HOBSON	35600 - Overhead Conductors, Device	12/01/2018	5,055
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033207SWP	TEXARKANA PLANT - 12TH ST A-1 HP INSULATORS	35600 - Overhead Conductors, Device	10/01/2018	2,190
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033264SWP	BOONEVILLE - BRANCH(CP WO 2 CONDITIONS	35500 - Poles and Fixtures	08/01/2018	8,092
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033264SWP	BOONEVILLE - BRANCH(CP WO 2 CONDITIONS	35600 - Overhead Conductors, Device	08/01/2018	130
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033265SWP	CHAMBERS SPRING - FL CP WO 1 CONDITIONS	35500 - Poles and Fixtures	08/01/2018	1,146

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033272SWP	FLINT CREEK - SILOAM CP WO 1 CONDITIONS	35500 - Poles and Fixtures	08/01/2018	12,036
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033302SWP	DYESS-SPRINGDALE N CP WO 12 CONDITIONS	35500 Poles and Fixtures	03/01/2019	118,568
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033302SWP	DYESS-SPRINGDALE N CP WO 12 CONDITIONS	35600 - Overhead Conductors, Device	03/01/2019	509
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033322SWP	DIERKS - MENA CP WO 16 CONDITIONS	35500 - Poles and Fixtures	06/01/2019	22,376
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033402SWP	EAST CENTERTON - NOR CP WO 2 CONDITIONS	35500 - Poles and Fixtures	11/01/2019	17,467
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033609SWP	FLINT CREEK - SILOAM 161KV 10+ CONDITIONS	35500 - Poles and Fixtures	11/01/2019	36,754
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033610SWP	W BOONEVILLE-N MAGAZ CP WO 4 CONDITIONS	35500 - Poles and Fixtures	07/01/2019	23,939
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033614SWP	NORTH HUNTINGTON DOUBLE CIRCUIT 3 CP WO 7 CONDITIONS	35600 - Overhead Conductors, Device	06/01/2019	27,447
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033622SWP	TEXARKANA P-BLOOMBUR STORM - DON VICKERS	35600 - Overhead Conductors, Device	12/01/2018	2,519
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL033692SWP	DIERKS - MENA CP	35500 - Poles and Fixtures	11/01/2019	39,352
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034008SWP	GREENLAND - PRAIRIE R/P BO POLES AND ARMS	35500 - Poles and Fixtures	07/01/2019	80,637
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034008SWP	GREENLAND - PRAIRIE R/P BO POLES AND ARMS	35600 - Overhead Conductors, Device	07/01/2019	1,001
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034014SWP	CHAMBERS DYESS 161 15 CONDITIONS	35500 - Poles and Fixtures	07/01/2019	93,430
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034014SWP	CHAMBERS - DYESS 161 15 CONDITIONS	35600 Overhead Conductors, Device	07/01/2019	32
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034015SWP	TONITOWN - DYESS #2 STOLDEN GROUNDS	35500 - Poles and Fixtures	01/01/2020	13,655
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034015SWP	TONITOWN - DYESS #2 STOLDEN GROUNDS	35600 - Overhead Conductors, Device	01/01/2020	15,382
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034048SWP	FULTON P-PATMOS APNL STORM PILKINGTON	35600 - Overhead Conductors, Device	03/01/2019	589
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034058SWP	FULTON P-PATMOS STORM DANGER TREE - PILKINGTON	35600 - Overhead Conductors, Device	03/01/2019	671
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034072SWP	GREENLAND-S FAYETTEV R/P STR'S	35500 - Poles and Fixtures	11/01/2019	8,680
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034072SWP	GREENLAND-S FAYETTEV R/P STR'S	35600 - Overhead Conductors, Device	11/01/2019	8
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034140SWP	DIERKS - WEST MURFRE CP WO 2 CONDITIONS	35500 Poles and Fixtures	11/01/2019	3,980
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034220SWP	N NEW BOSTON-PA (AR) #183 1 - R/W OROW-PILKINTON	35600 - Overhead Conductors, Device	03/01/2019	3,533
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034324SWP	DYESS-S SPRINGDALE 2 POLES	35500 - Poles and Fixtures	11/01/2019	23,730
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034739SWP	DYESS-SPRINGDALE NORTH 10 CONDITIONS	35500 - Poles and Fixtures	11/01/2019	8,888
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL034739SWP	DYESS-SPRINGDALE NORTH 10 CONDITIONS	35600 Overhead Conductors, Device	11/01/2019	992
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL035428SWP	SOUTH NASHVILLE - SO STORM - PILKINTON	35600 - Overhead Conductors, Device	12/01/2019	1,406
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL035430SWP	DEQUEEN - MENA (7) A 2 STRUCTURES (2) A-1 STRUCTURES	35500 - Poles and Fixtures	09/01/2019	82,812
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL035447SWP	CRAIG JCT-DEQUEE(AR) - STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	1,116
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL036034SWP	DEQUEEN - MENA CP A-1 # 176	35500 - Poles and Fixtures	11/01/2019	4,543
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL036166SWP	DEQUEEN - NASHVILLE CP # 139 A-1 ARM	35500 - Poles and Fixtures	11/01/2019	3,320
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL036197SWP	DIERKS - MENA 69KV - STORM REMOVE TREE-PILKINTON	35600 - Overhead Conductors, Device	12/01/2019	514
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARLRE	B111ARLRE T/SW/Shadow for B194ARLRE	TL036200SWP	HOSSTON-BLOOMBURG (AR) - STORM REMOVE TREE-PILKINTON	35600 Overhead Conductors, Device	12/01/2019	788
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	42685599SWP	PATTERSON SUB AR REPLACE MULTIPLEX W/SCHWEITZER ICON	35300 - Station Equipment	02/01/2019	51
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	42685616SWP	TURK SUB AR REPLACE MULTIPLEXER W/SCHWEITZER ICON	35300 Station Equipment	02/01/2019	4,228
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	42685617SWP	TELECOM DEMARC BLDG AR REPLACE MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	02/01/2019	1,909
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	42685620SWP	PLANT ELECTRONIC RM AR REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	02/01/2019	5,559
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	42685623SWP	NEW HOPE SWITCH AR REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	02/01/2019	6,452
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	42691760SWP	ARSENAL HILL SUB LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 Station Equipment	11/01/2018	1,954
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	42691771SWP	STALL CONTROL HOUSE LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	02/01/2019	4,414
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0179834SWP	CHAMBERS SPRING FR SDR-SEL1102 - REPLACE WITH SEL 3355	35300 - Station Equipment	01/01/2018	7,898
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0179835SWP	TONTITOWN FR SDR-SEL1102 - REPLACE WITH SEL 3355	35300 - Station Equipment	10/01/2017	6,597
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0185320SWP	HUNTINGTON STA - FAILED 12KV INSULATORS & MET CURRENT XFRMRS	35300 Station Equipment	06/01/2017	5,414
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0186359SWP	BONANZA STA REPLACE FAILED 34KV SWITCHES	35300 - Station Equipment	06/01/2017	1,340
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0186763SWP	EAST ROGERS STA - REPLACE FAILING BUS PT	35300 - Station Equipment	05/01/2018	4,725
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0187135SWP	NORTH HUNTINGTON STA REPLACE FAILED 69KV ARRESTERS	35300 - Station Equipment	11/01/2017	917
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0187143SWP	NORTH HUNTINGTON TRF P161 41 WEST-A MAJOR MAINTENANCE	35300 - Station Equipment	11/01/2017	30,092
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0187486SWP	FLINT CREEK SUB REPLACE FAILED 345KV ARRESTERS	35300 - Station Equipment	05/01/2018	13,393
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0187692SWP	S FAYETTEVILLE CAP BANK REPLACE FAILED CAPACITORS & LIMITER	35300 - Station Equipment	05/01/2018	75
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0187780SWP	EAST CENTERTON CCVT AECC CIRCUIT NORTH REPACE	35300 - Station Equipment	05/01/2018	2,690
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0187902SWP	EAST ROGERS CAP BANK REPLACE FAILED CAPACITORS & LIMITERS	35300 - Station Equipment	06/01/2017	6,308
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0188464SWP	REEVES ROAD DSC N HUNTINGTON CKT 32666 REPLACE INTERUPPTER	35300 - Station Equipment	07/01/2019	17,412
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0188475SWP	HOPE BAT BATTERY BANK BAT_4300011 CAPITAL PROJECT	35300 - Station Equipment	08/01/2017	6,008
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0188484SWP	EAST CENTERTON CCVT E ROGERS CKT WEST 574A93 REPLACE	35300 - Station Equipment	10/01/2017	2,574
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0188616SWP	FLINT CREEK - REPLACE DECATUR PHASE THREE METERS	35300 - Station Equipment	01/01/2019	10,504
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0188694SWP	TONTITOWN STATION - REPLACE AC SERVICE EQUIPMENT	35300 - Station Equipment	06/01/2017	978
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0188733SWP	SOUTH FAYETTEVILLE CB BUS TIE 10480 ADD CONTROL CABLE	35300 - Station Equipment	05/01/2017	5,901
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0188753SWP	SILOAM SPRINGS 161KV STATION REPLACE CABLE ON PT CB 4810	35300 - Station Equipment	11/01/2017	822
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0189361SWP	SILOAM SPRINGS 161KV STA REPLACE FAILED AC IN CONTROL HOUSE	35200 - Structures and Improvements	08/01/2017	476
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0189361SWP	SILOAM SPRINGS 161KV STA REPLACE FAILED AC IN CONTROL HOUSE	35300 - Station Equipment	08/01/2017	23
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0189487SWP	SOUTH DIERKS STA CAPITAL PROJECT/AC IN CONTROL HOUSE	35300 - Station Equipment	10/01/2017	2,714
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0189712SWP	DIXIELAND CAPITAL PROJECT RELAYS [BUS] BUS 69KV/PLC&RTU	35300 - Station Equipment	12/01/2018	78,120
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0190141SWP	FLINT CREEK SUB TRF P345 S0 EAST BUSHING FAILURE	35300 - Station Equipment	10/01/2018	143,135
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0190310SWP	FLINT CREEK SUB STA - AUTO TRANSFER SWITCH	35300 - Station Equipment	11/01/2017	1,996
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0190336SWP	HOPE STA CAPITAL PROJECT/ETHERNET SWITCH	35300 - Station Equipment	07/01/2018	1,430
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0194092SWP	NASHVILLE 69KV CB OKAY 3040 419Y2936 CAPITAL PROJECT	35300 - Station Equipment	01/01/2018	50,270
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0194218SWP	WEST BOONEVILLE STA REPLACE FAILED TRANSFER SWITCH	35300 - Station Equipment	05/01/2018	2,351
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0194266SWP	TURK TRF P345 S1 TB80068412 CAPITAL PROJECT/REPLACED SPR	35300 - Station Equipment	02/01/2018	1,458
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0195515SWP	SOUTH DIERKS BATCHARG BATTERY_CHARGER STA_1 14032633706 CAPI	35300 - Station Equipment	04/01/2018	2,251
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0195644SWP	SOUTHEAST TEXARKANA STA CAPITAL PROJECT/CCVT	35300 - Station Equipment	04/01/2018	2,209
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0195645SWP	SPRINGDALE CB DYESS 4850 352742 CAPITAL PROJECT/FUTURA METE	35300 - Station Equipment	07/01/2018	5,386
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0195783SWP	NORTH MAGAZINE - REPLACE AC UNIT	35200 - Structures and Improvements	03/01/2018	138

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0195783SWP	NORTH MAGAZINE - REPLACE AC UNIT	35300 - Station Equipment	03/01/2018	309
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0195819SWP	WEST BOONEVILLE REPLACE BATTERY CHARGER	35300 - Station Equipment	05/01/2018	2,134
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0195861SWP	DEQUEEN TRF P141 48 RPP39571 CAPITAL PROJECT	35300 - Station Equipment	02/01/2018	1,077
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0195887SWP	SUGAR HILL (SW) TRF P142 26 702081 CAPITAL PROJECT	35300 - Station Equipment	07/01/2018	2,159
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0197468SWP	DEQUEEN TRF P141 48 RPP39571 CAPITAL PROJECT/69KV ARRESTERS	35300 - Station Equipment	07/01/2018	3,908
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0197608SWP	FLINT CREEK SUB CB SHIPE RD 11750 REPLACE COMPRESSOR	35300 - Station Equipment	05/01/2018	1,781
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0197643SWP	EAST ROGERS STA REPLACE 3 ARRESTERS ON BUSS	35300 - Station Equipment	11/01/2018	3,485
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0197692SWP	DEQUEEN TRF P141 48 RPP39571 CAPITAL PROJECT/FAILED FANS	35300 - Station Equipment	04/01/2018	1,546
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0198036SWP	TURK STA TURK CAPITAL PROJECT	35300 - Station Equipment	06/01/2018	644
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0198064SWP	HOPE COMM ETHERNET SWITCH MPC_1003710008 CAPITAL PROJECT	35300 - Station Equipment	11/01/2018	93
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0198842SWP	2018 GEUPGRADE TONTITOWN STA_3 RELAYS	35300 - Station Equipment	12/01/2019	37
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0198842SWP	2018 GEUPGRADE TONTITOWN STA_3 RELAYS	35316 - Station Equipment-SmartGrid	12/01/2019	11,456
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0199151SWP	FLINT CREEK SUB CB 12280 & 11240 - REPLACE BUSHINGS	35300 - Station Equipment	08/01/2018	4,607
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0199627SWP	SUGAR HILL (SW) STA CAPITAL PROJECT/STATION BATTERY	35300 - Station Equipment	10/01/2018	8,423
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0199633SWP	CHAMBERS SPRING REPLACE FAILED 345KV CCVT	35300 - Station Equipment	09/01/2018	4,457
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0199755SWP	MENA TRF P145 02 70705A CAPITAL PROJECT/FAILED FANS	35300 - Station Equipment	08/01/2018	1,691
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0199812SWP	MENA STA MENA CAPITAL PROJECT	35300 - Station Equipment	01/01/2019	4,368
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0199950SWP	SOUTHEAST TEXARKANA DSC MOS 13128 V2981621 CAPITAL PROJECT	35300 - Station Equipment	10/01/2018	3,850
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0200058SWP	NASHVILLE 69KV CB OKAY 3040 CB 3040 230624020A CAPITAL PROJE	35300 - Station Equipment	07/01/2018	5,505
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0200330SWP	CHAMBERS SPRING CB 12730 498963 CAPITAL PROJECT/REPLACE SF6	35300 - Station Equipment	01/01/2019	49,761
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0200420SWP	TURK TRF AUTO #2 138/115 KV P141 24 D584570 CAPITAL PROJECT	35300 - Station Equipment	12/01/2018	78,609
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0200536SWP	NORTH HUNTINGTON REPLACE FAILED 69KV ARRESTERS	35300 - Station Equipment	08/01/2018	231
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0200858SWP	EAST ROGERS REPLACE FAILED 69KV CT	35300 - Station Equipment	01/01/2019	3,742
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0204263SWP	FLINT CREEK SUB CAPITAL PROJECT RELAYS [CKT] EAST CENTERTON	35300 - Station Equipment	12/01/2019	68
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0204263SWP	FLINT CREEK SUB CAPITAL PROJECT RELAYS [CKT] EAST CENTERTON	35316 - Station Equipment-SmartGrid	12/01/2019	3,658
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0204283SWP	SPRINGDALE CB DYESS 4850 REPLACE ARRESTERS	35300 - Station Equipment	06/01/2019	1,527
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0204643SWP	NORTH HUNTINGTON REPLACE FAILED 161KV CCVT	35300 - Station Equipment	08/01/2018	3,129
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0205287SWP	TURK STA CAPITAL PROJECT/FANS TRANSF 141 24	35300 - Station Equipment	12/01/2019	941
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0206710SWP	DIERKS CB MENA 1V90 522991 CAPITAL PROJECT/ARRESTER	35300 - Station Equipment	04/01/2019	608
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0206783SWP	DYESS XMFR P6635 NORTH REPLACE BUSHING	35300 - Station Equipment	05/01/2019	1,935
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0207775SWP	BOONEVILLE STA CAPITAL PROJECT/POTIENTAL TRANS,SURGE ARREST	35300 - Station Equipment	12/01/2018	2,835
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0211179SWP	TR080004497_DEQUEEN STA CAPITAL PROJECT/CB3630 & ARRESTER	35300 - Station Equipment	07/01/2019	6,548
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0211536SWP	TR080043999_OKAY CB1400 H14SA25S7202 CAPITAL PROJECT/REPLAC	35300 Station Equipment	07/01/2019	34,939
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0212102SWP	TONTITOWN TRF AUTO T1 SOUTH REPLACE ARRESTERS	35300 - Station Equipment	05/01/2019	16,030
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0212240SWP	FLINT CREEK PNEUMATIC MECHANISM REPLACEMENT FOR CB 11750	35300 - Station Equipment	08/01/2019	15,789
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0212242SWP	TR080055733_PRESCOTT POD BAT MOABS BATTERY 12K30AKTD777100 S	35300 - Station Equipment	07/01/2019	1,447
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0212269SWP	TR080055746_PRESCOTT POD STA CAPITAL PROJECT/ETHERNET SWITC	35300 - Station Equipment	12/01/2019	222
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0212626SWP	SOUTHEAST FAYETTEVILLE HYLAND LINE REPLACE CCVT	35300 Station Equipment	10/01/2019	3,423
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0212642SWP	SILOAM SPRINGS 161KV CCVT - REPLACE CCVT	35300 - Station Equipment	07/01/2019	3,446
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0215221SWP	SPRINGDALE VT BUS 69KV PT REPLACE PT'S AND ARRESTERS	35300 Station Equipment	07/01/2019	10,198
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0215490SWP	TR080055719_NE TEXARKANA TAP BAT BATTERY BANK BATT 421951132	35300 - Station Equipment	12/01/2019	949
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0215869SWP	NASHVILLE 69KV CB CB-3050 REPL FAILED CB AND REPL LINE PT	35300 Station Equipment	12/01/2019	20,256
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	T0219893SWP	HUNTINGTON REPLACE ARRESTERS AND RETIRE REGULATORS	35300 - Station Equipment	03/01/2020	2,647
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	TS0222179SWP	NORTH MAGAZINE BATTERY BANK - REPLACE FAILING BANK	35300 - Station Equipment	12/01/2019	4,617
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111ARSRE	B111ARSRE SHADOW for B194ARSRE	TS0222659SWP	SOUTH NASHVILLE CB-REPL FAILED AIR COMPRESSOR	35300 - Station Equipment	03/01/2020	2,390
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	42666826SWP	69 KV RED POINT-BELLVUE LINE 104 4 REPL 31 SETS X ARMS/INS	35500 - Poles and Fixtures	06/01/2017	75,927
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	42667978SWP	E LEESVILLE - N LEESVILLE TLN194 00348 REPL 30 XARM/8 POLES	35500 - Poles and Fixtures	06/01/2017	83,567
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	42674463SWP	2017 DOP - 138KV TRICHEL - WHITEHURST LINE 119 1	35500 - Poles and Fixtures	06/01/2017	8,738
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	42719405SWP	MANY - NOBLE 69 KV REPLACE CROSS PAY TRAILING INVOICES	35500 - Poles and Fixtures	07/01/2017	482
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	42731934SWP	E LEESVILLE - N LEESVILLE TLN194 00348 OPEN TO C/O CHARGES	35500 - Poles and Fixtures	09/01/2017	86,759
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL030070SWP	CALUMET- RED POINT POLE # 61	35500 - Poles and Fixtures	06/01/2017	14,427
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL030167SWP	ARSENAL HILL - WATERWORKS GROUNDS STOLEN	35500 - Poles and Fixtures	06/01/2017	6,735
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL030220SWP	FLOURNOY - SUMMER GR (WLWRTH RD # 22)	35500 - Poles and Fixtures	06/01/2017	17,087
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL030644SWP	ARSENAL HILL - BROOK # 1,2&3 A-2	35500 - Poles and Fixtures	10/01/2017	80,916
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL030843SWP	HOSSTON - NORTH BENTON REPLACE 40 STRUCTURES	35500 - Poles and Fixtures	10/01/2017	168,979
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL030844SWP	HOSSTON - SUPERIOR REPLACE 38 STRUCTURES	35500 - Poles and Fixtures	09/01/2018	131,526
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL030847SWP	FLOURNOY WASKOM LA REPLACE 35 STRUCTURES	35500 - Poles and Fixtures	10/01/2017	110,165
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL030863SWP	DOGWOOD TAP CP WO 1 CONDITIONS	35500 - Poles and Fixtures	09/01/2017	677
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL030909SWP	NOBLE - MOUNT ZION CP REPLACE ARMS ON 30 STRUCTURES	35500 - Poles and Fixtures	10/01/2017	49,072
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL030910SWP	BELMONT-MARTHAVILLE CP REPLACE 30 SETS OF ARMS AND 7 POLES	35500 - Poles and Fixtures	10/01/2017	72,961
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL030963SWP	FLOURNOY - WOODLAW2 STORM -REMOVE TREE FROM CONDUCOR - PILKI	35600 - Overhead Conductors, Device	02/01/2018	3,234
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL031014SWP	GENERAL MOTORS - SOU STORM DANGER TREE - PILKINGTON	35600 - Overhead Conductors, Device	02/01/2018	1,628
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL031021SWP	BLANCHARD - NORTH MARK # 167 A-1	35500 - Poles and Fixtures	09/01/2017	438
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL031173SWP	STONEWALL TAP CP # 50 - 53 A-1 TREE DAMAGE	35500 - Poles and Fixtures	09/01/2017	33,847
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL031225SWP	BELCHER - HOSSTON CP REPLACE 10 A2 H STRUCTURES	35500 - Poles and Fixtures	09/01/2019	0
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL031274SWP	NOBLE - MOUNT ZION CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	4,387
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL031572SWP	SOUTHWEST SHREVEP-WE CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2018	20,093
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL031984SWP	HARDY STREET - MIDWAY (10) A-2 WOOD POLES	35500 - Poles and Fixtures	10/01/2018	83,010
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032020SWP	FLOURNOY - SUMMER GROVE STR'S 60 - 65 A-2	35500 - Poles and Fixtures	10/01/2018	49,234
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032020SWP	FLOURNOY - SUMMER GROVE STR'S 60 - 65 A-2	35600 - Overhead Conductors, Device	10/01/2018	49,234
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032030SWP	LONGWOOD - EL DORADO # 0/2 ARM A-2	35500 - Poles and Fixtures	10/01/2018	13,566

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032045SWP	ARSENAL HILL-LONGWOD # 81 CAR HIT POLE A-1	35500 - Poles and Fixtures	09/01/2018	3,021
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032139SWP	WALLACE LAKE - MANSF # 128 & 154 XARMS	35500 - Poles and Fixtures	10/01/2018	9,526
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032360SWP	N LEESVILLE HORNBECK (30) SETS X-ARMS (2) POLES	35500 - Poles and Fixtures	10/01/2018	51,429
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032360SWP	N LEESVILLE-HORNBECK (30) SETS X-ARMS (2) POLES	35600 - Overhead Conductors, Device	10/01/2018	51,430
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032361SWP	ROBSON ROAD(POD-KING INCREASE CONDUCTOR HEIGHT	35400 - Towers and Fixtures	10/01/2018	46,737
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032587SWP	LOGANSPORT - STONEWALL (7) POLES & ANCHORS	35500 Poles and Fixtures	10/01/2018	66,736
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032650SWP	FLOURNOY - LONGWOOD CP WO 1 CONDITIONS	35500 - Poles and Fixtures	09/01/2018	8,336
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032658SWP	BRONLEE RD-MINDEN RD CP # 42 A 1 POLE	35500 - Poles and Fixtures	10/01/2018	2,958
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032687SWP	BRONLEE RD-MINDEN RD CP # 44 A-1 POLE	35500 Poles and Fixtures	10/01/2018	12,604
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032735SWP	RED POINT - BELLEVUE - DANGER TREE PILKINGTON	35600 Overhead Conductors, Device	12/01/2018	2,106
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032888SWP	TRICHEL STREET - WHITEHURST A 2 STUB POLE # 55	35500 - Poles and Fixtures	06/01/2019	3,291
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL032985SWP	BLANCHARD - LIEBERMAN A-1 # 97 X ARM	35500 - Poles and Fixtures	12/01/2018	941
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL033027SWP	SEVENTIETH STREET TAP (5) A-1 POLES, BAD LOCATION	35500 - Poles and Fixtures	10/01/2018	39,822
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL033275SWP	CAPLIS MCDADE STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2018	662
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL033320SWP	EDWARDS STREET - HUMBUG A-2 POLES	35500 - Poles and Fixtures	01/01/2019	48,420
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL033330SWP	CAPLIS MCDADE OUTAGE GROW IN - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2018	4,207
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL033342SWP	TRICHEL TAP - TRICHE - STORM PATROL AND GROUNDING - PILKINGT	35600 - Overhead Conductors, Device	12/01/2018	4,915
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL033558SWP	ROBSON ROAD(POD KING CP A-1 # 65 & 66 ARMS	35500 - Poles and Fixtures	10/01/2018	1,603
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL033608SWP	E LEESVILLE - HICKS CP A-1 ALL INSULATORS SHOT OUT	35500 - Poles and Fixtures	06/01/2019	2,955
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL033629SWP	RED POINT - WHITEHUR CP #55 WP DAMAGE	35500 - Poles and Fixtures	06/01/2019	18,401
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL033630SWP	LIEBERMAN RED POIN CP A-1 X-ARM # 153	35500 - Poles and Fixtures	06/01/2019	6,076
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL033682SWP	LOGANSPORT - STANLEY CP A-1 ARM	35500 - Poles and Fixtures	11/01/2019	3,694
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL033720SWP	LONGWOOD EL DORADO CP A-2 ARM 24/3	35500 - Poles and Fixtures	06/01/2019	13,286
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL034036SWP	HOSSTON - NORTH BENT CP	35500 - Poles and Fixtures	07/01/2019	35,548
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL034051SWP	BRONLEE RD-MINDEN RD CP # 56 A 2	35500 - Poles and Fixtures	07/01/2019	17,943
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL034224SWP	LOGANSPORT - STONEWA CP A-1 # 40	35500 - Poles and Fixtures	11/01/2019	1,943
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL034460SWP	CALUMET- RED POINT CP # 15 & 36 A-2 POLES	35500 - Poles and Fixtures	07/01/2019	20,156
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL034680SWP	LIEBERMAN RED POINT CP # 5 A-1 POLE	35500 - Poles and Fixtures	11/01/2019	3,961
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL034711SWP	RED POINT - BELLEVUE CP A-2 / 3 POLE ANGLE	35500 - Poles and Fixtures	07/01/2019	40,606
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL034882SWP	BLANCHARD - LIEBERMA CP A-1 X-ARM	35500 - Poles and Fixtures	11/01/2019	1,672
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035232SWP	NOBLE - MOUNT ZION STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	1,055
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035312SWP	HOSSTON-BLMBRG (LA) STORMS _ PILKINGTON	35600 - Overhead Conductors, Device	05/01/2019	6,538
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035351SWP	BLANCHARD - NORTH MA STORM - BIDDY	35600 - Overhead Conductors, Device	12/01/2019	1,325
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035395SWP	BLANCHARD - LIEBERMAN # 88 A 1 CROSSARM	35500 - Poles and Fixtures	09/01/2019	1,200
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035446SWP	RED POINT - BELLEVUE STORM _ PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	639
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035516SWP	LOGANSPORT - STONEWA STORM - PILKINGTONG	35600 - Overhead Conductors, Device	12/01/2019	1,420
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035517SWP	ELLERBE ROAD-FERN R/W STORM - PILKINGOTN	35600 - Overhead Conductors, Device	06/01/2019	2,192
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035551SWP	HOSSTON - NORTH BENT A-2 POLES 234 & 235	35500 - Poles and Fixtures	11/01/2019	42,470
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035728SWP	BRONLEE RD-MINDEN RD CP # 44 A-1 POLE	35500 - Poles and Fixtures	09/01/2019	14,755
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035852SWP	HOSSTON - NORTH BENT STORM - PILKINTON	35600 - Overhead Conductors, Device	12/01/2019	550
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035874SWP	FLOURNOY - SUMMER GROVE # 29 & 30 A-2 POLES	35500 - Poles and Fixtures	11/01/2019	9,871
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035984SWP	HOSSTON - SUPERIOR A-1 # 38	35500 - Poles and Fixtures	11/01/2019	3,621
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035985SWP	LONGWOOD - EL DORADO A-1 # 23/1	35500 - Poles and Fixtures	11/01/2019	16,744
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LALRE	B111LALRE T/SW/Shadow for B194LALRE	TL035991SWP	BLANCHARD - LIEBERMAN A-1 # 87 POLE	35500 Poles and Fixtures	11/01/2019	9,051
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LARMB	B111LARMB Reimbursable-DOP-111 LA Shadow	TL034222SWP	BRONLEE RD-MINDEN RD CP WO CAR HIT POLE FIRST TIME STR 53	35500 - Poles and Fixtures	04/01/2019	6,090
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LARMB	B111LARMB Reimbursable-DOP 111 LA Shadow	TL034223SWP	BRONLEE RD MINDEN RD CP WO CAR HIT POLE SECOND TIME STR 53	35500 - Poles and Fixtures	04/01/2019	5,714
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	42691736SWP	CAPLIS STATION LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	11/01/2018	25,533
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	42691741SWP	MCDADE STATION LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	11/01/2018	18,119
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	42691750SWP	HAUGHTON STATION LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	11/01/2018	18,329
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	42691754SWP	RED POINT STATION LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	11/01/2018	18,902
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0179520SWP	ARSENAL HILL CB CAPACITOR 13730 053881 CAPITAL PROJECT	35300 - Station Equipment	01/01/2018	12,362
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0179683SWP	GENERAL MOTORS STA GENERAL MOTORS CAPITAL PROJECT	35300 - Station Equipment	01/01/2017	44,069
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0179934SWP	SOUTHWEST SHREVEPORT REPL FAILED PAD MOUNT XFMR	35300 - Station Equipment	04/01/2017	4,315
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0180027SWP	SOUTHWEST SHREVEPORT STA PROJE MOABS 1003S	35300 - Station Equipment	12/01/2018	256
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0187368SWP	FORT HUMBUG STA CAPITAL PROJECT/POTENTIAL TRANS 69KV	35300 - Station Equipment	06/01/2017	2,479
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0187636SWP	CEDAR GROVE (SW) STA CAPITAL PROJECT/BATTERY&CHARGER	35300 - Station Equipment	06/01/2017	3,724
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0187875SWP	FORT HUMBUG STA CAPITAL PROJECT/69KV CB 10130	35300 - Station Equipment	06/01/2017	22,489
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0188203SWP	SUMMER GROVE STA CAPITAL PROJECT/CB 1P20	35300 - Station Equipment	07/01/2017	20,876
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0188223SWP	ARSENAL HILL STA CAPITAL PROJECT/ENG SERVICES	35300 - Station Equipment	11/01/2017	13,968
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0189263SWP	GENERAL MOTORS STA CAPITAL PROJECT/3 CCVTS	35300 - Station Equipment	10/01/2017	16,450
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0189828SWP	ARSENAL HILL STA CAPITAL PROJECT/P7184&P7202 FAILED FANS	35300 - Station Equipment	09/01/2017	566
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0189841SWP	BROADMOOR STA CAPITAL PROJECT/FAILED RMC 30	35300 - Station Equipment	09/01/2017	412
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0189860SWP	LOGANSPORT STA CAPITAL PROJECT/CHANGED OUT FAILED FANS	35300 - Station Equipment	12/01/2017	4,116
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0189977SWP	GENERAL MOTORS STA CAPITAL PROJECT/CB11000	35300 - Station Equipment	10/01/2017	33,767
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0190368SWP	LAYFIELD 500KV TRF P500 03 AUTO XFMR 3 PHASE C 14QP000002490	35300 - Station Equipment	10/01/2018	746
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0194096SWP	LUCAS STA CAPITAL PROJECT/REPLACE RMC 30	35300 - Station Equipment	11/01/2017	187
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0194189SWP	HARTS ISLAND CB TLINE FORT HUMBUG 10554 77232S2 CAPITAL PROJ	35300 - Station Equipment	05/01/2018	8,242
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0194309SWP	LUCAS CCVT ELLERBE MID 1646701007 CAPITAL PROJECT/FAILED69KV	35300 - Station Equipment	07/01/2018	3,049
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0195519SWP	ARSENAL HILL STA CAPITAL PROJECT/CAPACITOR CANS	35300 - Station Equipment	12/01/2017	1,297
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0199422SWP	ARSENAL HILL STA CAPITAL PROJECT/BREAKER 7280	35300 - Station Equipment	05/01/2018	18,303
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0199473SWP	LONGWOOD (SW) MET LONGWOOD_TO_SAREPTA_345KV OUT 30834190_EMS	35300 - Station Equipment	03/01/2020	1,137

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0199543SWP	SOUTHWEST SHREVEPORT STA CAPITAL PROJE/138KV ARRESTERS	35300 Station Equipment	09/01/2018	3,884
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0200264SWP	RED POINT CAPB CAP BANK 12207 CAPITAL PROJECT/CAPACITOR CAN	35300 - Station Equipment	08/01/2018	4,231
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0200287SWP	LIEBERMAN STA CAPITAL PROJECT/FAILED 138KV SWITCHES	35300 - Station Equipment	04/01/2019	26,585
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0200452SWP	PORT ROBSON MET BENTELER STEEL MILL 1 PRIMARY 1132810049 113	35300 - Station Equipment	03/01/2020	1,411
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0200843SWP	SOUTHWEST SHREVEPORT STA CAPITAL PROJ/345KV CB 10510	35300 - Station Equipment	09/01/2018	164,647
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0204353SWP	ARSENAL HILL GENERALCONDUCTOR 2 5? IPS SCH 40 CAPITAL PROJ	35300 - Station Equipment	01/01/2019	2,877
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0204504SWP	ARSENAL HILL STA CAPITAL PROJECT/CTVTS	35300 - Station Equipment	10/01/2018	31,020
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0204544SWP	LONGWOOD (SW) STA CAPITAL PROJECT/REPLACE BOTH BATTERY CHRG	35300 - Station Equipment	01/01/2019	4,732
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0204692SWP	SOUTH SHREVEPORT TRF P141 25 W AUTO D589213 CAPITAL PROJECT	35300 - Station Equipment	07/01/2019	6,479
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0204694SWP	WALLACE LAKE TRF P141 0 WEST C0190351 CAPITAL PROJECT/FANS	35300 - Station Equipment	07/01/2019	8,170
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0204713SWP	WALLACE LAKE STA CAPITAL PROJECT/AIR CONDITIONER UNIT	35300 - Station Equipment	09/01/2018	674
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0206204SWP	HARDY STREET CB FLOURNOY 1X90 237Y4497 CAPITAL PROJECT	35300 - Station Equipment	09/01/2018	39,881
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0206619SWP	NORTH BENTON STA CAPITAL PROJECT/FAILED FANS	35300 - Station Equipment	07/01/2019	9,102
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0206827SWP	ARSENAL HILL CAPB CAP BANK 13730 CAPBANK13730/FAILED CANS	35300 - Station Equipment	11/01/2018	1,439
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0206863SWP	SUPERIOR (SW) CB CB-9060 9739/FAILED BREAKER 9060	35300 - Station Equipment	07/01/2019	50,897
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0206963SWP	SOUTH SHREVEPORT CB CAPACITOR 1V00 364371/REPLACE BREAKER	35300 Station Equipment	07/01/2019	24,837
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0210566SWP	TRO80003257_LONGWOOD (SW)CAPITAL PROJECT/12KV HOOKSTICK	35300 - Station Equipment	07/01/2019	3,203
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0211087SWP	TRO80003538_SOUTHWEST SHREVEPORT STA/CONTROL HOUSE LIGHTS	35300 - Station Equipment	07/01/2019	680
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0211200SWP	TRO80003442_SOUTH SHREVEPORT STA CAPITAL P/PERIMITER FENCE	35200 - Structures and Improvements	01/01/2020	4,747
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0211200SWP	TRO80003442_SOUTH SHREVEPORT STA CAPITAL P/PERIMITER FENCE	35300 - Station Equipment	01/01/2020	31,901
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0211371SWP	TRO80003442_SOUTH SHREVEPORT STA CAPITAL P/ANTENNA	35300 - Station Equipment	01/01/2020	97
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0212554SWP	WHITEHURST CAPB 1P60 CAP BANK NA02 CAPITAL PROJECT/FUSE&CAP	35300 - Station Equipment	01/01/2020	666
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0212556SWP	TRO80004301_RED POINT CAPB CAP BANK 12207/FUSES&CAPACITORS	35300 - Station Equipment	01/01/2020	507
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0212557SWP	TRO80050478_WATERWORKS (SW) CAPB CAP BANK 6970/FUSES&CAPS	35300 - Station Equipment	01/01/2020	959
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0212559SWP	ARSENAL HILL CAPB CAP BANK 1U30/FUSES & CAPACITORS	35300 - Station Equipment	01/01/2020	1,385
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0215146SWP	TRO80003298_LIEBERMAN TRF P140 7 E AUTO 1998118 CAPITAL PROJ	35300 - Station Equipment	01/01/2020	2,941
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111LASRE	B111LASRE T/SW/Shadow for B194LASRE	T0215521SWP	TRO80003442_SOUTH SHREVEPORT STA CAPITAL/SECURITY PANELS	35300 - Station Equipment	01/01/2020	102,625
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42683357SWP	NETTLETON TAP REPLACE ARMS	35500 - Poles and Fixtures	04/01/2017	1,619
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42683749SWP	LONGWOOD - SCOTTSVILLE REPL POLES & CROSS ARMS	35500 - Poles and Fixtures	06/01/2017	103,345
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42684225SWP	ROCK HILL - KNOX LEE REPAIR/REPLACE STOLEN GROUNDS	35500 - Poles and Fixtures	06/01/2017	5,988
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42689417SWP	KNOX LEE - ROCK HILL C/O 39 POLES/STRUCTURES	35500 - Poles and Fixtures	11/01/2018	42,229
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42750932SWP	GREGGTON-WATERWORKS MID VALLEY TAP C/O VARIOUS STRUCTURES	35500 - Poles and Fixtures	12/01/2017	10,566
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42758166SWP	PILGRIMS PRIDE - WINFIELD - REPLACE BAD INSULATORS	35600 - Overhead Conductors, Device	12/01/2017	6,718
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42781303SWP	5-9-16 STRM N W TEXARKANA-LYDIA VALLIANT TRAILING INVOICES	35400 - Towers and Fixtures	01/01/2018	79,434
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42787246SWP	HAWKINS - PERDUE LINE 211 REPLACE 1 ARM	35500 - Poles and Fixtures	12/01/2017	2,288
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42814191SWP	GILMER-PITTSBURG STR 261 BROKE ARM	35500 - Poles and Fixtures	09/01/2018	488
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42814903SWP	NW TEXARKANA-VALLIANT DAVIT ARMS CHANGEOUT (16)	35500 - Poles and Fixtures	12/01/2018	42,529
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42830605SWP	2018 DOP HARRISON RD - PERDUE ST 142 CAR HIT POLE	35500 Poles and Fixtures	12/01/2018	4,904
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42831736SWP	2018-EASEMENT RENEWAL IPC DOMINO-WEST ATLANTA SEP TL241	35010 - Land Rights	12/01/2018	2,430
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42846494SWP	2018 WILKES N NEW BOSTON C/O BAD STRUCTURES	35500 - Poles and Fixtures	01/01/2019	25,214
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42849914SWP	ATLANTA - LINDEN REPLACE 9 STRUCTURES AND ARMS	35500 - Poles and Fixtures	01/01/2019	92,050
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	42899148SWP	QUITMAN-N MINEOLA - REPLACE BROKEN STRUCTURE 254	35500 - Poles and Fixtures	01/01/2019	10,784
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	43000092SWP	IPC DOMINO WEST AT CP WO 41 A-2 CONDITIONS	35500 - Poles and Fixtures	10/01/2019	(27,454)
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL0036467SWP	CLARENDON - JERICHO (T) CP WO 3 CONDITIONS TLN047	35500 - Poles and Fixtures	12/01/2019	3,241
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL029675SWP	MT VERNON TAP #1 CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	3,800
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030071SWP	BAN - IPC DOMINO # 221 POLE	35500 Poles and Fixtures	06/01/2017	16,415
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030149SWP	NORTHWEST TEXARKANA1 CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	3,896
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030191SWP	PETTY - WILKES OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	10/01/2017	1,182
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030204SWP	SHAMROCK-MAGIC CITY CP WO 1 CONDITIONS TLN200	35500 - Poles and Fixtures	06/01/2017	1,956
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030205SWP	W CHILDRESS SHAMROCK CP WO 1 CONDITIONS TLN00048	35500 - Poles and Fixtures	06/01/2017	525
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030289SWP	LK LAMOND-SE LONGVIE ALL GROUNDS STOLEN	35500 - Poles and Fixtures	06/01/2017	86,785
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030328SWP	DANGERFIELD - HUGHES # 106 A 1	35500 - Poles and Fixtures	06/01/2017	968
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030342SWP	MEMPHIS - CLARENDON CP WO 1 CONDITIONS TLN00046	35500 - Poles and Fixtures	06/01/2017	1,867
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030366SWP	LOGANSPORT-TENAHA OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2017	2,954
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030373SWP	LOGANSPORT-TENAHA OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2017	414
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030387SWP	W CHILDRESS-ESTELLIN CP WO 13 CONDITIONS TLN00045	35500 - Poles and Fixtures	06/01/2017	5,211
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030447SWP	MIDVALLEY PIPELINE T DEAD TREE JIMMY DON	35600 - Overhead Conductors, Device	11/01/2017	1,059
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030472SWP	CLARKSVILLE - PERDUE CP WO 2 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	498
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030500SWP	PERDUE N-CLAKSVILLE CP WO 2 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	6,011
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030538SWP	CLARKSVILLE PERDUE CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	4,636
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030548SWP	LOGANSPORT-TENAHA - STORM TREE - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2017	1,149
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030703SWP	LK LAMOND-SE LONGVIE # 127	35500 - Poles and Fixtures	09/01/2017	19,074
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030706SWP	SE LONGVIEW-WHITNEY # 36	35500 - Poles and Fixtures	09/01/2017	12,351
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030707SWP	KILGORE - WHITNEY 10 STRUCTURES STORM DAMAGE	35500 - Poles and Fixtures	09/01/2017	32,541
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030708SWP	LAKE LAMOND - LONGV	35500 - Poles and Fixtures	10/01/2017	34,625
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030756SWP	VERNON MAIN-N VERNON CP WO 4 CONDITIONS TLN00176	35500 - Poles and Fixtures	09/01/2017	13,991
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030767SWP	EVANSIDE - SAWMILL CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	2,912
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030801SWP	LAKE LAMOND - LONGVIEW HEIGHTS 18 - A-2 POLES # 73 THRU #	35500 - Poles and Fixtures	09/01/2017	65,753
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030824SWP	VERNON MAIN-N VERNON CP WO 22 CONDITIONS TLN00176	35500 - Poles and Fixtures	09/01/2017	34,551
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030826SWP	MARSHALL 69 - NORTH CP WO 1 CONDITIONS	35500 Poles and Fixtures	12/01/2017	4,602
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030839SWP	WINFIELD - WINNSBORO CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2017	5,566

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030848SWP	LONE STAR POWER PLAN A-1 # 7 BROKE X-ARM	35500 - Poles and Fixtures	09/01/2017	443
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030862SWP	PETTY - WILKES STORM - BIDDY	35600 - Overhead Conductors, Device	01/01/2018	1,577
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030916SWP	DIANA - PLILER ROAD STORM OROW TREE REMOVAL - PILKINGTON	35600 - Overhead Conductors, Device	01/01/2018	451
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030960SWP	TAYLOR STREET - BANN # 27 A-1	35500 - Poles and Fixtures	10/01/2017	2,102
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030962SWP	CLARKSVILLE - PERDUE #68 A 1 ARM	35500 - Poles and Fixtures	09/01/2017	990
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL030967SWP	LONE STAR SOUTH - WI R/W STORM - PILKINGTON	35600 Overhead Conductors, Device	08/01/2017	4,588
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL031030SWP	LETOURNEAU TAP CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2017	4,727
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL031032SWP	PITTSBURG - WINNSBOR CP WO 1 CONDITIONS	35500 Poles and Fixtures	12/01/2017	660
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL031157SWP	GILMER - PITTSBURG CP WO 1 CONDITIONS	35500 - Poles and Fixtures	01/01/2018	26,689
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL031159SWP	GILMER - PERDUE CP WO 1 CONDITIONS	35500 - Poles and Fixtures	01/01/2018	31,276
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL031166SWP	WINFIELD - WINNSBORO CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	4,808
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL031177SWP	PETTY - WILKES CP # 90 A-1 3 POLE STRUCTURE BROKEN	35500 - Poles and Fixtures	09/01/2017	27,228
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL031287SWP	IPC DOMINO WEST AT DEAD TREE - WELLBORN	35600 - Overhead Conductors, Device	02/01/2018	939
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL031338SWP	LK LAMOND-SE LONGVIE LAKE CROSSING H FRAMES	35500 - Poles and Fixtures	10/01/2017	53,228
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL031362SWP	PETTY - WILKES CP WO 1 CONDITIONS	35500 - Poles and Fixtures	11/01/2017	1,023
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL031512SWP	LONGVIEW HEIGHTS - MARSH - DANGER TREE AND PATROL DON VICKE	35600 - Overhead Conductors, Device	02/01/2018	684
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032065SWP	HUGHES SPRINGS - LSS A-1 # 59	35500 - Poles and Fixtures	08/01/2018	12,663
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032135SWP	PETTY - WILKES CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2018	23,076
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032140SWP	KILGORE - OVERTON CP WO 1 CONDITIONS	35500 - Poles and Fixtures	09/01/2018	641
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032378SWP	DIANA WELSH (CKT #2) DANGER TREE - BIDDY	35600 - Overhead Conductors, Device	12/01/2018	2,964
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032388SWP	PETTY PIGRIM'S PRIDE CP WO 2 CONDITIONS	35600 - Overhead Conductors, Device	10/01/2018	1,494
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032431SWP	WEST ATLANTA - WILKE -PILKINTON	35600 - Overhead Conductors, Device	11/01/2018	474
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032494SWP	JEFFERSON SWITCHING1 DANGER TREE	35600 - Overhead Conductors, Device	11/01/2018	69
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032505SWP	JEFFERSON - NORTH MA DANGER TREE - REPS	35600 - Overhead Conductors, Device	11/01/2018	1,124
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032514SWP	PIRKEY - SCOTTSVILLE #44 A-1	35500 - Poles and Fixtures	08/01/2018	8,785
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032516SWP	IPC JEFFERSON - LIE1 CP WO 3 CONDITIONS	35500 - Poles and Fixtures	08/01/2018	12,502
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032662SWP	BANN - THIRTY NINTH CP # 87 A-1 POLE	35600 - Overhead Conductors, Device	02/01/2019	6,004
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032664SWP	JEFFERSON - NORTH - PILKINGTON	35600 - Overhead Conductors, Device	11/01/2018	543
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032685SWP	WEST ATLANTA - WILKE CP A-1 # 92 - 3 POLE DDE	35500 - Poles and Fixtures	10/01/2018	33,030
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032686SWP	NORTH NEW BOSTON - WILKES CP A-2 # 601 - 3 POLE DDE	35500 - Poles and Fixtures	10/01/2018	22,652
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032855SWP	KILGORE - OVERTON CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2018	123
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032856SWP	BANN - THIRTY NINTH CP WO 2 CONDITIONS	35500 - Poles and Fixtures	10/01/2018	1,479
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL032996SWP	LOGANSPORT-TENAHA R/W WIDENING - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2018	697
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033052SWP	W CHILDRESS-ESTELLIN CP WO 1 CONDITIONS TLN00045	35500 - Poles and Fixtures	08/01/2018	1,131
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033104SWP	KNOX LEE - NORTHWEST STORM PATROL AND TREE REMOVAL - PILKINT	35600 - Overhead Conductors, Device	12/01/2018	762
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033140SWP	CLARKSVILLE - SABINE STORM TREE ON LINE - PILKINTON	35600 - Overhead Conductors, Device	12/01/2018	707
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033183SWP	PETTY - WILKES CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2018	8,804
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033231SWP	WINFIELD - WINNSBORO -LINE GROUNDING REMOVE TREE BIDDY	35600 - Overhead Conductors, Device	12/01/2018	290
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033232SWP	CLARENDON - JERICHO CP WO 2 CONDITIONS TLN00047	35500 - Poles and Fixtures	10/01/2018	1,558
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033260SWP	MIDVALLEY LONGVIEW T CP WO 18 CONDITIONS	35500 - Poles and Fixtures	06/01/2019	6,018
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033261SWP	HAWKINS PERDUE CP WO 4 CONDITIONS	35500 - Poles and Fixtures	06/01/2019	730
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033273SWP	JEFFERSON - SUPERIO2 R/W WIDENING	35600 - Overhead Conductors, Device	02/01/2019	956
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033276SWP	PIRKEY - WHITNEY STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2018	1,012
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033333SWP	IPC DOMINO - WEST AT CP WO 41 A-2 CONDITIONS	35500 - Poles and Fixtures	06/01/2019	192,388
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033341SWP	JEFFERSON - SUPERIO2 - STORM PATROL AND GROUNDING DON VICKER	35600 - Overhead Conductors, Device	12/01/2018	2,975
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033378SWP	PETTY PIGRIM'S PRIDE CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2019	14,605
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033406SWP	CLARENDON - JERICHO CP WO 4 CONDITIONS TLN00047	35500 - Poles and Fixtures	10/01/2018	5,536
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033617SWP	WELSH - WILKES CP WO 2 CONDITIONS	35600 - Overhead Conductors, Device	06/01/2019	1,942
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033627SWP	LAKE PAULINE RED RIV CP WO 22 CONDITIONS TLN0845	35500 - Poles and Fixtures	03/01/2019	53,343
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033679SWP	KNOX LEE-SE LONGVIEW CP A-1 INSULATORS (54) TOTAL	35600 - Overhead Conductors, Device	06/01/2019	12,803
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033712SWP	BANN - THIRTY NINTH CP WO 3 CONDITIONS	35500 - Poles and Fixtures	11/01/2019	2,752
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033738SWP	CENTER - TENAHA R/W STORM - PILKINGTON	35600 Overhead Conductors, Device	03/01/2019	115
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033834SWP	PIRKEY - SCOTTSVILLE CP WO 14 CONDITIONS	35500 - Poles and Fixtures	07/01/2019	42,448
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033839SWP	CARTHAGE - ROCK HILL STORM TREE PILKINGTON	35600 - Overhead Conductors, Device	03/01/2019	712
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033856SWP	LAKE LAMOND - LONGV1 CP 22 CONDITIONS	35500 - Poles and Fixtures	09/01/2019	65,069
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033888SWP	VERNON MAIN-FREDERIC CP WO 4 CONDITIONS	35500 - Poles and Fixtures	01/01/2019	9,210
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033899SWP	PIRKEY - SCOTTSVILLE STORM PATROL	35600 - Overhead Conductors, Device	12/01/2018	1,043
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL033900SWP	ATLANTA - LINDEN STORM PILKINTON	35600 - Overhead Conductors, Device	12/01/2018	678
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034059SWP	CARTHAGE - ROCK HILL STORM - DANGER TREE - PILKINGTON	35600 - Overhead Conductors, Device	03/01/2019	253
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034060SWP	CENTER-LOGANSPOR(TX) STORM DANGER TREE - PILKINGTON	35600 Overhead Conductors, Device	03/01/2019	353
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034221SWP	MIDVALLEY LONGVIEW TAP #225 4 - R/W OROW-PILKINTON	35600 - Overhead Conductors, Device	03/01/2019	2,490
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034279SWP	IPC JEFFERSON - LIE1 CP WO 1 CONDITIONS	35500 - Poles and Fixtures	07/01/2019	5,756
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034377SWP	IPC DOMINO - WEST ATL	35500 - Poles and Fixtures	07/01/2019	55,571
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034445SWP	BANN - NEW BOSTON CP (51) HP INSULATORS	35500 - Poles and Fixtures	07/01/2019	35,834
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034450SWP	DIANA - PURDUE CP WO 67 CONDITIONS	35500 - Poles and Fixtures	11/01/2019	15,079
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034454SWP	IPC JEFFERSON - LIE1 STORM VICKERS	35600 Overhead Conductors, Device	08/01/2019	2,296
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034525SWP	GILMER - PITTSBURG STORM - PILKINTON	35600 - Overhead Conductors, Device	08/01/2019	693
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034526SWP	KNOX LEE - OVERTON STORM _ PILKONTON	35600 - Overhead Conductors, Device	08/01/2019	1,065
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034603SWP	QUITMAN - WINNSBORO STORM - BIDDY	35600 - Overhead Conductors, Device	08/01/2019	1,714
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034740SWP	LOGANSPORT-TENAHA STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	1,197
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034747SWP	FLOURNOY - WOODLAWN A-1 # 157 SEE NOTES	35500 - Poles and Fixtures	07/01/2019	26,341

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034913SWP	KILGORE - WHITNEYSTORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	2,245
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034962SWP	DIANA - PURDUE STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	663
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034963SWP	MARSHALL 138 - PIRKE STORM PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	549
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034973SWP	CLARENDON - JERICHO CP WO 1 CONDITIONS TLN00305	35500 - Poles and Fixtures	04/01/2019	1,611
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL034998SWP	KILGORE - WHITNEY CP A 1 STORM DAMAGE	35500 - Poles and Fixtures	07/01/2019	18,739
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035230SWP	CARTHAGE - L A PACIFIC # 89 A-1 ARM	35500 - Poles and Fixtures	11/01/2019	5,188
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035237SWP	GILMER - PITTSBURG CP # 7 A-1	35500 - Poles and Fixtures	09/01/2019	580
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035311SWP	PIRKEY - WHITNEY STORMS - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	975
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035353SWP	BECKVILLE - POYNTER STORM - BIDDY	35600 - Overhead Conductors, Device	12/01/2019	1,399
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035401SWP	CLARKSVILLE - PERDUE R/W STORM - PILKINGTON	35600 - Overhead Conductors, Device	10/01/2019	2,745
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035402SWP	BLOOMBURG - ATLANTA CP # 41 A-1 POLE	35500 - Poles and Fixtures	09/01/2019	5,316
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035403SWP	KNOX LEE - OVERTON CP A 1 # 30 & 31 ARMS	35500 - Poles and Fixtures	11/01/2019	2,676
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035448SWP	BAN - IPC DOMINO - STORM PILKINTON	35600 - Overhead Conductors, Device	10/01/2019	239
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035463SWP	NORTH NEW BOSTON - STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	766
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035464SWP	HAWKINS - MINEOLA _ STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	1,174
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035465SWP	CENTER - TENAHA STORM PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	987
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035466SWP	HAWKINS PERDUE A-1 CROSS ARM # 204	35500 - Poles and Fixtures	11/01/2019	4,150
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035515SWP	CLARKSVILLE - GREGGT STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	1,282
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035518SWP	DIANA - PLILER ROAD - STORM PILKINGTON	35600 - Overhead Conductors, Device	07/01/2019	2,150
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035519SWP	JEFFERSON SWITCHING1 - STORM PILKINGTON	35600 - Overhead Conductors, Device	06/01/2019	3,095
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035537SWP	W CHILDRESS-SHAMROCK CP WO 9 CONDITIONS TLN00048	35500 - Poles and Fixtures	07/01/2019	9,193
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035661SWP	KILGORE - OVERTON R/W STORM - BIDDY	35600 - Overhead Conductors, Device	12/01/2019	834
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035663SWP	CROCKETT - TENASKA STORM - PILKINGTON	35600 - Overhead Conductors, Device	07/01/2019	3 677
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035666SWP	WOODLAWN-KARNACK SW A-2 # 20	35500 - Poles and Fixtures	09/01/2019	14,814
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035676SWP	BANN SE TEXARKANA A-2 DE INSULATORS	35500 - Poles and Fixtures	09/01/2019	5,816
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035800SWP	CROCKETT - TENASKA PILKINGTON STORM	35600 - Overhead Conductors, Device	10/01/2019	10,735
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035806SWP	KNOX LEE - PIRKEY A-1 INSULATOR FAILURE	35600 - Overhead Conductors, Device	09/01/2019	13,187
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035832SWP	LONGWOOD-WILKES(TX) STORMS - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	985
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035833SWP	WOODLAWN-KARNACK STORM - PILKINTON	35600 - Overhead Conductors, Device	12/01/2019	1,624
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035834SWP	KNOX LEE - PIRKEY CP A-1 GOABS	35500 - Poles and Fixtures	01/01/2020	31,070
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035839SWP	WOODLAWN-KARNACK SW CP WO 10 CONDITIONS	35500 - Poles and Fixtures	09/01/2019	77,733
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035961SWP	LONE STAR SOUTH - PITTS A-1 DAVIT ARMS S/3	35500 - Poles and Fixtures	11/01/2019	3,209
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035963SWP	PILGRIM'S PRIDE - WI STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	384
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035964SWP	DIANA - PLILER ROAD A-1 # 157 X ARM	35500 - Poles and Fixtures	11/01/2019	4,051
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035967SWP	HAWKINS PERDUE A-1 CROSSARM # 184	35600 - Overhead Conductors, Device	09/01/2019	2,455
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL035994SWP	BLOOMBURG - ATLANTA A-1 # 22 BROKE POLE	35500 - Poles and Fixtures	09/01/2019	7,182
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL036011SWP	DIANA - PURDUE STORM DAMAGE 10 STRUCTURES	35500 - Poles and Fixtures	11/01/2019	55,657
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL036015SWP	PITTSBURG - WINNSBOR STORM DAMAGE 5 STRUCTURES A-1	35600 - Overhead Conductors, Device	09/01/2019	11,603
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL036018SWP	DIANA - PLILER ROAD - STORM PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	1,350
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL036057SWP	JEFFERSON - NORTH - STORM PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	121
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL036164SWP	DIANA - LONE STAR SO # 20 A-1 IN LAKE	35500 - Poles and Fixtures	09/01/2019	38,897
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL036199SWP	MARSHALL-PIRKEY 138KV - STORM REMOVE TREE-PILKINTON	35600 - Overhead Conductors, Device	12/01/2019	196
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL036204SWP	CARTHAGE - L A PACIFIC A-1 ARM # 93	35500 - Poles and Fixtures	09/01/2019	428
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL036230SWP	DIANA - LAKE LAMOND CP FORESTRY	35500 - Poles and Fixtures	01/01/2020	268
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXLRE	B111TXLRE T/SW/Shadow for B194TXLRE	TL036267SWP	GILMER - PITTSBURG A-1 # 84 ARM	35500 - Poles and Fixtures	09/01/2019	842
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXRMB	B111TXRMB Reimbursable-DOP-111 TX Shadow	42980052SWP	DOP WINFIELD-MT VERNON 18WHEELER HIT POLE	35600 - Overhead Conductors, Device	09/01/2019	(1,969)
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXRMB	B111TXRMB Reimbursable-DOP-111 TX Shadow	43017876SWP	DOP JEFFERSON 69 KV SUBSTATION-REGULATOR DAMAGED BY H BROWN	35300 - Station Equipment	11/01/2019	677
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	42751996SWP	CHAPEL HILL SUBSTATION REPLACE ION 8600 METER	35300 - Station Equipment	01/01/2020	936
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	42921285SWP	WELSH HVDC STATION REPLACE FAILED AUTO TRANSFORMER TW01 L3	35300 - Station Equipment	05/01/2019	43,799
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0179823SWP	EVENSIDE STA REPLACE LIGHT AND FIXTURE	35300 - Station Equipment	11/01/2016	361
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0183430SWP	WELSH STA REPL FAILED SWITCH 11683	35300 - Station Equipment	04/01/2018	33,067
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0186562SWP	MARSHALL 138KV STA MARSHALL YARD REPLACE LIGHT FIXTURE	35300 - Station Equipment	01/01/2017	1,050
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0186906SWP	BANN STA BANN CAPITAL PROJECT/SWITCH 11432	35300 - Station Equipment	06/01/2017	6,882
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0186911SWP	KILGORE CAPITAL PROJECT RELAYS [CB] SABINE 1700/207688	35300 - Station Equipment	06/01/2017	698
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0187179SWP	KNOX LEE CAPB CAP BANK 1205 CAPBANK1205 CAPITAL PROJECT	35300 - Station Equipment	10/01/2017	35,737
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0187212SWP	OVERTON STA REPLACE FAILED CCVT & CARRIER TUNER PK	35300 - Station Equipment	10/01/2017	9,835
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0187283SWP	WEST ATLANTA BUSHING P137 9 EAST BUSHING REPL MAJOR MAINT	35300 - Station Equipment	06/01/2017	56,541
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0187450SWP	WEST ATLANTA STA WEST ATLANTA CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	8,041
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0187657SWP	NORTHWEST TEXARKANA STA CAPITAL PROJECT/CCVTS	35300 - Station Equipment	06/01/2017	12,245
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0187784SWP	WINNSBORO CB PITTSBURG 9820 448731 CAPITAL PROJECT/CB 9820	35300 - Station Equipment	10/01/2017	387
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0187995SWP	PIRKEY TRF P345 64 - N AUTO MAJOR MAINTENANCE	35300 - Station Equipment	11/01/2017	139,040
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188023SWP	NORTH MINEOLA STA - REPLACE ARRESTERS	35300 - Station Equipment	07/01/2017	2,376
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188035SWP	WELSH HVDC CONVERTER CB FILTER CB BM03 REP FAILED CTVT	35300 - Station Equipment	06/01/2017	2,636
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188067SWP	PIRKEY STA PIRKEY - REPLACE FAILED 3 TON AC UNIT	35300 - Station Equipment	04/01/2017	2,736
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188224SWP	TENASKA STA CAPITAL PROJECT/ENG SERVICE	35300 - Station Equipment	11/01/2017	24,618
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188274SWP	2017 GEUPGRADE DIANA STA_1 RELAY	35300 - Station Equipment	10/01/2019	0
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188274SWP	2017 GEUPGRADE DIANA STA_1 RELAY	35316 - Station Equipment-SmartGrid	10/01/2019	5,560
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188443SWP	HEDLEY C/O FAILED MOS 1663 1662	35300 - Station Equipment	03/01/2018	7,584
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188478SWP	DIANA STA DIANA REPLACE SWITCHES 12062 12063	35300 - Station Equipment	06/01/2018	53,903
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188592SWP	MOUNT PLEASANT STA REPLACE FLOODED RELAYS	35300 - Station Equipment	06/01/2017	1,378
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188684SWP	MOUNT VERNON (SW) DSC MOAB H S NORTH XFR 9046 V2721521 CAPI	35300 - Station Equipment	07/01/2018	3,891

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188803SWP	TEXARKANA OPERATIONS CENTER STA TEXARKANA OPERATIONS CENTER	35300 - Station Equipment	07/01/2017	6,190
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188827SWP	CROCKETT BUSHING P345 26 NORTH H1 REPL FANS	35300 - Station Equipment	10/01/2017	866
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188881SWP	PIRKEY TRF P345 40 - S AUTO REPLACE 7 FANS	35300 - Station Equipment	08/01/2017	1,966
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188883SWP	LEBROCK STA LEBROCK REPL SW 13242, 13243, 13222, 13252	35300 - Station Equipment	08/01/2019	97,993
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0188920SWP	BUFORD SURVEY DSC MOABS 7625 REPLACE FAILED SWITCH	35300 - Station Equipment	09/01/2018	61,786
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0189069SWP	SE LONGVIEW TCC 69 [CB] WHITNEY 6630 REPL LIGHTNING ARRESTER	35300 - Station Equipment	09/01/2017	472
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0189284SWP	PERDUE CAPB 86 4 MVAR CAP BANK 138KV REPLACE FAILED CAPACITO	35300 - Station Equipment	06/01/2017	4,040
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0189327SWP	WINNSBORO STA CAPITAL PROJECT/RTU REPLACEMENT	35300 - Station Equipment	08/01/2018	20,625
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0189431SWP	NORTH MINEOLA TRF P142 17 REPLACE 3 FANS	35300 - Station Equipment	09/01/2017	744
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0189432SWP	OVERTON TRF P137 1 NORTH REPLACE 2 FANS	35300 - Station Equipment	07/01/2017	1,156
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0189465SWP	JERICHO STA INSTALL IED FOR DISTANCE TO FAULT INFORMATION	35300 - Station Equipment	09/01/2018	11,281
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0189466SWP	CLARENDON STA INSTALL IED FOR DISTANCE TO FAULT INFORMATION	35300 - Station Equipment	09/01/2018	8,547
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0189714SWP	BANN TRF P141 58 AUTO SOUTH 9311401237 CAPITAL PROJECT	35300 - Station Equipment	12/01/2017	45,667
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0189993SWP	MONROE CORNERS METERING UPGRADE	35300 - Station Equipment	01/01/2019	893
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0190140SWP	BANN STA CAPITAL PROJECT/ BREAKER#2A40	35300 - Station Equipment	04/01/2018	29,262
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0190186SWP	DIANA STA CAPITAL REPL FAILED SWITCH 13098	35300 - Station Equipment	01/01/2018	18,591
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0190366SWP	PILGRIMS PRIDE CB WINFIE/WMTPL & PETTY 4470 437Y3124 CAPITAL	35300 - Station Equipment	07/01/2018	47,682
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0193176SWP	NORTHWEST TEXARKANA TRF P345 39 NORTH 7002868 CAPITAL PROJEC	35300 - Station Equipment	04/01/2018	5,170
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0193246SWP	DIANA STA REPL FAILED SWITCH 13105	35300 - Station Equipment	11/01/2017	15,777
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0193274SWP	NORTH MARSHALL DSC GND SWITCH 7525 SW_405000002457 CAPITAL P	35300 - Station Equipment	10/01/2017	5,390
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0194129SWP	NORTHWEST HENDERSON REPL SUMP PUMP CAPITAL PROJECT	35300 - Station Equipment	12/01/2017	1,493
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0194212SWP	PERDUE MET ENERGY METER 601A020_EMS CAPITAL PROJECT	35300 - Station Equipment	01/01/2020	1,378
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0194355SWP	NORTHWEST TEXARKANA CAPITAL PROJECT RELAYS	35300 - Station Equipment	01/01/2018	2,449
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0194395SWP	POYNTER VT LINE PT FOR CB 1J40 A 71165 CAPITAL PROJECT	35300 - Station Equipment	12/01/2017	3,094
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0195475SWP	WELSH HVDC CONVERTER STA CAPITAL PROJE/TW01 L2 B	35300 - Station Equipment	04/01/2018	4,141
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0195570SWP	DIANA STA DIANA REPLACE FAILED CVT'S	35300 - Station Equipment	01/01/2018	10,481
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0195649SWP	SHAMROCK C/O FAILED CAP BANK CS 6730	35300 - Station Equipment	03/01/2018	56,875
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0195657SWP	NORTH NEW BOSTON CB 11360 137Y2021 CAPITAL PROJEC	35300 - Station Equipment	04/01/2018	519
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0195658SWP	WILKES DSC SW 1J75 SW_40500000300 CAPITAL PROJECT	35300 - Station Equipment	06/01/2018	12,108
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0195822SWP	DIANA STA DIANA CAPITAL PROJECT	35300 - Station Equipment	06/01/2018	1,850
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0195885SWP	EASTON SUBSTATION- REPLACE FAILED ION METER	35300 - Station Equipment	01/01/2020	905
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0197607SWP	PETTY STA CAPITAL PROJECT/FUTURA METER	35300 - Station Equipment	08/01/2018	2,994
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0197628SWP	OVERTON STA CAPITAL PROJECT REPL 2 CAPACITORS	35300 - Station Equipment	01/01/2018	597
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0198768SWP	THIRTY-NINTH STREET CB CIRCUIT BREAKER 8650 0139A9023201 CAP	35300 - Station Equipment	07/01/2018	67,372
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0198923SWP	JERICHO C/O FAILED A/C UNIT	35200 - Structures and Improvements	03/01/2018	290
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0198923SWP	JERICHO C/O FAILED A/C UNIT	35300 - Station Equipment	03/01/2018	372
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0198943SWP	PETTY STA CAPITAL PROJECT/WEST 69KV BUS POTENTIAL TRANS	35300 - Station Equipment	04/01/2018	10,649
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0198946SWP	WEST ATLANTA STA CAPITAL PROJECT/138 & 69KV BUS ARRESTERS	35300 - Station Equipment	06/01/2018	5,631
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0198953SWP	LYDIA MET LYDIA 345 - VALLIANT 345 REPLACETWO FAILED METERS	35300 - Station Equipment	10/01/2018	1,517
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0198980SWP	SOUTHEAST LONGVIEW CB WHITNEY 6630 537Y2615 CAPITAL PROJECT	35300 - Station Equipment	07/01/2018	958
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0198986SWP	LONE STAR (SEP) CB GSU #4/A-C BUS 1500A 111V118S CAPITAL PRO	35300 - Station Equipment	07/01/2018	733
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0199715SWP	KNOX LEE CB CB-2600E 378443 CAPITAL PROJECT/CB 2600E	35300 - Station Equipment	10/01/2018	29,172
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0200099SWP	BANN STA CAPITAL PROJECT/SWITCH 9435 RETIREMENT	35300 - Station Equipment	01/01/2019	590
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0200103SWP	WELSH DSC MOAB DIANA WEST 11925 A33796 CAPITAL PROJECT	35300 - Station Equipment	03/01/2020	49,010
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0200111SWP	WELSH STA CAPITAL PROJECT/138KV SWITCH 10504	35300 - Station Equipment	03/01/2019	10,453
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0200147SWP	LONE STAR SOUTH STA CAPITAL PROJECT/CONTROL HOUSE A/C	35300 - Station Equipment	01/01/2019	4,196
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0204149SWP	TAYLOR STREET CB TEXARAKANA PLANT 7560 319635 CAPITAL PROJEC	35300 - Station Equipment	07/01/2019	38,589
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0204172SWP	CAMP COUNTY POD CAPITAL PROJECT/REPLACE FAILED HVAC	35300 - Station Equipment	12/01/2019	1,862
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0204310SWP	SHAMROCK C/O FAILED RELAY 38062R2	35300 - Station Equipment	10/01/2018	2,686
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0204310SWP	SHAMROCK C/O FAILED RELAY 38062R2	35316 - Station Equipment-SmartGrid	10/01/2018	480
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0204533SWP	LEBROCK MET STG 001 BACKUP 907A716_REPLACE FAILED METER	35300 - Station Equipment	03/01/2020	1,288
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0204635SWP	JERICHO C/O FAILED BATTERY ONLY	35300 - Station Equipment	09/01/2018	3,580
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0206218SWP	CHAPEL HILL (M O LINE SW) DSC MOAB 6333 C0735181 CAPITAL PR	35300 - Station Equipment	01/01/2020	565
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0206344SWP	HUGHES SPRINGS LA CB-1890 ARR PH B CAPITAL PROJECT/ARRESTE	35300 - Station Equipment	12/01/2018	446
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0206525SWP	WOODLAWN (SW) CB CB-2090 REPLACE FAILED COMPRESSOR AND MOTOR	35300 - Station Equipment	12/01/2019	629
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0206851SWP	NEW BOSTON STA NEW BOSTON CAPITAL PROJECT	35300 - Station Equipment	12/01/2018	1,607
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0206888SWP	MARSHALL 69KV CB ROCKHILL 1340 REPLACE FAILED CB	35300 - Station Equipment	12/01/2018	30,636
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0207671SWP	BANN STA CAPITAL PROJECT/STATION SERVICE UPGRADE	35300 - Station Equipment	03/01/2019	769
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0207730SWP	HAWKINS RTU REMOTE TERMINAL UNIT RTU_1004225929/REPLACE	35300 - Station Equipment	01/01/2020	32,065
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0207750SWP	WEST ATLANTA STA CAPITAL PROJECT	35300 - Station Equipment	12/01/2018	2,680
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0207824SWP	TRO80004983_PETTY STA CAPITAL PROJECT/NEW TRANSFORMER	35300 - Station Equipment	12/01/2019	39,921
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0210070SWP	TRO80002772_PIRKEY STA REPL 3 FAILED LIGHTNING ARRESTERS	35300 - Station Equipment	01/01/2020	8,813
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0211230SWP	BRADY SW COMM REMOTE ACCESS SERVER MPC_1003272982 CAPITAL PR	35316 - Station Equipment-SmartGrid	01/01/2020	5,921
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0211530SWP	TRO80044043_NORTHWEST TEXARKANA STA CAP/FL LIGHTS&FAN	35300 - Station Equipment	12/01/2019	4,941
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0212166SWP	TRO80004465_PITTSBURG (SW) STA CAPITAL PROJE/OCB6220AUXRELAY	35300 - Station Equipment	03/01/2020	368
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0212227SWP	TRO80004465_PITTSBURG (SW) STA CAPITAL PROJE(HVAC)	35300 - Station Equipment	07/01/2019	2,184
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0212309SWP	TRO80055714_RED SPRINGS STA CAPITAL PROJECT/STOLEN GROUNDS	35300 - Station Equipment	07/01/2019	3,584
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0212695SWP	TRO80037224_WHITNEY STA CAPITAL/UNDERGROUND POWER CABLE	35300 - Station Equipment	08/01/2019	35,341
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0215164SWP	ESTELLINE C/O SEL-167 W/ SEL-321	35316 - Station Equipment-SmartGrid	02/01/2020	13,347
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0215642SWP	ROCK HILL CB CB-10120 REPLACE FAILED COMPRESSOR	35300 - Station Equipment	11/01/2019	2,936
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T0215649SWP	NORTH MINEOLA CB WINNSBORO/TRANS #1 4280 REPL AIR COMPRESSOR	35300 - Station Equipment	11/01/2019	1,440

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	T02158566SWP	MEMPHIS NW JOURNAL T0200690 TO HERE	35300 Station Equipment	01/01/2020	13
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	TS0221818SWP	DIANA CB CB 12050 499821 CAPITAL PROJECT	35300 - Station Equipment	02/01/2020	52,673
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	TS0221898SWP	WELSH CB CB-11670 CAPITAL PROJECT	35300 - Station Equipment	11/01/2019	410
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	TS0222165SWP	TRO80055863_WILKES STA INSTALL SDR	35300 - Station Equipment	03/01/2020	196
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	TS0222194SWP	WELSH HVDC CONVERTER STA - INSTALL TUNING PACK	35300 - Station Equipment	01/01/2020	9,963
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	TS0222225SWP	JERICHO C/O 9300 TO SEL 421	35316 - Station Equipment-SmartGrid	11/01/2019	18,612
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	TS0222372SWP	MEMPHIS NW C/O 3G ROUTER WITH 4G LTE	35316 - Station Equipment-SmartGrid	11/01/2019	3,635
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	TS0222402SWP	CHILDRESS WEST C/O FAILED CB 6480	35300 - Station Equipment	12/01/2019	26,962
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B111TXSRE	B111TXSRE T/SW/Shadow for B194TXSRE	TS0222727SWP	NORTH MINEOLA BATTERY BANK	35300 Station Equipment	02/01/2020	7,483
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	42636603	DEQUEEN - MENA 69KV TLN152 REPLACE INSULATORS & ARMS	35500 Poles and Fixtures	06/01/2017	47,479
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non Specific Work - Line	42652362	SILOAM SPR - PRAIRIE GR (AR) REPLACE 10 STRUCTURES	35500 - Poles and Fixtures	04/01/2017	177,766
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	42706335	BRANCH-N MAGAZINE LINE 162	35500 Poles and Fixtures	06/01/2017	34,214
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	42729292	PATTERSON - S NASHVILLE SEPTL181	35500 - Poles and Fixtures	09/01/2017	7,866
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	42769879	DOP 2017 - SWEPCO - CHAMBER SPRINGS-TONTITOWN ST #85	35500 - Poles and Fixtures'	02/01/2018	5,740
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	42943676	ARKLAHOMA DISSOLUTION ASSET PUR TOTAL SWEPCO	35600 - Overhead Conductors, Device	11/01/2019	67,919
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	42997559	DEQUEEN - MENA CP REPLACE 24 H-STRUCTURES	35500 - Poles and Fixtures	06/01/2019	106,874
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL0036327	DYESS SPRINGDALE SOUTH (T) RP 3 HX	35500 - Poles and Fixtures	10/01/2019	70,225
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL0036327	DYESS - SPRINGDALE SOUTH (T) RP 3 HX	35600 - Overhead Conductors, Device	10/01/2019	1,164
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL0036437	PRAIRIE GROVE - SILOAM SPRINGS (T) CP WO 12 CONDITIONS	35500 Poles and Fixtures	10/01/2019	98,278
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non Specific Work - Line	TL0036437	PRAIRIE GROVE - SILOAM SPRINGS (T) CP WO 12 CONDITIONS	35600 Overhead Conductors, Device	10/01/2019	10,924
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL0036471	DYESS - FLINT CREEK RP DAMAGED STR3	35500 Poles and Fixtures	10/01/2019	47,918
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL0036622	WEST BOONEVILLE - NORTH MAGAZINE 2 CONDITIONS	35500 - Poles and Fixtures	10/01/2019	22,191
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL0036622	WEST BOONEVILLE - NORTH MAGAZINE 2 CONDITIONS	35600 - Overhead Conductors, Device	10/01/2019	5,548
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL029915	TEXARKANA P BLOOMBUR # 204	35500 - Poles and Fixtures	06/01/2017	26,876
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030059	W BOONEVILLE-N MAGAZ CP WO 1 CONDITIONS	35500 Poles and Fixtures	06/01/2017	8,948
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030063	EAST ROGERS - ROGERS #282-29	35500 - Poles and Fixtures	09/01/2017	36,177
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030064	CRAIG JCT-DEQUEE(OK) CP WO 1 CONDITIONS	35500 - Poles and Fixtures	09/01/2017	4,015
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030169	N HUNTINGTON-WALDRON WEST # 188 & 13	35500 - Poles and Fixtures	09/01/2017	5,985
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030193	U S MOTORS TAP # 11 A-1	35500 Poles and Fixtures	06/01/2017	7,681
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030404	SOUTH NASHVILLE - SO CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	645
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030469	EAST ROGERS - BEAVER - DANGER TREE - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2017	15,953
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030517	HOSSTON-BLMBRG (AR) DEAD TREE - DON VICKERS	35600 - Overhead Conductors, Device	12/01/2017	1,199
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030558	FLINT CREEK - SILOAM CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	5,027
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030567	FLINT CREEK - BROOKL CP WO 1 CONDITIONS	35500 - Poles and Fixtures	11/01/2017	120
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030568	EAST CENTERTON - NOR CP WO 1 CONDITIONS	35500 - Poles and Fixtures	07/01/2017	555
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL030590	FLINT CREEK - SILOAM CP A1 POLE # STR100	35500 - Poles and Fixtures	06/01/2017	89,454
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL030593	CHAMBERS SPRING - FL STR 8 ARM & STR 20 POLE	35500 - Poles and Fixtures	06/01/2017	31,139
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL030666	EAST CENTERTON - NOR DANGER TREE HOBSON	35600 - Overhead Conductors, Device	06/01/2017	2,596
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL030705	PATTERSON - SOUTH NASH # 159	35500 Poles and Fixtures	06/01/2017	29,226
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL030815	W BOONEVILLE-N MAGAZ CP WO 1 CONDITIONS	35500 - Poles and Fixtures	07/01/2017	6,117
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL030925	DIERKS - MENA CP #455 A-1 INSULATORS	35500 - Poles and Fixtures	09/01/2017	7,228
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non Specific Work Line	TL030941	GREENLAND VBI NORT - TREE ON LINE	35600 - Overhead Conductors, Device	11/01/2018	443
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL031010	GREENLAND - VBI NORT CP WO 2 CONDITIONS	35500 Poles and Fixtures	11/01/2017	2,993
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL031204	HOSSTON-BLMBRG (AR) - STORM BIDDY	35600 - Overhead Conductors, Device	02/01/2018	1,630
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL031473	PATTERSON - SOUTH DI HAZARD TREE - BIDDY	35600 Overhead Conductors, Device	02/01/2018	796
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL031518	ASHDOWN - TWELFTH ST CP WO 1 CONDITIONS	35500 - Poles and Fixtures	01/01/2018	1,649
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL031661	S FAYETTEV-SE FAYETT RP 4 B/O STRUCTURES	35500 Poles and Fixtures	10/01/2018	88,159
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL031835	FLINT CREEK - BROOKL CP WO 1 CONDITIONS	35500 - Poles and Fixtures	02/01/2018	21,038
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non Specific Work Line	TL031835	FLINT CREEK - BROOKL CP WO 1 CONDITIONS	35600 Overhead Conductors, Device	02/01/2018	212
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non Specific Work - Line	TL031912	EAST CENTERTON - E ROG B/O INSUATOR	35500 - Poles and Fixtures	01/01/2018	3,788
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032064	SOUTH DIERKS- DIERKS A-1 # 20	35500 - Poles and Fixtures	10/01/2018	5,185
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032097	DYESS - EAST ROGERS POLES AND ARMS	35500 - Poles and Fixtures	10/01/2018	220,639
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032480	FLINT CREEK - BROOKL CP WO 2 CONDITIONS	35600 - Overhead Conductors, Device	03/01/2018	7,208
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032502	EUREKA SPRINGS - HAR CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2018	1,612
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032502	EUREKA SPRINGS - HAR CP WO 1 CONDITIONS	35600 - Overhead Conductors, Device	06/01/2018	4,835
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032503	DYESS-SPRINGDALE #2 REMOVE SW	35500 - Poles and Fixtures	06/01/2018	8,265
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032503	DYESS-SPRINGDALE #2 REMOVE SW	35600 - Overhead Conductors, Device	06/01/2018	24,795
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032875	GREENLAND - VBI NORT HOBSON - STORM	35600 - Overhead Conductors, Device	01/01/2019	1,336
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032898	PRAIRIE GROVE SILO STR 72 A1	35500 - Poles and Fixtures	06/01/2018	560
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032899	EAST CENTERTON NOR CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2018	212
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032899	EAST CENTERTON - NOR CP WO 1 CONDITIONS	35600 - Overhead Conductors, Device	06/01/2018	1,179
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032962	EAST ROGERS BEAVER CP WO 1 CONDITIONS	35500 - Poles and Fixtures	11/01/2019	16,169
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032963	DYESS-HYLAND CP WO 3 CONDITIONS	35500 - Poles and Fixtures	04/01/2019	101,081
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL032997	DEQUEEN - MENA CP REPLACE 24 H-STRUCTURES	35500 - Poles and Fixtures	06/01/2019	255,826
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL033086	W BOONEVILLE-N MAGAZ CP WO 1 CONDITIONS	35600 - Overhead Conductors, Device	06/01/2019	11,682
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non Specific Work - Line	TL033206	BOONEVILLE - BRANCH GROUNDING LINE - HOBSON	35600 - Overhead Conductors, Device	12/01/2018	9,855
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL033207	TEXARKANA PLANT - 12TH ST A-1 HP INSULATORS	35600 - Overhead Conductors, Device	10/01/2018	4,482
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL033264	BOONEVILLE - BRANCH(CP WO 2 CONDITIONS	35500 - Poles and Fixtures	08/01/2018	15,749
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL033264	BOONEVILLE - BRANCH(CP WO 2 CONDITIONS	35600 - Overhead Conductors, Device	08/01/2018	254
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL033265	CHAMBERS SPRING - FL CP WO 1 CONDITIONS	35500 - Poles and Fixtures	08/01/2018	2,291
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL033272	FLINT CREEK - SILOAM CP WO 1 CONDITIONS	35500 - Poles and Fixtures	08/01/2018	23,468

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL033302	DYESS-SPRINGDALE N CP WO 12 CONDITIONS	35500 - Poles and Fixtures	03/01/2019	231,721
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL033302	DYESS SPRINGDALE N CP WO 12 CONDITIONS	35600 - Overhead Conductors, Device	03/01/2019	996
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL033322	DIERKS - MENA CP WO 16 CONDITIONS	35500 - Poles and Fixtures	06/01/2019	44,644
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL033402	EAST CENTERTON - NOR CP WO 2 CONDITIONS	35500 - Poles and Fixtures	11/01/2019	34,570
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL033609	FLINT CREEK - SILOAM 161KV 10+ CONDITIONS	35500 - Poles and Fixtures	11/01/2019	71,706
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL033610	W BOONEVILLE-N MAGAZ CP WO 4 CONDITIONS	35500 - Poles and Fixtures	07/01/2019	46,882
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL033614	NORTH HUNTINGTON DOUBLE CIRCUIT 3 CP WO 7 CONDITIONS	35600 - Overhead Conductors, Device	06/01/2019	53,994
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL033622	TEXARKANA P-BLOOMBUR STORM - DON VICKERS	35600 - Overhead Conductors, Device	12/01/2018	5,140
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL033692	DIERKS - MENA CP	35500 - Poles and Fixtures	11/01/2019	76,879
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL034008	GREENLAND - PRAIRIE R/P BO POLES AND ARMS	35500 - Poles and Fixtures	07/01/2019	157,456
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL034008	GREENLAND - PRAIRIE R/P BO POLES AND ARMS	35600 - Overhead Conductors, Device	07/01/2019	1,955
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL034014	CHAMBERS - DYESS 161 15 CONDITIONS	35500 - Poles and Fixtures	07/01/2019	182,551
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL034014	CHAMBERS - DYESS 161 15 CONDITIONS	35600 - Overhead Conductors, Device	07/01/2019	62
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL034015	TONITOWN - DYESS #2 STOLDEN GROUNDS	35500 - Poles and Fixtures	01/01/2020	26,579
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL034015	TONITOWN - DYESS #2 STOLDEN GROUNDS	35600 - Overhead Conductors, Device	01/01/2020	29,939
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL034048	FULTON P-PATMOS APNL STORM - PILKINGTON	35600 - Overhead Conductors, Device	03/01/2019	1,226
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL034058	FULTON P-PATMOS STORM DANGER TREE - PILKINGTON	35600 - Overhead Conductors, Device	03/01/2019	1,442
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL034072	GREENLAND-S FAYETTEV R/P STR'S	35500 - Poles and Fixtures	11/01/2019	17,323
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL034072	GREENLAND-S FAYETTEV R/P STR'S	35600 - Overhead Conductors, Device	11/01/2019	16
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL034140	DIERKS - WEST MURFRE CP WO 2 CONDITIONS	35500 - Poles and Fixtures	11/01/2019	8,264
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL034220	N NEW BOSTON-PA (AR) #183 1 - R/W OROW-PILKINTON	35600 - Overhead Conductors, Device	03/01/2019	6,877
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non Specific Work - Line	TL034324	DYESS-S SPRINGDALE 2 POLES	35500 - Poles and Fixtures	11/01/2019	47,033
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL034739	DYESS-SPRINGDALE NORTH 10 CONDITIONS	35500 - Poles and Fixtures	11/01/2019	17,823
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non Specific Work - Line	TL034739	DYESS-SPRINGDALE NORTH 10 CONDITIONS	35600 - Overhead Conductors, Device	11/01/2019	1,989
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL035428	SOUTH NASHVILLE - SO STORM - PILKINTON	35600 - Overhead Conductors, Device	12/01/2019	2,909
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL035430	DEQUEEN - MENA (7) A-2 STRUCTURES (2) A-1 STRUCTURES	35500 - Poles and Fixtures	09/01/2019	161,264
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL035447	CRAIG JCT-DEQUEE(AR) - STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	2,319
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work Line	TL036034	DEQUEEN - MENA CP A-1 # 176	35500 - Poles and Fixtures	11/01/2019	8,975
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL036166	DEQUEEN - NASHVILLE CP # 139 A-1 ARM	35500 - Poles and Fixtures	11/01/2019	6,463
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL036197	DIERKS - MENA 69KV - STORM REMOVE TREE-PILKINTON	35600 - Overhead Conductors, Device	12/01/2019	1,067
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARLRE	B194ARLRE T/SW/Non-Specific Work - Line	TL036200	HOSSTON-BLOOMBURG (AR) - STORM REMOVE TREE-PILKINTON	35600 - Overhead Conductors, Device	12/01/2019	1,660
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	42685599	PATTERSON SUB AR REPLACE MULTIPLEX W/SCHWEITZER ICON	35300 - Station Equipment	02/01/2019	104
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	42685616	TURK SUB AR REPLACE MULTIPLEXER W/SCHWEITZER ICON	35300 Station Equipment	02/01/2019	8,364
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	42685617	TELECOM DEMARC BLDG AR REPLACE MULTIPLEXER W/SCHWEITZER ICON	35300 Station Equipment	02/01/2019	3,783
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	42685620	PLANT ELECTRONIC RM AR REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	02/01/2019	11,019
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	42685623	NEW HOPE SWITCH AR REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	02/01/2019	12,644
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	42691760	ARSENAL HILL SUB LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	11/01/2018	3,800
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work Station	42691771	STALL CONTROL HOUSE LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	02/01/2019	8,705
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0179834	CHAMBERS SPRING FR SDR-SEL1102 - REPLACE WITH SEL 3355	35300 - Station Equipment	01/01/2018	15,479
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0179835	TONTITOWN FR SDR-SEL1102 - REPLACE WITH SEL 3355	35300 - Station Equipment	10/01/2017	13,056
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0185320	HUNTINGTON STA - FAILED 12KV INSULATORS & MET CURRENT XFRMRS	35300 Station Equipment	06/01/2017	10,870
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non Specific Work-Station	T0186359	BONANZA STA REPLACE FAILED 34KV SWITCHES	35300 - Station Equipment	06/01/2017	2,950
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0186763	EAST ROGERS STA - REPLACE FAILING BUS PT	35300 - Station Equipment	06/01/2018	9,282
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0187135	NORTH HUNTINGTON STA REPLACE FAILED 69KV ARRESTERS	35300 Station Equipment	11/01/2017	1,784
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0187143	NORTH HUNTINGTON TRF P161 41 WEST-A MAJOR MAINTENANCE	35300 Station Equipment	11/01/2017	59,095
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non Specific Work-Station	T0187486	FLINT CREEK SUB REPLACE FAILED 345KV ARRESTERS	35300 Station Equipment	06/01/2018	26,365
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0187692	S FAYETTEVILLE CAP BANK REPLACE FAILED CAPACITORS & LIMITER	35300 - Station Equipment	06/01/2018	149
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work Station	T0187780	EAST CENTERTON CCVT AECC CIRCUIT NORTH REPACE	35300 Station Equipment	06/01/2018	5,355
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0187902	EAST ROGERS CAP BANK REPLACE FAILED CAPACITORS & LIMITERS	35300 - Station Equipment	06/01/2017	12,288
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work Station	T0188464	REEVES ROAD DSC N HUNTINGTON CKT 32666 REPLACE INTERUPPTER	35300 - Station Equipment	07/01/2019	34,682
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0188475	HOPE BAT BATTERY BANK BAT_ 4300011 CAPITAL PROJECT	35300 Station Equipment	08/01/2017	11,888
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0188484	EAST CENTERTON CCVT E ROGERS CKT WEST S74A93 REPLACE	35300 Station Equipment	10/01/2017	5,073
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work Station	T0188616	FLINT CREEK REPLACE DECATUR PHASE THREE METERS	35300 Station Equipment	01/01/2019	20,807
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0188694	TONTITOWN STATION - REPLACE AC SERVICE EQUIPMENT	35300 - Station Equipment	06/01/2017	1,932
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0188733	SOUTH FAYETTEVILLE CB BUS TIE 10480 ADD CONTROL CABLE	35300 - Station Equipment	05/01/2017	11,645
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work Station	T0188753	SILOAM SPRINGS 161KV STATION REPLACE CABLE ON PT CB 4810	35300 - Station Equipment	11/01/2017	1,642
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0189361	SILOAM SPRINGS 161KV STA REPLACE FAILED AC IN CONTROL HOUSE	35200 Structures and Improvements	08/01/2017	949
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0189361	SILOAM SPRINGS 161KV STA REPLACE FAILED AC IN CONTROL HOUSE	35300 - Station Equipment	08/01/2017	45
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0189487	SOUTH DIERKS STA CAPITAL PROJECT/AC IN CONTROL HOUSE	35300 - Station Equipment	10/01/2017	5,335
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work Station	T0189712	DIXIELAND CAPITAL PROJECT RELAYS [BUS] BUS 69KV/PLC&RTU	35300 - Station Equipment	12/01/2018	155,120
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0190141	FLINT CREEK SUB TRF P345 50 EAST BUSHING FAILURE	35300 - Station Equipment	10/01/2018	284,512
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0190310	FLINT CREEK SUB STA - AUTO TRANSFER SWITCH	35300 - Station Equipment	11/01/2017	4,049
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work Station	T0190336	HOPE STA CAPITAL PROJECT/ETHERNET SWITCH	35300 - Station Equipment	07/01/2018	2,784
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0194092	NASHVILLE 69KV CB OKAY 3040 419Y2936 CAPITAL PROJECT	35300 - Station Equipment	01/01/2018	98,973
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0194218	WEST BOONEVILLE STA REPLACE FAILED TRANSFER SWITCH	35300 - Station Equipment	06/01/2018	4,625
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0194266	TURK TRF P345 51 TB80068412 CAPITAL PROJECT/REPLACED SPR	35300 - Station Equipment	02/01/2018	3,001
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0195515	SOUTH DIERKS BATCHARG BATTERY_CHARGER STA_1 14032633706 CAPI	35300 - Station Equipment	04/01/2018	4,456
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work Station	T0195644	SOUTHEAST TEXARKANA STA CAPITAL PROJECT/CCVT	35300 - Station Equipment	04/01/2018	4,299
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0195645	SPRINGDALE CB DYESS 4850 352742 CAPITAL PROJECT/FUTURA METE	35300 - Station Equipment	07/01/2018	10,587
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0195783	NORTH MAGAZINE - REPLACE AC UNIT	35200 - Structures and Improvements	03/01/2018	274
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0195783	NORTH MAGAZINE - REPLACE AC UNIT	35300 - Station Equipment	03/01/2018	616

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0195819	WEST BOONEVILLE REPLACE BATTERY CHARGER	35300 - Station Equipment	06/01/2018	4,182
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0195861	DEQUEEN TRF P141 48 RPP39571 CAPITAL PROJECT	35300 - Station Equipment	02/01/2018	2,217
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0195887	SUGAR HILL (SW) TRF P142 26 702081 CAPITAL PROJECT	35300 - Station Equipment	07/01/2018	4,299
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0197468	DEQUEEN TRF P141 48 RPP39571 CAPITAL PROJECT/69KV ARRESTERS	35300 Station Equipment	07/01/2018	8,014
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0197608	FLINT CREEK SUB CB SHIPE RD 11750 REPLACE COMPRESSOR	35300 - Station Equipment	06/01/2018	3,505
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0197643	EAST ROGERS STA REPLACE 3 ARRESTERS ON BUSS	35300 - Station Equipment	11/01/2018	7,015
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0197692	DEQUEEN TRF P141 48 RPP39571 CAPITAL PROJECT/FAILED FANS	35300 - Station Equipment	04/01/2018	3,048
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0198036	TURK STA TURK CAPITAL PROJECT	35300 - Station Equipment	06/01/2018	1,253
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0198064	HOPE COMM ETHERNET SWITCH MPC_1003710008 CAPITAL PROJECT	35300 - Station Equipment	11/01/2018	194
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0198842	2018 GEUPGRADE TONTITOWN STA_3 RELAYS	35300 - Station Equipment	12/01/2019	73
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0198842	2018 GEUPGRADE TONTITOWN STA_3 RELAYS	35316 - Station Equipment-SmartGrid	12/01/2019	22,525
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0199151	FLINT CREEK SUB CB 12280 & 11240 REPLACE BUSHINGS	35300 - Station Equipment	08/01/2018	9,327
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0199627	SUGAR HILL (SW) STA CAPITAL PROJECT/STATION BATTERY	35300 - Station Equipment	10/01/2018	16,647
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0199633	CHAMBERS SPRING REPLACE FAILED 345KV CCVT	35300 Station Equipment	09/01/2018	8,783
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0199755	MENA TRF P145 02 70705A CAPITAL PROJECT/FAILED FANS	35300 - Station Equipment	08/01/2018	3,350
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0199812	MENA STA MENA CAPITAL PROJECT	35300 - Station Equipment	01/01/2019	8,556
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0199950	SOUTHEAST TEXARKANA DSC MOS 13128 V2981621 CAPITAL PROJECT	35300 - Station Equipment	10/01/2018	7,732
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0200058	NASHVILLE 69KV CB OKAY 3040 CB 3040 230624020A CAPITAL PROJE	35300 - Station Equipment	07/01/2018	10,715
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0200330	CHAMBERS SPRING CB 12730 498963 CAPITAL PROJECT/REPLACE SF6	35300 - Station Equipment	01/01/2019	99,183
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0200420	TURK TRF AUTO #2 138/115 KV P141 24 D584570 CAPITAL PROJECT	35300 Station Equipment	12/01/2018	154,721
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0200536	NORTH HUNTINGTON REPLACE FAILED 69KV ARRESTERS	35300 - Station Equipment	08/01/2018	493
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0200858	EAST ROGERS REPLACE FAILED 69KV CT	35300 - Station Equipment	01/01/2019	7,494
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0204263	FLINT CREEK SUB CAPITAL PROJECT RELAYS [CKT] EAST CENTERTON	35300 Station Equipment	12/01/2019	135
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0204263	FLINT CREEK SUB CAPITAL PROJECT RELAYS [CKT] EAST CENTERTON	35316 - Station Equipment SmartGrid	12/01/2019	7,237
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0204283	SPRINGDALE CB DYESS 4850 REPLACE ARRESTERS	35300 - Station Equipment	06/01/2019	3,061
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0204643	NORTH HUNTINGTON REPLACE FAILED 161KV CCVT	35300 - Station Equipment	08/01/2018	6,210
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0205287	TURK STA CAPITAL PROJECT/FANS TRANSF 141 24	35300 - Station Equipment	12/01/2019	1,837
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0206710	DIERKS CB MENA 1V90 522991 CAPITAL PROJECT/ARRESTER	35300 - Station Equipment	04/01/2019	1,232
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work Station	T0206783	DYESS XMFR P6635 NORTH REPLACE BUSHING	35300 - Station Equipment	05/01/2019	4,049
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0207775	BOONEVILLE STA CAPITAL PROJECT/POTIENTAL TRANS,SURGE ARREST	35300 - Station Equipment	12/01/2018	5,519
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non Specific Work-Station	T0211179	TRO80004497_DEQUEEN STA CAPITAL PROJECT/CB3630 & ARRESTER	35300 - Station Equipment	07/01/2019	13,111
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0211536	TRO80043999_OKAY CB1400 H145A2557202 CAPITAL PROJECT/REPLAC	35300 Station Equipment	07/01/2019	69,782
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work Station	T0212102	TONTITOWN TRF AUTO T1 SOUTH REPLACE ARRESTERS	35300 - Station Equipment	05/01/2019	31,731
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0212240	FLINT CREEK PNEUMATIC MECHANISM REPLACEMENT FOR CB 11750	35300 - Station Equipment	08/01/2019	30,899
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0212242	TRO80055733_PRESCOTT POD BAT MOABS BATTERY 12K30AKTD777100 5	35300 - Station Equipment	07/01/2019	2,937
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0212269	TRO80055746_PRESCOTT POD STA CAPITAL PROJECT/ETHERNET SWITC	35300 - Station Equipment	12/01/2019	452
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0212626	SOUTHEAST FAYETTEVILLE HYLAND LINE REPLACE CCVT	35300 - Station Equipment	10/01/2019	6,771
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0212642	SILOAM SPRINGS 161KV CCVT REPLACE CCVT	35300 - Station Equipment	07/01/2019	6,798
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work Station	T0215221	SPRINGDALE VT BUS 69KV PT REPLACE PT'S AND ARRESTERS	35300 Station Equipment	07/01/2019	20,431
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0215490	TRO80055719_NE TEXARKANA TAP BAT BATTERY BANK BATT 421951132	35300 - Station Equipment	12/01/2019	1,925
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0215869	NASHVILLE 69KV CB CB-3050 REPL FAILED CB AND REPL LINE PT	35300 Station Equipment	12/01/2019	41,247
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	T0219893	HUNTINGTON REPLACE ARRESTERS AND RETIRE REGULATORS	35300 Station Equipment	03/01/2020	5,165
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	TS0222179	NORTH MAGAZINE BATTERY BANK - REPLACE FAILING BANK	35300 - Station Equipment	12/01/2019	9,199
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194ARSRE	B194ARSRE T/SW/Non-Specific Work-Station	TS0222659	SOUTH NASHVILLE CB-REPL FAILED AIR COMPRESSOR	35300 - Station Equipment	03/01/2020	4,838
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	42666826	69 KV RED POINT-BELLVUE LINE 104 4 REPL 31 SETS X ARMS/INS	35500 - Poles and Fixtures	06/01/2017	147,791
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	42667978	E LEESVILLE - N LEESVILLE TLN194 00348 REPL 30 XARM/8 POLES	35500 - Poles and Fixtures	06/01/2017	162,727
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	42674463	2017 DOP - 138KV TRICHEL - WHITEHURST LINE 119 1	35500 - Poles and Fixtures	06/01/2017	17,026
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	42719405	MANY - NOBLE 69 KV REPLACE CROSS PAY TRAILING INVOICES	35500 - Poles and Fixtures	07/01/2017	938
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	42731934	E LEESVILLE N LEESVILLE TLN194 00348 OPEN TO C/O CHARGES	35500 - Poles and Fixtures	09/01/2017	168,865
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL030070	CALUMET- RED POINT POLE # 61	35500 Poles and Fixtures	06/01/2017	28,091
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL030167	ARSENAL HILL - WATERWORKS GROUNDS STOLEN	35500 - Poles and Fixtures	06/01/2017	13,114
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL030220	FLOURNOY - SUMMER GR (WLWRTH RD # 22)	35500 - Poles and Fixtures	06/01/2017	33,274
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL030644	ARSENAL HILL - BROOK # 1,2&3 A-2	35500 - Poles and Fixtures	10/01/2017	157,672
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL030843	HOSSTON - NORTH BENTON REPLACE 40 STRUCTURES	35500 - Poles and Fixtures	10/01/2017	329,446
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL030844	HOSSTON - SUPERIOR REPLACE 38 STRUCTURES	35500 - Poles and Fixtures	09/01/2018	256,161
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL030847	FLOURNOY - WASKOM LA REPLACE 35 STRUCTURES	35500 Poles and Fixtures	10/01/2017	214,756
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL030863	DOGWOOD TAP CP WO 1 CONDITIONS	35500 - Poles and Fixtures	09/01/2017	1,395
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL030909	NOBLE - MOUNT ZION CP REPLACE ARMS ON 30 STRUCTURES	35500 Poles and Fixtures	10/01/2017	95,513
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL030910	BELMONT-MARTHAVILLE CP REPLACE 30 SETS OF ARMS AND 7 POLES	35500 - Poles and Fixtures	10/01/2017	142,063
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL030963	FLOURNOY - WOODLAW2 STORM -REMOVE TREE FROM CONDUCOR - PILKI	35600 Overhead Conductors, Device	02/01/2018	6,495
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL031014	GENERAL MOTORS - SOU STORM DANGER TREE - PILKINGTON	35600 Overhead Conductors, Device	02/01/2018	3,146
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL031021	BLANCHARD - NORTH MARK # 167 A-1	35500 - Poles and Fixtures	09/01/2017	853
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL031173	STONEWALL TAP CP # 50 - S3 A-1 TREE DAMAGE	35500 - Poles and Fixtures	09/01/2017	66,105
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL031225	BELCHER - HOSSTON CP REPLACE 10 A2 H STRUCTURES	35500 Poles and Fixtures	09/01/2019	(0)
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL031274	NOBLE - MOUNT ZION CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	8,934
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL031572	SOUTHWEST SHREVEP WE CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2018	39,146
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL031984	HARDY STREET MIDWAY (10) A-2 WOOD POLES	35500 Poles and Fixtures	10/01/2018	161,823
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL032020	FLOURNOY - SUMMER GROVE STR'S 60 - 65 A-2	35500 - Poles and Fixtures	10/01/2018	95,946
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL032020	FLOURNOY - SUMMER GROVE STR'S 60 - 65 A-2	35600 - Overhead Conductors, Device	10/01/2018	95,945
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL032030	LONGWOOD - EL DORADO # 0/2 ARM A-2	35500 - Poles and Fixtures	10/01/2018	26,442
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL032045	ARSENAL HILL-LONGWOO # 81 CAR HIT POLE A-1	35500 - Poles and Fixtures	09/01/2018	5,881

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non Specific Work Line	TL032139	WALLACE LAKE - MANSF # 128 & 154 XARMS	35500 - Poles and Fixtures	10/01/2018	18,607
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL032360	N LEESVILLE-HORNBECK (30) SETS X-ARMS (2) POLES	35500 Poles and Fixtures	10/01/2018	100,207
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non Specific Work Line	TL032360	N LEESVILLE-HORNBECK (30) SETS X ARMS (2) POLES	35600 - Overhead Conductors, Device	10/01/2018	100,207
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non Specific Work Line	TL032361	ROBSON ROAD(POD-KING INCREASE CONDUCTOR HEIGHT	35400 - Towers and Fixtures	10/01/2018	91,107
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL032587	LOGANSPORT - STONEWALL (7) POLES & ANCHORS	35500 Poles and Fixtures	10/01/2018	130,140
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL032650	FLOURNOY - LONGWOOD CP WO 1 CONDITIONS	35500 - Poles and Fixtures	09/01/2018	16,440
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL032658	BRONLEE RD-MINDEN RD CP # 42 A-1 POLE	35500 - Poles and Fixtures	10/01/2018	5,969
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL032687	BRONLEE RD-MINDEN RD CP # 44 A-1 POLE	35500 - Poles and Fixtures	10/01/2018	24,615
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL032735	RED POINT - BELLEVUE - DANGER TREE - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2018	4,112
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL032888	TRICHEL STREET - WHITEHURST A-2 STUB POLE # 55	35500 - Poles and Fixtures	06/01/2019	(3,209)
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non Specific Work Line	TL032985	BLANCHARD - LIEBERMAN A-1 # 97 X ARM	35500 Poles and Fixtures	12/01/2018	1,902
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL033027	SEVENTIETH STREET TAP (5) A-1 POLES, BAD LOCATION	35500 - Poles and Fixtures	10/01/2018	77,591
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL033275	CAPLIS - MCDADE STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2018	1,359
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL033320	EDWARDS STREET - HUMBUG A-2 POLES	35500 - Poles and Fixtures	01/01/2019	94,324
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non Specific Work Line	TL033330	CAPLIS - MCDADE OUTAGE GROW IN - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2018	8,189
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL033342	TRICHEL TAP - TRICHE - STORM PATROL AND GROUNDING - PILKINGT	35600 - Overhead Conductors, Device	12/01/2018	9,567
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL033558	ROBSON ROAD(POD-KING CP A-1 # 65 & 66 ARMS	35500 - Poles and Fixtures	10/01/2018	3,317
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non Specific Work Line	TL033608	E LEESVILLE - HICKS CP A-1 ALL INSULATORS SHOT OUT	35500 - Poles and Fixtures	06/01/2019	5,787
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL033629	RED POINT - WHITEHUR CP #55 WP DAMAGE	35500 - Poles and Fixtures	06/01/2019	35,898
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL033630	LIEBERMAN - RED POIN CP A-1 X-ARM # 153	35500 - Poles and Fixtures	06/01/2019	11,887
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL033682	LOGANSPORT - STANLEY CP A-1 ARM	35500 - Poles and Fixtures	11/01/2019	7,235
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL033720	LONGWOOD - EL DORADO CP A-2 ARM 24/3	35500 - Poles and Fixtures	06/01/2019	25,940
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL034036	HOSSTON - NORTH BENT CP	35500 - Poles and Fixtures	07/01/2019	69,277
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL034051	BRONLEE RD-MINDEN RD CP # 56 A-2	35500 - Poles and Fixtures	07/01/2019	35,028
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL034224	LOGANSPORT STONEWA CP A-1 # 40	35500 - Poles and Fixtures	11/01/2019	4,270
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL034460	CALUMET- RED POINT CP # 15 & 36 A-2 POLES	35500 - Poles and Fixtures	07/01/2019	39,381
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL034680	LIEBERMAN - RED POINT CP # 5 A-1 POLE	35500 - Poles and Fixtures	11/01/2019	7,732
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL034711	RED POINT - BELLEVUE CP A-2 / 3 POLE ANGLE	35500 - Poles and Fixtures	07/01/2019	79,097
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL034882	BLANCHARD - LIEBERMA CP A 1 X-ARM	35500 - Poles and Fixtures	11/01/2019	3,456
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035232	NOBLE - MOUNT ZION STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	2,225
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035312	HOSSTON-BLMBRG (LA) STORMS _ PILKINGTON	35600 - Overhead Conductors, Device	05/01/2019	13,618
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035351	BLANCHARD - NORTH MA STORM - BIDDY	35600 - Overhead Conductors, Device	12/01/2019	2,730
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035395	BLANCHARD - LIEBERMAN # 88 A-1 CROSSARM	35500 - Poles and Fixtures	09/01/2019	2,373
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035446	RED POINT - BELLEVUE STORM _ PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	1,316
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035516	LOGANSPORT - STONEWA STORM - PILKINGTONG	35600 - Overhead Conductors, Device	12/01/2019	2,860
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035517	ELLERBE ROAD-FERN R/W STORM - PILKINGOTN	35600 - Overhead Conductors, Device	06/01/2019	4,462
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035551	HOSSTON - NORTH BENT A-2 POLES 234 & 235	35500 - Poles and Fixtures	11/01/2019	82,732
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035728	BRONLEE RD MINDEN RD CP # 44 A-1 POLE	35500 - Poles and Fixtures	09/01/2019	28,788
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035852	HOSSTON - NORTH BENT STORM - PILKINTON	35600 - Overhead Conductors, Device	12/01/2019	1,180
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035874	FLOURNOY - SUMMER GROVE # 29 & 30 A-2 POLES	35500 Poles and Fixtures	11/01/2019	19,285
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035984	HOSSTON - SUPERIOR A-1 # 38	35500 - Poles and Fixtures	11/01/2019	7,095
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non-Specific Work Line	TL035985	LONGWOOD - EL DORADO A-1 # 23/1	35500 - Poles and Fixtures	11/01/2019	32,754
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LALRE	B194LALRE T/SW/Non Specific Work Line	TL035991	BLANCHARD LIEBERMAN A-1 # 87 POLE	35500 - Poles and Fixtures	11/01/2019	17,926
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LARMB	B194LARMB Reimbursable-DOP-194 LA	TL034222	BRONLEE RD-MINDEN RD CP WO CAR HIT POLE FIRST TIME STR 53	35500 - Poles and Fixtures	04/01/2019	12,674
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LARMB	B194LARMB Reimbursable-DOP-194 LA	TL034223	BRONLEE RD-MINDEN RD CP WO CAR HIT POLE SECOND TIME STR 53	35500 - Poles and Fixtures	04/01/2019	11,877
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	42691736	CAPLIS STATION LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	11/01/2018	49,840
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	42691741	MCDADE STATION LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	11/01/2018	35,231
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	42691750	HAUGHTON STATION LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	11/01/2018	35,698
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	42691754	RED POINT STATION LA REPL MULTIPLEXER W/SCHWEITZER ICON	35300 - Station Equipment	11/01/2018	36,871
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0179520	ARSENAL HILL CB CAPACITOR 13730 053881 CAPITAL PROJECT	35300 - Station Equipment	01/01/2018	24,738
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0179683	GENERAL MOTORS STA GENERAL MOTORS CAPITAL PROJECT	35300 - Station Equipment	01/01/2017	87,937
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0179934	SOUTHWEST SHREVEPORT REPL FAILED PAD MOUNT XFMR	35300 - Station Equipment	04/01/2017	8,929
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0180027	SOUTHWEST SHREVEPORT STA PROJE MOABS 10035	35300 - Station Equipment	12/01/2018	470
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0187368	FORT HUMBUG STA CAPITAL PROJECT/POTENTIAL TRANS 69KV	35300 - Station Equipment	06/01/2017	4,826
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0187636	CEDAR GROVE (SW) STA CAPITAL PROJECT/BATTERY&CHARGER	35300 - Station Equipment	06/01/2017	7,282
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0187875	FORT HUMBUG STA CAPITAL PROJECT/69KV CB 10130	35300 - Station Equipment	06/01/2017	43,773
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0188203	SUMMER GROVE STA CAPITAL PROJECT/CB 1P20	35300 Station Equipment	07/01/2017	40,876
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0188223	ARSENAL HILL STA CAPITAL PROJECT/ENG SERVICES	35300 - Station Equipment	11/01/2017	27,186
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0189263	GENERAL MOTORS STA CAPITAL PROJECT/3 CCVTS	35300 - Station Equipment	10/01/2017	33,127
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0189828	ARSENAL HILL STA CAPITAL PROJECT/P7184&P7202 FAILED FANS	35300 - Station Equipment	09/01/2017	1,174
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0189841	BROADMOOR STA CAPITAL PROJECT/FAILED RMC 30	35300 - Station Equipment	09/01/2017	812
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0189860	LOGANSPORT STA CAPITAL PROJECT/CHANGED OUT FAILED FANS	35300 - Station Equipment	12/01/2017	8,205
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0189977	GENERAL MOTORS STA CAPITAL PROJECT/CB11000	35300 - Station Equipment	10/01/2017	66,383
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0190368	LAYFIELD 500KV TRF P500 03 AUTO XFMR 3 PHASE C 14QP000002490	35300 - Station Equipment	10/01/2018	1,469
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0194096	LUCAS STA CAPITAL PROJECT/REPLACE RMC 30	35300 - Station Equipment	11/01/2017	363
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0194189	HARTS ISLAND CB TLINE FORT HUMBUG 10554 7723252 CAPITAL PROJ	35300 - Station Equipment	06/01/2018	16,074
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0194309	LUCAS CCVT ELLERBE MID 1646701007 CAPITAL PROJECT/FAILED69KV	35300 - Station Equipment	07/01/2018	6,029
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0195519	ARSENAL HILL STA CAPITAL PROJECT/CAPACITOR CANS	35300 - Station Equipment	12/01/2017	2,538
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0199422	ARSENAL HILL STA CAPITAL PROJECT/BREAKER 7280	35300 - Station Equipment	06/01/2018	36,578
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0199473	LONGWOOD (SW) MET LONGWOOD_TO_SAREPTA_345KV OUT 30834190_EMS	35300 - Station Equipment	03/01/2020	2,274
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0199543	SOUTHWEST SHREVEPORT STA CAPITAL PROJE/138KV ARRESTERS	35300 - Station Equipment	09/01/2018	7,729

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0200264	RED POINT CAPB CAP BANK 12207 CAPITAL PROJECT/CAPACITOR CAN	35300 - Station Equipment	08/01/2018	8,383
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0200287	LIEBERMAN STA CAPITAL PROJECT/FAILED 138KV SWITCHES	35300 - Station Equipment	04/01/2019	52,994
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0200452	PORT ROBSON MET BENTELER STEEL MILL 1 PRIMARY 1132810049 113	35300 - Station Equipment	03/01/2020	2,845
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0200843	SOUTHWEST SHREVEPORT STA CAPITAL PROJ/345KV CB 10510	35300 - Station Equipment	09/01/2018	324,534
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0204353	ARSENAL HILL GENERALCONDUCTOR 2 5? IPS SCH 40 CAPITAL PROJ	35300 - Station Equipment	01/01/2019	5,762
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0204504	ARSENAL HILL STA CAPITAL PROJECT/CTVTS	35300 - Station Equipment	10/01/2018	60,971
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0204544	LONGWOOD (SW) STA CAPITAL PROJECT/REPLACE BOTH BATTERY CHRG	35300 - Station Equipment	01/01/2019	9,308
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0204692	SOUTH SHREVEPORT TRF P141 25 W AUTO D589213 CAPITAL PROJECT	35300 - Station Equipment	07/01/2019	12,769
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0204694	WALLACE LAKE TRF P141 0 WEST C0190351 CAPITAL PROJECT/FANS	35300 - Station Equipment	07/01/2019	16,211
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0204713	WALLACE LAKE STA CAPITAL PROJECT/AIR CONDITIONER UNIT	35300 - Station Equipment	09/01/2018	1,354
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0206204	HARDY STREET CB FLOURNOY 1X90 237Y4497 CAPITAL PROJECT	35300 - Station Equipment	09/01/2018	79,067
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0206619	NORTH BENTON STA CAPITAL PROJECT/FAILED FANS	35300 - Station Equipment	07/01/2019	18,161
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0206827	ARSENAL HILL CAPB CAP BANK 13730 CAPBANK13730/FAILED CANS	35300 - Station Equipment	11/01/2018	2,869
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0206863	SUPERIOR (SW) CB CB-9060 9739/FAILED BREAKER 9060	35300 - Station Equipment	07/01/2019	101,965
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0206963	SOUTH SHREVEPORT CB CAPACITOR 1V00 364371/REPLACE BREAKER	35300 - Station Equipment	07/01/2019	49,167
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0210566	TRO80003257_LONGWOOD (SW)CAPITAL PROJECT/12KV HOOKSTICK	35300 - Station Equipment	07/01/2019	6,438
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation LA	T0211087	TRO80003S538_SOUTHWEST SHREVEPORT STA/CONTROL HOUSE LIGHTS	35300 - Station Equipment	07/01/2019	1,406
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0211200	TRO80003442_SOUTH SHREVEPORT STA CAPITAL P/PERIMITER FENCE	35200 - Structures and Improvements	01/01/2020	9,239
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0211200	TRO80003442_SOUTH SHREVEPORT STA CAPITAL P/PERIMITER FENCE	35300 - Station Equipment	01/01/2020	62,091
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0211371	TRO80003442_SOUTH SHREVEPORT STA CAPITAL P/ANTENNA	35300 - Station Equipment	01/01/2020	188
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0212554	WHITEHURST CAPB 1P60 CAP BANK NA02 CAPITAL PROJECT/FUSE&CAP	35300 - Station Equipment	01/01/2020	1,371
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0212556	TRO80004301_RED POINT CAPB CAP BANK 12207/FUSES&CAPACITORS	35300 - Station Equipment	01/01/2020	1,061
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0212557	TRO80050478_WATERWORKS (SW) CAPB CAP BANK 6970/FUSES&CAPS	35300 - Station Equipment	01/01/2020	1,925
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0212559	ARSENAL HILL CAPB CAP BANK 1U30/FUSES & CAPACITORS	35300 - Station Equipment	01/01/2020	2,770
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0215146	TRO80003298_LIEBERMAN TRF P140 7 E AUTO 1998118 CAPITAL PROJ	35300 - Station Equipment	01/01/2020	5,917
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194LASRE	B194LASRE T/SW/NonSpecificWorkStation-LA	T0215521	TRO80003442_SOUTH SHREVEPORT STA CAPITAL/SECURITY PANELS	35300 - Station Equipment	01/01/2020	199,748
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work - Line	42683357	NETTLETON TAP REPLACE ARMS	35500 - Poles and Fixtures	04/01/2017	3,196
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	42683749	LONGWOOD - SCOTTSVILLE REPL POLES & CROSS ARMS	35500 - Poles and Fixtures	06/01/2017	201,183
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work Line	42684225	ROCK HILL - KNOX LEE REPAIR/REPLACE STOLEN GROUNDS	35500 - Poles and Fixtures	06/01/2017	11,813
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work Line	42689417	KNOX LEE - ROCK HILL C/O 39 POLES/STRUCTURES	35500 - Poles and Fixtures	11/01/2018	83,977
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	42750932	GREGGTON-WATERWORKS MID VALLEY TAP-C/O VARIOUS STRUCTURES	35500 - Poles and Fixtures	12/01/2017	21,771
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	42758166	PILGRIMS PRIDE - WINFIELD - REPLACE BAD INSULATORS	35600 - Overhead Conductors, Device	12/01/2017	13,160
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work - Line	42781303	5-9-16 STRM N W TEXARKANA-LYDIA-VALLIANT TRAILING INVOICES	35400 - Towers and Fixtures	01/01/2018	154,609
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work - Line	42787246	HAWKINS - PERDUE LINE 211 REPLACE 1 ARM	35500 Poles and Fixtures	12/01/2017	4,654
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	42814191	GILMER-PITTSBURG STR 261 BROKE ARM	35500 - Poles and Fixtures	09/01/2018	1,026
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	42814903	NW TEXARKANA-VALLIANT DAVIT ARMS CHANGEOUT (16)	35500 - Poles and Fixtures	12/01/2018	82,776
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	42830605	2018 DOP HARRISON RD - PERDUE ST 142 CAR HIT POLE	35500 - Poles and Fixtures	12/01/2018	9,771
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	42831736	2018-EASEMENT RENEWAL IPC DOMINO-WEST ATLANTA SEP TL241	35010 - Land Rights	12/01/2018	4,730
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	42846494	2018 WILKES - N NEW BOSTON C/O BAD STRUCTURES	35500 - Poles and Fixtures	01/01/2019	50,458
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	42849914	ATLANTA - LINDEN REPLACE 9 STRUCTURES AND ARMS	35500 - Poles and Fixtures	01/01/2019	182,242
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	42899148	QUITMAN-N MINEOLA - REPLACE BROKEN STRUCTURE 254	35500 - Poles and Fixtures	01/01/2019	21,745
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	43000092	IPC DOMINO - WEST AT CP WO 41 A-2 CONDITIONS	35500 - Poles and Fixtures	10/01/2019	(53,435)
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	TL0036467	CLARENDON - JERICHO (T) CP WO 3 CONDITIONS TLN047	35500 - Poles and Fixtures	12/01/2019	6,601
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL029675	MT VERNON TAP #1 CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	8,168
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	TL030071	BAN - IPC DOMINO # 221 POLE	35500 - Poles and Fixtures	06/01/2017	31,955
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030149	NORTHWEST TEXARKANA1 CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	7,637
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030191	PETTY - WILKES OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	10/01/2017	2,334
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030204	SHAMROCK-MAGIC CITY CP WO 1 CONDITIONS TLN200	35500 - Poles and Fixtures	06/01/2017	3,838
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030205	W CHILDRESS-SHAMROCK CP WO 1 CONDITIONS TLN00048	35500 - Poles and Fixtures	06/01/2017	1,037
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030289	LK LAMOND-SE LONGVIE ALL GROUNDS STOLEN	35500 - Poles and Fixtures	06/01/2017	168,951
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030328	DANGERFIELD - HUGHES # 106 A-1	35500 - Poles and Fixtures	06/01/2017	1,916
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030342	MEMPHIS - CLARENDON CP WO 1 CONDITIONS TLN00046	35500 - Poles and Fixtures	06/01/2017	3,674
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030366	LOGANSPORT-TENAHA OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2017	5,749
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030373	LOGANSPORT-TENAHA OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2017	820
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030387	W CHILDRESS-ESTELLIN CP WO 13 CONDITIONS TLN00045	35500 - Poles and Fixtures	06/01/2017	10,153
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030447	MIDVALLEY PIPELINE T DEAD TREE - JIMMY DON	35600 Overhead Conductors, Device	11/01/2017	2,073
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030472	CLARKSVILLE - PERDUE CP WO 2 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	969
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030500	PERDUE N-CLAKSVILLE CP WO 2 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	11,857
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030538	CLARKSVILLE - PERDUE CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	9,128
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030548	LOGANSPORT-TENAHA - STORM TREE - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2017	2,282
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030703	LK LAMOND-SE LONGVIE # 127	35500 - Poles and Fixtures	09/01/2017	37,225
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030706	SE LONGVIEW-WHITNEY # 36	35500 - Poles and Fixtures	09/01/2017	24,083
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030707	KILGORE - WHITNEY 10 STRUCTURES STORM DAMAGE	35500 - Poles and Fixtures	09/01/2017	63,355
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030708	LAKE LAMOND - LONGV	35500 - Poles and Fixtures	10/01/2017	67,511
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030756	VERNON MAIN-N VERNON CP WO 4 CONDITIONS TLN00176	35500 - Poles and Fixtures	09/01/2017	27,922
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030767	EVANSIDE - SAWMILL CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	5,805
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030801	LAKE LAMOND - LONGVIEW HEIGHTS 18 - A 2 POLES # 73 THRU #	35500 - Poles and Fixtures	09/01/2017	130,564
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030824	VERNON MAIN-N VERNON CP WO 22 CONDITIONS TLN00176	35500 - Poles and Fixtures	09/01/2017	69,498
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030826	MARSHALL 69 - NORTH CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2017	9,396
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030839	WINFIELD - WINNSBORO CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2017	11,024
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030848	LONE STAR POWER PLAN A-1 # 7 BROKE X-ARM	35500 - Poles and Fixtures	09/01/2017	915

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work - Line	TL030862	PETTY - WILKES STORM - BIDDY	35600 - Overhead Conductors, Device	01/01/2018	3,121
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030916	DIANA - PLILER ROAD STORM OROW TREE REMOVAL - PILKINGTON	35600 - Overhead Conductors, Device	01/01/2018	908
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030960	TAYLOR STREET - BANN # 27 A 1	35500 - Poles and Fixtures	10/01/2017	4,205
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	TL030962	CLARKSVILLE - PERDUE #68 A-1 ARM	35500 - Poles and Fixtures	09/01/2017	1,966
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL030967	LONE STAR SOUTH - WI R/W STORM - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2017	9,131
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL031030	LETOURNEAU TAP CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2017	9,430
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL031032	PITTSBURG - WINNSBOR CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2017	1,285
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL031157	GILMER - PITTSBURG CP WO 1 CONDITIONS	35500 - Poles and Fixtures	01/01/2018	53,815
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL031159	GILMER - PERDUE CP WO 1 CONDITIONS	35500 Poles and Fixtures	01/01/2018	62,835
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL031166	WINFIELD WINNSBORO CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	9,554
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL031177	PETTY - WILKES CP # 90 A 1 3 POLE STRUCTURE BROKEN	35500 - Poles and Fixtures	09/01/2017	53,956
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL031287	IPC DOMINO - WEST AT DEAD TREE - WELLBORN	35600 - Overhead Conductors, Device	02/01/2018	1,987
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL031338	LK LAMOND-SE LONGVIE LAKE CROSSING H FRAMES	35500 - Poles and Fixtures	10/01/2017	103,784
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL031362	PETTY - WILKES CP WO 1 CONDITIONS	35500 - Poles and Fixtures	11/01/2017	2,109
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work - Line	TL031512	LONGVIEW HEIGHTS - MARSH - DANGER TREE AND PATROL -DON VICKE	35600 Overhead Conductors, Device	02/01/2018	1,414
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work - Line	TL032065	HUGHES SPRINGS - LSS A-1 # 59	35500 - Poles and Fixtures	08/01/2018	25,424
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032135	PETTY - WILKES CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2018	46,362
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032140	KILGORE - OVERTON CP WO 1 CONDITIONS	35500 - Poles and Fixtures	09/01/2018	1,352
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032378	DIANA WELSH (CKT #2) DANGER TREE - BIDDY	35600 - Overhead Conductors, Device	12/01/2018	5,892
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032388	PETTY PIGRIM'S PRIDE CP WO 2 CONDITIONS	35600 - Overhead Conductors, Device	10/01/2018	3,044
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032431	WEST ATLANTA WILKE -PILKINTON	35600 - Overhead Conductors, Device	11/01/2018	981
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032494	JEFFERSON SWITCHING1 DANGER TREE	35600 - Overhead Conductors, Device	11/01/2018	142
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032505	JEFFERSON NORTH MA DANGER TREE - REPS	35600 - Overhead Conductors, Device	11/01/2018	2,234
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work - Line	TL032514	PIRKEY - SCOTTSVILLE #44 A-1	35500 - Poles and Fixtures	08/01/2018	17,296
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work - Line	TL032516	IPC JEFFERSON - LIE1 CP WO 3 CONDITIONS	35500 - Poles and Fixtures	08/01/2018	24,711
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032662	BANN - THIRTY NINTH CP # 87 A-1 POLE	35600 - Overhead Conductors, Device	02/01/2019	11,758
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	TL032664	JEFFERSON - NORTH - PILKINGTON	35600 - Overhead Conductors, Device	11/01/2018	1,124
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032685	WEST ATLANTA WILKE CP A-1 # 92 - 3 POLE DDE	35500 - Poles and Fixtures	10/01/2018	64,361
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032686	NORTH NEW BOSTON - WILKES CP A-2 # 601 3 POLE DDE	35500 - Poles and Fixtures	10/01/2018	44,185
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032855	KILGORE - OVERTON CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2018	255
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work - Line	TL032856	BANN - THIRTY NINTH CP WO 2 CONDITIONS	35500 - Poles and Fixtures	10/01/2018	2,984
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL032996	LOGANSPORT-TENAHA R/W WIDENING - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2018	1,450
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033052	W CHILDRESS-ESTELLIN CP WO 1 CONDITIONS TLN00045	35500 - Poles and Fixtures	08/01/2018	2,377
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033104	KNOX LEE - NORTHWEST STORM PATROL AND TREE REMOVAL - PILKINT	35600 - Overhead Conductors, Device	12/01/2018	1,607
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033140	CLARKSVILLE - SABINE STORM TREE ON LINE - PILKINTON	35600 - Overhead Conductors, Device	12/01/2018	1,506
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033183	PETTY - WILKES CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2018	17,302
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033231	WINFIELD - WINNSBORO -LINE GROUNDING REMOVE TREE BIDDY	35600 - Overhead Conductors, Device	12/01/2018	594
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033232	CLARENDON - JERICHO CP WO 2 CONDITIONS TLN00047	35500 - Poles and Fixtures	10/01/2018	3,131
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033260	MIDVALLEY LONGVIEW T CP WO 18 CONDITIONS	35500 - Poles and Fixtures	06/01/2019	12,001
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033261	HAWKINS PERDUE CP WO 4 CONDITIONS	35500 - Poles and Fixtures	06/01/2019	1,478
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033273	JEFFERSON SUPERIO2 R/W WIDENING	35600 - Overhead Conductors, Device	02/01/2019	1,964
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033276	PIRKEY - WHITNEY STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2018	2,078
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033333	IPC DOMINO WEST AT CP WO 41 A-2 CONDITIONS	35500 - Poles and Fixtures	06/01/2019	375,183
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033341	JEFFERSON - SUPERIO2 - STORM PATROL AND GROUNDING DON VICKER	35600 - Overhead Conductors, Device	12/01/2018	5,809
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033378	PETTY PIGRIM'S PRIDE CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2019	28,569
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033406	CLARENDON - JERICHO CP WO 4 CONDITIONS TLN00047	35500 - Poles and Fixtures	10/01/2018	10,968
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033617	WELSH WILKES CP WO 2 CONDITIONS	35600 - Overhead Conductors, Device	06/01/2019	4,041
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033627	LAKE PAULINE RED RIV CP WO 22 CONDITIONS TLN0845	35500 - Poles and Fixtures	03/01/2019	108,857
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work - Line	TL033679	KNOX LEE SE LONGVIEW CP A-1 INSULATORS (54) TOTAL	35600 - Overhead Conductors, Device	06/01/2019	25,794
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033712	BANN - THIRTY NINTH CP WO 3 CONDITIONS	35500 - Poles and Fixtures	11/01/2019	5,829
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033738	CENTER - TENAHA R/W STORM PILKINGTON	35600 - Overhead Conductors, Device	03/01/2019	223
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	TL033834	PIRKEY SCOTTSVILLE CP WO 14 CONDITIONS	35500 - Poles and Fixtures	07/01/2019	82,899
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033839	CARTHAGE - ROCK HILL STORM TREE - PILKINGTON	35600 - Overhead Conductors, Device	03/01/2019	1,510
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033856	LAKE LAMOND - LONGV1 CP 22 CONDITIONS	35500 - Poles and Fixtures	09/01/2019	127,218
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033888	VERNON MAIN-FREDERIC CP WO 4 CONDITIONS	35500 - Poles and Fixtures	01/01/2019	18,838
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033899	PIRKEY SCOTTSVILLE STORM PATROL	35600 - Overhead Conductors, Device	12/01/2018	2,217
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL033900	ATLANTA - LINDEN STORM PILKINTON	35600 - Overhead Conductors, Device	12/01/2018	1,425
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034059	CARTHAGE ROCK HILL STORM - DANGER TREE - PILKINGTON	35600 - Overhead Conductors, Device	03/01/2019	543
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034060	CENTER-LOGANSPOR(TX) STORM DANGER TREE PILKINGTON	35600 - Overhead Conductors, Device	03/01/2019	766
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034221	MIDVALLEY LONGVIEW TAP #225 4 - R/W OROW-PILKINTON	35600 - Overhead Conductors, Device	03/01/2019	4,847
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034279	IPC JEFFERSON - LIE1 CP WO 1 CONDITIONS	35500 - Poles and Fixtures	07/01/2019	11,366
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034377	IPC DOMINO - WEST ATL	35500 Poles and Fixtures	07/01/2019	108,355
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034445	BANN - NEW BOSTON CP (S1) HP INSULATORS	35500 - Poles and Fixtures	07/01/2019	70,049
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034450	DIANA - PURDUE CP WO 67 CONDITIONS	35500 Poles and Fixtures	11/01/2019	31,645
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034454	IPC JEFFERSON - LIE1 STORM VICKERS	35600 Overhead Conductors, Device	08/01/2019	4,697
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034525	GILMER - PITTSBURG STORM - PILKINTON	35600 - Overhead Conductors, Device	08/01/2019	1,471
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034526	KNOX LEE - OVERTON STORM _ PILKONTON	35600 - Overhead Conductors, Device	08/01/2019	2,207
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034603	QUITMAN - WINNSBORO STORM BIDDY	35600 - Overhead Conductors, Device	08/01/2019	3,640
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034740	LOGANSPORT-TENAHA STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	2,459
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034747	FLOURNOY - WOODLAWN A-1 # 157 SEE NOTES	35500 - Poles and Fixtures	07/01/2019	52,118
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034913	KILGORE WHITNEYSTORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	4,475

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034962	DIANA - PURDUE STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	1,360
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non Specific Work - Line	TL034963	MARSHALL 138 - PIRKE STORM PILKINGTON	35600 Overhead Conductors, Device	12/01/2019	1,133
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034973	CLARENDON - JERICHO CP WO 1 CONDITIONS TLN00305	35500 - Poles and Fixtures	04/01/2019	3,278
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL034998	KILGORE - WHITNEY CP A-1 STORM DAMAGE	35500 - Poles and Fixtures	07/01/2019	37,160
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035230	CARTHAGE - L A PACIFIC # 89 A-1 ARM	35500 - Poles and Fixtures	11/01/2019	10,123
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035237	GILMER - PITTSBURG CP # 7 A-1	35500 - Poles and Fixtures	09/01/2019	1,169
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035311	PIRKEY - WHITNEY STORMS - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	2,050
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035353	BECKVILLE - POYNTER STORM - BIDDY	35600 - Overhead Conductors, Device	12/01/2019	2,881
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035401	CLARKSVILLE - PERDUE R/W STORM - PILKINGTON	35600 - Overhead Conductors, Device	10/01/2019	5,352
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035402	BLOOMBURG - ATLANTA CP # 41 A 1 POLE	35500 - Poles and Fixtures	09/01/2019	10,364
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035403	KNOX LEE - OVERTON CP A-1 # 30 & 31 ARMS	35500 - Poles and Fixtures	11/01/2019	5,318
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035448	BAN - IPC DOMINO - STORM PILKINTON	35600 - Overhead Conductors, Device	10/01/2019	500
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	TL035463	NORTH NEW BOSTON - STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	1,587
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035464	HAWKINS - MINEOLA _ STORM - PILKINGTON	35600 Overhead Conductors, Device	12/01/2019	2,437
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035465	CENTER - TENAHA -STORM PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	2,043
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035466	HAWKINS PERDUE A-1 CROSS ARM # 204	35500 Poles and Fixtures	11/01/2019	8,102
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035515	CLARKSVILLE - GREGGT STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	2,607
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035518	DIANA - PLILER ROAD - STORM PILKINGTON	35600 - Overhead Conductors, Device	07/01/2019	4,285
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035519	JEFFERSON SWITCHING1 - STORM PILKINGTON	35600 Overhead Conductors, Device	06/01/2019	6,300
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035537	W CHILDRESS-SHAMROCK CP WO 9 CONDITIONS TLN00048	35500 - Poles and Fixtures	07/01/2019	18,550
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035661	KILGORE OVERTON R/W STORM BIDDY	35600 - Overhead Conductors, Device	12/01/2019	1,761
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035663	CROCKETT - TENASKA STORM - PILKINGTON	35600 - Overhead Conductors, Device	07/01/2019	7,805
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035666	WOODLAWN-KARNACK SW A-2 # 20	35500 - Poles and Fixtures	09/01/2019	28,895
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035676	BANN - SE TEXARKANA A-2 DE INSULATORS	35500 - Poles and Fixtures	09/01/2019	11,320
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035800	CROCKETT - TENASKA PILKINGTON STORM	35600 - Overhead Conductors, Device	10/01/2019	20,894
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035806	KNOX LEE - PIRKEY A-1 INSULATOR FAILURE	35600 - Overhead Conductors, Device	09/01/2019	27,104
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035832	LONGWOOD-WILKES(TX) STORMS - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	2,091
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	TL035833	WOODLAWN-KARNACK STORM - PILKINTON	35600 - Overhead Conductors, Device	12/01/2019	3,446
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035834	KNOX LEE - PIRKEY CP A-1 GOABS	35500 - Poles and Fixtures	01/01/2020	60,980
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035839	WOODLAWN-KARNACK SW CP WO 10 CONDITIONS	35500 - Poles and Fixtures	09/01/2019	157,216
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035961	LONE STAR SOUTH - PITTS A-1 DAVIT ARMS 5/3	35500 Poles and Fixtures	11/01/2019	6,888
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035963	PILGRIM'S PRIDE WI STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	829
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035964	DIANA PLILER ROAD A-1 # 157 X-ARM	35500 - Poles and Fixtures	11/01/2019	7,972
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035967	HAWKINS PERDUE A-1 CROSSARM # 184	35600 - Overhead Conductors, Device	09/01/2019	5,235
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL035994	BLOOMBURG - ATLANTA A-1 # 22 BROKE POLE	35500 - Poles and Fixtures	09/01/2019	14,836
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL036011	DIANA - PURDUE STORM DAMAGE 10 STRUCTURES	35500 - Poles and Fixtures	11/01/2019	110,343
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL036015	PITTSBURG - WINNSBOR STORM DAMAGE 5 STRUCTURES A-1	35600 - Overhead Conductors, Device	09/01/2019	22,939
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL036018	DIANA - PLILER ROAD - STORM PILKJINGTON	35600 - Overhead Conductors, Device	12/01/2019	2,811
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL036057	JEFFERSON - NORTH - STORM PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	261
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL036164	DIANA - LONE STAR SO # 20 A-1 IN LAKE	35500 Poles and Fixtures	09/01/2019	76,416
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL036199	MARSHALL-PIRKEY 138KV - STORM REMOVE TREE-PILKINTON	35600 - Overhead Conductors, Device	12/01/2019	411
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work Line	TL036204	CARTHAGE L A PACIFIC A-1 ARM # 93	35500 - Poles and Fixtures	09/01/2019	886
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL036230	DIANA - LAKE LAMOND CP FORESTRY	35500 - Poles and Fixtures	01/01/2020	564
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXLRE	B194TXLRE T/SW/Non-Specific Work - Line	TL036267	GILMER PITTSBURG A-1 # 84 ARM	35500 Poles and Fixtures	09/01/2019	1,704
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXRMB	B194TXRMB Reimbursable-DOP-194 Texas	42980052	DOP WINFIELD-MT VERNON 18WHEELER HIT POLE	35600 - Overhead Conductors, Device	09/01/2019	(3,626)
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXRMB	B194TXRMB Reimbursable-DOP-194 Texas	43017876	DOP JEFFERSON 69 KV SUBSTATION-REGULATOR DAMAGED BY H BROWN	35300 Station Equipment	11/01/2019	2,008
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	42751996	CHAPEL HILL SUBSTATION REPLACE ION 8600 METER	35300 - Station Equipment	01/01/2020	1,853
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	42921285	WELSH HVDC STATION REPLACE FAILED AUTO TRANSFORMER TW01 L3	35300 - Station Equipment	05/01/2019	89,845
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0179823	EVENSIDE STA REPLACE LIGHT AND FIXTURE	35300 - Station Equipment	11/01/2016	794
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0183430	WELSH STA REPL FAILED SWITCH 11683	35300 - Station Equipment	04/01/2018	65,749
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0186562	MARSHALL 138KV STA MARSHALL YARD REPLACE LIGHT FIXTURE	35300 - Station Equipment	01/01/2017	2,391
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0186906	BANN STA BANN CAPITAL PROJECT/SWITCH 11432	35300 - Station Equipment	06/01/2017	13,571
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0186911	KILGORE CAPITAL PROJECT RELAYS (CB) SABINE 1700/207688	35300 - Station Equipment	06/01/2017	1,490
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0187179	KNOX LEE CAPB CAP BANK 1205 CAPBANK1205 CAPITAL PROJECT	35300 - Station Equipment	10/01/2017	70,177
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0187212	OVERTON STA REPLACE FAILED CCVT & CARRIER TUNER PK	35300 - Station Equipment	10/01/2017	19,322
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0187283	WEST ATLANTA BUSHING P137 9 EAST BUSHING REPL MAJOR MAINT	35300 - Station Equipment	06/01/2017	110,117
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0187450	WEST ATLANTA STA WEST ATLANTA CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	15,720
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0187657	NORTHWEST TEXARKANA STA CAPITAL PROJECT/CCVTS	35300 - Station Equipment	06/01/2017	23,921
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0187784	WINNSBORO CB PITTSBURG 9820 448731 CAPITAL PROJECT/CB 9820	35300 - Station Equipment	10/01/2017	753
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0187995	PIRKEY TRF P345 64 - N AUTO MAJOR MAINTENANCE	35300 - Station Equipment	11/01/2017	272,598
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188023	NORTH MINEOLA STA - REPLACE ARRESTERS	35300 - Station Equipment	07/01/2017	4,653
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188035	WELSH HVDC CONVERTER CB FILTER CB BM03 REP FAILED CTVT	35300 - Station Equipment	06/01/2017	5,232
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188067	PIRKEY STA PIRKEY - REPLACE FAILED 3 TON AC UNIT	35300 - Station Equipment	04/01/2017	5,325
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188224	TENASKA STA CAPITAL PROJECT/ENG SERVICE	35300 - Station Equipment	11/01/2017	47,915
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188274	2017 GEUPGRADE DIANA STA_1 RELAY	35300 - Station Equipment	10/01/2019	0
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188274	2017 GEUPGRADE DIANA STA_1 RELAY	35316 - Station Equipment-SmartGrid	10/01/2019	10,822
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188443	HEDLEY C/O FAILED MOS 1663 1662	35300 - Station Equipment	03/01/2018	15,451
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188478	DIANA STA DIANA REPLACE SWITCHES 12062 12063	35300 - Station Equipment	06/01/2018	107,625
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188592	MOUNT PLEASANT STA REPLACE FLOODED RELAYS	35300 - Station Equipment	06/01/2017	2,797
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188684	MOUNT VERNON (SW) DSC MOAB H S NORTH XFR 9046 V2721521 CAPI	35300 Station Equipment	07/01/2018	7,790
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188803	TEXARKANA OPERATIONS CENTER STA TEXARKANA OPERATIONS CENTER	35300 - Station Equipment	07/01/2017	12,047

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188827	CROCKETT BUSHING P345 26 NORTH H1 REPL FANS	35300 - Station Equipment	10/01/2017	1,755
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188881	PIRKEY TRF P345 40 - S AUTO REPLACE 7 FANS	35300 - Station Equipment	08/01/2017	3,959
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188883	LEBROCK STA LEBROCK REPL SW 13242, 13243, 13222, 132S2	35300 - Station Equipment	08/01/2019	191,539
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0188920	BUFORD SURVEY DSC MOABS 762S REPLACE FAILED SWITCH	35300 - Station Equipment	09/01/2018	122,783
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0189069	SE LONGVIEW TCC 69 [CB] WHITNEY 6630 REPL LIGHTNING ARRESTER	35300 Station Equipment	09/01/2017	956
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0189284	PERDUE CAPB 86 4 MVAR CAP BANK 138KV REPLACE FAILED CAPACITO	35300 - Station Equipment	06/01/2017	7,990
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0189327	WINNSBORO STA CAPITAL PROJECT/RTU REPLACEMENT	35300 - Station Equipment	08/01/2018	41,359
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0189431	NORTH MINEOLA TRF P142 17 REPLACE 3 FANS	35300 - Station Equipment	09/01/2017	1,540
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0189432	OVERTON TRF P137 1 NORTH REPLACE 2 FANS	35300 - Station Equipment	07/01/2017	2,281
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0189465	JERICHO STA INSTALL IED FOR DISTANCE TO FAULT INFORMATION	35300 Station Equipment	09/01/2018	22,701
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0189466	CLARENDON STA INSTALL IED FOR DISTANCE TO FAULT INFORMATION	35300 - Station Equipment	09/01/2018	17,159
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0189714	BANN TRF P141 58 AUTO SOUTH 9311401237 CAPITAL PROJECT	35300 - Station Equipment	12/01/2017	90,068
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0189993	MONROE CORNERS METERING UPGRADE	35300 - Station Equipment	01/01/2019	1,781
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0190140	BANN STA CAPITAL PROJECT/ BREAKER#2A40	35300 Station Equipment	04/01/2018	57,715
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0190186	DIANA STA CAPITAL REPL FAILED SWITCH 13098	35300 - Station Equipment	01/01/2018	37,059
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0190366	PILGRIMS PRIDE CB WINFIE/WMTPL & PETTY 4470 437Y3124 CAPITAL	35300 - Station Equipment	07/01/2018	94,151
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0193176	NORTHWEST TEXARKANA TRF P345 39 NORTH 7002868 CAPITAL PROJEC	35300 - Station Equipment	04/01/2018	10,185
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0193246	DIANA STA REPL FAILED SWITCH 13105	35300 - Station Equipment	11/01/2017	31,115
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0193274	NORTH MARSHALL DSC GND SWITCH 7525 SW_405000002457 CAPITAL P	35300 - Station Equipment	10/01/2017	10,797
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0194129	NORTHWEST HENDERSON REPL SUMP PUMP CAPITAL PROJECT	35300 - Station Equipment	12/01/2017	3,078
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0194212	PERDUE MET ENERGY METER 601A020_EMS CAPITAL PROJECT	35300 - Station Equipment	01/01/2020	2,787
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0194355	NORTHWEST TEXARKANA CAPITAL PROJECT RELAYS	35300 - Station Equipment	01/01/2018	4,973
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0194395	POYNTER VT LINE PT FOR CB 1J40 A 71165 CAPITAL PROJECT	35300 - Station Equipment	12/01/2017	6,170
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0195475	WELSH HVDC CONVERTER STA CAPITAL PROJE/TW01 L2 B	35300 Station Equipment	04/01/2018	8,059
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0195570	DIANA STA DIANA REPLACE FAILED CVT'S	35300 Station Equipment	01/01/2018	20,730
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0195649	SHAMROCK C/O FAILED CAP BANK CS 6730	35300 Station Equipment	03/01/2018	112,704
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0195657	NORTH NEW BOSTON CB 11360 137Y2021 CAPITAL PROJEC	35300 - Station Equipment	04/01/2018	1,010
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0195658	WILKES DSC SW 1J75 SW_40500000300 CAPITAL PROJECT	35300 - Station Equipment	06/01/2018	24,189
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0195822	DIANA STA DIANA CAPITAL PROJECT	35300 - Station Equipment	06/01/2018	3,657
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0195885	EASTON SUBSTATION- REPLACE FAILED ION METER	35300 - Station Equipment	01/01/2020	1,810
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0197607	PETTY STA CAPITAL PROJECT/FUTURA METER	35300 - Station Equipment	08/01/2018	6,022
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0197628	OVERTON STA CAPITAL PROJECT REPL 2 CAPACITORS	35300 - Station Equipment	01/01/2018	1,189
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0198768	THIRTY NINTH STREET CB CIRCUIT BREAKER 8650 0139A9023201 CAP	35300 - Station Equipment	07/01/2018	131,912
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0198923	JERICHO C/O FAILED A/C UNIT	35200 - Structures and Improvements	03/01/2018	579
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0198923	JERICHO C/O FAILED A/C UNIT	35300 - Station Equipment	03/01/2018	744
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0198943	PETTY STA CAPITAL PROJECT/WEST 69KV BUS POTENTIAL TRANS	35300 - Station Equipment	04/01/2018	21,043
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0198946	WEST ATLANTA STA CAPITAL PROJECT/138 & 69KV BUS ARRESTERS	35300 - Station Equipment	06/01/2018	11,322
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0198953	LYDIA MET LYDIA 345 - VALLIANT 345 REPLACETWO FAILED METERS	35300 Station Equipment	10/01/2018	2,952
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0198980	SOUTHEAST LONGVIEW CB WHITNEY 6630 S37Y2615 CAPITAL PROJECT	35300 - Station Equipment	07/01/2018	1,900
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0198986	LONE STAR (SEP) CB GSU #4/A-C BUS 1500A 111V1185 CAPITAL PRO	35300 - Station Equipment	07/01/2018	1,427
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0199715	KNOX LEE CB CB-2600E 378443 CAPITAL PROJECT/CB 2600E	35300 - Station Equipment	10/01/2018	58,403
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0200099	BANN STA CAPITAL PROJECT/SWITCH 9435 RETIREMENT	35300 - Station Equipment	01/01/2019	1,147
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0200103	WELSH DSC MOAB DIANA WEST 11925 A33796 CAPITAL PROJECT	35300 - Station Equipment	03/01/2020	96,010
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0200111	WELSH STA CAPITAL PROJECT/138KV SWITCH 10504	35300 Station Equipment	03/01/2019	20,906
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0200147	LONE STAR SOUTH STA CAPITAL PROJECT/CONTROL HOUSE A/C	35300 - Station Equipment	01/01/2019	8,235
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0204149	TAYLOR STREET CB TEXARAKANA PLANT 7560 319635 CAPITAL PROJEC	35300 - Station Equipment	07/01/2019	76,033
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0204172	CAMP COUNTY POD CAPITAL PROJECT/REPLACE FAILED HVAC	35300 - Station Equipment	12/01/2019	3,623
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0204310	SHAMROCK C/O FAILED RELAY 38062R2	35300 - Station Equipment	10/01/2018	5,306
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0204310	SHAMROCK C/O FAILED RELAY 38062R2	35316 - Station Equipment-SmartGrid	10/01/2018	949
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0204533	LEBROCK MET STG 001 BACKUP 907A716_REPLACE FAILED METER	35300 - Station Equipment	03/01/2020	2,606
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0204635	JERICHO C/O FAILED BATTERY ONLY	35300 - Station Equipment	09/01/2018	7,240
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0206218	CHAPEL HILL (M O LINE SW) DSC MOAB 6333 CO735181 CAPITAL PR	35300 - Station Equipment	01/01/2020	1,099
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0206344	HUGHES SPRINGS LA CB-1890 ARR PH B CAPITAL PROJECT/ARRESTE	35300 Station Equipment	12/01/2018	896
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0206525	WOODLAWN (SW) CB CB-2090 REPLACE FAILED COMPRESSOR AND MOTOR	35300 Station Equipment	12/01/2019	1,283
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0206851	NEW BOSTON STA NEW BOSTON CAPITAL PROJECT	35300 Station Equipment	12/01/2018	3,444
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0206888	MARSHALL 69KV CB ROCKHILL 1340 REPLACE FAILED CB	35300 - Station Equipment	12/01/2018	61,335
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0207671	BANN STA CAPITAL PROJECT/STATION SERVICE UPGRADE	35300 Station Equipment	03/01/2019	1,537
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0207730	HAWKINS RTU REMOTE TERMINAL UNIT RTU_1004225929/REPLACE	35300 - Station Equipment	01/01/2020	63,456
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0207750	WEST ATLANTA STA CAPITAL PROJECT	35300 - Station Equipment	12/01/2018	6,127
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0207824	TRO80004983_PETTY STA CAPITAL PROJECT/NEW TRANSFORMER	35300 - Station Equipment	12/01/2019	80,104
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0210070	TRO80002772_PIRKEY STA REPL 3 FAILED LIGHTNING ARRESTERS	35300 - Station Equipment	01/01/2020	17,394
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0211230	BRADY SW COMM REMOTE ACCESS SERVER MPC_1003272982 CAPITAL PR	35316 - Station Equipment-SmartGrid	01/01/2020	11,712
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0211530	TRO80044043_NORTHWEST TEXARKANA STA CAP/FL LIGHTS&FAN	35300 - Station Equipment	12/01/2019	9,617
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0212166	TRO80004465_PITTSBURG (SW) STA CAPITAL PROJE/OCB6220AUXRELAY	35300 - Station Equipment	03/01/2020	715
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0212227	TRO80004465_PITTSBURG (SW) STA CAPITAL PROJE(HVAC)	35300 - Station Equipment	07/01/2019	4,269
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non Specific Work Station	T0212309	TRO80055714_RED SPRINGS STA CAPITAL PROJECT/STOLEN GROUNDS	35300 - Station Equipment	07/01/2019	7,247
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0212695	TRO80037224_WHITNEY STA CAPITAL/UNDERGROUND POWER CABLE	35300 - Station Equipment	08/01/2019	68,905
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0215164	ESTELLINE C/O SEL-167 W/ SEL-321	35316 - Station Equipment-SmartGrid	02/01/2020	26,651
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0215642	ROCK HILL CB CB-10120 REPLACE FAILED COMPRESSOR	35300 - Station Equipment	11/01/2019	5,901
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0215649	NORTH MINEOLA CB WINNSBORO/TRANS #1 4280 REPL AIR COMPRESSOR	35300 - Station Equipment	11/01/2019	2,802
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	T0215856	MEMPHIS NW JOURNAL T0200690 TO HERE	35300 - Station Equipment	01/01/2020	8,070

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	TS0221818	DIANA CB CB 12050 499821 CAPITAL PROJECT	35300 - Station Equipment	02/01/2020	106,452
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	TS0221898	WELSH CB CB-11670 CAPITAL PROJECT	35300 - Station Equipment	11/01/2019	880
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	TS0222165	TR080055863_WILKES STA INSTALL SDR	35300 - Station Equipment	03/01/2020	432
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	TS0222194	WELSH HVDC CONVERTER STA - INSTALL TUNING PACK	35300 - Station Equipment	01/01/2020	20,537
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	TS0222225	JERICHO C/O 9300 TO SEL 421	35316 - Station Equipment-SmartGrid	11/01/2019	39,325
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	TS0222372	MEMPHIS NW C/O 3G ROUTER WITH 4G LTE	35316 - Station Equipment-SmartGrid	11/01/2019	7,178
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	TS0222402	CHILDRESS WEST C/O FAILED CB 6480	35300 - Station Equipment	12/01/2019	54,300
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	B194TXSRE	B194TXSRE T/SW/Non-Specific Work Station	TS0222727	NORTH MINEOLA BATTERY BANK	35300 - Station Equipment	02/01/2020	14,815
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P15039001	P15039001 Center- Metering	42380362	CENTER-METERING	35300 - Station Equipment	12/01/2015	411
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P15039002	P15039002 Holly Meter	42380353	HOLLY METER	35300 - Station Equipment	12/01/2015	113
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P15039003	P15039003 T/SW/Shadow for P15039001	42380362SWP	CENTER-METERING	35300 - Station Equipment	12/01/2015	204
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P15039004	P15039004 T/SW/Shadow for P15039002	42380353SWP	HOLLY METER	35300 - Station Equipment	12/01/2015	58
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P15207001	P15207001 AECC Farmington- Add Scada	42494404	AECC FARMINGTON - ADD SCADA	35300 - Station Equipment	05/01/2016	674
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P15207502	P15207502 T/SW/Shadow for P15207001	42494404SWP	AECC FARMINGTON - ADD SCADA	35300 - Station Equipment	05/01/2016	346
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P17015001	P17015001 Avoca - Station	42681610	AVOCA 161KV SUBSTATION	35200 - Structures and Improvements	09/01/2017	2,762
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P17015001	P17015001 Avoca - Station	42681610	AVOCA 161KV SUBSTATION	35300 - Station Equipment	09/01/2017	89,253
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P17015001	P17015001 Avoca - Station	42681610	AVOCA 161KV SUBSTATION	35316 - Station Equipment-SmartGrid	09/01/2017	5,245
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	P17015002	P17015002 Shadow for P17015001	42681610SWP	AVOCA 161KV SUBSTATION	35200 - Structures and Improvements	09/01/2017	1,389
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P17015002	P17015002 Shadow for P17015001	42681610SWP	AVOCA 161KV SUBSTATION	35300 - Station Equipment	09/01/2017	44,901
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P17015002	P17015002 Shadow for P17015001	42681610SWP	AVOCA 161KV SUBSTATION	35316 - Station Equipment-SmartGrid	09/01/2017	2,639
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P18113001	P18113001 Arsenal Hill Bus Replacement	42876399	ARSENAL HILL BUS REPLACEMENT	35300 - Station Equipment	11/01/2018	216,198
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	P18113002	P18113002 Shadow for P18113001	42876399SWP	ARSENAL HILL BUS REPLACEMENT	35300 - Station Equipment	11/01/2018	111,005
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SEARA1702	SEARA1702 SWEPCO - AR - Storm Shadow - T	TL030527SWP	CHAMBERS SPRING FL STR 118 A1	35500 Poles and Fixtures	10/01/2017	12,250
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SEARA1801	SEARA1801 SWEPCO - AR - Storm Shadow	42839847SWP	04/14/18 STORM SWEPCO DIERKS-MENA UMPI (AR) MULT STRUCTURES	35500 - Poles and Fixtures	01/01/2019	53,912
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SEARA1804	SEARA1804 SWEPCO - AR - Storm Shadow	42925898SWP	2018 STORM PATTERSON-NW TEXARK 3 H STRUCTURES	35500 Poles and Fixtures	01/01/2019	27,855
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SEARS1702	SEARS1702 SWEPCO - AR - Storm - Transmis	TL030527	CHAMBERS SPRING FL STR 118 A1	35500 - Poles and Fixtures	10/01/2017	23,843
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SEARS1704	SEARS1704 SWEPCO AR - Storm - Transmis	TL031210	S FAYETTEV-SE FAYETT CP WO 1 CONDITIONS	35500 - Poles and Fixtures	11/01/2017	23,292
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SEARS1704	SEARS1704 SWEPCO - AR - Storm Transmis	TL031212	CHAMB SPRING-S FAYET CP WO 6 CONDITIONS	35500 - Poles and Fixtures	11/01/2017	75,501
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SEARS1801	SEARS1801 Storm SWEPCO-AR 4-14-18	42839847	04/14/18 STORM SWEPCO DIERKS-MENA UMPI (AR) MULT STRUCTURES	35500 - Poles and Fixtures	01/01/2019	105,826
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SEARS1804	SEARS1804 SWEPCO - AR - Storm	42925898	2018 STORM PATTERSON-NW TEXARK 3 H-STRUCTURES	35500 - Poles and Fixtures	01/01/2019	55,059
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SEARS5704	SEARS5704 Shadow for SEARS1704	TL031210SWP	S FAYETTEV-SE FAYETT CP WO 1 CONDITIONS	35500 - Poles and Fixtures	11/01/2017	11,967
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SEARS5704	SEARS5704 Shadow for SEARS1704	TL031212SWP	CHAMB SPRING-S FAYET CP WO 6 CONDITIONS	35500 - Poles and Fixtures	11/01/2017	38,788
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SELAA1602	SELAA1602 SWEPCO - LA - Storm Shadow - T	TL028164SWP	PERDUE NORTH MINEO CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2016	873
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SELAA1802	SELAA1802 SWEPCO - LA - Storm Shadow	42839848SWP	04/14/18 STORM SWEPCO HOSSTON-GODFREY STR 81	35500 - Poles and Fixtures	12/01/2018	26,742
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SELAS1802	SELAS1802 SWEPCO LA - Storm	42839848	04/14/18 STORM SWEPCO HOSSTON-GODFREY STR 81	35500 - Poles and Fixtures	12/01/2018	52,569
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1501	SETXA1501 T/SEP/TX/Assoc w/SETXS 00/00/0	42664029SWP	NW HENDERSON REPLACE FAILED CB 10930	35300 - Station Equipment	06/01/2017	15,525
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1503	SETXA1503 T/SEP/TX/Assoc w/SETXS 00/00/0	42487825SWP	GOLIATH STM WILKES - LONGWOOD 345 KV REPLACE STRUCTURE 97	35400 - Towers and Fixtures	07/01/2016	58,815
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1503	SETXA1503 T/SEP/TX/Assoc w/SETXS 00/00/0	42488298SWP	TLN194 00299 SHAMROCK-MAGIC CITY GOLIATH STORM (BOWERS)	35500 Poles and Fixtures	08/01/2017	6,834
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1503	SETXA1503 T/SEP/TX/Assoc w/SETXS 00/00/0	42488326SWP	TLN192 00045 WEST CHILDRESS-ESTELLINE STORM GOLIATH SWEPCO	35500 - Poles and Fixtures	12/01/2016	45,901
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1503	SETXA1503 T/SEP/TX/Assoc w/SETXS 00/00/0	42488342SWP	TLN194 00296 SHAMROCK-NICHOLS (KIRBY) GOLIATH STORM	35500 - Poles and Fixtures	02/01/2017	30,896
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1703	SETXA1703 SWEPCO - TX - Storm Shadow - T	42718948SWP	STORM 05/28/17 KNOX LEE - HARRISON 138KV	35500 - Poles and Fixtures	09/01/2017	45,682
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1801	SETXA1801 SWEPCO - TX - Storm Shadow	TL032088SWP	IPC DOMINO WEST AT CP WO 3 CONDITIONS	35500 - Poles and Fixtures	08/01/2018	11,854
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1802	SETXA1802 SWEPCO TX - Storm Shadow	42832583SWP	2018 STORM EASTEX SWITCHING-HARRISON RD 138KV LINE	35500 - Poles and Fixtures	03/01/2020	113,873
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1802	SETXA1802 SWEPCO - TX Storm Shadow	TL032491SWP	DIANA-SW SHRPRT (TX) CP WO 1 CONDITIONS	35600 Overhead Conductors, Device	08/01/2018	21,388
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1803	SETXA1803 SWEPCO - TX - Storm Shadow - T	TL033141SWP	HAWKINS - MINEOLA CP A-1 STR 80 & 81	35500 - Poles and Fixtures	09/01/2018	19,908
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1804	SETXA1804 SWEPCO - TX - Storm Shadow - T	42839567SWP	04/14/18 SWEPCO STORM IPC JEFFERSON-LIEBERMAN BROKEN ST 207	35500 - Poles and Fixtures	09/01/2018	6,032
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1804	SETXA1804 SWEPCO - TX - Storm Shadow - T	42839801SWP	04/14/18 STORM SWEPCO KNOX LEE-NW HEND-OAK HILL STR 140,144	35500 - Poles and Fixtures	09/01/2018	11,370
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1804	SETXA1804 SWEPCO - TX Storm Shadow - T	42839844SWP	04/14/18 STORM SWEPCO PIRKEY-SCOTTSVILLE ST 27	35500 - Poles and Fixtures	09/01/2018	5,358
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1804	SETXA1804 SWEPCO - TX - Storm Shadow - T	42839845SWP	04/14/18 STORM SWEPCO DIANA-PLILER MULTIPLE STRUCTURES	35500 - Poles and Fixtures	09/01/2018	22,123
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1804	SETXA1804 SWEPCO - TX Storm Shadow - T	42839846SWP	04/14/18 STORM SWEPCO KILGORE-OVERTON REPL STR 83, 84	35500 - Poles and Fixtures	09/01/2018	7,194
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1804	SETXA1804 SWEPCO - TX - Storm Shadow - T	42839849SWP	04/14/18 STORM SWEPCO MINEOLA GRAND SALINE STR 43	35500 - Poles and Fixtures	09/01/2018	20,086
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1901	SETXA1901 SWEPCO - TX - Storm Shadow	TL035303SWP	TEXAS EASTERN TAP A-1 BROKE POLE	35500 - Poles and Fixtures	09/01/2019	7,351
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXA1902	SETXA1902 SWEPCO - TX - Storm Shadow	42983635SWP	2019 STORM 05/09/19 LONGVIEW HEIGHTS-LAKE LAMOND 7 STR	35500 - Poles and Fixtures	09/01/2019	57,797
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1501	SETXS1501 T/SEP/TX/Maj Min Storm 00/00/0	42664029	NW HENDERSON REPLACE FAILED CB 10930	35300 - Station Equipment	06/01/2017	30,218
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1503	SETXS1503 T/SEP/TX/Maj Min Storm 00/00/0	42487825	GOLIATH STM WILKES - LONGWOOD 345 KV REPLACE STRUCTURE 97	35400 - Towers and Fixtures	07/01/2016	115,593
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1503	SETXS1503 T/SEP/TX/Maj Min Storm 00/00/0	42488298	TLN194 00299 SHAMROCK-MAGIC CITY GOLIATH STORM (BOWERS)	35500 - Poles and Fixtures	08/01/2017	16,030
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1503	SETXS1503 T/SEP/TX/Maj Min Storm 00/00/0	42488326	TLN192 00045 WEST CHILDRESS-ESTELLINE STORM GOLIATH SWEPCO	35500 - Poles and Fixtures	12/01/2016	90,641
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1503	SETXS1503 T/SEP/TX/Maj Min Storm 00/00/0	42488342	TLN194 00296 SHAMROCK-NICHOLS (KIRBY) GOLIATH STORM	35500 - Poles and Fixtures	02/01/2017	60,616
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1602	SETXS1602 SWEPCO - TX - Storm - Transmis	TL028164	PERDUE - NORTH MINEO CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2016	1,700
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1703	SETXS1703 SWEPCO - TX - Storm - Transmis	42718948	STORM 05/28/17 KNOX LEE - HARRISON 138KV	35500 - Poles and Fixtures	09/01/2017	88,961
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1801	SETXS1801 SWEPCO - TX - Storm - Transmis	TL032088	IPC DOMINO - WEST AT CP WO 3 CONDITIONS	35500 - Poles and Fixtures	08/01/2018	24,019
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1802	SETXS1802 SWEPCO - TX Storm - Transmis	42832583	2018 STORM EASTEX SWITCHING-HARRISON RD 138KV LINE	35500 - Poles and Fixtures	03/01/2020	222,270
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1802	SETXS1802 SWEPCO TX Storm Transmis	TL032491	DIANA-SW SHRPRT (TX) CP WO 1 CONDITIONS	35600 - Overhead Conductors, Device	08/01/2018	42,390
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1803	SETXS1803 SWEPCO - TX - Storm - Transmis	TL033141	HAWKINS - MINEOLA CP A-1 STR 80 & 81	35500 - Poles and Fixtures	09/01/2018	39,320
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1804	SETXS1804 SWEPCO - TX Storm - Transmis	42839567	04/14/18 SWEPCO STORM IPC JEFFERSON LIEBERMAN BROKEN ST 207	35500 - Poles and Fixtures	09/01/2018	11,986
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1804	SETXS1804 SWEPCO - TX - Storm Transmis	42839801	04/14/18 STORM SWEPCO KNOX LEE NW HEND-OAK HILL STR 140,144	35500 - Poles and Fixtures	09/01/2018	22,437
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SETXS1804	SETXS1804 SWEPCO - TX - Storm - Transmis	42839844	04/14/18 STORM SWEPCO PIRKEY-SCOTTSVILLE ST 27	35500 - Poles and Fixtures	09/01/2018	10,707
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1804	SETXS1804 SWEPCO - TX - Storm - Transmis	42839845	04/14/18 STORM SWEPCO DIANA-PLILER MULTIPLE STRUCTURES	35500 - Poles and Fixtures	09/01/2018	43,624
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SETXS1804	SETXS1804 SWEPCO - TX - Storm - Transmis	42839846	04/14/18 STORM SWEPCO KILGORE-OVERTON REPL STR 83, 84	35500 - Poles and Fixtures	09/01/2018	14,029
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1804	SETXS1804 SWEPCO - TX Storm Transmis	42839849	04/14/18 STORM SWEPCO MINEOLA GRAND SALINE STR 43	35500 - Poles and Fixtures	09/01/2018	39,159
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1901	SETXS1901 SWEPCO - TX - Storm - Transmis	TL035303	TEXAS EASTERN TAP A-1 BROKE POLE	35500 - Poles and Fixtures	09/01/2019	14,527

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SETXS1902	SETXS1902 SWEPCO - TX - Storm - Transmis	42983635	2019 STORM 05/09/19 LONGVIEW HEIGHTS-LAKE LAMOND 7 STR	35500 - Poles and Fixtures	09/01/2019	113,457
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	42539020SWP	TAYLOR ST - BANN 69KV INSTALL POLE FOR DISTRIBUTION	35500 - Poles and Fixtures	07/01/2016	4,582
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP Tx ASSOC W/SI194ARLR	42552460SWP	DYESS - EAST ROGERS LINE 189 2 REPLACE POLES & CROSS ARMS	35500 - Poles and Fixtures	12/01/2016	205,243
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	42571430SWP	SILOAM SPRINGS - PRAIRIE GROVE REPL ROTTEN POLES & ARMS	35500 - Poles and Fixtures	10/01/2016	52,051
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	42579933SWP	DIERKS - MENA REPLACE FAILED CROSS ARM	35500 - Poles and Fixtures	08/01/2016	1,419
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	42586154SWP	PATTERSON - N NEW BOSTON REPLACE STRUCTURE 41	35500 - Poles and Fixtures	09/01/2016	5,149
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	42588776SWP	PATTERSON - S NASHVILLE REPL POLES, ARMS, & INSULATORS	35500 - Poles and Fixtures	12/01/2016	135,951
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL028254SWP	DYESS-SPRINGDALE S	35500 - Poles and Fixtures	07/01/2016	2,956
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL028409SWP	FLINT CREEK - SILOAM #1 POLE A-1	35500 - Poles and Fixtures	07/01/2016	2,740
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL028530SWP	GREENLAND - VBI NORT CP WO 1 CONDITIONS	35500 - Poles and Fixtures	08/01/2016	13,934
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL028706SWP	GREENLAND-S FAYETTE #60C ROTTEN XARM	35500 - Poles and Fixtures	12/01/2016	5,803
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL028764SWP	DEQUEEN - MENA 104 STRUCTURE	35500 - Poles and Fixtures	09/01/2016	26,118
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL028765SWP	N HUNTINGTON-WALDRON # 31,127&130 WEST	35500 - Poles and Fixtures	09/01/2016	5,839
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL028778SWP	EAST ROGERS - BEAVER # 31 A-1	35500 - Poles and Fixtures	12/01/2016	5,354
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL028883SWP	HYLAND - SOUTHEAST FAY 59,60&61 POLES	35500 - Poles and Fixtures	09/01/2017	9,618
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL028953SWP	GREENLAND-S FAYETTEV POLES AND ARMS	35500 - Poles and Fixtures	12/01/2016	84,275
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL029017SWP	EAST ROGERS - BEAVER 8 CONDITIONS	35500 Poles and Fixtures	06/01/2017	72,839
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL029020SWP	GREENLAND - PRAIRIE 10 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	39,019
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL029178SWP	DEQUEEN - MENA CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	422
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL029179SWP	BOONEVILLE - BRANCH(CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2016	2,789
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP Tx ASSOC W/SI194ARLR	TL029353SWP	GREENLAND - VBI NORT # 131 ARM	35500 - Poles and Fixtures	10/01/2017	2,423
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111ARLR	SI111ARLR TB/SEP-Tx ASSOC W/SI194ARLR	TL029402SWP	GREENLAND-S FAYETTEV S DBL CIRCUIT STRUCTURES OUT OF GREENLA	35500 - Poles and Fixtures	06/01/2017	118,342
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP Tx ASSOC W/SI194LALR	42549984SWP	FORT HUMBUG - SOUTH STR 17 REFER TO W/O TL026664	35500 - Poles and Fixtures	09/01/2018	4,229
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	42551330SWP	MANY - NOBLE 69 KV REPLACE CROSS ARMS ON VARIOUS STRUCTURES	35500 - Poles and Fixtures	09/01/2016	103,353
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	42565246SWP	MANY - BELMONT REPLACE INSULATORS ON STRUCTURE 10	35600 - Overhead Conductors, Device	08/01/2016	1,750
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	42571424SWP	RED POINT - BELLEVUE REPL CROSS ARMS ON VARIOUS STRUCTURES	35500 - Poles and Fixtures	12/01/2016	53,903
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	42571424SWP	RED POINT - BELLEVUE REPL CROSS ARMS ON VARIOUS STRUCTURES	35600 - Overhead Conductors, Device	12/01/2016	13,476
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	42586136SWP	HOSSTON - BLOOMBURG REPLACE ARMS & INSULATORS	35500 - Poles and Fixtures	12/01/2016	153,239
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	42586136SWP	HOSSTON - BLOOMBURG REPLACE ARMS & INSULATORS	35600 - Overhead Conductors, Device	12/01/2016	19,834
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL016992SWP	BLANCHARD-N MARKET C/O BROKEN ARM	35500 - Poles and Fixtures	08/01/2011	(20)
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028183SWP	ROBSON ROAD(POD-KING	35400 - Towers and Fixtures	07/01/2016	34,610
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028391SWP	FLOURNOY - SUMMER # 40 CROSS ARMS A-1	35500 - Poles and Fixtures	07/01/2016	874
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028443SWP	ELLERBE ROAD - FERN # 9 A-1 ARM	35500 - Poles and Fixtures	07/01/2016	1,508
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028444SWP	ELLERBE RD - FERN # 25-27 POLES	35500 - Poles and Fixtures	08/01/2016	46,836
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028478SWP	MANY - NEGREET CROSS ARMS	35500 - Poles and Fixtures	09/01/2016	19,745
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028506SWP	BLANCHARD - NORTH MA #12 A-1	35500 - Poles and Fixtures	07/01/2016	3,376
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028507SWP	LIEBERMAN - RED POIN # 130 A-1	35500 - Poles and Fixtures	07/01/2016	3,584
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028508SWP	RED POINT - BELLEVUE # 11 A-1	35500 - Poles and Fixtures	07/01/2016	3,316
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028538SWP	BRONLEE RD-MINDEN RD # 38 A-1	35500 Poles and Fixtures	07/01/2016	1,366
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028649SWP	BLANCHARD - LIEBERMAN # 77 BRK ARM	35500 - Poles and Fixtures	08/01/2016	807
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028693SWP	LOGANSPORT - STANLEY # 26 POLE	35500 - Poles and Fixtures	09/01/2017	881
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028845SWP	E LEESVILLE - HICKS CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2016	1,722
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028863SWP	FINNEY TAP # 66 & 67 POLE REPLACEMENT	35500 - Poles and Fixtures	10/01/2016	7,885
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL028999SWP	ELLBERTE ROAD - FERN # 39 BROKEN AT TOP A-1	35500 - Poles and Fixtures	09/01/2017	11,213
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL029032SWP	BLANCHARD NORTH MA CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2017	922
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL029053SWP	FLOURNOY - SUMMER GROVE (18) WISHBONE ARMS	35500 - Poles and Fixtures	09/01/2017	83,422
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP Tx ASSOC W/SI194LALR	TL029054SWP	SOUTHWEST SHREVEP-WE # 2	35500 - Poles and Fixtures	06/01/2017	7,241
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP-Tx ASSOC W/SI194LALR	TL029428SWP	LONGWOOD - EL DORADO CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	21,454
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111LALR	SI111LALR TB/SI/SEP Tx ASSOC W/SI194LALR	TL029511SWP	LOGANSPORT - STONEWALL A-1 ANCHORS 17 DEG	35500 - Poles and Fixtures	06/01/2017	41,031
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111OKRE	SI111OKRE TB/SEP-Tx ASSOC W/SI194OKRE	T0124080SWP	CLARKSVILLE 345KV (SWEPCO) RTU REMOTE TERMINAL UNIT RTU_100	35300 - Station Equipment	08/01/2017	10,045
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP Tx ASSOC W/SI194TXLR	42527989SWP	2016 EM/ SHAMROCK - MAGIC CITY 69KV TLN 00200 (FIRE)	35500 - Poles and Fixtures	09/01/2016	15,221
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	42559018SWP	S E LONGVIEW - LAKE LAMOND REPLACE BAD POLES & ARMS	35500 - Poles and Fixtures	09/01/2016	56,486
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	42576669SWP	HAWKINS - MINEOLA 69KV REPLACE POLES & ARMS	35500 - Poles and Fixtures	12/01/2016	35,905
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	42576686SWP	PITTSBURG - WINNSBORO 69KV REPLACE POLES & ARMS	35500 - Poles and Fixtures	12/01/2016	11,583
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	42585366SWP	WINFIELD - WINNSBORO REPLACE 3 STRUCTURES	35500 - Poles and Fixtures	09/01/2016	12,382
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	42586632SWP	MT PLEASANT - DAINGERFIELD REPL POLES, ARMS, & INSULATORS	35500 - Poles and Fixtures	12/01/2016	19,996
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	42596063SWP	KILGORE - OVERTON REPLACE STRUCTURES	35500 - Poles and Fixtures	07/01/2017	42,351
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	42616525SWP	2016 NSW JEFFERSON-N MARSHALL C/O VARIOUS BAD A2 STRUCTURES	35500 - Poles and Fixtures	04/01/2017	121,808
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	42616553SWP	2016 NSW GRAND SALINE - QUITMAN REPL STR 260 SEPTL214B	35500 - Poles and Fixtures	12/01/2016	4,486
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	42625768SWP	HUGHES SPRINGS LONE STAR STEEL 69KV REPLACE BROKEN XARM	35500 - Poles and Fixtures	08/01/2017	311
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	42647326SWP	2017 NSW CP MEMPHIS - ESTELLINE 69KV TLN00045	35500 - Poles and Fixtures	06/01/2017	75,087
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	42647352SWP	2014 LONE STAR STEEL TAP SEPTL216D TRAILING INVOICES	35500 - Poles and Fixtures	08/01/2017	9,017
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL027447SWP	LONGVIEW HEIGHTS - M OROW HAXARD - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	1,502
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL027582SWP	PILGRIM'S PRIDE - WINFIELD	35500 - Poles and Fixtures	07/01/2016	2,500
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL027939SWP	CLARENDON - JERICHO CP WO 2 CONDITIONS TLN00047	35500 - Poles and Fixtures	09/01/2016	(2,352)
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL027983SWP	JEFFERSON - SUPERIO2 R/W OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	628
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028011SWP	PIRKEY - SCOTTSVILLE R/W OROW HAZARD TREE	35600 - Overhead Conductors, Device	07/01/2016	1,091
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028103SWP	NORTH NEW BOSTON - WILES OROW HAZARD TREE - VICKER	35600 - Overhead Conductors, Device	08/01/2016	764
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028105SWP	JEFFERSON SWITCHING1 R/W OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	733
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028313SWP	KNOX LEE-SE LONGVIEW OROW HAZARD TREE - BIDDY	35600 - Overhead Conductors, Device	08/01/2016	478
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028394SWP	GILMER - PERDUE #149 A-1 POLE	35500 - Poles and Fixtures	07/01/2016	1,761

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028595SWP	W CHILDRESS-ESTELLIN CP WO 1 CONDITIONS TLN00045	35500 - Poles and Fixtures	12/01/2016	673
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028651SWP	DIANA - PILLER ROAD OROW HAZARD TREE PROGRAM - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	580
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028660SWP	MT PLEASANT - NEW B R/W OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	879
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028747SWP	WEST ATLANTA - WILKE OROW HAZARD - PILKINGTON	35600 - Overhead Conductors, Device	10/01/2016	586
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028748SWP	KILGORE OVERTON HAZARD OROW - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	1,205
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028784SWP	KNOX LEE - ROCK HILL #80A A-1	35500 - Poles and Fixtures	10/01/2016	3,609
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028815SWP	W CHILDRESS-ESTELLIN CP WO 19 CONDITIONS TLN00045	35500 - Poles and Fixtures	12/01/2016	42,800
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL028887SWP	JPC DOMINO - WEST ATL # 272 A-1	35500 - Poles and Fixtures	10/01/2016	3,487
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL029023SWP	KNOX LEE - SOUTH TEX CP WO 2 CONDITIONS	35500 - Poles and Fixtures	12/01/2016	4,127
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL029049SWP	PIRKEY - SCOTTSVILLE CP WO 8 CONDITIONS	35500 - Poles and Fixtures	12/01/2016	26,989
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL029192SWP	JEFFERSON NORTH MA OROW HAZARD TREE	35600 - Overhead Conductors, Device	02/01/2017	1,129
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP Tx ASSOC W/SI194TXLR	TL029193SWP	HUGHES SPRING - LIND OROW HAZRD TREE	35600 - Overhead Conductors, Device	02/01/2017	1,175
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL029213SWP	JEFFERSON SWITCHING1 OROW HAZARD TREE - VICKERS	35600 - Overhead Conductors, Device	04/01/2017	893
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL029328SWP	ESTELLINE - MEMPHIS CP WO 6 CONDITIONS TLN00053	35500 - Poles and Fixtures	04/01/2017	10,942
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL029400SWP	LNGWD-SCOTTSVILL(TX) # 144 POLE	35500 - Poles and Fixtures	06/01/2017	5,040
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL029406SWP	ESTELLINE - MEMPHIS CP WO 5 CONDITIONS TLN00045	35500 Poles and Fixtures	04/01/2017	15,093
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL029484SWP	GILMER - PERDUE R/W OROW HAZARD TREE - BIDDY	35600 - Overhead Conductors, Device	05/01/2017	923
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI111TXLR	SI111TXLR TB/SI/SEP-Tx ASSOC W/SI194TXLR	TL029510SWP	WINNSBORO-NO MINEOLA A-1 ANCHORS 15 DEG	35500 - Poles and Fixtures	06/01/2017	24,690
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR LINE REHAB	42539020	TAYLOR ST - BANN 69KV INSTALL POLE FOR DISTRIBUTION	35500 - Poles and Fixtures	07/01/2016	9,059
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	42552460	DYESS - EAST ROGERS LINE 189 2 REPLACE POLES & CROSS ARMS	35500 - Poles and Fixtures	12/01/2016	399,627
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	42571430	SILOAM SPRINGS - PRAIRIE GROVE REPL ROTTEN POLES & ARMS	35500 - Poles and Fixtures	10/01/2016	101,341
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	42579933	DIERKS - MENA REPLACE FAILED CROSS ARM	35500 - Poles and Fixtures	08/01/2016	2,859
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	42586154	PATTERSON - N NEW BOSTON REPLACE STRUCTURE 41	35500 - Poles and Fixtures	09/01/2016	10,270
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	42588776	PATTERSON - S NASHVILLE REPL POLES, ARMS, & INSULATORS	35500 - Poles and Fixtures	12/01/2016	265,553
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL028254	DYESS-SPRINGDALE S	35500 - Poles and Fixtures	07/01/2016	5,786
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL028409	FLINT CREEK - SILOAM #1 POLE A-1	35500 - Poles and Fixtures	07/01/2016	5 402
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL028530	GREENLAND - VBI NORT CP WO 1 CONDITIONS	35500 - Poles and Fixtures	08/01/2016	27,161
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL028706	GREENLAND-S FAYETTE #60C ROTTEN XARM	35500 - Poles and Fixtures	12/01/2016	11,295
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL028764	DEQUEEN - MENA 104 STRUCTURE	35500 - Poles and Fixtures	09/01/2016	50,852
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL028765	N HUNTINGTON-WALDRON # 31,127&130 WEST	35500 - Poles and Fixtures	09/01/2016	11,381
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL028778	EAST ROGERS - BEAVER # 31 A-1	35500 - Poles and Fixtures	12/01/2016	10,476
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR LINE REHAB	TL028883	HYLAND - SOUTHEAST FAY 59,60&61 POLES	35500 - Poles and Fixtures	09/01/2017	18,930
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL028953	GREENLAND-S FAYETTEV POLES AND ARMS	35500 - Poles and Fixtures	12/01/2016	164,285
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL029017	EAST ROGERS - BEAVER 8 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	143,682
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL029020	GREENLAND - PRAIRIE 10 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	76,836
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL029178	DEQUEEN - MENA CP WO 1 CONDITIONS	35500 - Poles and Fixtures	10/01/2017	908
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL029179	BOONEVILLE - BRANCH(CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2016	5,926
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL029353	GREENLAND - VBI NORT # 131 ARM	35500 Poles and Fixtures	10/01/2017	4,777
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARLR	SI194ARLR TB/SI/SEP/AR - LINE REHAB	TL029402	GREENLAND-S FAYETTEV 5 DBL CIRCUIT STRUCTURES OUT OF GREENLA	35500 - Poles and Fixtures	06/01/2017	231,477
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	42347751	CHAMBERS SPRING-TONTITOWN SPECIAL PERMITTING	35010 - Land Rights	10/01/2016	8,051
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	42413705	CONTINUE TONTITOWN 161KV CAPACITOR INSTALL T0127459	35300 - Station Equipment	09/01/2016	124,568
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	42417203	ARMY CORPS OF ENGINEERS NEW TERM EASEMENT	35010 - Land Rights	10/01/2016	11,061
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0084007	WEST BOONEVILLE CB 9380 - REPLACE 3 FAILING 69KV SURGE ARRES	35300 - Station Equipment	11/01/2008	(127)
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0149602	PRAIRIE GROVE CB GREENLAND 3820 REPLACE FAILED CABLE	35300 - Station Equipment	08/01/2016	10,527
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0149773	MENA TRF P145 2 REPLACE FAILED FANS	35300 - Station Equipment	11/01/2016	2,652
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0150240	SOUTH FAYETTEVILLE REPLACE FAILED METERS ON TRANSFORMERS	35300 - Station Equipment	07/01/2016	4,657
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0150362	SILOAM SPRINGS 161KV CCVT REPLACE CCVT AND LINE TUNER	35300 - Station Equipment	07/01/2016	15,328
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0151049	POTTER SUB (POD) BCHGR BATTERY CHARGER STA_1 POTTER_SUB_BCHR	35300 - Station Equipment	11/01/2016	1,536
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0151156	OKAY CAPITAL PROJECT - REPLACE ARRESTERS ON 69KV CCVT	35300 - Station Equipment	03/01/2017	3,097
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0152501	TURK TRF AUTO #2 138/115 KV P141 2 DS84570 CAPITAL PROJECT	35300 - Station Equipment	11/01/2016	2,109
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0152698	SOUTHEAST TEXARKANA CAP PROJ -REPL COMPRESSOR CB4720	35300 - Station Equipment	11/01/2016	711
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0152707	NORTH MAGAZINE PT CSIT12035635 - REPLACE FAILED PT WITH CCVT	35300 - Station Equipment	11/01/2016	5,149
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0152823	TEXARKANA PLANT CB 12TH ST 4720 137Y4119 CAPITAL PROJECT	35300 - Station Equipment	11/01/2016	1,737
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0153230	SOUTH FAYETTEVILLE TRF P161 31 REPLACE FAILED 69 KV PT	35300 - Station Equipment	11/01/2016	4,757
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0153581	TURK DFR FAULT RECORDER DFR_1003240251 CAPITAL PROJECT	35300 - Station Equipment	09/01/2017	12,210
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0153868	FLINT CREEK SUB TRF P345 43 REPLACE 345KV SWITCH 11123	35300 - Station Equipment	09/01/2018	27,258
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0154121	EUREKA SPRINGS 161KV - REPLACE FAILED CCVT	35300 - Station Equipment	11/01/2016	8,458
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0154124	DEQUEEN CB MENA 3610 13014 CAPITAL PROJECT	35300 - Station Equipment	12/01/2016	15,253
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0163698	EUREKA SPRINGS 161KV STA EUREKA SPRINGS 161KV CAPITAL PROJE	35300 - Station Equipment	07/01/2016	404
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0163848	TURK TRF P345 51 TB80068412 CAPITAL PROJECT	35300 - Station Equipment	06/01/2018	249,959
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0163977	SOUTHEAST TEXARKANA TRF P145 1 3 70704A CAPITAL PROJECT	35300 - Station Equipment	02/01/2017	4,572
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0165957	OKAY FR N/A DFR_1003709055 CAPITAL PROJECT-SEL 1102 SDR	35300 - Station Equipment	07/01/2018	12,027
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0166269	NASHVILLE 69KV TCC 69 [CB] DEQUEEN 3050 CAPITAL PROJECT	35300 - Station Equipment	02/01/2017	1,768
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0166343	EAST ROGERS REPLACE STATION BATTERY	35300 - Station Equipment	07/01/2016	13,221
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0166788	FLINT CREEK SUB TRF P345 43 WEST REPLACE SURGE ARRESTERS	35300 - Station Equipment	10/01/2018	15,403
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0166789	FLINT CREEK SUB TRF P345 50 EAST REPLACE SURGE ARRESTERS	35300 - Station Equipment	01/01/2018	21,862
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0175506	EAST ROGERS CAP BANK - REPLACE CAPACITOR AND LIMITERS	35300 - Station Equipment	07/01/2016	3,643
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0175831	DEQUEEN STA DEQUEEN CAPITAL PROJECT	35300 - Station Equipment	01/01/2019	9,436
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0176402	WEST BOONEVILLE STA - REPLACE TRANSFER SWITCH	35300 - Station Equipment	06/01/2016	0
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0176865	NASHVILLE 69KV CAPB 69KV CAP BANK 10810 40828 CAPITAL PROJEC	35300 - Station Equipment	12/01/2016	12,697
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0177120	FLINT CREEK SUB STATION - REPLACE TRANSFER SWITCH	35300 - Station Equipment	08/01/2016	4,613

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0177295	SOUTH DIERKS TRF P141 17 C0229752CAPITAL PROJECT/FANS&ASSEC	35300 - Station Equipment	12/01/2016	4,399
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0177384	REA - ELM SPRINGS DYESS 10457 REPLACE FAILED SF6 INTERUPTERS	35300 - Station Equipment	07/01/2019	33,232
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0177502	SOUTH FAYETTEVILLE CAP BANK REPLACE LIMITERS & CAPACITORS	35300 - Station Equipment	12/01/2016	9,140
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0177508	DEQUEEN STA DEQUEEN CAPITAL PROJECT	35300 - Station Equipment	12/01/2016	2,200
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0177511	PATTERSON STA CAPITAL PROJECT/FANS&ACCESSORIES	35300 - Station Equipment	12/01/2016	1,571
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0177574	EAST ROGERS TRF P161 22 REPLACE 6 COOLING FANS	35300 - Station Equipment	11/01/2017	4,699
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0177590	SUGAR HILL (SW) STA CAPITAL PROJECT/2 TON BARD 208/230V	35300 - Station Equipment	01/01/2017	4,529
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0177860	EUREKA SPRINGS 161KV STA REPLACE FAILED INTERCONNECT METERS	35300 - Station Equipment	06/01/2017	28,355
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0177909	SOUTH SPRINGDALE RTU REPLACE WITH COOPER SG4250	35300 - Station Equipment	10/01/2017	71,086
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0178095	TWELFTH STREET (SW) STA CAPITAL PROJECT/FUTURA METERS	35300 - Station Equipment	02/01/2017	6,366
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0178206	NORTH HUNTINGTON STA REPLACE AC UNIT	35300 Station Equipment	09/01/2016	7,626
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0178808	PATTERSON STA CAPITAL PROJECT/ETHERNET SWITCH	35300 - Station Equipment	02/01/2017	3,652
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0178912	PATTERSON STA PATTERSON CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	6,277
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194ARRE	SI194ARRE TBSISEP-NT ARK SYS REHAB	T0178975	TURK TRF P345 51 TB80068412 CAPITAL PROJECT	35300 - Station Equipment	10/01/2018	480
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	42549984	FORT HUMBUG - SOUTH STR 17 REFER TO W/O TL026664	35500 - Poles and Fixtures	09/01/2018	8,184
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	42551330	MANY - NOBLE 69 KV REPLACE CROSS ARMS ON VARIOUS STRUCTURES	35500 - Poles and Fixtures	09/01/2016	201,453
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	42565246	MANY - BELMONT REPLACE INSULATORS ON STRUCTURE 10	35600 - Overhead Conductors, Device	08/01/2016	3,407
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	42571424	RED POINT - BELLEVUE REPL CROSS ARMS ON VARIOUS STRUCTURES	35500 - Poles and Fixtures	12/01/2016	104,967
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	42571424	RED POINT BELLEVUE REPL CROSS ARMS ON VARIOUS STRUCTURES	35600 - Overhead Conductors, Device	12/01/2016	26,242
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	42586136	HOSSTON - BLOOMBURG REPLACE ARMS & INSULATORS	35500 - Poles and Fixtures	12/01/2016	298,617
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	42586136	HOSSTON - BLOOMBURG REPLACE ARMS & INSULATORS	35600 - Overhead Conductors, Device	12/01/2016	38,650
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA LINE REHAB	TL028183	ROBSON ROAD(POD-KING	35400 - Towers and Fixtures	07/01/2016	67,422
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028391	FLOURNOY - SUMMER # 40 CROSS ARMS A-1	35500 - Poles and Fixtures	07/01/2016	1,836
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028443	ELLERBE ROAD - FERN # 9 A-1 ARM	35500 - Poles and Fixtures	07/01/2016	2,988
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028444	ELLERBE RD - FERN # 25-27 POLES	35500 - Poles and Fixtures	08/01/2016	91,178
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028478	MANY - NEGREET CROSS ARMS	35500 - Poles and Fixtures	09/01/2016	38,431
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA LINE REHAB	TL028506	BLANCHARD NORTH MA #12 A-1	35500 - Poles and Fixtures	07/01/2016	6,611
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028507	LIEBERMAN - RED POIN # 130 A-1	35500 - Poles and Fixtures	07/01/2016	7,041
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028508	RED POINT - BELLEVUE # 11 A-1	35500 - Poles and Fixtures	07/01/2016	6,507
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028538	BRONLEE RD-MINDEN RD # 38 A-1	35500 - Poles and Fixtures	07/01/2016	2,702
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028649	BLANCHARD - LIEBERMAN # 77 BRK ARM	35500 - Poles and Fixtures	08/01/2016	1,625
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028693	LOGANSPORT - STANLEY # 26 POLE	35500 - Poles and Fixtures	09/01/2017	1,731
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028845	E LEESVILLE HICKS CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2016	3,351
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028863	FINNEY TAP # 66 & 67 POLE REPLACEMENT	35500 - Poles and Fixtures	10/01/2016	16,022
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL028995	ELLBERTE ROAD - FERN # 39 BROKEN AT TOP A-1	35500 - Poles and Fixtures	09/01/2017	22,207
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL029032	BLANCHARD - NORTH MA CP WO 1 CONDITIONS	35500 - Poles and Fixtures	12/01/2017	1,893
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL029053	FLOURNOY - SUMMER GROVE (18) WISHBONE ARMS	35500 - Poles and Fixtures	09/01/2017	162,690
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL029054	SOUTHWEST SHREVEP-WE # 2	35500 - Poles and Fixtures	06/01/2017	14,157
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL029428	LONGWOOD - EL DORADO CP WO 1 CONDITIONS	35500 - Poles and Fixtures	06/01/2017	43,034
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LALR	SI194LALR TB/SI/SEP/LA - LINE REHAB	TL029511	LOGANSPORT - STONEWALL A-1 ANCHORS 17 DEG	35500 - Poles and Fixtures	06/01/2017	81,298
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	42396695	BLANCHARD NTEC 12 KV SUB - REPLACE METER	35300 - Station Equipment	04/01/2018	1,374
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	42669575	CAMPTI METERING POINT INSTALL TRILLIANT 2G PHONES	35300 - Station Equipment	08/01/2017	995
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	42683413	STANLEY NTEC REPLACE FAILED METER	35300 - Station Equipment	04/01/2018	1,813
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0118446	CEDAR GROVE (SW) PT CAP BNK REP CAPACITORS	35300 - Station Equipment	04/01/2018	(1,396)
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0149849	LONGWOOD (SW) REPLACE 3 CCVTS - FLOURNOY CIRCUIT	35300 - Station Equipment	03/01/2017	31,380
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0150629	LIEBERMAN CB SUPERIOR 4380 499864 CAPITAL PROJECT	35300 Station Equipment	03/01/2017	1,097
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0150949	STONEWALL CB WESTERN ELE/SW SHREV 5590 SURGE ARRESTERS	35300 - Station Equipment	03/01/2017	14,799
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0151125	LONGWOOD (SW) REPL ANNUNCIATOR RELAYS & RADIATOR BRACKETS	35300 Station Equipment	03/01/2017	16,010
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0152694	FORT HUMBUG CB TRICHEL/ARSENAL HILL 290 510292 CAPITAL PROJE	35300 - Station Equipment	09/01/2017	10,211
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0153008	ARSENAL HILL CB HUMBUG/SOUTH AUTO 7500 21731 CAPITAL PROJECT	35300 - Station Equipment	09/01/2017	25,651
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0153158	SOUTH SHREVEPORT CB 7260 REPL FAILED SURGE ARRESTERS	35300 - Station Equipment	09/01/2017	4,976
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0153693	STONEWALL CB WESTERN ELE/SW SHREV 5590 H145A2777201 CAPITAL	35300 - Station Equipment	09/01/2017	22,186
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0153694	SOUTHWEST SHREVEPORT CB E AUTO/W ELEC/STWALL 11620 380263 CA	35300 - Station Equipment	09/01/2017	23,884
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0155138	LIEBERMAN - REPLACE FAILED 138 KV SWITCH 3015	35300 - Station Equipment	09/01/2016	23,858
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0165696	FORT HUMBUG STA FORT HUMBUG CAPITAL PROJECT/BATT&CHG	35300 - Station Equipment	08/01/2016	10,710
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0170151	ARSENAL HILL STA ARSENAL HILL CAPITAL PROJECT	35300 - Station Equipment	07/01/2017	2,739
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP NT LA SYS REHAB	T0171367	SUPERIOR (SW) STA SUPERIOR (SW) CAPITAL PROJECT	35300 - Station Equipment	11/01/2016	5,925
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0175440	SOUTHWEST SHREVEPORT CB E AUTO/DOLET HILLS 11610 0283A790220	35300 - Station Equipment	08/01/2016	212,841
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP NT LA SYS REHAB	T0175555	STONEWALL CAPITAL PROJECT RELAYS [CB] LOGANSPORT 5580	35300 - Station Equipment	08/01/2016	11,224
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0175586	SOUTHWEST SHREVEPORT STA SOUTHWEST SHREVEPORT CAPITAL PROJE	35300 - Station Equipment	08/01/2016	68,108
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0176333	SOUTHWEST SHREVEPORT STA SOUTHWEST SHREVEPORT CAPITAL PROJE	35300 - Station Equipment	10/01/2018	18,458
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0176462	SOUTH SHREVEPORT STA SOUTH SHREVEPORT CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	1,130
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0176784	BAYOU PIERRE STA BAYOU PIERRE CAPITAL PROJECT	35300 - Station Equipment	11/01/2016	11,396
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0176870	ELLERBE ROAD STA ELLERBE ROAD CAPITAL PROJECT	35300 - Station Equipment	11/01/2016	6,952
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0177155	LIEBERMAN STA CAPITAL PROJECT/REPLACE SWITCH 6363	35300 - Station Equipment	12/01/2016	9,304
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0177199	HAUGHTON STA CAPITAL PROJECT/CULVERTS	35300 - Station Equipment	01/01/2017	16,234
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0177889	ARSENAL HILL BAT MOBILE TRAILER BAT_11202008 CAPITAL PROJECT	35300 - Station Equipment	01/01/2018	3,302
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0178412	LIEBERMAN DSC MOABS 1690CD SW_1690CD CAPITAL PROJECT	35300 - Station Equipment	02/01/2017	21,505
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0178718	FLOURNOY STA CAPITAL PROJECT/69KV BREAKER 9080	35300 - Station Equipment	02/01/2017	45,961
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194LARE	SI194LARE TB/SI/SEP-NT LA SYS REHAB	T0179451	SOUTH SHREVEPORT TRF P141 16 E AUTO C0229751 CAPITAL PROJECT	35300 - Station Equipment	10/01/2017	96,186
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194LAUN	SI194LAUN TB SI SEPCO - LA UNCAT	42253648	IDS UPGRADE- SWEPCO CELLEMETRY	35300 - Station Equipment	09/01/2016	4,265

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194OKRE	SI194OKRE TB/SEP/OK-STATION REHAB	T0124080	CLARKSVILLE 345KV (SWEPCO) RTU REMOTE TERMINAL UNIT RTU_100	35300 - Station Equipment	08/01/2017	20,596
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	42527989	2016 EM/ SHAMROCK - MAGIC CITY 69KV TLN 00200 (FIRE)	35500 - Poles and Fixtures	09/01/2016	30,393
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	42559018	S E LONGVIEW - LAKE LAMOND REPLACE BAD POLES & ARMS	35500 - Poles and Fixtures	09/01/2016	111,914
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	42576669	HAWKINS - MINEOLA 69KV REPLACE POLES & ARMS	35500 - Poles and Fixtures	12/01/2016	70,234
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	42576686	PITTSBURG - WINNSBORO 69KV REPLACE POLES & ARMS	35500 Poles and Fixtures	12/01/2016	22,724
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	42585366	WINFIELD - WINNSBORO REPLACE 3 STRUCTURES	35500 - Poles and Fixtures	09/01/2016	24,527
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	42586632	MT PLEASANT - DAINGERFIELD REPL POLES, ARMS, & INSULATORS	35500 - Poles and Fixtures	12/01/2016	39,672
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX LINE REHAB	42596063	KILGORE - OVERTON REPLACE STRUCTURES	35500 - Poles and Fixtures	07/01/2017	83,468
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	42616525	2016 NSW JEFFERSON-N MARSHALL C/O VARIOUS BAD A2 STRUCTURES	35500 - Poles and Fixtures	04/01/2017	239,218
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	42616553	2016 NSW GRAND SALINE QUITMAN REPL STR 260 SEPTL214B	35500 - Poles and Fixtures	12/01/2016	8,979
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	42625768	HUGHES SPRINGS - LONE STAR STEEL 69KV REPLACE BROKEN XARM	35500 - Poles and Fixtures	08/01/2017	640
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	42647326	2017 NSW CP MEMPHIS - ESTELLINE 69KV TLN00045	35500 - Poles and Fixtures	06/01/2017	152,677
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	42647352	2014 LONE STAR STEEL TAP - SEPTL216D - TRAILING INVOICES	35500 - Poles and Fixtures	08/01/2017	17,627
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX LINE REHAB	TL027447	LONGVIEW HEIGHTS M OROW HAXARD - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	3,047
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL027582	PILGRIM'S PRIDE - WINFIELD	35500 - Poles and Fixtures	07/01/2016	5,138
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX LINE REHAB	TL027939	CLARENDON JERICHO CP WO 2 CONDITIONS TLN00047	35500 - Poles and Fixtures	09/01/2016	(4,199)
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL027983	JEFFERSON - SUPERIO2 R/W OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	1,277
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL028011	PIRKEY SCOTTSVILLE R/W OROW HAZARD TREE	35600 - Overhead Conductors, Device	07/01/2016	2,210
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL028103	NORTH NEW BOSTON - WILES OROW HAZARD TREE - VICKER	35600 - Overhead Conductors, Device	08/01/2016	1,590
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX LINE REHAB	TL028105	JEFFERSON SWITCHING1 R/W OROW HAZARD TREE PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	1,490
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL028313	KNOX LEE-SE LONGVIEW OROW HAZARD TREE - BIDDY	35600 - Overhead Conductors, Device	08/01/2016	1,011
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL028394	GILMER - PERDUE #149 A-1 POLE	35500 - Poles and Fixtures	07/01/2016	3,565
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL028595	W CHILDRESS-ESTELLIN CP WO 1 CONDITIONS TLN00045	35500 - Poles and Fixtures	12/01/2016	1,356
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL028651	DIANA - PULER ROAD OROW HAZARD TREE PROGRAM - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	1,170
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL028660	MT PLEASANT - NEW B R/W OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	1,774
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL028747	WEST ATLANTA - WILKE OROW HAZARD - PILKINGTON	35600 - Overhead Conductors, Device	10/01/2016	1,182
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL028748	KILGORE - OVERTON HAZARD OROW - PILKINGTON	35600 - Overhead Conductors, Device	08/01/2016	2,449
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL028784	KNOX LEE - ROCK HILL #80A A-1	35500 Poles and Fixtures	10/01/2016	7,131
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX LINE REHAB	TL028815	W CHILDRESS ESTELLIN CP WO 19 CONDITIONS TLN00045	35500 - Poles and Fixtures	12/01/2016	84,390
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL028887	IPC DOMINO WEST ATL # 272 A-1	35500 - Poles and Fixtures	10/01/2016	6,903
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX LINE REHAB	TL029023	KNOX LEE - SOUTH TEX CP WO 2 CONDITIONS	35500 - Poles and Fixtures	12/01/2016	8,498
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL029049	PIRKEY - SCOTTSVILLE CP WO 8 CONDITIONS	35500 Poles and Fixtures	12/01/2016	57,003
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL029192	JEFFERSON - NORTH MA OROW HAZARD TREE	35600 Overhead Conductors, Device	02/01/2017	2,536
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL029193	HUGHES SPRING - LIND OROW HAZRD TREE	35600 - Overhead Conductors, Device	02/01/2017	2,636
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL029213	JEFFERSON SWITCHING1 OROW HAZARD TREE - VICKERS	35600 Overhead Conductors, Device	04/01/2017	2,006
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL029328	ESTELLINE - MEMPHIS CP WO 6 CONDITIONS TLN00053	35500 - Poles and Fixtures	04/01/2017	23,084
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL029400	LNGWD-SCOTTSVILL(TX) # 144 POLE	35500 - Poles and Fixtures	06/01/2017	9,945
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL029406	ESTELLINE - MEMPHIS CP WO 5 CONDITIONS TLN00045	35500 Poles and Fixtures	04/01/2017	29,479
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL029484	GILMER PERDUE R/W OROW HAZARD TREE - BIDDY	35600 Overhead Conductors, Device	05/01/2017	2,082
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXLR	SI194TXLR TB/SI/SEP/TX - LINE REHAB	TL029510	WINNSBORO-NO MINEOLA A-1 ANCHORS 15 DEG	35500 - Poles and Fixtures	06/01/2017	49,353
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42393085	PITTSBURG CB 6210 - REPLACE FAILED SWITCH 6213	35300 - Station Equipment	08/01/2016	19,157
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42393780	DE KALB 12 SKV REPLACE FAILED METER	35300 - Station Equipment	04/01/2018	2,419
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42396672	OAK HILL 138KV SUB REPLACE METER	35300 - Station Equipment	04/01/2018	1,404
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42397319	FOREST HILL NTEC 138KV SUB - REPLACE METER	35300 - Station Equipment	04/01/2018	4,553
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42397355	TATUM SUB - RELPACE METER	35300 - Station Equipment	09/01/2018	3,107
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42466046	NTEC DETC CENTER STATION REPLACE FAILED METER	35300 - Station Equipment	04/01/2018	6,247
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42526820	PERDUE SUBSTATION CHANGE OUT FAILED METER	35300 - Station Equipment	04/01/2018	1,458
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42531436	JEFFERSON 138KV NTEC SUBSTATION CHANGE OUT METER	35300 - Station Equipment	07/01/2017	1,631
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	42531459	OAKHILL 2 SUBSTATION CHANGE METER	35300 - Station Equipment	07/01/2017	1,651
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42531464	CENTER SOUTH STATION CHANGE METER	35300 - Station Equipment	07/01/2017	1,574
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	42531470	BOND 69KV SUBSTATION CHANGE METER	35300 - Station Equipment	04/01/2018	2,333
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42538717	E BURGESS SUBSTATION CHANGE OUT FAILED METER	35300 - Station Equipment	07/01/2017	1,631
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42574344	WELSH HVDC REPLACE FAILED VALVE MODULE REACTORS	35300 - Station Equipment	11/01/2017	46,775
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42626692	KILGORE SUBSTATION CHANGE OUT METER	35300 - Station Equipment	04/01/2018	1,297
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42626989	FRIARS SWITCH STATION REPLACE METER	35300 - Station Equipment	04/01/2018	1,915
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42627012	CARTHAGE SUBSTATION REPLACE METER	35300 - Station Equipment	04/01/2018	1,562
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	42682350	TATUM SUBSTATION REPLACE ION METERS WITH UPGRADE	35300 - Station Equipment	09/01/2018	1,656
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0130312	MARSHALL P142 64 - REPLACE 138KV BUSHINGS, 69KV & 138KV LA'S	35300 - Station Equipment	10/01/2016	88,625
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0141539	CARTHAGE POD - REPLACE FAILED CARRIER TUNER IN CCVT	35300 - Station Equipment	05/01/2016	5
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0150479	ROCK HILL CB 1P70 - REPLACE (2) FAILED BUSHINGS	35300 - Station Equipment	12/01/2016	25,178
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0151155	BUFORD SURVEY SW MOABS 7625 REPLACE BATTERY	35300 - Station Equipment	11/01/2016	1,178
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0152088	HUGHES SPRINGS CB 1200 CAPITAL PROJ-REPL FAILED SWITCH 1203	35300 - Station Equipment	11/01/2016	12,180
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0152505	MOUNT PLEASANT CB 1860 REPL FAILED SWITCH 1863 CAP	35300 - Station Equipment	11/01/2016	17,559
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0153159	CHAPEL HILL (M O LINE SW) SW MOAB WILKES 6333/6331	35300 - Station Equipment	08/01/2016	926
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0153334	NORTHWEST TEXARKANA CB 10690 REP FAILED SW 10693	35300 Station Equipment	12/01/2016	60,860
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0153604	ANDERSON CREEK CRSET CARRIER SET S1AXNAS12002231 CAPITAL PR	35300 - Station Equipment	02/01/2017	8,832
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0154118	WILKES CB GSU#2/BUS#1 1M00 230975 CAPITAL PROJECT	35300 - Station Equipment	02/01/2017	79,174
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0154119	NORTHWEST TEXARKANA CB SUGAR HILL/PATTERSON 10780 388902 CAP	35300 Station Equipment	09/01/2016	160,756
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0154418	MOUNT PLEASANT CB 1860 - REPLACE FAILED LIGHTNING ARRESTERS	35300 - Station Equipment	09/01/2016	17,566
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0163996	PETTY STA PETTY CAPITAL PROJECT CABLE REPLACEMENT	35300 Station Equipment	07/01/2018	40,247
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0164235	IPC JEFFERSON - REPLACE FAILED DLP RELAY WITH SEL 421 RELAY	35300 Station Equipment	10/01/2017	10,694

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0164453	CHILDRESS WEST (SEP) - C/O FAILED 69KV PTS	35300 - Station Equipment	06/01/2017	30,532
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0165135	KNOX LEE - UPGRADE CARRIER ON OVERTON CIRCUIT TO TC10B	35300 - Station Equipment	11/01/2017	10,033
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0165136	OVERTON UPGRADE CARRIER ON KNOX LEE CIRCUIT TO TC10B	35300 - Station Equipment	11/01/2017	7,804
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0165160	CHILDRESS WEST (SEP) C/O COOLING FAN	35300 - Station Equipment	11/01/2016	2,129
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0165629	SCOTTSVILLE (SW) STA SCOTTSVILLE(SW) CAP PROJECT P141 32BUSH	35300 - Station Equipment	11/01/2016	73,535
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0166256	NWTEXARKANA CAPITAL PROJECT RELAYS (PCMIS) P&C STAT/COMPRESS	35300 - Station Equipment	02/01/2017	1,615
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0166307	MOUNT PLEASANT CB WEST MOUNT PLEASANT 1860 K6566145CM501 CAP	35300 - Station Equipment	07/01/2017	102
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0166339	PITTSBURG (SW) TCC 69 [CB] WINNSBORO 9810 CAPITAL PROJECT	35300 - Station Equipment	02/01/2017	2,599
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0166507	NORTHWEST TEXARKANA CAPITAL PROJECT/SWITCH 10692	35300 - Station Equipment	06/01/2017	71,016
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0171759	LAKE PAULINE C/O FAILED DISC SWITCHES	35300 - Station Equipment	09/01/2016	4,627
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0175558	PETTY CB PILGRIMS PRIDE 1L20 0139A4907201 CAPITAL PROJECT	35300 - Station Equipment	08/01/2016	23,240
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0175699	ESTELLINE INSTALL MOBILE C/O ARRESTORS, CUTOUTS, INSULATORS	35300 - Station Equipment	07/01/2016	33,989
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0175827	SCOTTSVILLE - REPLACE FAILED CARRIER WITH A TC10B SET	35300 - Station Equipment	11/01/2017	8,265
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0176005	LYDIA STA LYDIA CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	78,370
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0176025	WELSH STA WELSH CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	59,687
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0176277	DIANA CB PIRKEY/SW SHREVEPORT - REPLACE FAILED CB11910	35300 - Station Equipment	07/01/2016	140,018
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0176473	WILKES STA WILKES CAPITAL PROJECT	35300 - Station Equipment	06/01/2017	62,015
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0176910	BANN STA BANN CAPITAL PROJECT/138KV GOABS 11432	35300 - Station Equipment	12/01/2016	14,097
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0177398	WELSH REPLACE FAILED LIGHT FIXTURES	35300 - Station Equipment	12/01/2016	41,317
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0177424	WHITNEY P141 66 NORTH - REPLACE (2) FAILED 24" FANS	35300 - Station Equipment	07/01/2016	887
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0177494	DIANA P345 29 CENTER - REPLACE (3) FAILED 24" FANS	35300 - Station Equipment	08/01/2016	450
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0177495	DIANA P345 25 SOUTH - REPLACE (2) FAILED 24" FANS	35300 - Station Equipment	08/01/2016	874
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0177690	IPC 138KV STA CAPITAL PROJECT/REPLACE SURGE ARRESTERS	35300 - Station Equipment	11/01/2016	5,143
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0177736	MARSHALL 138KV P142 64 NORTH - REPLACE (1) FAILED 24" FAN	35300 - Station Equipment	08/01/2016	701
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0177760	IPC-JEFFERSON - REPLACE CONTROL HOUSE AIR CONDITIONER	35300 - Station Equipment	10/01/2016	1,284
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP Tx TEXAS SYS REHAB	T0177861	SHAMROCK C/O FAILED CAPACITORS	35300 - Station Equipment	08/01/2016	9,969
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0177890	LONGVIEW OPS RESERVE BAT BATTERY TRAILER CAPITAL PROJECT	35300 Station Equipment	07/01/2018	7,074
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0178034	CHILDRESS WEST (SEP) C/O SEL 387E ON XFMR	35300 - Station Equipment	08/01/2017	16,820
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0178310	KNOX LEE P141 S4 - REPLACE (2) FAILED 24" FANS	35300 Station Equipment	08/01/2016	1,252
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0178314	MEMPHIS NW DELIVER FUSE TO STATION	35300 - Station Equipment	08/01/2016	1,181
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0178475	JEFFERSON STA CAPITAL PROJECT/RTU COOPER SG4250	35300 - Station Equipment	07/01/2017	64,818
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0178645	JEFFERSON SWITCHING - REPLACE CONTROL HOUSE AC	35300 - Station Equipment	09/01/2017	1,480
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0178672	NORTHWEST HENDERSON P142 66 REPLACE ONE 24" FAN	35300 - Station Equipment	11/01/2016	1,077
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0178709	LONE STAR (SEP) STA LONE STAR (SEP) CAPITAL PROJECT	35300 - Station Equipment	12/01/2016	66,925
TBLANKTSW	TBLANKTSW Trans Capital Blanket SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0178903	PIRKEY TRF P345 40 - S AUTO REPLACE 5 24" FANS	35300 Station Equipment	10/01/2016	3,509
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0178958	IPC-DOMINO STA CAPITAL PROJECT - AC UNIT	35300 Station Equipment	06/01/2017	6,156
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXRE	SI194TXRE TB/SI/SEP-Tx TEXAS SYS REHAB	T0179275	WEST ATLANTA TRF P137 9 EAST 236941 CAPITAL PROJECT	35300 - Station Equipment	12/01/2016	4,323
TBLANKTSW	TBLANKTSW Trans Capital Blanket - SWEPCo	SI194TXUN	SI194TXUN TB/SI/SEPCO - TEXAS UNCAT	42417869	ACCESS CONTROL- LYDIA 345 SS	35200 - Structures and Improvements	05/01/2017	22,932
	TBLANKTSW Trans Capital Blanket - SWEPCo Total							38,309,881
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL027363	DOLET HILLS S W S R/W WIDENING - BRAMLETT (NERC)	35600 - Overhead Conductors, Device	04/01/2017	6,647
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL027472	LONGWOOD - SOUTHWEST R/W WIDENING - PHILLIPS (NERC)	35600 - Overhead Conductors, Device	09/01/2016	1,356
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL027484	DIANA-SW SHRPRT (LA) R/W WIDENING - PHILLIPS (NERC)	35600 - Overhead Conductors, Device	08/01/2016	500
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL028462	LONGWOOD - EL DORADO R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	09/01/2016	343
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL029154	LONGWOOD - EL DORADO R/W WIDENING KUENNEN (NERC)	35600 - Overhead Conductors, Device	01/01/2017	7,773
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL029497	LONGWOOD - SOUTHWEST DEAD TREE REMOVAL (NERC)	35600 - Overhead Conductors, Device	02/01/2017	5,835
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL030930	LONGWOOD - EL DORADO DANGER TREE - CORBAN (NERC)	35600 - Overhead Conductors, Device	11/01/2017	2,610
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL031012	LONGWOOD - SOUTHWEST DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	04/01/2018	1,706
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL031027	DOLET HILLS - S W S HAZARD TREE - HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	1,329
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL032042	LONGWOOD SOUTHWEST DANGER TREE HIGHTOWER (NERC)	35600 Overhead Conductors, Device	11/01/2018	1,170
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL032043	DOLET HILLS - S W DANGER TREE- HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	6,523
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL032044	LONGWOOD - EL DORADO DANGER TREE - HIGHTOWER (NERC)	35600 Overhead Conductors, Device	11/01/2018	2,334
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL032565	LONGWOOD - EL DORADO DANGER TREE - CORBIN (NERC)	35600 - Overhead Conductors, Device	06/01/2018	3,029
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL032933	DOLET HILLS - S W S DANGER TREE - HIGHTOWER (NERC)	35600 Overhead Conductors, Device	01/01/2019	1,558
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL032934	LONGWOOD - EL DORADO DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	01/01/2019	302
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL032935	LONGWOOD - SOUTHWEST DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	02/01/2019	3,124
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL033479	DOLET HILLS - S W DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	05/01/2019	807
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL033862	LONGWOOD - EL DORADO DANGER TREE - HIGHTOWER (NERC)	35600 Overhead Conductors, Device	06/01/2019	3,599
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL035134	LONGWOOD - EL DORADO DANGER TREE REMOVAL - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	10/01/2019	14,094
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010383	000010383 Forestry SEPLA T NERC parent	TL036091	LONGWOOD - EL DORADO 345KV #135 - DANGER TREE REMOV HIGHTOWE	35600 - Overhead Conductors, Device	10/01/2019	127,373
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010384	000010384 Forestry SEP/AR T NERC parent	TL0036887	TURK NW TEXARKANA (AR) (T) LDRC/LIDAR-NORGAARD (NERC)	35600 - Overhead Conductors, Device	01/01/2020	16,143
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010384	000010384 Forestry SEP/AR T NERC parent	TL027775	FLINT CREEK - BROOKL R/W WIDENING - BEWLEY (NERC)	35600 Overhead Conductors, Device	07/01/2016	2,758
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010384	000010384 Forestry SEP/AR T NERC parent	TL028639	NORTHWEST TEXAR-PATT R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	01/01/2017	34,478
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010384	000010384 Forestry SEP/AR T NERC parent	TL029566	CHAMBER SP-TONTITOWN DEAD TREE - NORAARD (NERC)	35600 - Overhead Conductors, Device	08/01/2017	1,740
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010384	000010384 Forestry SEP/AR T NERC parent	TL030331	FLINT CREEK-SHIPE RD R/W DEAD TREE REMOVAL (NERC)	35600 - Overhead Conductors, Device	11/01/2017	11,773
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010384	000010384 Forestry SEP/AR T NERC parent	TL031462	FLINT CREEK-SHIPE RD DEAD TREE - NORGAARD (NERC)	35600 - Overhead Conductors, Device	06/01/2018	4,774
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010384	000010384 Forestry SEP/AR T NERC parent	TL031463	FLINT CREEK - BROOKL R/W WIDENING NORGAARD (NERC)	35600 - Overhead Conductors, Device	06/01/2018	1,973
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010384	000010384 Forestry SEP/AR T NERC parent	TL032345	CHAMBERS SPRING - C2 WIDING - RADEBAUGH (NERC)	35600 - Overhead Conductors, Device	01/01/2019	13,938
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL0036385	VALLIANT - NW TEXARKANA 345KV (T) #90-928 - CAP SPRAY-CORBIN	35600 - Overhead Conductors, Device	12/01/2019	140,233
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL0036519	CROCKETT - TENASKA RUSK CO 345KV #273A (T) HAZ TREE REMV-HI	35600 - Overhead Conductors, Device	02/01/2020	1,103
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL026812	LYDIA - VALLIANT S R/W WIDENING (NERC)	35600 Overhead Conductors, Device	10/01/2016	601
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL027358	CROCKETT - GRIMES(GS R/W WIDENING - BRAMLETT (NERC)	35600 - Overhead Conductors, Device	08/01/2016	2,816

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL027359	CROCKETT - TENASKA R/W WIDENING - BRAMLETT (NERC)	35600 - Overhead Conductors, Device	08/01/2016	21,867
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL027360	DIANA-SW SHRPRT (TX) R/W WIDENING - BRAMLETT (NERC)	35600 - Overhead Conductors, Device	08/01/2016	6,350
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL027361	DIANA - WELSH (CKT # R/W WIDENING - BRAMLETT (NERC)	35600 - Overhead Conductors, Device	08/01/2016	1,095
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL027362	DIANA WELSH (CKT #2) R/W WIDENING - BRAMLETT (NERC)	35600 - Overhead Conductors, Device	08/01/2016	1,412
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL027473	WELSH - LYDIA R/W WIDENING - PHILLIPS (NERC)	35600 - Overhead Conductors, Device	10/01/2016	3,334
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL027475	NORTHWEST TEXARKANA2 R/W WIDENING - PHILLIPS (NERC)	35600 - Overhead Conductors, Device	01/01/2017	9,584
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL027476	DIANA - PIRKEY R/W WIDENING - PHILLIPS (NERC)	35600 - Overhead Conductors, Device	08/01/2016	3,898
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL027477	WELSH - WILKES R/W WIDENING - PHILLIPS (NERC)	35600 - Overhead Conductors, Device	08/01/2016	2,601
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL027490	LYDIA - NORTHWEST TE R/W WIDENING - PHILLIPS (NERC)	35600 - Overhead Conductors, Device	01/01/2017	1,716
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL027660	WELSH - WELSH DC R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	08/01/2016	207
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL028858	LONGWOOD-WILKES(TX) R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	02/01/2017	16,130
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029088	DIANA - PIRKEY R/W WIDENING KUENNEN (NERC)	35600 Overhead Conductors, Device	03/01/2017	9,755
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029118	WELSH - WELSH DC R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	02/01/2017	264
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029124	CROCKETT - GRIMES(GS R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	02/01/2017	1,846
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029130	PIRKEY - LEBROCK R/W WIDENING KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	1,654
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029135	WELSH - WELSH DC R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	02/01/2017	612
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029632	DIANA SW SHRPRT (TX) (DEAD TREE REMOVAL) - KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	6,211
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029723	DIANA WELSH (CKT #1 DANGER TREE - KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	1,333
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029724	DIANA WELSH (CKT #2) DANGER TREE - KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	2,569
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029733	LYDIA - VALLIANT S R/W DANGER TREE - CORBIN (NERC)	35600 - Overhead Conductors, Device	08/01/2017	461
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029814	WELSH - WILKES DEAD TREE - KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	3,872
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029815	PIRKEY - TENASKA RUS DEAD TREE - KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	6,386
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029953	TURK NW TEXARKANA-T HAZARD TREE REMOVAL - CORBIN (NERC)	35600 - Overhead Conductors, Device	10/01/2017	(21)
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL029960	WELSH - LYDIA DEAD TREE - CORBIN (NERC)	35600 - Overhead Conductors, Device	10/01/2017	(658)
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL030052	CROCKETT - TENASKA DEAD TREE REMOVAL (NERC)	35600 - Overhead Conductors, Device	10/01/2017	5,734
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL031366	TURK-NW TEXARKANA-T DANGRER TREE CORBIN (NERC)	35600 Overhead Conductors, Device	11/01/2017	1,149
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL031798	NORTH NEW BOSTON - HAZARD TREE HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	599
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL031900	PIRKEY - TENASKA RUS DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	642
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL031988	CROCKETT - GRIMES DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	1,102
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032041	CROCKETT - TENASKA DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	644
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032298	LYDIA - NORTHWEST TE DANGER TREE- CORBIN (NERC)	35600 - Overhead Conductors, Device	02/01/2019	2,886
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032299	NORTHWEST TEXARKANA2 DANGER TREE - CORBIN	35600 - Overhead Conductors, Device	12/01/2018	7,118
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032374	DIANA WELSH (CKT #2) DANGER TREE - CORBIN (NERC)	35600 - Overhead Conductors, Device	11/01/2018	917
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032380	DIANA - WELSH (CKT #1 EAST - DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	263
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032453	VALLIANT - NWTEXARK - DANGER TREE - CORBIN (NERC)	35600 - Overhead Conductors, Device	11/01/2018	978
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032553	CROCKETT - TENASKA R/W WIDENING HIGHTOWER DANGER TREE (NER	35600 - Overhead Conductors, Device	06/01/2018	1,288
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032554	PIRKEY - TENASKA RUS R/W WIDENING - HIGHTOWER - DANGER TREE	35600 - Overhead Conductors, Device	06/01/2018	444
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032555	DIANA - WELSH (CKT # R/W WIDENING HIGHTOWER - DANGER TREE	35600 - Overhead Conductors, Device	11/01/2018	806
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032556	DIANA SW SHRPRT (TX) R/W WIDENING - HIGHTOWER - DANGER TREE	35600 - Overhead Conductors, Device	11/01/2018	997
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032557	DIANA WELSH (CKT #2) HIGHTOWER DANGER TREE (NERC)	35600 - Overhead Conductors, Device	11/01/2018	586
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032930	CROCKETT - TENASKA DANGER TREE (NERC)	35600 - Overhead Conductors, Device	01/01/2019	688
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL032931	PIRKEY - TENASKA RUS DANGER TREE (NERC)	35600 - Overhead Conductors, Device	01/01/2019	4,326
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL033117	PIRKEY - TENASKA RUS DANGER TREE - HIGHTOWER (NERC)	35600 Overhead Conductors, Device	01/01/2019	3,766
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL033438	CROCKETT - TENASKA DANGER TREE HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	03/01/2019	1,360
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL033657	LONGWOOD-WILKES(TX) DANGER TREE - JASON (NERC)	35600 Overhead Conductors, Device	03/01/2019	1,424
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL033739	WELSH WILKES 345KV #271 4 DANGER TREE-HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	03/01/2019	278
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL033789	CROCKETT - GRIMES DANGER TREE REMOVAL - HIGHTOWER (NERC)	35600 Overhead Conductors, Device	03/01/2019	506
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL033993	DIANA - PIRKEY R/W DANGER TREE HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	03/01/2019	473
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL034516	WELSH - LYDIA R/W DANGER TREE - CORBIN (NERC)	35600 - Overhead Conductors, Device	10/01/2019	395
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL035492	TRUPULSE 360 CAPITAL PURCHASE - TRANSMISSION FORESRTY	35600 - Overhead Conductors, Device	10/01/2019	2,691
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL035552	NW TEXARKANA-WELSH 345KV #274 10 DANGER TREE REMO-CORBIN	35600 - Overhead Conductors, Device	10/01/2019	66
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL035554	WELSH - LYDIA 345KV #271 20 - DANGER TREE REMOV CORBIN (NERC	35600 - Overhead Conductors, Device	01/01/2020	388
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL035555	LYDIA - VALLIANT (TX) 345KV #271 10 - DANGER TREE REMV-CORBI	35600 - Overhead Conductors, Device	01/01/2020	532
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000010385	000010385 Forestry SEP/TX T NERC parent	TL036016	MIDVALLEY PIPELINE T STORM PILKINGTON (NERC)	35600 Overhead Conductors, Device	12/01/2019	652
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011436	000011436 Forestry SEP/AR T NERC shadow	TL0036887SWP	TURK - NW TEXARKANA (AR) (T) LDRC/LIDAR-NORGAARD (NERC)	35600 - Overhead Conductors, Device	01/01/2020	8,294
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011436	000011436 Forestry SEP/AR T NERC shadow	TL027775SWP	FLINT CREEK - BROOKL R/W WIDENING - BEWLEY (NERC)	35600 - Overhead Conductors, Device	07/01/2016	1,417
TREESSWEP	TREESSWEP Forestry T&O Widening - SWEPCo	000011436	000011436 Forestry SEP/AR T NERC shadow	TL028639SWP	NORTHWEST TEXAR-PATT R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	01/01/2017	17,472
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011436	000011436 Forestry SEP/AR T NERC shadow	TL029566SWP	CHAMBER SP-TONTITOWN DEAD TREE - NORAARD (NERC)	35600 - Overhead Conductors, Device	08/01/2017	894
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011436	000011436 Forestry SEP/AR T NERC shadow	TL030331SWP	FLINT CREEK-SHIPE RD R/W DEAD TREE REMOVAL (NERC)	35600 Overhead Conductors, Device	11/01/2017	6,049
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011436	000011436 Forestry SEP/AR T NERC shadow	TL031462SWP	FLINT CREEK-SHIPE RD DEAD TREE - NORGAARD (NERC)	35600 - Overhead Conductors, Device	06/01/2018	2,453
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011436	000011436 Forestry SEP/AR T NERC shadow	TL031463SWP	FLINT CREEK - BROOKL R/W WIDENING NORGAARD (NERC)	35600 - Overhead Conductors, Device	06/01/2018	1,013
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011436	000011436 Forestry SEP/AR T NERC shadow	TL032345SWP	CHAMBERS SPRING - C2 - WIDING - RADEBAUGH (NERC)	35600 Overhead Conductors, Device	01/01/2019	7,161
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL027363SWP	DOLET HILLS - S W S R/W WIDENING - BRAMLETT (NERC)	35600 - Overhead Conductors, Device	04/01/2017	3,415
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL027472SWP	LONGWOOD - SOUTHWEST R/W WIDENING - PHILLIPS (NERC)	35600 - Overhead Conductors, Device	09/01/2016	697
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL027484SWP	DIANA-SW SHRPRT (LA) R/W WIDENING PHILLIPS (NERC)	35600 - Overhead Conductors, Device	08/01/2016	257
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL028462SWP	LONGWOOD - EL DORADO R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	09/01/2016	176
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL029154SWP	LONGWOOD - EL DORADO R/W WIDENING - KUENNEN (NERC)	35600 Overhead Conductors, Device	01/01/2017	3,994
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL029497SWP	LONGWOOD - SOUTHWEST DEAD TREE REMOVAL (NERC)	35600 - Overhead Conductors, Device	02/01/2017	2,998
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL030930SWP	LONGWOOD - EL DORADO DANGER TREE - CORBAN (NERC)	35600 - Overhead Conductors, Device	11/01/2017	1,341
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL031012SWP	LONGWOOD - SOUTHWEST DANGER TREE HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	04/01/2018	883
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL031027SWP	DOLET HILLS - S W S HAZARD TREE - HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	688

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL032042SWP	LONGWOOD - SOUTHWEST DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	601
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL032043SWP	DOLET HILLS S W DANGER TREE- HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	3,351
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL032044SWP	LONGWOOD EL DORADO DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	1,199
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL032565SWP	LONGWOOD - EL DORADO DANGER TREE - CORBIN (NERC)	35600 Overhead Conductors, Device	05/01/2018	1,556
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL032933SWP	DOLET HILLS S W S DANGER TREE HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	01/01/2019	800
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL032934SWP	LONGWOOD EL DORADO DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	01/01/2019	155
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL032935SWP	LONGWOOD SOUTHWEST DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	02/01/2019	1,605
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL033479SWP	DOLET HILLS - S W DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	05/01/2019	415
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL033862SWP	LONGWOOD - EL DORADO DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	06/01/2019	1,849
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL035134SWP	LONGWOOD EL DORADO DANGER TREE REMOVAL - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	10/01/2019	7,241
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011437	000011437 Forestry SEP/LA T NERC shadow	TL036091SWP	LONGWOOD - EL DORADO 345KV #135 - DANGER TREE REMOV-HIGHTOWE	35600 - Overhead Conductors, Device	10/01/2019	65,441
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL0036385SWP	VALLIANT - NW TEXARKANA 345KV (T) #90-928 - CAP SPRAY-CORBIN	35600 - Overhead Conductors, Device	12/01/2019	65,342
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL0036519SWP	CROCKETT - TENASKA RUSK CO 345KV #273A (T) HAZ TREE REMV-HI	35600 - Overhead Conductors, Device	02/01/2020	567
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL026812SWP	LYDIA - VALLIANT S R/W WIDENING (NERC)	35600 - Overhead Conductors, Device	10/01/2016	309
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL027358SWP	CROCKETT - GRIMES(GS R/W WIDENING - BRAMLETT (NERC)	35600 - Overhead Conductors, Device	08/01/2016	1,447
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL027359SWP	CROCKETT - TENASKA R/W WIDENING - BRAMLETT (NERC)	35600 - Overhead Conductors, Device	08/01/2016	11,233
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL027360SWP	DIANA-SW SHRPRT (TX) R/W WIDENING BRAMLETT (NERC)	35600 Overhead Conductors, Device	08/01/2016	3,263
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL027361SWP	DIANA - WELSH (CKT # R/W WIDENING - BRAMLETT (NERC)	35600 - Overhead Conductors, Device	08/01/2016	563
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL027362SWP	DIANA WELSH (CKT #2) R/W WIDENING - BRAMLETT (NERC)	35600 - Overhead Conductors, Device	08/01/2016	726
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL027473SWP	WELSH - LYDIA R/W WIDENING PHILLIPS (NERC)	35600 - Overhead Conductors, Device	10/01/2016	1,713
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL027475SWP	NORTHWEST TEXARKANA2 R/W WIDENING - PHILLIPS (NERC)	35600 Overhead Conductors, Device	01/01/2017	4,905
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL027476SWP	DIANA - PIRKEY R/W WIDENING - PHILLIPS (NERC)	35600 - Overhead Conductors, Device	08/01/2016	2,003
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL027477SWP	WELSH - WILKES R/W WIDENING - PHILLIPS (NERC)	35600 - Overhead Conductors, Device	08/01/2016	1,336
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL027490SWP	LYDIA - NORTHWEST TE R/W WIDENING PHILLIPS (NERC)	35600 - Overhead Conductors, Device	01/01/2017	874
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL027660SWP	WELSH - WELSH DC R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	08/01/2016	107
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL028858SWP	LONGWOOD-WILKES(TX) R/W WIDENING KUENNEN (NERC)	35600 - Overhead Conductors, Device	02/01/2017	8,224
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029088SWP	DIANA - PIRKEY R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	03/01/2017	5,009
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029118SWP	WELSH - WELSH DC R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	02/01/2017	135
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029124SWP	CROCKETT - GRIMES(GS R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	02/01/2017	945
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029130SWP	PIRKEY - LEBROCK R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	849
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029135SWP	WELSH - WELSH DC R/W WIDENING - KUENNEN (NERC)	35600 - Overhead Conductors, Device	02/01/2017	314
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029632SWP	DIANA-SW SHRPRT (TX) (DEAD TREE REMOVAL) - KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	3,191
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029723SWP	DIANA - WELSH (CKT #1 DANGER TREE - KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	685
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029724SWP	DIANA WELSH (CKT #2) DANGER TREE - KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	1,320
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029733SWP	LYDIA - VALLIANT S R/W DANGER TREE - CORBIN (NERC)	35600 - Overhead Conductors, Device	08/01/2017	237
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029814SWP	WELSH - WILKES DEAD TREE - KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	1,989
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029815SWP	PIRKEY - TENASKA RUS DEAD TREE - KUENNEN (NERC)	35600 - Overhead Conductors, Device	04/01/2017	3,281
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029953SWP	TURK-NW TEXARKANA-T HAZARD TREE REMOVAL - CORBIN (NERC)	35600 - Overhead Conductors, Device	10/01/2017	(11)
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL029960SWP	WELSH - LYDIA DEAD TREE - CORBIN (NERC)	35600 - Overhead Conductors, Device	10/01/2017	(338)
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL030052SWP	CROCKETT - TENASKA DEAD TREE REMOVAL (NERC)	35600 - Overhead Conductors, Device	10/01/2017	2,946
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL031366SWP	TURK-NW TEXARKANA-T DANGRER TREE CORBIN (NERC)	35600 - Overhead Conductors, Device	11/01/2017	590
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL031798SWP	NORTH NEW BOSTON - HAZARD TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	308
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL031900SWP	PIRKEY - TENASKA RUS DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	330
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL031988SWP	CROCKETT GRIMES DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	566
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032041SWP	CROCKETT - TENASKA DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	11/01/2018	331
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032298SWP	LYDIA NORTHWEST TE DANGER TREE- CORBIN (NERC)	35600 - Overhead Conductors, Device	02/01/2019	1,483
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032299SWP	NORTHWEST TEXARKANA2 DANGER TREE - CORBIN	35600 Overhead Conductors, Device	12/01/2018	3,657
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032374SWP	DIANA WELSH (CKT #2) DANGER TREE - CORBIN (NERC)	35600 - Overhead Conductors, Device	11/01/2018	471
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032380SWP	DIANA - WELSH (CKT #1 EAST - DANGER TREE - HIGHTOWER (NERC)	35600 Overhead Conductors, Device	11/01/2018	135
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032453SWP	VALLIANT - NWTEXARK DANGER TREE CORBIN (NERC)	35600 - Overhead Conductors, Device	11/01/2018	503
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032553SWP	CROCKETT - TENASKA R/W WIDENING - HIGHTOWER DANGER TREE (NER	35600 - Overhead Conductors, Device	05/01/2018	662
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032554SWP	PIRKEY - TENASKA RUS R/W WIDENING - HIGHTOWER - DANGER TREE	35600 - Overhead Conductors, Device	05/01/2018	228
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032555SWP	DIANA - WELSH (CKT # R/W WIDENING - HIGHTOWER - DANGER TREE	35600 - Overhead Conductors, Device	11/01/2018	414
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032556SWP	DIANA-SW SHRPRT (TX) R/W WIDENING - HIGHTOWER - DANGER TREE	35600 Overhead Conductors, Device	11/01/2018	512
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032557SWP	DIANA WELSH (CKT #2) HIGHTOWER - DANGER TREE (NERC)	35600 - Overhead Conductors, Device	11/01/2018	301
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032930SWP	CROCKETT - TENASKA DANGER TREE (NERC)	35600 - Overhead Conductors, Device	01/01/2019	354
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL032931SWP	PIRKEY - TENASKA RUS DANGER TREE (NERC)	35600 - Overhead Conductors, Device	01/01/2019	2,222
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL033112SWP	PIRKEY - TENASKA RUS DANGER TREE - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	01/01/2019	1,935
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL033438SWP	CROCKETT - TENASKA DANGER TREE- HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	03/01/2019	699
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL033657SWP	LONGWOOD-WILKES(TX) DANGER TREE - JASON (NERC)	35600 - Overhead Conductors, Device	03/01/2019	732
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL033739SWP	WELSH - WILKES 345KV #271 4 DANGER TREE-HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	03/01/2019	143
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL033789SWP	CROCKETT - GRIMES DANGER TREE REMOVAL - HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	03/01/2019	260
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL033993SWP	DIANA - PIRKEY R/W DANGER TREE HIGHTOWER (NERC)	35600 - Overhead Conductors, Device	03/01/2019	243
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL034516SWP	WELSH - LYDIA R/W DANGER TREE - CORBIN (NERC)	35600 - Overhead Conductors, Device	10/01/2019	203
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL035492SWP	TRUPULSE 360 CAPITAL PURCHASE TRANSMISSION FORESRTY	35600 - Overhead Conductors, Device	10/01/2019	1,383
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL035552SWP	NW TEXARKANA-WELSH 345KV #274 10 - DANGER TREE REMO-CORBIN	35600 - Overhead Conductors, Device	10/01/2019	34
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL035554SWP	WELSH - LYDIA 345KV #271 20 - DANGER TREE REMOV-CORBIN (NERC	35600 Overhead Conductors, Device	01/01/2020	199
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL035555SWP	LYDIA - VALLIANT (TX) 345KV #271 10 - DANGER TREE REMV-CORBI	35600 - Overhead Conductors, Device	01/01/2020	274
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000011438	000011438 Forestry SEP/TX T NERC shadow	TL036016SWP	MIDVALLEY PIPELINE T -STORM PILKINGTON (NERC)	35600 - Overhead Conductors, Device	12/01/2019	302
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL027027SWP	MT PLEASANT NEW B R/W WIDENING	35600 Overhead Conductors, Device	07/01/2016	1,642
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL027414SWP	PIRKEY - SCOTTSVILLE R/W WIDENING - BRAMLETT	35600 Overhead Conductors, Device	07/01/2016	2,469

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL027415SWP	LNGWD-SCOTTSVILL(TX) R/W WIDENING - BRAMLETT	35600 - Overhead Conductors, Device	08/01/2016	7,805
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL027416SWP	BAN IPC DOMINO R/W WIDENING - BRAMLETT	35600 - Overhead Conductors, Device	01/01/2017	560
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non NERC shadow	TL027540SWP	IPC DOMINO - WEST AT R/W WIDENING - PHILLIPS	35600 - Overhead Conductors, Device	07/01/2016	6,937
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL027672SWP	PETTY - WILKES R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	572
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL027757SWP	DIANA - PLILER RD 138KV #249 20 - TREE REMOVAL-KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	6,110
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL027795SWP	LONE STAR SOUTH - PI R/W WIDENING - KUENNAN	35600 Overhead Conductors, Device	07/01/2016	293
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL027889SWP	JEFFERSON - NORTH MA R/W WIDENING - KEUNNANA	35600 - Overhead Conductors, Device	07/01/2016	236
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL027962SWP	GILMER - PERDUE R/W WIDENING - KEUNNEN	35600 - Overhead Conductors, Device	01/01/2017	402
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL028139SWP	MINEOLA - NORTH MIEO R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	974
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL028223SWP	DANGERFIELD - HUGHES R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	09/01/2016	324
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non NERC shadow	TL028721SWP	CLARKSVILLE - PERDUE R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	12/01/2016	1,655
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non NERC shadow	TL028826SWP	PITTSBURG - WINNSBOR R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	4,370
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL028864SWP	DANGERFIELD - HUGHES - DANGER TREES - CORBIN	35600 - Overhead Conductors, Device	05/01/2017	4,819
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL028992SWP	DIANA - LONE STAR SO R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	5,582
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029089SWP	GILMER - PITTSBURG R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	1,139
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029094SWP	IPC DOMINO - WEST AT R/W WIDENING - CORBIN	35600 - Overhead Conductors, Device	06/01/2017	634
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029095SWP	HUGHES SPRING LIND R/W WIDENING - CORBIN	35600 - Overhead Conductors, Device	06/01/2017	2,427
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029096SWP	W CHILDRESS-SHAMROCK R/W WIDENING - CORBIN	35600 Overhead Conductors, Device	05/01/2017	13,128
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029107SWP	NORTHWEST TEXARKANA1 R/W WIDENING - CORBIN	35600 - Overhead Conductors, Device	06/01/2017	215
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029140SWP	GRAND SALINE - MINEO R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	202
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029269SWP	ATLANTA - LINDEN R/W DEAD TREE AND LARGE REMOVALS - CORBIN	35600 - Overhead Conductors, Device	08/01/2017	944
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029287SWP	FLOURNOY - WOODLAW3 TREE REMOVAL - KUENNEN	35600 - Overhead Conductors, Device	02/01/2017	277
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029288SWP	MIDVALLEY PIPELINE T TREE REMOVAL KUENNEN	35600 Overhead Conductors, Device	02/01/2017	1,572
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029376SWP	WEST ATLANTA - WILKE DEAD TREE KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	2,908
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029474SWP	GILMER - PERDUE DEAD TREE - STORM - KUENNEN	35600 - Overhead Conductors, Device	02/01/2017	617
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029917SWP	PETTY - WILKES DEAD TREE - KUENNEN	35600 - Overhead Conductors, Device	10/01/2017	1,170
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL029946SWP	JEFFERSON - NORTH MA DEAD TREE - KUENNEN	35600 - Overhead Conductors, Device	10/01/2017	1,105
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL030156SWP	NORTH NEW BOSTON - HAZZARD TREE NON-NERC KUENNEN	35600 - Overhead Conductors, Device	10/01/2017	1,604
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL030322SWP	N NEW BOSTON - WILKES 138KV - TREE REMOVAL-CORBIN	35600 - Overhead Conductors, Device	10/01/2017	2,296
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL030334SWP	PLILER ROAD - WHITNE OROW HAZARD TREE PILKINGTON	35600 - Overhead Conductors, Device	11/01/2018	1,513
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non NERC shadow	TL030400SWP	LOGANSPORT-TENAHA HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	184
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL030513SWP	NETTLETON TEXOMA TAP DEAD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	680
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non NERC shadow	TL030610SWP	BANN - NEW BOSTON HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	1,377
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL030873SWP	HARRISON ROAD - KNOX HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	598
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL031013SWP	JEFFERSON SWITCHING2 DANGER TREE HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	225
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL031344SWP	EASTEX SWITCHING ST5 HAZARD TREE - HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	2,831
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL031391SWP	LONE STAR ORDINANCE HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	397
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL031440SWP	MINEOLA - NORTH MIEO HAZARD TREE - HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2018	1,988
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL031999SWP	NORTH NEW BOSTON - W R/W HAZARD TREE	35600 - Overhead Conductors, Device	11/01/2018	221
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL032120SWP	PILGRIM'S PRIDE - WIN - DANGER TREE- HIGHTOWER	35600 - Overhead Conductors, Device	11/01/2018	179
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL032230SWP	IPC DOMINO - WEST AT R/W WIDENING - CORBIN	35600 - Overhead Conductors, Device	01/01/2019	72,167
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL032370SWP	DIANA PURDUE DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	11/01/2018	189
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non NERC shadow	TL032454SWP	NORTHWEST HENDER POY - DANGER TREE HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2019	1,139
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL032580SWP	ATLANTA - LINDEN R/W WIDENING	35600 - Overhead Conductors, Device	10/01/2018	2,228
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non NERC shadow	TL032794SWP	MT PLEASANT - NEW DANGER TREE - CORBIN	35600 - Overhead Conductors, Device	01/01/2019	2,600
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL032877SWP	PIRKEY - SCOTTSVILLE DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	12/01/2018	1,899
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL032878SWP	MT PLEASANT - PETTY DANGER TREE - HIGHTOWET	35600 - Overhead Conductors, Device	01/01/2019	2,484
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL032932SWP	DIANA-SW SHRPRT (TX) DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	01/01/2019	841
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL033012SWP	EVENSIDE - POYNTER DEAD TREE - HIGHTOWER	35600 - Overhead Conductors, Device	01/01/2019	71
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL033047SWP	WINNSBORO-NO MINEOLA DAMAGE CLAIM - HIGHTOWER	35600 - Overhead Conductors, Device	01/01/2019	4,062
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non NERC shadow	TL033106SWP	JEFFERSON SWITCHING1 DANGER TREE REMOVAL - HIGHTOWER	35600 - Overhead Conductors, Device	01/01/2019	244
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL033131SWP	MARSHALL 69 - ROCK H - HIGHTOWER	35600 - Overhead Conductors, Device	01/01/2019	254
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL033218SWP	HAWKINS - MINEOLA DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2019	396
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL033224SWP	DIANA - PLILER ROAD - DANGER TREE HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2019	1,181
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL033289SWP	BANN - THIRTY NINTH HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	02/01/2019	721
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL033373SWP	BECKVILLE - POYNTER R/W WIDENING - HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2019	215
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL033731SWP	W ATLANTA - LINDEN 69KV #201 20 - R/W WIDENING-CORBIN	35600 - Overhead Conductors, Device	03/01/2019	279
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL033737SWP	EASTEX SWITCHING ST5 - DANGER TREE - HIGHTOWER	35600 Overhead Conductors, Device	03/01/2019	260
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL033928SWP	HAWKINS PERDUE - DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	03/01/2019	593
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL034458SWP	DAINGERFIELD - MT P R/W DANGER TREE - CORBIN	35600 - Overhead Conductors, Device	10/01/2019	405
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL034462SWP	CARTHAGE MURVAUL R DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	08/01/2019	163
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL034463SWP	LONGWOOD-WILKES(TX) DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	08/01/2019	964
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL034548SWP	BLOOMBURG - ATLANTADANGER TREE CORBIN	35600 - Overhead Conductors, Device	10/01/2019	96
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL034580SWP	HAWKINS - MINEOLA DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	08/01/2019	445
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL034623SWP	WINNSBORO-NO MINEOLA DANGER TREE HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2020	200
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL034774SWP	FLOURNOY - WOODLAW1 DANGER TREE - CORBIN	35600 - Overhead Conductors, Device	10/01/2019	320
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL035202SWP	CARTHAGE - MURVAUL R STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	1,227
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL035556SWP	IPC DOMINO W ATLANTA 138KV #241 7 - DANGER TREE REMV-CORBI	35600 - Overhead Conductors, Device	12/01/2019	394
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL035828SWP	WINFIELD WINNSBORO NONNERC - DANGER TREE REMOVAL-HIGHTOWER	35600 Overhead Conductors, Device	03/01/2020	1,336
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012879	000012879 Forestry SEPTX non-NERC shadow	TL036060SWP	DIANA - PLILER ROAD 138KV #249 - DANGER TREE REMOV-HIGHTOWER	35600 - Overhead Conductors, Device	08/01/2019	1,980
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027304SWP	LIEBERMAN - LONGWOOD R/W WIDENING - BRAMLETT	35600 - Overhead Conductors, Device	07/01/2016	271

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027417SWP	LONGWOOD-WILKES(LA) R/W WIDENING BRAMLETT	35600 - Overhead Conductors, Device	08/01/2016	285
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027471SWP	LONGWOOD-SCOTTSVILLE R/W WIDENING PHILLIPS	35600 - Overhead Conductors, Device	09/01/2016	654
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027758SWP	LOGANSPORT - STONEWALL 138KV #107 4 TREE REMOVAL-KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	1,144
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027774SWP	FORT HUMBUG - SOUTH R/W WIDENING - KUENNAN	35600 - Overhead Conductors, Device	07/01/2016	372
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027834SWP	BLANCHARD NORTH MA R/W WIDENING KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	232
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027878SWP	HOSSTON - NORTH BENT R/W WIDENING - KUENNAN	35600 - Overhead Conductors, Device	07/01/2016	472
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027961SWP	FLOURNOY - HARDY STR R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	1,072
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027963SWP	CALUMET-GETTY OIL R/W WIDENING - KEUNNEN	35600 - Overhead Conductors, Device	07/01/2016	113
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027964SWP	MANY - BELMONT R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	300
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027965SWP	MANY - NEGREET R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	68
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027966SWP	ROBSON ROAD(POD-KING R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	113
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL027969SWP	HOSSTON-BLMBRG (LA) R/W WIDENING KEUNNEN	35600 - Overhead Conductors, Device	07/01/2016	226
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL028009SWP	RED POINT BELLEVUE R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	491
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL028010SWP	RED POINT - WHITEHUR R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	118
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL028072SWP	FLOURNOY - SUMMER GR R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	1,224
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL028176SWP	SOUTH SHREVEPORT - 2 R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	02/01/2017	222
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL028297SWP	GENERAL MOTORS - SOU R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	09/01/2016	450
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL028298SWP	SOUTHWEST SHREVEP-WE R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	09/01/2016	755
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL028494SWP	MARTHAVILLE-ROBELINE R/W WIDENING CASSANDRA	35600 - Overhead Conductors, Device	09/01/2016	144
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL028515SWP	SEVENTIETH STREET TA R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	09/01/2016	669
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL028796SWP	SOUTHWEST SHREVEP-WE R/W WIDENING 138KV C KUENNEN	35600 Overhead Conductors, Device	02/01/2017	136
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL029052SWP	ARSENAL HILL-LONGWOD R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	1,389
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL029187SWP	LONGWOOD-SCOTTSVILLE R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	232
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL029230SWP	STONEWALL TAP R/W TREE REMOVAL - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	3,553
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL029417SWP	IPC JEFFERSON LIE2 DEAD TREE- KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	6,925
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL029467SWP	LOGANSPORT - STONEWA DEAD TREE - KUENNEN	35600 Overhead Conductors, Device	01/01/2017	1,010
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL029544SWP	LIEBERMAN - LONGWOOD YARD TREES KUENNEN	35600 - Overhead Conductors, Device	02/01/2017	978
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL029918SWP	LOGANSPORT - STONEWA DEAD TREE - KUENNEN	35600 - Overhead Conductors, Device	10/01/2017	3,050
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL029959SWP	SOUTHWEST SHREVEP-WE OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	04/01/2017	1,005
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL029984SWP	STONEWALL TAP DANGER TREE - KUENNEN	35600 - Overhead Conductors, Device	10/01/2017	262
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL030339SWP	RED POINT - WHITEHUR HAZARD TREE REMOVAL - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	1,290
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL030340SWP	IPC JEFFERSON - LIE2 DEAD TREE REMOVAL	35600 - Overhead Conductors, Device	11/01/2017	293
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL030341SWP	WALLACE LAKE - MANSF DEAD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	228
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL030377SWP	LOGANSPORT - STANLEY DEAD TREE - CORBIN	35600 Overhead Conductors, Device	11/01/2017	2,107
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL030413SWP	ELLBERTE ROAD - FREN DEAD/DANGER TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	3,822
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL030653SWP	FLOURNOY - HARDY STR HAZARD TREE REMOVAL - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	987
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL030789SWP	LIEBERMAN - RED POIN HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	394
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL030790SWP	TRICHEL STREET - WHI HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	1,148
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL030805SWP	BLANCHARD - LIEBERMA HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	1,360
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL030853SWP	ELLBERTE ROAD - SOUT HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	221
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL030885SWP	HOSSTON - SUPERIOR 2 HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	1,374
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL031003SWP	FLOURNOY - WOODLAW2 STORM HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	282
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL031026SWP	GENERAL MOTORS - SOU HAZARD TREE - HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	1,325
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL031028SWP	FLOURNOY - LONGWOOD HAZARD TREE HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	1,236
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL031130SWP	MANY - BELMONT DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	89
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL031137SWP	BELMONT-MARTHAVILLE DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	10/01/2017	12,590
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL031262SWP	ARSENAL HILL - LONGWOOD (127 1), SWEPCO LA, NON-NERC, $5,000	35600 - Overhead Conductors, Device	04/01/2018	221
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL031546SWP	LOGANSPORT - STANLEY HAZARD TREE HIGHTOWER	35600 - Overhead Conductors, Device	06/01/2018	225
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL031808SWP	HOSSTON-BLMBRG (LA) HAZARD TREE	35600 - Overhead Conductors, Device	11/01/2018	614
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL032086SWP	CALUMET-GETTY OIL DANGER TREE HIGHTOWER	35600 - Overhead Conductors, Device	11/01/2018	211
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL032222SWP	HOSSTON - SUPERIOR 2 R/W WIDENING HIGHTOWER	35600 - Overhead Conductors, Device	11/01/2018	4,473
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL032393SWP	SOUTH SHREVEPORT - WALLACE LAKE DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	11/01/2018	155
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL032496SWP	FORT HUMBUG SOUTH DANGER TREE	35600 - Overhead Conductors, Device	11/01/2018	2,381
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL032600SWP	N LEESVILLE-HORNBECK HIGHTOWER - DANGER TREE	35600 - Overhead Conductors, Device	01/01/2019	4,286
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL032641SWP	FLOURNOY - LONGWOOD DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	12/01/2018	2,679
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL032733SWP	FLOURNOY - SUMMER GR R/W DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	12/01/2018	894
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL032857SWP	BELCHER - HOSSTON DANGER TREE REMOVAL	35600 - Overhead Conductors, Device	01/01/2019	1,075
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL032928SWP	HOSSTON - NORTH BENT DANGER TREE	35600 - Overhead Conductors, Device	01/01/2019	2,258
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL033057SWP	E LEESVILLE - HICKS DANGER TREE	35600 - Overhead Conductors, Device	01/01/2019	1,660
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL033389SWP	HOSSTON - NORTH BENT DANGER TREE	35600 - Overhead Conductors, Device	02/01/2019	4,790
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL034020SWP	ARSENAL HILL-LONGWOD DANGER TREE HIGHTOWWER	35600 - Overhead Conductors, Device	03/01/2019	291
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL034452SWP	JEFFERSON - SUPERIO1 DANGER TREE - JASON	35600 - Overhead Conductors, Device	08/01/2019	1,532
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL034661SWP	SOUTH SHREVEPORT - WALLACE LAKE - DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2020	620
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL034768SWP	MARTHAVILLE-ROBELINE 69KV #V-102 - DANGER TREE REM-HIGHTOWER	35600 - Overhead Conductors, Device	10/01/2019	1,757
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012880	000012880 Forestry SEPLA non-NERC shadow	TL035288SWP	LOGANSPORT STONEWALL 138KV #107 1 - DANGER TREE REMO-HIGHT	35600 - Overhead Conductors, Device	08/01/2019	1,426
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL0036496SWP	CHAMBERS SPRING - FLINT CREEK 161KV - NORGAARD CAPITAL TREE	35600 - Overhead Conductors, Device	12/01/2019	218
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL0036724SWP	EAST CENTERTON - NORTH ROGERS CAPITAL HAZARD TREE - NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	2,061
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL025790SWP	PRAIRIE GROVE - SILO R/W WIDENING - PHILLIPS	35600 - Overhead Conductors, Device	07/01/2016	4,606
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL026600SWP	NORTHWEST TEXARKANA REA-RICHMOND RD 69KV	35600 - Overhead Conductors, Device	01/01/2017	787
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL027017SWP	EUREKA SPRINGS HAR R/W WIDENING	35600 - Overhead Conductors, Device	07/01/2016	3,890
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL027018SWP	N MAGAZINE-DANVILLE R/W WIDENING	35600 - Overhead Conductors, Device	07/01/2016	5,691

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL027399SWP	DYESS-SPRINGDALE N R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	3,166
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL027403SWP	SOUTH DIERKS DIERKS R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	245
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL027776SWP	N HUNTINGTON-WALDRON R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	1,303
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL027778SWP	BOONEVILLE - WEST BO R/W WIDENING - BELWEY	35600 - Overhead Conductors, Device	07/01/2016	114
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL027782SWP	OKAY - PATTERSON R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	2,205
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL027783SWP	ASHDOWN - PATTERSON R/W WIDENING - BEWLEY	35600 Overhead Conductors, Device	10/01/2016	1,565
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL027784SWP	DEQUEEN - PATTERSON R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	5,253
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL027786SWP	DIERKS - MENA R/W WIDENING - BEWLEY	35600 Overhead Conductors, Device	07/01/2016	4,563
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL027787SWP	FULTON P-PATMOS AP&L R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	(487)
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL028382SWP	SOUTH NASHVILLE - SO R/W WIDENING - KUENNAN	35600 Overhead Conductors, Device	07/01/2016	12,154
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL028632SWP	SOUTH NASHVILLE - SO R/W WIDENING - JUENNEN	35600 - Overhead Conductors, Device	08/01/2016	25,474
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL028852SWP	PATTERSON - NEKOOSA- R/W DEAD TREE REMOVAL - KUENNAN	35600 - Overhead Conductors, Device	01/01/2017	889
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL028979SWP	SOUTH NASHVILLE - SO R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	9,296
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL029377SWP	DEQUEEN - MENA R/W WIDENING - NORGAARD	35600 - Overhead Conductors, Device	02/01/2017	30,155
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL029500SWP	DYESS-HYLAND DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	10/01/2017	5,269
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL029567SWP	CRAIG JCT DEQUEE(AR) HOT SPOT	35600 - Overhead Conductors, Device	06/01/2017	155
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL029725SWP	CHAMBERS SPRING DY DANGER TREE - NORGAARD	35600 - Overhead Conductors, Device	10/01/2017	1,029
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL029940SWP	DEQUEEN - MENA DEAD TREE REMOVAL	35600 - Overhead Conductors, Device	08/01/2017	2,842
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL029945SWP	MURFREESBORO TAP DEAD TREE REMOVAL - NORGAARD	35600 - Overhead Conductors, Device	08/01/2017	225
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL029954SWP	ASHDOWN PATTERSON DEAD TREE REMOVAL - NORGAARD	35600 - Overhead Conductors, Device	08/01/2017	2,306
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL030414SWP	SOUTH NASHVILLE - SO MUF DEAD TREE - NORGAARD	35600 Overhead Conductors, Device	08/01/2017	19,358
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL030570SWP	GREENLAND VBI NORT RE BUILD CLEARING - NORGAARD	35600 - Overhead Conductors, Device	06/01/2017	412
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL030736SWP	DYESS - FLINT CREEK R/W WIDENING - NORGAARD	35600 - Overhead Conductors, Device	12/01/2017	656
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL030739SWP	ABBOTT TEE - WALDRON HAZARD TREE NORGAARD	35600 - Overhead Conductors, Device	12/01/2017	293
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL030931SWP	GREENLAND - VBI NORT EMERGENCY PATROL HOBSON	35600 - Overhead Conductors, Device	10/01/2017	1,857
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL031114SWP	DIERKS - MENA R/W DEAD TREE - NORGAARD	35600 Overhead Conductors, Device	11/01/2018	9,348
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL031372SWP	PATTERSON - SOUTH DI DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	01/01/2018	32,258
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL031725SWP	GREENLAND VBI NORT TREE REMOVAL - NORGAARD	35600 - Overhead Conductors, Device	01/01/2019	6,252
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL032405SWP	OKAY - PATTERSON - DANGER TREE - NORGAARD	35600 - Overhead Conductors, Device	11/01/2018	296
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL032469SWP	EUREKA SPRINGS HAR HAZARD AND DANGER TREE - NORGAARD	35600 - Overhead Conductors, Device	01/01/2019	27,811
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL032638SWP	SOUTH DIERKS- DIERKS DEAD TREE REMOVAL - NORGAARD	35600 - Overhead Conductors, Device	11/01/2018	586
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL032736SWP	EAST ROGERS - BEAVER R/W WIDENING NORGAARD	35600 - Overhead Conductors, Device	03/01/2019	38,688
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL032760SWP	ASHDOWN - TWELFTH DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	12/01/2018	877
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL032880SWP	DEQUEEN - NASHVILLE R/W DEAD TREE NORGAARD	35600 - Overhead Conductors, Device	01/01/2019	11,671
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL032881SWP	MURFREESBORO W NASHV DEAD TREE NORGAARD	35600 - Overhead Conductors, Device	01/01/2019	1,457
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL033441SWP	PATTERSON SOUTH DI DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	01/01/2019	2,739
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL033634SWP	DIERKS WEST MURFRE DEAD TREE NORGAARD	35600 - Overhead Conductors, Device	03/01/2019	996
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL033635SWP	TURK - SE TEXARKANA DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	08/01/2019	17,841
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL034203SWP	MURFREESBORO W NARROWS DAM 69KV #152 10 - R/W WIDENING-NORG	35600 - Overhead Conductors, Device	07/01/2019	13,530
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL034485SWP	DYESS-SPRINGDALE N CAPITAL WIDING - NORGAARD	35600 - Overhead Conductors, Device	08/01/2019	3,942
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL035493SWP	CRAIG JCT-DEQUEE(AR) 138KV R/W WIDENING-NORGAARD	35600 - Overhead Conductors, Device	10/01/2019	1,116
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL035571SWP	SILOAM SPRINGS-W SILOAM GRDA 161KV #178 2 - R/W WIDENING-NOR	35600 - Overhead Conductors, Device	08/01/2019	406
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL036127SWP	DYESS-HYLAND 161KV - HAZARD TREE REMOV-NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	14,625
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL036128SWP	DYESS - EAST ROGERS HAZARD TREE REMOVAL - NORGAARD	35600 Overhead Conductors, Device	12/01/2019	5,298
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL036129SWP	FAYETTEVIL-VAN ASCHE HAZARD TREE - NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	2,239
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL036130SWP	BOONEVILLE - BRANCH HAZARD TREE - NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	3,586
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL036131SWP	CHAMBERS SPRING DY STORM DAMAGE - NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	1,144
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL036206SWP	HOSSTON-BLOOMBURG (AR) 69KV - STORM THS-NORGAARD	35600 Overhead Conductors, Device	12/01/2019	4,643
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012881	000012881 Forestry SEPAR non-NERC shadow	TL036297SWP	N MAGAZINE-DANVILLE 161KV CAP TREE REMOVAL NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	760
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL027027	MT PLEASANT - NEW 8 R/W WIDENING	35600 - Overhead Conductors, Device	07/01/2016	3,196
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL027414	PIRKEY - SCOTTSVILLE R/W WIDENING - BRAMLETT	35600 - Overhead Conductors, Device	07/01/2016	4,805
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL027415	LNGWD-SCOTTSVILL(TX) R/W WIDENING - BRAMLETT	35600 - Overhead Conductors, Device	08/01/2016	15,191
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL027416	BAN - IPC DOMINO R/W WIDENING - BRAMLETT	35600 - Overhead Conductors, Device	01/01/2017	1,099
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL027540	IPC DOMINO - WEST AT R/W WIDENING PHILLIPS	35600 - Overhead Conductors, Device	07/01/2016	13,501
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL027672	PETTY - WILKES R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	1,113
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL027757	DIANA - PLILER RD 138KV #249 20 - TREE REMOVAL KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	11,892
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL027795	LONE STAR SOUTH - PI R/W WIDENING - KUENNAN	35600 - Overhead Conductors, Device	07/01/2016	570
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL027889	JEFFERSON - NORTH MA R/W WIDENING KEUNNANA	35600 - Overhead Conductors, Device	07/01/2016	459
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL027962	GILMER - PERDUE R/W WIDENING - KEUNNEN	35600 - Overhead Conductors, Device	01/01/2017	788
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL028139	MINEOLA - NORTH MIEO R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	1,895
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL028223	DANGERFIELD - HUGHES R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	09/01/2016	631
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL028721	CLARKSVILLE PERDUE R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	12/01/2016	3,221
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL028826	PITTSBURG - WINNSBOR R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	8,549
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL028864	DANGERFIELD - HUGHES DANGER TREES - CORBIN	35600 - Overhead Conductors, Device	05/01/2017	9,424
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL028992	DIANA - LONE STAR SO R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	10,898
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL029089	GILMER - PITTSBURG R/W WIDENING KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	2,217
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL029094	IPC DOMINO - WEST AT R/W WIDENING - CORBIN	35600 Overhead Conductors, Device	06/01/2017	1,238
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL029095	HUGHES SPRING - LIND R/W WIDENING - CORBIN	35600 Overhead Conductors, Device	06/01/2017	4,731
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL029096	W CHILDRESS SHAMROCK R/W WIDENING - CORBIN	35600 - Overhead Conductors, Device	05/01/2017	25,600
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL029107	NORTHWEST TEXARKANA1 R/W WIDENING - CORBIN	35600 - Overhead Conductors, Device	06/01/2017	419
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL029140	GRAND SALINE - MINEO R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	394

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL029269	ATLANTA - LINDEN R/W DEAD TREE AND LARGE REMOVALS - CORBIN	35600 - Overhead Conductors, Device	08/01/2017	1,843
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL029287	FLOURNOY - WOODLAW3 TREE REMOVAL - KUENNEN	35600 - Overhead Conductors, Device	02/01/2017	543
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL029288	MIDVALLEY PIPELINE T TREE REMOVAL - KUENNEN	35600 - Overhead Conductors, Device	02/01/2017	3,076
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL029376	WEST ATLANTA WILKE DEAD TREE KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	5,687
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL029474	GILMER - PERDUE _DEAD TREE - STORM KUENNEN	35600 - Overhead Conductors, Device	02/01/2017	1,200
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL029917	PETTY WILKES DEAD TREE - KUENNEN	35600 - Overhead Conductors, Device	10/01/2017	2,277
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL029946	JEFFERSON - NORTH MA DEAD TREE - KUENNEN	35600 - Overhead Conductors, Device	10/01/2017	2,151
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL030156	NORTH NEW BOSTON - HAZZARD TREE NON-NERC KUENNEN	35600 - Overhead Conductors, Device	10/01/2017	3,122
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL030322	N NEW BOSTON - WILKES 138KV - TREE REMOVAL CORBIN	35600 - Overhead Conductors, Device	10/01/2017	4,468
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL030334	PLILER ROAD - WHITNE OROW HAZARD TREE - PILKINGTON	35600 - Overhead Conductors, Device	11/01/2018	2,990
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL030400	LOGANSPORT-TENAHA HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	359
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL030513	NETTLETON TEXOMA TAP DEAD TREE CORBIN	35600 - Overhead Conductors, Device	11/01/2017	1,323
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL030610	BANN - NEW BOSTON HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	2,680
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL030873	HARRISON ROAD - KNOX HAZARD TREE - CORBIN	35600 Overhead Conductors, Device	11/01/2017	1,190
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL031013	JEFFERSON SWITCHING2 DANGER TREE HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	438
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL031344	EASTEX SWITCHING ST5 HAZARD TREE - HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	5,511
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL031391	LONE STAR ORDINANCE HAZARD TREE CORBIN	35600 - Overhead Conductors, Device	11/01/2017	772
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL031440	MINEOLA - NORTH MIEO HAZARD TREE - HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2018	3,869
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL031999	NORTH NEW BOSTON - W R/W HAZARD TREE	35600 - Overhead Conductors, Device	11/01/2018	431
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL032120	PILGRIM'S PRIDE - WIN - DANGER TREE- HIGHTOWER	35600 - Overhead Conductors, Device	11/01/2018	349
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL032230	IPC DOMINO - WEST AT R/W WIDENING CORBIN	35600 - Overhead Conductors, Device	01/01/2019	140,464
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL032370	DIANA PURDUE DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	11/01/2018	369
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL032454	NORTHWEST HENDER-POY - DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2019	2,277
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL032580	ATLANTA - LINDEN R/W WIDENING	35600 Overhead Conductors, Device	10/01/2018	4,336
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL032794	MT PLEASANT - NEW - DANGER TREE - CORBIN	35600 Overhead Conductors, Device	01/01/2019	5,061
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL032877	PIRKEY - SCOTTSVILLE DANGER TREE - HIGHTOWER	35600 Overhead Conductors, Device	12/01/2018	3,697
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL032878	MT PLEASANT - PETTY DANGER TREE - HIGHTOWET	35600 - Overhead Conductors, Device	01/01/2019	4,835
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL032932	DIANA SW SHRPRT (TX) DANGER TREE HIGHTOWER	35600 - Overhead Conductors, Device	01/01/2019	1,636
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL033012	EVENSIDE - POYNTER DEAD TREE - HIGHTOWER	35600 - Overhead Conductors, Device	01/01/2019	138
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL033047	WINNSBORO NO MINEOLA DAMAGE CLAIM HIGHTOWER	35600 - Overhead Conductors, Device	01/01/2019	7,905
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL033106	JEFFERSON SWITCHING1 DANGER TREE REMOVAL - HIGHTOWER	35600 - Overhead Conductors, Device	01/01/2019	475
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL033131	MARSHALL 69 ROCK H - HIGHTOWER	35600 - Overhead Conductors, Device	01/01/2019	494
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL033218	HAWKINS - MINEOLA DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2019	771
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL033224	DIANA - PLILER ROAD - DANGER TREE HIGHTOWER	35600 Overhead Conductors, Device	02/01/2019	2,352
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL033289	BANN - THIRTY NINTH HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	02/01/2019	1,402
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non NERC parent	TL033373	BECKVILLE - POYNTER R/W WIDENING - HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2019	4,529
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL033731	W ATLANTA LINDEN 69KV #201 20 - R/W WIDENING-CORBIN	35600 - Overhead Conductors, Device	03/01/2019	543
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL033737	EASTEX SWITCHING ST5 - DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	03/01/2019	506
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL033928	HAWKINS PERDUE DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	03/01/2019	1,154
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL034458	DAINGERFIELD - MT P R/W DANGER TREE CORBIN	35600 - Overhead Conductors, Device	10/01/2019	789
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL034462	CARTHAGE - MURVAUL R DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	08/01/2019	318
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL034463	LONGWOOD-WILKES(TX) DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	08/01/2019	1,877
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL034548	BLOOMBURG ATLANTADANGER TREE - CORBIN	35600 - Overhead Conductors, Device	10/01/2019	187
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL034580	HAWKINS - MINEOLA DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	08/01/2019	866
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL034623	WINNSBORO-NO MINEOLA DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2020	389
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL034774	FLOURNOY - WOODLAW1 DANGER TREE - CORBIN	35600 - Overhead Conductors, Device	10/01/2019	622
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL035202	CARTHAGE - MURVAUL R STORM - PILKINGTON	35600 - Overhead Conductors, Device	12/01/2019	2,593
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL035556	IPC DOMINO - W ATLANTA 138KV #241 7 - DANGER TREE REMV-CORBI	35600 - Overhead Conductors, Device	12/01/2019	767
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL035828	WINFIELD - WINNSBORO NONNERC - DANGER TREE REMOVAL-HIGHTOWER	35600 - Overhead Conductors, Device	03/01/2020	2,714
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012900	000012900 Forestry SEPTX non-NERC parent	TL036060	DIANA PLILER ROAD 138KV #249 - DANGER TREE REMOV-HIGHTOWER	35600 - Overhead Conductors, Device	08/01/2019	3,854
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL0036496	CHAMBERS SPRING - FLINT CREEK 161KV - NORGAARD CAPITAL TREE	35600 - Overhead Conductors, Device	12/01/2019	423
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL0036724	EAST CENTERTON - NORTH ROGERS CAPITAL HAZARD TREE - NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	4,011
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL025790	PRAIRIE GROVE SILO R/W WIDENING - PHILLIPS	35600 - Overhead Conductors, Device	07/01/2016	9,096
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL026600	NORTHWEST TEXARKANA REA-RICHMOND RD 69KV	35600 Overhead Conductors, Device	01/01/2017	1,553
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL027017	EUREKA SPRINGS - HAR R/W WIDENING	35600 - Overhead Conductors, Device	07/01/2016	7,707
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL027018	N MAGAZINE-DANVILLE R/W WIDENING	35600 - Overhead Conductors, Device	07/01/2016	11,278
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL027399	DYESS-SPRINGDALE N R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	6,161
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL027403	SOUTH DIERKS- DIERKS R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	477
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL027776	N HUNTINGTON-WALDRON R/W WIDENING BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	2,537
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL027778	BOONEVILLE - WEST BO R/W WIDENING - BELWEY	35600 - Overhead Conductors, Device	07/01/2016	223
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL027782	OKAY - PATTERSON R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	4,293
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL027783	ASHDOWN - PATTERSON R/W WIDENING BEWLEY	35600 - Overhead Conductors, Device	10/01/2016	3,045
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL027784	DEQUEEN - PATTERSON R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	10,224
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL027786	DIERKS - MENA R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	8,881
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL027787	FULTON P-PATMOS AP&L R/W WIDENING - BEWLEY	35600 - Overhead Conductors, Device	07/01/2016	(948)
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL028382	SOUTH NASHVILLE - SO R/W WIDENING - KUENNAN	35600 Overhead Conductors, Device	07/01/2016	23,655
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL028632	SOUTH NASHVILLE SO R/W WIDENING JUENNEN	35600 - Overhead Conductors, Device	08/01/2016	49,582
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL028852	PATTERSON - NEKOOSA- R/W DEAD TREE REMOVAL - KUENNAN	35600 - Overhead Conductors, Device	01/01/2017	1,754
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL028979	SOUTH NASHVILLE - SO R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	18,392
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL029377	DEQUEEN - MENA R/W WIDENING - NORGAARD	35600 - Overhead Conductors, Device	02/01/2017	59,230
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012901	000012901 Forestry SEPAR non NERC parent	TL029500	DYESS-HYLAND DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	10/01/2017	10,256

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL029567	CRAIG JCT-DEQUEE(AR) HOT SPOT	35600 - Overhead Conductors, Device	06/01/2017	301
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL029725	CHAMBERS SPRING - DY DANGER TREE NORGAARD	35600 - Overhead Conductors, Device	10/01/2017	2,003
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL029940	DEQUEEN - MENA DEAD TREE REMOVAL	35600 - Overhead Conductors, Device	08/01/2017	5,531
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL029945	MURFREESBORO TAP DEAD TREE REMOVAL - NORGAARD	35600 Overhead Conductors, Device	08/01/2017	438
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL029954	ASHDOWN - PATTERSON DEAD TREE REMOVAL - NORGAARD	35600 - Overhead Conductors, Device	08/01/2017	4,488
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL030414	SOUTH NASHVILLE - SO MUF DEAD TREE NORGAARD	35600 - Overhead Conductors, Device	08/01/2017	37,677
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL030570	GREENLAND - VBI NORT RE-BUILD CLEARING - NORGAARD	35600 - Overhead Conductors, Device	06/01/2017	821
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL030736	DYESS - FLINT CREEK R/W WIDENING - NORGAARD	35600 - Overhead Conductors, Device	12/01/2017	1,277
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL030739	ABBOTT TEE - WALDRON HAZARD TREE NORGAARD	35600 - Overhead Conductors, Device	12/01/2017	569
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL030931	GREENLAND - VBI NORT EMERGENCY PATROL - HOBSON	35600 - Overhead Conductors, Device	10/01/2017	3,652
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL031114	DIERKS - MENA R/W DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	11/01/2018	18,195
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012901	000012901 Forestry SEPAR non NERC parent	TL031372	PATTERSON - SOUTH DI DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	01/01/2018	62,786
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non NERC parent	TL031725	GREENLAND - VBI NORT TREE REMOVAL - NORGAARD	35600 - Overhead Conductors, Device	01/01/2019	18,846
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL032405	OKAY PATTERSON DANGER TREE - NORGAARD	35600 - Overhead Conductors, Device	11/01/2018	577
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL032469	EUREKA SPRINGS - HAR HAZARD AND DANGER TREE - NORGAARD	35600 - Overhead Conductors, Device	01/01/2019	60,465
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non NERC parent	TL032638	SOUTH DIERKS DIERKS DEAD TREE REMOVAL - NORGAARD	35600 - Overhead Conductors, Device	11/01/2018	1,141
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL032736	EAST ROGERS - BEAVER R/W WIDENING - NORGAARD	35600 - Overhead Conductors, Device	03/01/2019	92,876
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL032760	ASHDOWN - TWELFTH DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	12/01/2018	1,706
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL032880	DEQUEEN NASHVILLE R/W DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	01/01/2019	23,944
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL032881	MURFREESBORO W-NASHV DEAD TREE - NORGAARD	35600 Overhead Conductors, Device	01/01/2019	2,835
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL033441	PATTERSON SOUTH DI DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	01/01/2019	13,854
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL033634	DIERKS - WEST MURFRE DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	03/01/2019	1,939
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL033635	TURK - SE TEXARKANA DEAD TREE - NORGAARD	35600 - Overhead Conductors, Device	08/01/2019	34,725
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL034203	MURFREESBORO W -NARROWS DAM 69KV #152 10 - R/W WIDENING-NORG	35600 - Overhead Conductors, Device	07/01/2019	26,334
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL034485	DYESS-SPRINGDALE N CAPITAL WIDING NORGAARD	35600 - Overhead Conductors, Device	08/01/2019	7,673
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL035493	CRAIG JCT-DEQUEE(AR) 138KV R/W WIDENING-NORGAARD	35600 - Overhead Conductors, Device	10/01/2019	2,172
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL035571	SILOAM SPRINGS W SILOAM GRDA 161KV #178 2 - R/W WIDENING-NOR	35600 - Overhead Conductors, Device	08/01/2019	789
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL036127	DYESS HYLAND 161KV - HAZARD TREE REMOV-NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	28,465
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL036128	DYESS EAST ROGERS HAZARD TREE REMOVAL - NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	10,313
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL036129	FAYETTEVIL-VAN ASCHE HAZARD TREE NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	4,359
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL036130	BOONEVILLE - BRANCH HAZARD TREE - NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	6,979
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL036131	CHAMBERS SPRING - DY STORM DAMAGE - NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	2,227
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL036206	HOSSTON-BLOOMBURG (AR) 69KV - STORM THS-NORGAARD	35600 - Overhead Conductors, Device	12/01/2019	9,036
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012901	000012901 Forestry SEPAR non-NERC parent	TL036297	N MAGAZINE-DANVILLE 161KV - CAP TREE REMOVAL-NORGAARD	35600 Overhead Conductors, Device	12/01/2019	1,479
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027304	LIEBERMAN - LONGWOOD R/W WIDENING - BRAMLETT	35600 - Overhead Conductors, Device	07/01/2016	527
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non NERC parent	TL027417	LONGWOOD-WILKES(LA) R/W WIDENING - BRAMLETT	35600 - Overhead Conductors, Device	08/01/2016	554
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027471	LONGWOOD-SCOTTSVILLE R/W WIDENING - PHILLIPS	35600 - Overhead Conductors, Device	09/01/2016	1,274
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027758	LOGANSPORT STONEWALL 138KV #107 4 - TREE REMOVAL-KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	2,227
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027774	FORT HUMBUG - SOUTH R/W WIDENING - KUENNAN	35600 - Overhead Conductors, Device	07/01/2016	724
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027834	BLANCHARD - NORTH MA R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	451
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027878	HOSSTON - NORTH BENT R/W WIDENING - KUENNAN	35600 - Overhead Conductors, Device	07/01/2016	918
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027961	FLOURNOY - HARDY STR R/W WIDENING KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	2,087
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027963	CALUMET-GETTY OIL R/W WIDENING - KEUNNEN	35600 - Overhead Conductors, Device	07/01/2016	220
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027964	MANY - BELMONT R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	584
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027965	MANY - NEGREET R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	132
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027966	ROBSON ROAD(POD-KING R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	220
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL027969	HOSSTON-BLMBRG (LA) R/W WIDENING - KEUNNEN	35600 Overhead Conductors, Device	07/01/2016	440
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL028009	RED POINT BELLEVUE R/W WIDENING KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	956
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL028010	RED POINT - WHITEHUR R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	230
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL028072	FLOURNOY - SUMMER GR R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	07/01/2016	2,382
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL028176	SOUTH SHREVEPORT - 2 R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	02/01/2017	431
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL028297	GENERAL MOTORS SOU R/W WIDENING KUENNEN	35600 - Overhead Conductors, Device	09/01/2016	876
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL028298	SOUTHWEST SHREVEP-WE R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	09/01/2016	1,470
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL028494	MARTHAVILLE-ROBELINE R/W WIDENING - CASSANDRA	35600 Overhead Conductors, Device	09/01/2016	281
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL028515	SEVENTIETH STREET TA R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	09/01/2016	1,302
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL028796	SOUTHWEST SHREVEP-WE R/W WIDENING 138KV C KUENNEN	35600 Overhead Conductors, Device	02/01/2017	265
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL029052	ARSENAL HILL-LONGWOD R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	2,703
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL029187	LONGWOOD-SCOTTSVILLE R/W WIDENING - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	451
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL029230	STONEWALL TAP R/W TREE REMOVAL - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	6,916
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL029417	IPC JEFFERSON - LIE2 DEAD TREE- KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	13,479
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non NERC parent	TL029467	LOGANSPORT - STONEWA DEAD TREE - KUENNEN	35600 - Overhead Conductors, Device	01/01/2017	1,967
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL029544	LIEBERMAN - LONGWOOD YARD TREES - KUENNEN	35600 - Overhead Conductors, Device	02/01/2017	1,903
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL029918	LOGANSPORT - STONEWA DEAD TREE - KUENNEN	35600 - Overhead Conductors, Device	10/01/2017	5,938
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL029959	SOUTHWEST SHREVEP-WE OROW HAZARD TREE - PILKINGTON	35600 Overhead Conductors, Device	04/01/2017	1,986
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL029984	STONEWALL TAP DANGER TREE - KUENNEN	35600 - Overhead Conductors, Device	10/01/2017	511
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL030339	RED POINT - WHITEHUR HAZARD TREE REMOVAL - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	2,510
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL030340	IPC JEFFERSON - LIE2 DEAD TREE REMOVAL	35600 - Overhead Conductors, Device	11/01/2017	570
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL030341	WALLACE LAKE MANSF DEAD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	444
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL030377	LOGANSPORT - STANLEY DEAD TREE - CORBIN	35600 Overhead Conductors, Device	11/01/2017	4,102
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL030413	ELLBERTE ROAD - FREN DEAD/DANGER TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	7,440
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non NERC parent	TL030653	FLOURNOY - HARDY STR HAZARD TREE REMOVAL - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	1,922

SWEPCO TRANSMISSION
Blanket/Program Projects

CPP_ID	CPP_DESC	PROJECT_ID	PROJ_DESC	WO_ID	WO_DESC	UTILITY_ACCOUNT	IN-SERVICE_DATE	ACTIVITY_COST
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL030789	LIEBERMAN - RED POIN HAZARD TREE - CORBIN	35600 Overhead Conductors, Device	11/01/2017	767
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL030790	TRICHEL STREET WHI HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	2,235
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL030805	BLANCHARD - LIEBERMA HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	2,648
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non NERC parent	TL030853	ELLBERTE ROAD - SOUT HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	431
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL030885	HOSSTON - SUPERIOR 2 HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	2,675
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL031003	FLOURNOY WOODLAW2 STORM HAZARD TREE - CORBIN	35600 - Overhead Conductors, Device	11/01/2017	550
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL031026	GENERAL MOTORS - SOU HAZARD TREE - HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	2,573
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL031028	FLOURNOY - LONGWOOD HAZARD TREE HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	2,389
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL031130	MANY - BELMONT DANGER TREE HIGHTOWER	35600 - Overhead Conductors, Device	04/01/2018	171
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL031137	BELMONT-MARTHAVILLE DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	10/01/2017	24,505
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non NERC parent	TL031262	ARSENAL HILL - LONGWOOD (127 1), SWEPCO LA, NON-NERC, $5,000	35600 Overhead Conductors, Device	04/01/2018	428
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non NERC parent	TL031546	LOGANSPORT - STANLEY HAZARD TREE - HIGHTOWER	35600 - Overhead Conductors, Device	06/01/2018	435
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL031808	HOSSTON-BLMBRG (LA) HAZARD TREE	35600 - Overhead Conductors, Device	11/01/2018	1,196
TREESSWEP	TREESSWEP Forestry T&D Widening SWEPCo	000012902	000012902 Forestry SEPLA non NERC parent	TL032086	CALUMET-GETTY OIL DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	11/01/2018	411
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non NERC parent	TL032222	HOSSTON - SUPERIOR 2 R/W WIDENING - HIGHTOWER	35600 - Overhead Conductors, Device	11/01/2018	8,706
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL032393	SOUTH SHREVEPORT - WALLACE LAKE DANGER TREE HIGHTOWER	35600 Overhead Conductors, Device	11/01/2018	302
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL032496	FORT HUMBUG - SOUTH DANGER TREE	35600 - Overhead Conductors, Device	11/01/2018	4,635
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL032600	N LEESVILLE-HORNBECK HIGHTOWER - DANGER TREE	35600 - Overhead Conductors, Device	01/01/2019	8,341
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL032641	FLOURNOY - LONGWOOD DANGER TREE HIGHTOWER	35600 - Overhead Conductors, Device	12/01/2018	5,214
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL032733	FLOURNOY - SUMMER GR R/W DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	12/01/2018	1,740
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL032857	BELCHER - HOSSTON DANGER TREE REMOVAL	35600 - Overhead Conductors, Device	01/01/2019	2,092
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL032928	HOSSTON - NORTH BENT DANGER TREE	35600 - Overhead Conductors, Device	01/01/2019	4,395
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL033057	E LEESVILLE - HICKS DANGER TREE	35600 - Overhead Conductors, Device	01/01/2019	3,231
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL033389	HOSSTON - NORTH BENT DANGER TREE	35600 - Overhead Conductors, Device	02/01/2019	9,324
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL034020	ARSENAL HILL-LONGWOD DANGER TREE HIGHTOWWER	35600 - Overhead Conductors, Device	03/01/2019	566
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL034452	JEFFERSON - SUPERIO1 DANGER TREE - JASON	35600 - Overhead Conductors, Device	08/01/2019	2,983
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL034661	SOUTH SHREVEPORT - WALLACE LAKE - DANGER TREE - HIGHTOWER	35600 - Overhead Conductors, Device	02/01/2020	1,206
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL034768	MARTHAVILLE-ROBELINE 69KV #V-102 - DANGER TREE REM-HIGHTOWER	35600 - Overhead Conductors, Device	10/01/2019	3,419
TREESSWEP	TREESSWEP Forestry T&D Widening - SWEPCo	000012902	000012902 Forestry SEPLA non-NERC parent	TL035288	LOGANSPORT - STONEWALL 138KV #107 1 DANGER TREE REMO HIGHT	35600 - Overhead Conductors, Device	08/01/2019	2,776
	TREESSWEP Forestry T&D Widening - SWEPCo Total							2,737,054
	Grand Total							114,928,658

AMERICAN® ELECTRIC POWER

AEP Transmission Planning Criteria and Guidelines for End-Of-Life and Other Asset Management Needs

December 2020

Document Control

Document Review and Approval

Action	Name(s)	Title
Prepared by:	Jomar M. Perez	Manager, Asset Performance and Renewal
Approved by:	Nicolas Koehler	Director, East Transmission Planning
Approved by:	Wayman L. Smith	Director, West Transmission Planning
Approved by:	Kamran Ali	Managing Director, Transmission Planning

Review Cycle

Quarterly	Semi-annual	Annual	As Needed
			X

Revision History

Version	Revision Date	Changes	Comments
1.0	01/04/2017	N/A	1st Release
2.0	1/18/2018	Format Update	2nd Release
3.0	11/09/2018	Content Additions	3rd Release
4.0	12/14/2020	End-Of-Life Criteria	4th Release

Table of Contents

1.0 Introduction 4

2.0 Process Overview 6

3.1 Methodology and Process Overview 8

3.2 Asset Condition (Factor 1) 8

3.2.1 Transmission Line Considerations 9

3.2.2 Substation Considerations 10

3.3 Historical Performance (Factor 2) 11

3.4 Future Risk (Factor 3) 12

4.0 Step 2: Solution Development 14

5.0 Step 3: Solution Scheduling 14

6.0 Conclusion 15

7.0 References 15

1.0 Introduction

The American Electric Power (AEP) transmission system consists today of approximately 40,000 miles of transmission lines, 3,600 stations, 5,000 power transformers, 8,000 circuit breakers, and operating voltages between 23 kV and 765 kV in three different RTOs – the Electric Reliability Council of Texas (ERCOT), the PJM Interconnection (PJM), and the Southwest Power Pool (SPP), connecting over 30 different electric utilities while providing service to over 5.4 million customers in 11 different states.

AEP's interconnected transmission system was established in 1911 and is comprised of a very large and diverse combination of line, station, and telecommunication assets, each with its own unique installation date, design specifications, and operating history. As the transmission owner, it is AEP's obligation and responsibility to manage and maintain this diverse set of assets to provide for a safe, adequate, reliable, flexible, efficient, cost-effective and resilient transmission system that meets the needs of all customers while complying with Federal, State, RTO and industry standards. This requires, among other considerations, that AEP determine when the useful life of these transmission assets is coming to an end and when the capability of those assets no longer meets current needs, so that appropriate improvements can be deployed. AEP refers to these issues as transmission owner identified needs that address condition, performance and risk. AEP identifies these needs through the transmission planning criteria and guidelines outlined in this document. Specifically, this document constitutes the AEP transmission planning criteria and guidelines for End-Of-Life and other asset management needs as required in the FERC-approved Attachment M-3 to the PJM Tariff. AEP does not address any End-Of-Life or other asset management needs through the baseline planning criteria AEP files with its FERC Form 715.

AEP's transmission owner identified needs must be addressed to achieve AEP's obligations and responsibilities. Meeting these obligations requires that AEP ensures the transmission system can deliver electricity to all points of consumption in the quantity and quality expected by customers, while reducing the magnitude and duration of disruptive events. Given these considerations, criteria and guidelines are necessary to identify and quantify needs associated with transmission facilities comprising AEP's system. AEP identifies the needs and the solutions necessary to address those needs on a continuous basis using an in-depth understanding of the condition of its assets, and their

associated operational performance and risk, while exercising engineering judgment coupled with Good Utility Practices [1].

Whereas the End-Of-Life needs, as defined in the FERC-approved Attachment M-3 to the PJM Tariff, are limited to transmission facilities rated above 100 kV, these criteria and guidelines apply to all transmission voltages that comprise the AEP transmission system, including those defined as End-Of-Life needs in the FERC-approved Attachment M-3 to the PJM Tariff. In addition, projections of candidate End-Of-Life needs that result from the process outlined in these AEP criteria and guidelines will be provided to PJM in accordance with the provisions in the FERC-approved Attachment M-3 to the PJM Tariff. Current End-Of-Life and other asset management needs will be vetted with stakeholders in accordance with the provisions in the FERC-approved Attachment M-3 to the PJM Tariff.

Addressing these owner identified transmission system asset management needs, as they pertain to condition, performance and risk, will result in the following benefits to customers:

- Safe operation of the electric grid.
- Reduction in frequency of outage interruptions.
- Reduction in duration of outage interruptions.
- Improvement in service reliability and adequacy to customers.
- Reduction of risk of service disruptions (improved resilience) associated with man-made and environmental threats.
- Proactive correction of reliability constraints that stem from asset failures.
- Effective utilization of resources to provide efficient and cost-effective service to customers.

2.0 Process Overview

AEP's transmission owner needs identification criteria and guidelines are used for projects that address equipment material conditions, performance, and risk. AEP uses the three-step process shown in Figure 1 and discussed in detail in this document to determine the best solutions to address the transmission owner identified needs and meet AEP's obligations and responsibilities. This process is completed on an annual basis. In developing the most efficient and cost-effective solutions, AEP's long-term strategy is to pursue holistic transmission solutions in order to reduce the overall AEP transmission system needs.

Figure 1 – AEP Process for Identifying and Addressing Transmission Asset Condition, Performance and Risk Needs

3.0 Step 1: Needs Identification

Needs Identification is the first step in the process of determining system and asset improvements that help meet AEP's obligations and responsibilities. AEP gathers information from many internal and external sources to identify assets with needs. A collective evaluation of these inputs is conducted and considered, and thus, individual thresholds do not apply. In addition, factors can change over time. A sampling of the inputs and data sources is listed below in Table 1.

Table 1 – Inputs Considered by AEP to Identify Transmission System Needs

Internal, External, or Both	Inputs	Examples
Internal	Reports on asset conditions	Transmission line and station equipment deterioration identified during routine inspections (pole rot, steel rusting or cracking)
	Capabilities and abnormal conditions	Relay misoperations; Voltage unbalance
	Legacy system configurations	Ground switch protection schemes for transformers;; Transmission Line Taps without switches (hard taps); Equipment without vendor support
	Outage duration and frequency	Outages resulting from equipment failures, misoperations, or inadequate lightning protection
	Operations and maintenance costs	Costs to operate and maintain equipment
External	Regional Transmission Operator (RTO) or Independent System Operator (ISO) issued notices	Post Contingency Local Load Relief Warnings (PCLLRWs) issued by the RTO that can lead to customer load impacts
	Stakeholder input	Input received through stakeholder meetings, such as PJM's Sub Regional RTEP Committee (SRRTEP) meetings or through the AEP hosted Annual Stakeholder Summits
	Customer feedback	Voltage sag issues to customer delivery points due to poor sectionalizing; frequent outages to facilities directly affecting customers
	State and Federal policies, standards, or guidelines	NERC standards for dynamic disturbance recording
Both	Environmental and community impacts	Equipment oil/gas leaks; facilities currently installed at or near national parks, national forests, or metropolitan areas
	Standards and Guidelines	Minimum Design Standards, Radial Lines, Three Terminal Lines, Overlapping Zones of Protection
	Safety risks and concerns	Station and Line equipment that does not meet ground clearances; Facilities identified as being in flood zones; New Occupational Safety and Hazards Administration (OSHA) regulations

These inputs are reviewed and analyzed to identify the transmission assets that are exhibiting unacceptable condition, performance and risk, and thus, must be addressed through the FERC-approved Attachment M-3 planning process.

3.1 Methodology and Process Overview

The AEP transmission system is composed of a very large number of assets that provide specific functionality and must work in conjunction with each other in the operation of the grid. These assets have been deployed over a long period of time using engineering principles, design standards, safety codes, and Good Utility Practices that were applicable at the time of installation and have been exposed to varying operating conditions over their life. The Needs Identification methodology is shown below in Figure 2. AEP addresses the identified needs considering factors including severity of the asset condition and overall system impacts. These are subsequently evaluated versus constraints such as outage availability, siting requirements, availability of labor and material, constructability, and available capital funding in determining the timing and scope of mitigation.

Figure 2 – Needs Identification Methodology

It is AEP's strategy and goal to develop and provide the more efficient, cost-effective, safe, reliable, resilient, and holistic long-term solutions for the identified needs.

3.2 Asset Condition (Factor 1)

The Asset Condition assessment gathers a standard set of physical characteristics associated with an asset or a group of assets. The set of data points recorded is determined based on the asset type and class. Information assembled during the Asset Condition assessment is used to show the historical

deterioration, current condition, and future expectation of the asset or group of assets on the AEP system.

AEP annually assembles a list of reported condition issues for all of its assets in its system. A detailed follow-up review is conducted to determine if a transmission asset is in need of upgrade and/or replacement. Additionally, this Asset Condition review is used to determine an adequate scope of work required to mitigate the risk associated with a facility's performance and its identified issues. This level of risk is determined through the Future Risk assessment (Factor 3).

Beyond physical condition, AEP's ability to restore the asset in case of a failure is also considered. This is referred to as the future probability of failure adder. Typically, assets that are no longer supported by manufacturers or lack available spare parts are assigned a higher probability of failure adder.

To perform condition assessments, AEP classifies its Transmission assets in two main categories: Transmission Lines and Substations.

3.2.1 Transmission Line Considerations

Design Portion

A. Age (Original Installation Date)
B. Structure Type (Wood, Steel, Lattice)
C. Conductor Type (Size, Material & Stranding)
D. Static Wire Type (Size & Material)
E. Foundation Type (Grillage, Direct Embed, Caisson, Guyed V, Drilled Pier etc.)
F. Insulator Type (Material)
G. Shielding and Grounding Design Criteria (Ground Rod, Counterpoise, "Butt Wrap" etc.)
H. Electrical Configuration
    a. Three Terminal Lines
    b. Radial Facilities
I. NESC Standards Compliance
    a. Structural Strength (NESC 250B, 250C & 250D Compliance)
    b. Clearances (TLES-047 Compliance)

J. Easement Adequacy (Width, Encroachments, Type; etc.)

Physical Condition

A. Open Conditions (existing and unaddressed physical conditions associated with a Transmission Line component)
B. Closed Conditions (previously addressed physical conditions associated with a Transmission Line component)
C. Emergency Fixes (History of emergency fixes)
D. Accessibility (Identified areas of difficult access)

3.2.2 Substation Considerations

A. Transformers
   a. Manufacturer
   b. Manufacturing Date
   c. In Service Date
   d. Load Tap Changer Type & Operation History (if applicable)
   e. Dissolved Gas Analysis
   f. Bushing Power Factor
   g. Through Fault Events (Duval Triangles)
   h. Moisture Content (Oil)
   i. Oil Interfacial Tension
   j. Dielectric Strength
   k. Maintenance History
   l. Malfunction Records
B. Circuit Breakers
   a. Manufacturer & Type
   b. Manufacturing Date
   c. In Service Date
   d. Interrupting Medium
   e. Fault Operations
   f. Switched Operations

g. Spare Part Availability
h. Maintenance History
i. Malfunction Records
j. Breaker Type Population

C. Secondary/Auxiliary Substation Equipment*
a. Station Batteries
b. Control House
c. Station Security
d. Station Structures
e. Capacitor Banks
f. Bus, Cable and Insulators
g. Disconnect Switches
h. Station Configuration
i. Station Service
j. Relay Types
k. RTU Types
l. Voltage Sensing Devices

**AEP substation inspections include assessments of secondary/ancillary equipment If needed, upgrades to these components are typically included in the scope of projects addressing major equipment and may not necessarily drive stand-alone projects*

3.3 Historical Performance (Factor 2)

AEP's Historical Performance assessment quantifies how an asset or a group of assets has historically impacted the Transmission system's reliability and Transmission connected customers, helps identify the primary contributing factors to a facility's performance, and baselines the outage probability used in our Future Risk analysis. The metrics used as part of this historical performance assessment include:

A. Forced Outage Rates
B. Manual Outage Rates
C. Outage Durations (Forced Outage Duration in Hours)
D. System Average Interruption Indices (T-SAIDI, T-SAIFI, T-SAIFI-S, T-MAIFI)

E. Customer Minutes of Interruption (CMI)

F. Customer Average Interruption Indices (IEEE SAIDI, CAIDI & SAIFI)

G. Number of Customers Interrupted (CI)

AEP utilizes this standard set of metrics as a means to quantify the historical performance of an asset. These historical performance metrics allow AEP to further investigate assets that have historically impacted customers the most.

Due to the vast size of the AEP operating territory covering 11 states, AEP segments its needs into seven distinct operating company regions and six voltage classes. This segmentation ensures that variations in geography with respect to vegetation, weather patterns, and terrain can be accounted for within the process of identifying needs for each operating company area. In addition to customers of AEP operating companies, consideration for retail customers that are served at non-AEP wholesale customer service points is also included. In order to account for customers served behind wholesale meter points, AEP gathers information from the parent wholesale provider or in its absence, applies a surrogate customers per MW ratio to estimate the number of customers served by a wholesale power provider's delivery point. This customer count is used to calculate the individual metrics above.

AEP's standard approach is to annually review the historical performance of its assets based on a rolling three-year average, but in some cases AEP may extend the review period beyond three years. AEP classifies all transmission asset outage causes into the following five categories to conduct this review: Transmission Line Component Failure, Substation Component Failure, Vegetation (AEP), Vegetation (Non-AEP), and External Factors. Each transmission asset and its associated performance is quantified and compared against corresponding system totals to determine its percentage contribution to aggregated system performance. An evaluation of outage rates is also performed for Transmission line assets. The observed performance of the assets in any of these categories can point to a need that may need to be addressed.

3.4 Future Risk (Factor 3)

AEP reviews the associated risk exposure (future risk) inherent with each identified asset to determine an asset's level of risk. This risk exposure is quantified assuming the probability of an outage scenario

and is based on the reported condition of the asset and the severity of that condition and what the impact could be to customers or to the operation of AEP's Transmission system. Some of the key items to assess these impacts included in the risk criteria are:

A. Number of Customers Served
B. Load Served
C. Operational Risks
    a. Post Contingency Load Loss Relief Warnings (PCLLRW's)
    b. History of Load Shed Events
    c. Stations in Black Start Paths

In addition to the future risk calculation performed through this process, AEP is systematically reviewing its system to identify and remediate equipment and practices that have resulted in operational, restoration, environmental, or safety issues in the past that cannot be directly quantified, but that remain as acknowledged risks in the AEP Transmission system. These include:

A. Wood pole construction
B. Pilot wire protection schemes
C. Oil circuit breakers
D. Air Blast circuit breakers
E. Pipe type oil filled cables
F. Electromechanical relays
G. Legacy system configurations
    a. Missing or inadequate line switches (e.g., hard-taps)
    b. Missing or inadequate transformer/bus protection
    c. Three-terminal lines
    d. Overlapping zones of protection
H. Non-Standard Voltage Classes
I. Poor Lightning & Grounding Performance
J. Radial Facilities
K. Public vulnerability

These items as described above are reviewed on a case by case basis and considered when holistic system solutions are being developed.

4.0 Step 2: Solution Development

The development of solutions for the identified needs considers a holistic view of all of the needs in which several solution options are developed and scoped. AEP applies the appropriate industry standards, engineering judgment, and Good Utility Practices to develop these solution options. AEP solicits customer and external stakeholder input on potential solutions through the Annual Stakeholder Summits hosted by AEP and also through the PJM Project Submission process. This ensures that input from external stakeholders on identified needs can be received and considered as part of the solution development process.

Solution options consider many factors including, but not limited to, environmental conditions, community impacts, land availability, permitting requirements, customer needs, system needs, and asset conditions in ultimately identifying the best solution to address the identified need. Once the selected solution for a need or group of needs is defined, it is reviewed using the current RTO provided power-flow, short circuit, and stability system models (as needed) to ensure that the proposed solution does not adversely impact or create baseline planning criteria violations on the transmission grid. Finally, AEP reviews its existing portfolio of baseline planning criteria driven reliability projects and evaluates opportunities to combine or complement existing baseline planning criteria driven reliability projects with the transmission owner needs driven solutions developed through this process. This step ultimately results in the implementation of the more efficient, cost-effective, and holistic long-term solutions. Stand-alone projects are created to implement the proposed solution where transmission owner needs driven solutions cannot be integrated into existing projects.

5.0 Step 3: Solution Scheduling

Once solutions are developed to address the identified needs, the scheduling of the solutions will take place. As mentioned in the previous section, if opportunities exist to combine or complement existing baseline planning criteria driven reliability projects with the needs driven solutions developed

through this process, the scheduling will be aligned to the extent possible. In all other situations, AEP will schedule the implementation of the identified solutions in consideration of various factors including severity of the asset condition, overall system impacts, outage availability, siting requirements, availability of labor and material, constructability, and available capital funding. AEP uses its discretion and engineering judgment to determine suitable timelines for project execution.

6.0 Conclusion

This document outlines AEP's criteria and guidelines for transmission owner identified needs that address equipment material conditions, performance, and risk. It outlines the sources and methods considered by AEP to identify assets with needs on a continuous basis and it outlines how solutions are developed and scheduled. AEP will review and modify these criteria and guidelines as appropriate based upon our continuing experience with the methodology, acquisition of data sources, deployment of improved performance statistics and the receipt of stakeholder input in order to provide a safe, adequate, reliable, flexible, efficient, cost-effective and resilient transmission system that meets the evolving needs of all of the customers it serves.

7.0 References

[1] FERC Pro Forma Open Access Transmission Tariff, Section 1.14, Definition of "Good Utility Practice"
Link: https://www ferc.gov/legal/maj-ord-reg/land-docs/rm95-8-0aa.txt

[2] AEP Transmission Planning Documents and Transmission Guidelines.
Link: http://www.aep.com/about/codeofconduct/OASIS/TransmissionStudies/