



Filing Receipt

Received - 2021-10-29 11:25:41 AM
Control Number - 52299
ItemNumber - 763



DEPARTMENT OF THE AIR FORCE
HEADQUARTERS 7TH BOMB WING (AFGSC)
DYESS AIR FORCE BASE, TEXAS

29 October 2021

MEMORANDUM FOR PUCT

FROM: 7 CES/CEOIU
7th Civil Engineer Sq
710 3rd St.
Dyess AFB, TX 79607

SUBJECT: TWC 13.1396 CRITICAL LOAD STATUS FOR PWS 2210013

1. As per TWC requirement 13.396 project 52299, below is the general description of all water and sewer facilities that qualify for critical load status.
2. Primary Water Plant Building 8215
 - a. Primary water plant located on 4th street and Avenue D at Dyess AFB.
 - b. Water plant receives purchased water from the city of Abilene.
 - c. Water plant has 3 1600 GPM pumps that draw from a 750K gallon above ground storage tank.
 - d. The Water plant stores the water and maintains the chlorine residuals through injection system prior to entering the storage tank.
3. Secondary Water Plant Building 9199
 - a. Secondary water plant located on Hospital Creek.
 - b. Water plant receives purchased water from the city of Abilene.
 - c. Water plant has 2 600 GPM pumps that draw from a 25K gallon clear well storage tank.
 - d. The Water plant stores the water and maintains the chlorine residuals through injection system prior to entering the storage tank.
4. Water Tower Building 6221
 - a. Elevated storage tank 500K Gallons located on 4th street and Avenue B.
 - b. Water Tower receives water from the 2 water plants.
 - c. Maintains base water pressure.
5. Dyess AFB does not have a sewer treatment facility.
6. Emergency Points of Contact
 - a. Primary Christopher Angel 325-696-3389
 - b. Alternate Roberto Ruiz 325-696-4747

Death from above