THE UNDERSIGNED PARTY enters into this Consent Decree in the matter of United States and State of Texas y. San Antonio Water System.

FOR UNITED STATES ENVIRONMENTAL PROTECTION AGENCY;

Date: <u>6.4.13</u>

JOHN BLEVINS Division Director Compliance Assurance and Enforcement Division U.S. EPA, Region 6 1445 Ross Ave., Suite 1200 (6EN-W) Dallas, TX 75202 Phone: (214) 665-2266

Date:

EFREN ORDONEZ Qffice of Regional Counsel U.S. EPA, Region 6 1445 Ross Ave., Suite 1200 (6RC-EW) Dallas, TX 75202 Phone: (214) 665 2181 THE UNDERSIGNED PARTY enters into this Consent Decree in the matter of <u>United States</u> and <u>State of Texas v. San Antonio Water System.</u>

FOR PLAINTIFF STATE OF TEXAS:

Date: <u>7-3-20</u>13

١,

Ľ

MARK L. WALTERS Assistant Attorney General Office of the Attorney General P.O. Box 12548 Austin, TX 78711-2548 Phone: (512) 463-2012 THE UNDERSIGNED PARTY enters into this Consent Decree in the matter of <u>United States</u> and <u>State of Texas v. San Antonio Water System.</u>

FOR DEFENDANT SAN ANTONIO WATER SYSTEM:

Date: 6-5-13

ROBERT R. PUENTE President and Chief Executive Officer San Antonio Water System 2800 U.S. Highway 281 North San Antonio, TX 78212

# APPENDIX A

#### APPENDIX A

#### TRAINING PROGRAM IN CMOM


#### **SAWS Employee Training Categories**

Following is a summary of the different types of employees and wastewater collection system crews that SAWS utilizes to perform operation and maintenance activities related to SSO reduction and mitigation in the SAWS wastewater collection system. Following each employee or crew type is a summary of the typical technical and skills training topics that SAWS may typically offer to each employee or crew type. The specific training received by each employee or crew will depend on the actual types of work assigned to each employee or crew.

- 1. Typical training topics that may be offered to specific types of wastewater collection system operations and maintenance employees or crews:
  - a. Sewer Cleaning Crews:
    - i. sewer cleaning
    - ii. mechanical proofing
    - iii. collection of manhole inspection data
    - iv. collection of sewer visual inspection data
  - b. Sanitary sewer overflow (SSO) response Crews:
    - i. sewer cleaning (for blockage removal)
    - ii. SSO containment
    - iii. SSO clean-up
  - c. Sewer construction and/or repair crews:
    - i. sewer repair methods
    - ii. sewer pipe patching
  - d. Sewer and manhole inspection crews:
    - i. NASSCO PACP defect code training (or other sewer defect coding system training) for sewer CCTV camera operators
    - ii. collection of manhole inspection data
    - iii. collection of visual sewer inspection data
  - e. FOG Inspectors
    - i. grease removal equipment inspection procedures
    - ii. inspection data collection
  - f. Lift station operations and maintenance crews
    - i. lift station equipment maintenance
  - g. Lift station emergency response crews
    - i. lift station alarm response procedures
    - ii. SSO containment
    - iii. SSO clean-up
  - h. Crew supervisors
  - i. when appropriate, attend training attended by crews they supervise
  - i. Crews or employees responsible for SSO documentation and reporting:
    - i. data collection for SSO events
    - ii. SSO volume estimation

# APPENDIX B

Case 5:13-cv-00666-DAE Document 8-1 Filed 10/15/13 Page 4 of 74




Case 5:13-cv-00666-DAE Document 8-1 Filed 10/15/13 Page 5 of 74

# Appendix B SAWS System-Wide Cleaning Program Process and Guidelines

ନ୍ଶ<del>ଥ</del>େ ବିଶ୍ୱାର୍ଥ


Large Diameter (LD) Pipes – Greater than or Equal to 24-inch Diameter



# APPENDIX C

# Appendix C SAWS Condition Assessment and Remediation Program Process and Guidelines Overview


Page 1 of 3



# Appendix C SAWS Condition Assessment and Remediation Program Process and Guidelines Rese 2 of 3


		<u>ዋቂ</u> ድረ ብ ን		
	22 Plan Schedurstand <u>sondu</u> nesespravity Saviet Maine Han 24 - Olamora Maine Mar 24 - Olamora Maine Mar	ি লৈলেৰি জ্যানসং	ining a subartanta aning a subartanta	Mennoles Mennoles Mennors
ac evicenty the generation	ម្ភាលី ស្រុកស្រុកស្រុកស្រុកស្រុកស្រុកស្រុកស្រុក	erenden in der Stander eine Stander einen Stander einen Stander einen Stander einen Stander einen Stander einen	n Canada da Barra da 1994. Barra da Barra da Bar Barra da Barra da Ba	tery tery tery torstard
	annethor that instance and the second s		ragencia liques (surfrages) - 2224 or methods (that is spe lable)	avalace style: no consumer so ctonactivite:
an inerted film	juog->: es (such is cuiv rectinologies o seimeren lante) es sault su	essellet endortanoze 11. angles estatorialiy: 2. angles estatorialiy:	olpes for inspection, and so	inspectantic confluencion with smaller and large diameter 2 and gravity sew a main
camera by pole camera by www.camera by requency and y	(Utepide selectical function an are installely prolysis of past of the selection of sewer plo and other sectors rate factors	d SLD Constant of the surface water Constant of the surface water Constant of the surface Group pice	sewe opeans (Sand on Constant) (Sand on Constant) (Sand on Constant) (Sand on Constant) (Sand on Constant)	
	ections as needed to the second s		nspections as a second s	
	dule visual inszection interniu Sereravity soy increase leanin			
et Stising PACA Doin	sment nased on these guidelin view of aspection data based anatoget in general to view of	do, the seventy of (indines - P pes with grade 5 and 4 defec	e state sta	e er gravity sewer ploes a grade 3:2: or 1 de toets
Category	Source of the structural cond structural cond structural conditions of the structural structural conditions of the structural method structure of the structure of the structure method structure of the structure of the structure structure of the structure of the	tions SAWS Anticipates for Each Cracularitikely cause SSC of Cracularitikely cause SSC of	infine average and the second	Linguyes-Analysis
	1917 taala da	dente in national, severe con applied to be all deformation of the big level, deformation of the big level, deformation on 25% from structure level.		A CONTRACTOR
	endomed with filling and 2016 Endoopipe woll and Crosmen Preswall deformed and ranged Contraction structure, dese	tvisible istuction inpact of estimate	10% af a 1	Annenance Analysis
	alspiaced fracture constraint Mild defects white matched up matched degrad and a <b>Marched</b> On assessment on inspection o	etightnonidisulates est at	o other mild	uggance Analysis
Collewing Type a Type a Histori	nd Severity of Spacetural petect callo Denator Pana maintenance noncologicationer complaintenance	s Service of the service of the serv	, deating findings, cleaning	
Site co Site co	nditions Provensights, acces restoration far thements, and the used to and view maintenan	stor plate enance and const other unique cliques incess	ruchion dectri soli syné renvi or each individual essetter	






# APPENDIX D


# Appendix D SAWS Capacity Assessment and Remediation Program Process and Guidelines Overview



# Appendix D SAWS Capacity Assessment and Remediation Program Process and Guidelines




# Appendix D SAWS Capacity Assessment and Remediation Program Process and Guidelines





Page 4 of 4



# APPENDIX E

# APPENDIX E LIFT STATION REHABILITATION AND ELIMINATION PROGRAM

SAWS has been implementing a phased lift station rehabilitation and elimination program since 2005. Under this program SAWS assesses each lift station in its collection system (totaling approximately 170 lift stations from 2005 through June 2012). Based on each lift station assessment, SAWS makes a determination regarding 1) which lift stations can be eliminated by the diversion of flow to gravity mains and 2) for the remaining lift stations, what if any measures are warranted to upgrade the lift station. While SAWS lift station assessments are conducted on a case-by-case basis, a number of typical evaluation factors are routinely considered. These factors are described below. In addition, decisions to eliminate or upgrade a lift station are made on a case-by-case basis, applying the types of considerations described below.

Generally, the primary consideration in determining whether a lift station will be eliminated is the feasibility and merits of diverting flow to Gravity Sewer Mains. For those lift stations that will not be eliminated, an assessment is conducted to determine what repairs or rehabilitation may be warranted. The assessment process develops information and considers a wide variety of factors to determine the condition, capacity and operating performance of a lift station and identifies potential measures to improve condition, capacity and/or operating performance. Not all considerations are applicable to each lift station, nor does each consideration apply to each lift station in the same way, since each lift station is unique. Thus, the improvements selected for each lift station will vary, although in each case SAWS 1) installs a SCADA system for each lift station that is to be upgraded and 2) compares the lift station attributes to the Texas regulations for the design and construction of new lift stations in 30 Tex.

#### Case 5:13-cv-00666-DAE Document 8-1 Filed 10/15/13 Page 17 of 74

Admin. Code, Chapter 217. These Texas regulations provide numerous design and construction requirements including, among many others, wet well capacity, pump capacity and velocities, provisions for power quick connect facilities for portable electric generators, pump cycle times and criteria for air release valves and vaults. The purpose of the comparison is to determine for each lift station whether upgrades to conform to these new lift station regulations are appropriate. SAWS is not required by law to retrofit its lift stations to new lift station design or construction standards.

Generally, the assessment process examines the condition, capacity and operating performance of the lift station including the following types of considerations:

- 1. Drawdown tests are performed to determine pump capacity.
- 2. The condition of the wet well is inspected for structural defects.
- 3. The condition of the wet well liner is inspected to determine if lining repair is necessary.
- 4. The condition of the pumps and motors is determined.
- 5. Determination of the need for secondary pumps is made.
- 6. The condition of all inlet piping is examined.
- 7. Upgrading the power supply to 480 volts is analyzed.
- 8. The addition of soft start motor starters is considered.
- 9. The addition of surge arrestors for power surge protection is considered.
- 10. The condition of pump suction pipes is determined.
- 11. An analysis of site security features is made.
- 12. Settings on any floats or switches that operate based on fluid level are inspected.
- 13. The condition of wet well suction piping is examined.
- 14. The pump priming system is examined.

### Case 5:13-cv-00666-DAE Document 8-1 Filed 10/15/13 Page 18 of 74

Based upon the information developed in the assessment process, SAWS identifies recommendations for each lift station for potential upgrades. Such recommendations are unique to each lift station, based upon the results of the assessment. Improvements that SAWS determines to make are then planned, funded and implemented, typically through contracts subject to the public bidding process that SAWS is required by law to follow.

The current status of the lift station rehabilitation and elimination program is described in the attached table.

	ang sa tabuna sa					Field									Selven i Sur Ring generation	
		1. <sup>19</sup> - 19 - 19 - 19 - 19 - 19 - 19 - 19 -				Measured	Model				*** ****** *** ****	4	Date of			
	Construction or	a			Assessment for		Predicted Peak		Equipped				Anticipated	Date of	h	
		Construction			15 Elimination		Hydraulic	Availability and Type		Overall	Risk of	Consequence	Upgrade or	Upgrade		
Station au		or Rehab Note		SSG	or Rehab	Capacity		of Backup Power	SCADA	Condition	Failure	of Failure	Decommission	Note	Comments	
4	7/1/1956		N/A		3/27/2007		N/M	QC	No.:	Adequate	Low	Low	9/30/2014			<u> </u>
	12/5/1983		-	5/21/2011	· · · · · · · · · · · · · · · · · · ·	4.878			Na	Adequate	LOW	High	12/31/2016	D		
16	4/30/2012	-		/24/2003		1.21		Generator	Yes 🌅	Good	LOW	Hìgh .	Completed			i nêrose i l
20	9/22/2009	·	N/A		9/14/2004		N/M	QC	Yes	Good	Low	Low	Completed			
	5/8/2012	R : .		9/7/2010			N/M	QC 💥	Yes	Good	LOW	Low	Completed			
26	1/1/1961		N/A		3/27/2007	+- ··	N/M	ac	No	Adequate	Low	Low	12/31/2018			
35	8/24/1970	··· ··	N/A	<u> </u>	3/28/2007		N/M	QC	No 🔛	Adequate	Low	Low	9/30/2014			
52	11/12/2009	R	N/A	-	9/14/2004	1.412	,	QC	Yes	Good	Low	Low	Completed			
57	5/24/1990	Program	N/A		3/28/2007		1.237		No	Adequate	Low 🗄 🕤	High	8/31/2013		1.1.1.2.2	
61	5/22/2012		N/A		3/26/2007		N/M	QC	Yes	Good	Low	Low	Completed			
73	4/22/1977		N/A	1.1	3/29/2007		N/M 👘	QC.	No	Adequate	Low	Low	212/31/2017	0		
74	4/22/1977			5/14/2011	3/29/2007		N/M	QC	No	Adequate	Low	Low	9/30/2014			
90	7/29/1976		N/A	nin ki	9/16/2004	<u>N/M (</u> ∰	N/M	QC	No	Good	Low	Low ·			Lift station is	not in operation
94	11/15/1979		N/A		4/5/2007	N/M	N/M	QC	No	Adequate	Low	Low	12/31/2017	0		
100	10/19/2009			720/2006	<u>9/1/2004 وال</u>	N/M	N/M	Generator	Yes 👘	Good	Low	High-EARZ	Completed			
102	10/19/2009	R	N/A		9/1/2004	N/M	N/M	Generator	Yes	Good	Low	High-EARZ	Completed	· · · ·		
103	8/29/1980	·	N/A	: Ji	4/26/2007	N/M	N/Masteriol	QC	No 22	Adequate 100	Low	Low	12/31/2017	D		
105	2/23/1981		N/A		9/14/2004	N/M	N/M	QC	No	Adequate	LOW	LOW	12/31/2018			<u></u>
	12/29/1981	New Sector	2017-89	/22/2010	3/26/2007	N/M <sup>1</sup> 8.1	N/M	QC .	No 🗇	Adequate	Low	Low		D	· · · · · · · · · · · · · · · · · · ·	
121	1/25/2012	R	5	/27/2012	9/30/2004	3.386	1.481	Generator	Yes	Good	Low	High-EARZ	Completed			
126	10/22/2010 A	<b>*</b>	N/A		8/31/2004	N/M	N/M	Generator	Yes	Good	Low	High-EARZ	Completed			
131	1/1/1985			4/7/2003	9/1/2004	N/M	N/M	QC	No	Adequate	LOW	Low	12/31/2015			······································
् 132	10/19/2009	R	N/A		9/1/2004	N/M	N/M	Generator	Yes.	Good	Low	High-EARZ				
134	1/22/2010	R	N/A		8/31/2004	N/M	N/M	Generator	Yes	Good	Low	High-EARZ	Completed			7
135	V 020 11/20/1985		N/A	20 <b>2</b> 22	8/21/2004	N/M ::::::	N/M	og 🖉 👘 🖓	No	Adequate	LÖŴ	High-EARZ	12/31/2017	<b>n</b>		
137	11/12/1985		N/A		3/27/2007	N/M	N/M	ac	No	Adequate	Low	Low	12/31/2018	• <u>/ ·</u>	- 22200024	- <u> </u>
144	2/1/2012	R (	N/A	ia di	9/9/2004	N/M	N/M	QC A CARACTER	Yes	Good	LOW	Low	Completed			
145	1/31/1975		N/A		4/5/2007	· · ·	N/M	OC	No	Adequate	Low	Low	12/31/2017	<u>.</u>		
147	11/29/2011	R	N/A		9/1/2004		N/M asked	Generator	Yes	Good	Low		Completed I			
148	11/12/1986		10	/10/2009			N/M	OC	No	Adequate	Low	Low	9/30/2014		*:)::	
C. 150	3/14/2012	R	N/A		8/31/2004			Generator	Yes	Göod	Low	High-EARZ	Completed			
151	10/27/2010	R	1.11	3/4/2008			N/M	Generator	Yes	Good	Low	High-EARZ	Completed	<u></u>		
156	12/10/2011	R	N/A	<u></u>	3/28/2007	0.956	0,374		Yes	Good		High	Completed	·	······································	· · · · · · · · · · · · · · · · · · ·
162	1/13/1988		N/A		3/26/2007	1.789	1.359		No	Adequate	Low	Hìgh			······································	
163	3/10/1988		· · · · · · · · · · · · · · · · · · ·	/23/2009	9/16/2008		N/M		Notic	Adequate	Low	Low	9/30/2014		1	
164	8/4/1988		N/A		3/26/2012		N/M		No							
165	10/27/1987	Y.SE	<u> </u>	/19/2012	<u> </u>	1.051	1.051			Adequate	Low	Low	9/30/2014			
166	6/15/1988	· ·	N/A	1.1.07 2012	3/28/2007		N/M	QC	No	Adequate	LOW	High-EARZ	9/30/2014	<u> </u>		
167	6/15/1988		N/A S		3/28/2007				No	Adequate	Low	Low	12/31/2018			
10,		···	1			on y ny Lija	N/M PASS	QC	No	Adequate	LOW	Low	12/31/2018			
169	10/27/2010			/14/2010	0/1/2004	NUM	N /6 /	C					Completed &			
170	10/27/2010 5/9/1989	n.		714/2010 6/6/2011	9/1/2004		N/M	Generator	Yes	Good	Low	Low	12/31/2020	0	,	
170	5/2/2012	na mainin an	N/A	0/0/2011	3/29/2007		, .	QC	No	Adequate	Low	Low	8/31/2013			
171				laciance	9/1/2004		N/M	QC	Yes	Good	Low	High-EARZ	Completed			
175				/26/2009	9/14/2004	23 342	10.315	Generator	No	Adequate	Low	High	9/30/2014			
175	10/18/1993		N/A		9/9/2004			oc	No	Adequate	Low	Low	9/30/2014		12.5.000	
170	·		N/A		9/11/2008	N/M	N/M 👘	0 <b>C</b>	No	Adequate	Low	Low	12/31/2014	2.2		

178 10/10/1991 N/	/A	3/29/2007	N/M	N/M		No	Adequate	Ti	<u>.</u>			·
179 00/10/1991 M	A	3/29/2007	,	NPD		No	Adequate	Low 7	Low	9/30/2015		
180 10/10/1991 N/	201 2/	3/29/2007	0.936	0.346		No.		<u> </u>	High	12/31/2013		
	/A:01	9/17/2008		N/M	ac	No	Adequate Adequate	Low	High	8/31/2013		
187 10/6/1986	7/18/2012			NPD	Generator	No No	Adequate	Low C.	Low	12/31/2018	D	
5/17/2001	8/19/2012	9/9/2008	2.463		QC - Central	No Ser	Adequate	Low	High	12/31/2018		····
189 8/23/1968	7/26/2007	9/26/2008			ac	No	Adequate		High	12/31/2014		
190 .4/29/1992		3/27/2007	1.1.1	N/M	QC	No	Adequate :	Low	Low Jos (16)	12/31/2014		and the second is the second is
191 3/14/2012 R	12/27/2010	8/31/2004	3.168		Generator	Yes	Good		Low COSCE	12/31/2014	· 2011.	
192 8/2/2012 R	3/27/2012	3/29/2007		N/M	QC	Yes	Good	Low	High-EARZ	Completed		
193 1/22/1993 N/		10/1/2008		N/M		No		Low	Low	Completed		
1/22/2012 R N/		9/9/2004		N/M	ac an	Yes Sec	Adequate	LOW	Low	12/31/2016		
197 6/7/1994 N/		9/15/2008	<u> </u>	N/M	QC		Good	Low	Low	Completed	(1.14) -	
			NY 191	NY IVI	<u>uc</u>	No	Adequate	Low	Low	12/31/2018	D	
198 2/15/2007	1 August 1 1 1 1 1 1 1 1	Not assessed to be eliminated	NPD	NPD	Generator	No	Adequate	Low	High	12/31/2019		
		Not assessed-to							ing.		D : 200	
199 11/21/1994			NPD I	NPD	Generator	No	Adequate	Low	High	12/31/2019		withing we are a second s
200 11/21/1994	10.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.	Not assessed to be eliminated	NPD		Generator							
201 11/21/1994					Generator	No	Adequate	Low 🔅	High	12/31/2019	D	
202 202 201 1/17/2011 R. 1997 N/		9/1/2004			QC	No	Adequate	Low	High	12/31/2018	****	
203 7/19/2012 R N/		3/28/2007		· · · · · · · · · · · · · · · · · · ·	QC	Yes	Good	Low	Low	Completed Completed	-	
205 11/9/1995	6/14/2010	9/16/2008 N				Yes		Low	Low	8/31/2014		
206 3/5/1996 N/		9/1/2004 N				No 📰	· · · · · · · · · · · · · · · · · · ·	Low 🗧 🤅	Low	12/31/2014		
207 5/6/1996 N/		9/15/2008 N				No. No.	Adequate	Low	Low	9/30/2014		
208 7/1/1996 N/J		9/1/2004					Adequate	LOW R	Low	<u>1</u> 2/31/2014		
209 4/14/1997	7/27/2010	9/1/2004 N			QC-38	No	Adequate	Low	Low	9/3 <b>0/2</b> 014		
210 2/14/1997 N//		9/18/2008			QC	No	Adequate	Low	High-EARZ	9/30/2014		
6/24/1997 N//		9/23/2008 N				No	Adequate	Low	Low	12/31/2014	,	
213 12/1/1984 N//		9/9/2004 N			<u>ac in the Margani</u> ac	No Basel		Low	Low	12/31/2014	<u>. (35</u>	
(X) (and (X)	ANDER	8/31/2004 N				No	Adequate	Low	Low	8/31/2013		
217 8/19/1998 N//		3/29/2007		11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Generator	Yes		Low		Completed	1946	
218		9/1/2004 N		· · · · · · · · · · · · · · · · · · ·	QC	No		Low	Low	12/31/2017	-	
219 10/13/1999	8/18/2012	9/22/2008	2.914			No 👾		Low	Low	9/30/2014	1000	i i i i i i i i i i i i i i i i i i i
220 6/24/1999 N//		3/22/2008			Generator	No		Low	High	12/31/2016		
221 8/25/1999 N/A		3/27/2007		· · · · · · · · · · · · · · · · · · ·				Low	Low	9/30/2014		
222 6/13/2012 R			3.199			No		Low	High	9/30/2013		
223 6/21/2012 R N/A	and a set	3/28/2012 N				Yes			Low	Completed		
224 8/18/2000 M//		3/28/2007 N						Low	Low	Completed		
225 8/10/2007		9/22/2008 N					· · · · · · · · · · · · · · · · · · ·	Low ಜ್ಜಿ	Low	12/31/2019	D	
223 3/10/2007	8/17/2007	9/14/2004 N			QC			Low	Low	12/31/2019		
228 9/28/2001 N/A		8/31/2004 N	-					L <b>ow</b> 2	High-EARZ	9/30/2014		
191		9/18/2008 N		· · · · · · · · · · · · · · · · · · ·	QC	No		Low	Low	12/31/2014		
		9/9/2004 N				No 🤅		Low 🗽	High=EARZ	9/30/2014	N. 74	
		8/31/2004 N						Low	High-EARZ	9/30/2014		
	10/3/2010	9/1/2004 N						ow 👔	Low Com	12/31/2020	D	
	5/29/2008	9/9/2004 N							Low	9/30/2014		
			176.4 151	VM I								
235 5/31/2012 R	10/31/2010	9/16/2004 N				· · · · · · · · · · · · · · · · · · ·			Low High-EARZ	9/30/2013		

236 237 238 239	8/20/2003 5/26/2003	20 20	N/A		5	3/16/2004	N/M (802	N/M	QC XXX	No	Adequate	Low .	High-EARZ	9/30/2014		· · ·	¥.	· · · · · · · · · · · · · · · · · · ·
238	5/26/2003							and date in			ride,q date		THEILERINE					
	-,,		N/A		9	9/17/2008	N/M	N/M	QC	No	Adequate	Low	Low	12/31/2014				
220	3/9/2004			2/18/2009	1	3/27/2007	4.07	5	93 Generator	No	Adequate	LOW	High	9/30/2013				
1 233	8/25/1999			8/31/2007	9	9/23/2008	N/M	N/M	Generator	N¢	Adequate	Low	Low	12/31/2014				
240	6/7/2004	e for the		7/5/2006		9/1/2004	N/M	N/M	QC HART	No. 🐡	Adequate	Low ( 17	High-EARZ	9/30/2014		- Aux Aux		
241	12/30/2010			12/21/2010	NC		N/M	N/M	QC	Yes	Good	Low	Low	Completed				
242	12/30/2010	R2-5	N/A		NC	W	N/M	N/M		Yes	Good	Low	Low	Completed			79. NO	÷.
243	12/30/2010	R	N/A		NC		N/M	N/M	Generator	Yes	Good	Low	Low	Completed				
244	12/30/2010	R (1997)	N/A	80. a 193	NC	··	N/M	N/M	e, ac di di A	Yes	Good	Low 5	Low	Completed				9000 1 90,740 -
245	7/1/2005		N/A		9	9/23/2008	N/M	N/M	lac	No	Adequate	Low	Low	12/31/2014				
246	10/6/2006	nga shila	N/A		NC		NPD	NPD	Generator	Yes	Good	Low	High	NR				Š.
247	12/30/2010		N/A		NC	· · · · · · · ·	N/M	N/M	QC	Yes	Good	Low	High-EARZ	Completed				
248			N/A		NC.		N/M	N/M	Generator	No	Good 20	Low	Low	Balaci 9/30/2014		:		47 - XX
249	9/8/2005		N/A		NC		NPD	NPD	Generator	No	Good	Low	High-EARZ	9/30/2014			•• *	
0.170250	12/30/2010	·R	N/A	an de Aeropara	NC		NPD	NPD.		Yes	Good	Low	High 👘	Completed			141 - NE	λ <sup>1</sup> θ
		·····	1					*******		1. E. E. L. M. P. L.	1			Completed &				
251	12/30/2010	R	N/A		NC		N/M	N/M	Generator	Yes	Good	Low	Low	12/31/2019	Ь			
251	2/3/2006		N/A	·	NG		N/M	N/M	Colorian Colorian	No	Good State	Low	High-EARZ	12/31/2014				
253	2/3/2006		N/A	-		9/26/2008		N/M	QC	No	Adequate	Low	Low	12/31/2014		~~~~		
205	2/1/2008		+	·····	402473		7 21.7 MANAN	· · · ·			FOEGO VE			Completed &	1			
					1.2.1.2	<u>.</u>					Canal		Low	12/31/2016	D			
254	12/30/2010		···	9/11/2007			N/M 🔆	- · · · · · · · · · · · · · · · · · · ·	Generator	Yes	Good	Low			<i>v</i>	<i>.</i>	X.S+	
255	12/30/2010		N/A		NC		N/M	N/M	QC	Yes	Good	LOW	Low	Completed		1.55	· · · · ·	
256	12/30/2010		N/A	fi.	NC		N/M (980)	N/M	<b>QC</b> 2000 1.05	S Yes	Good 1 STR	LOW	Low	Completed		-87	.ä.	14446213
257	7/24/2006		N/A		NC		N/M	N/M	QC	No	Good	Low	Low	12/31/2014		in sim		
258	8/14/2006		N/A	25. 25.	NC		NPD	NPD	Generator	No	Good	Low	High	12/31/2014	den stägter og		÷	
259	12/30/2010		N/A		NC		N/M	N/M	QC	Yes	Good	Low	Low	Completed				
260			N/A		NC		N/M 🔌	N/M	Generator 👾 🖧	Yes	Good	Low 6	High-EARZ	Completed 200			22.1	
261	12/30/2010			6/22/2011			N/M	N/M	QC	Yes	Good	Low	Low	Completed				
262	12/30/2010	Refusive the	N/A		NC		N/M	N/M	QC C	Yes	Good	LOW	LOW	Completed				
263	4/25/2007		N/A		NC		N/M	N/M	Generator	No	Good	Low	High-EAR2	12/31/2014		1		
. §264	10/9/2007		N/A	<u>.</u>	NC		N/M	N/MS 11	Generator	No	Good	Low diff.	Low	12/31/2014	1693 ( ) 1993		<u> </u>	
265	1/3/2008		N/A		NĊ		N/M	N/M	Generator	No	Good	Low	High-EARZ	12/31/2014				
266	7/3/2008		N/A	4.00	NC		N/Miiiii	N/ME	QC	Yes .	Good	Low 🔅	LOW	NR		1.85¥,	<u> </u>	
267	7/9/2008		N/A		NC		N/M	N/M	QC	No	Adequate	Low	Low	12/31/2019	D			
268	9/23/2008		N/A	×.	NC	Ξζ2	N/M	N/M C.	Generator	Yes	Gööd	LOW	High-EARZ	NR 🔅 🔆 🛱	50. je 4 s.	1. 3. V.: 		
269	11/3/2008			6/16/2009	NC		NPD	NPD	Generator	Yes	Good	Low	High	NR				,, .· .·- <b>-</b>
270		konsegijen	N/A	- 1 <u>.</u>	NC		N/M	N/MEEDE	Generator	No 🦂	Good	Low	Low	12/31/2014	$\{[0,1],\ldots,[n]\}$		-3 :20	<u>.</u>
271	5/21/2009		N/A		NC		N/M	N/M	qc	Yes	Good	Low	Low	NR				
272	ST -der 11 1:012/22/2009	an el composi	N/A		NC		N/M	N/M Salar	QC 🚔	Yes	Good	Low 👌 🗄	Low	NR				
273	2/3/2009		N/A		NC		N/M	N/M	Generator	Yeş	Good	Low	Low	NR				
274	3/22/2010		N/A	14.98°	NC		N/M	. N/M	ac See	Yes	Good	LOW	Low	NR			(† <u>7</u> 44	
276	12/13/2010		N/A		NC		N/M	N/M	Generator	Yes	Good	Low	Low	NR			<u>,</u>	
277	5/24/2011	5. (82)	N/A		NC		N/M	N/M		Yes	Good	Low	Low	NR			94	
278	9/15/2011		N/A	<u></u>	NC		N/M	N/M	qc	Yes	Good	Low	Low	NR				
		· · · · ·	+		,							1		10 years after Date		. (Se	ŵ 19 - I	
300	6/1/1965	·	N/A		li de la come	9/5/2008	N/M	N/M	Generator	No	Adequate	Low	Low	of Lodging	4		×.	
	011100	<b> </b>	1 TA	:-:::\ <u>\</u>	1	. 9/0/2006		A 14/14/1		· · · · · · · · · · · · · · · · · · ·				10 years after Date			· · · · · · ·	
303	8/9/1996		N/A		.	9/11/2008	51./6.4	N/M	Generator	No	Adequate	Low	Low	of Lodging				
503	ela\1930		INVA.				DIVINI DIVINI							10 vears after Date				····
1	· · · · · · · · · · · · · · · · · · ·		N/A			9/4/2008		м/м	Generator	No	Adequate	LOW	Low	of Lodging		· ** (24	<b>.</b>	

		i		1			T		<u>,                                     </u>		T	10 years after Date		1	
305			N/A	Not assessed	N/M	N/M	q¢	No	Adequate	Low	Low	of Lodging			I
· ·			N/A	· .						1 33		10 years after Date			
307	6/1/1965	<u> </u>	N/A 🔆 👘 👘	9/4/2008	N/M	N/M	OC GALLER	No	Adequate	Low	Low	of Lodging			
												10 years after Date		· · · · · · · · · · · · · · · · · · ·	
308			N/A	9/4/2008	N/M	N/M	QC	No	Adequate	Low	Low	of Lodging			1
1 A					- as a sub-					1.12		10 years after Date			NVS (Sector
905	6/1/1965	- Artes	N/A	9/4/2008	N/M	N/M	ac	No	Adequate	Low	Low	of Lodging			
												10 years after Date			
310		· · · ·	N/A	9/10/2008	N/M	N/M	ac	No	Adequate	LOW	Low	of Lodging			
	1 A.C.		N/A						1.	N. 41		10 years after Date			1.152
311	8/9/1996		N/A	9/23/2008	N/M	N/M	QC	No	Adequate	Low	Low	of Lodging			A. 15)
												10 years after Date			<u> </u>
312	8/9/1996		N/A	9/23/2008	N/M	N/M	QC	No	Adequate	Low	Low	of Lodging			
	6/1/1965								i i i i i i i i i i i i i i i i i i i	Low		10 years after Date		366 <b>X</b> .	
313	6/1/1965	5 3 <u>1</u> 5	N/A	9/5/2008	N/M	N/M 🤅	QC	No	Adequate	Low	Low	of Lodging			
												10 years after Date		· · · · ·	
315	6/1/1965		N/A	9/5/2008	N/M	N/M	QC	No	Adequate	low	Law	of Lodging			
316		l ·	정성된 사실의						19	. : X		10 years after Date			
<u>316</u>	6/1/1965		N/A	9/5/2008	N/M	N/M	oc an	No Mai	Adequate	Low	Low	oficidging			gi li
												10 years after Date			
317	8/9/1996		N/A	9/23/2008	N/M	N/M	<u>ac</u>	No	Adequate	Low	Low	of Lodging			
318	8/9/1996									Low	Low	10 years after Date			- ( <u>) ()</u>
318	8/ <del>9</del> /1996		N/A	<b>9/</b> 23/2008	N/ME/E/REAR	N/M 👘	QC .	No	Adequate	Low	Low	of Lodging	945. SAN		
245												10 years after Date			
319	8/9/1996		N/A	9/23/2008	N/M	N/M	QC	No	Adequate	Low	Low	of Lodging			
320	6/1/1965		N/A			N/M	QC		Adequate	`4e	- 38° 50° 11.	10 years after Date	17		
	6/1/1965		NVA:	9/10/2008	N/M	N/M TEX	QC	No	Adequate 🔛	Low	Low	of Lodging			
321	6/1/1965		N/A	0/2//2000			_					10 years after Date			
321	2021/1/0	·	N/A	9/24/2008	N/M		Generator	No	Adequate	Low	Low	of Lodging			
322	6/1/1965		N/A				9.94 · · ·			Low	Low	10 years after Date	- N - F - 1		
	6/1/1965		м/А .	<u>\$\$</u> 9 <b>/1</b> 0/2008	N/M stars ( )	<b>N/M</b> <u>i≷t</u>	Generator	No	Adequate	Low					48. v.
323	6/1/1965		1/23/2012	0/0/2028								10 years after Date			
				9/9/2008	NY MI	N/M	Generator		Adequate	Low	Low	of Lodging			
	6/1/1965		NA	9/9/2008	NI/RA	N/M	QC	No				10 years after Date			
			weige weigen	57,57-2008	ny n/i	MANAGE Services		NOHASSING	Adequate	Low.	Low 👘	of Lodging	. <b>.</b>		
325	6/1/1965		N/A	9/9/2008	NZKA	N/M	qç		4.4			10 years after Date			
		13. J.		3/ 3/ 2008	ny n/			No :	Adequate	Low	Low	of Lodging			
326			N/A	9/9/2008	NZMA	N/M	oc	е н.		Low	Low	10 years after Date			
		Contraction of Contraction			A IN THE COMPANY	nay nel services	424 ·	No .	Adequate	LOW 🔆	Low		2 <u>1</u>	<u>. 412 ./2</u>	6
328	6/1/1965		N/A	9/9/2008	N/B4	N/M	oc.	<b>.</b> .		.		10 years after Date			
		<b>2</b> 49.0		5/9/2008	iyivi		QC			Low	Low	of Lodging			
329	6/1/1965	19 - C	N/A	9/10/2008	N/64	N/M		No		2.00 		10 years after Date			
			and the second second	37.101 4.008		INT INC DEVICES		NO me	Adequate 🐘	Low	Low . State	of Lodging		<u>2210</u> . X.	
330	6/1/1965		N/A	9/24/2008	NIZEZ	N/M	QC				1	10 years after Date			
	· · · · · · · · · · · · · · · · · · ·			3/24/2008				N¢	Adequate	LOW	Low	of Lodging		invinit.	
331	10/26/2004		N/A	9/18/2008		N/M	oc	No			Low	10 years after Date			
				0.000 101 101 2000	A MARKEN AND AND AND	ny ny i		NO /	Adequate	Low 🕺	LOW	of Lodging	.e. (		<u>4.</u>

#### SAWS Lift Station Data for CD Appendix

1 "N/A" indicates that a lift station has not had an SSO.

2 "N/M" indicates that a lift station is not individually modeled in the hydraulic model and therefore no comparison of field measured and model predicted flow is available.

3 Flow from field measured pump drawdown tests was aggregated and converted from GPM to MGD,

4 "R" refers to the date that rehabilitation was completed

S "Adequate" indicates that a lift station is fully performing, but that it will be rehabilitated/upgraded as described in this Appendix.

6 All lift stations have a low risk of failure. Any risks identified by SAWS lift station maintenance department are corrected.

7 Lift stations that do not have a generator either have, or will have on completion of rehabilitation, quick- connect facilities for portable power generation,

8 All lift stations will have SCADA on completion of rehabilitation. A Verbatim alert system is in operation pending SCADA installation.

9 A "High" consequence indicates a lift station that Is located over the Edwards Aquifer Recharge Zone (EARZ) or that is a large volume flow (ZMGD and greater) lift station.

10 "D" indicates the date of anticipated decommissioning.

11 "Completed" indicates that rehabilitation of a lift station has been completed.

12 "NPD" indicates that a field pump drawdown test for all pumps in a lift station is not available. A comparison with model predicted flow is, therefore, not possible.

13 Rehabilitation/upgrade has been completed, but the lift station will also be decommissioned.

14 "NC" indicates that a lift station was recently constructed and met TCEQ and SAWS guidelines at the time of SAWS acceptance, or required only SCADA installation that has now been completed. No further assessment was necessary,

15 "NR" indicates lift stations that have been recently constructed and that meet TCEQ and SAWS guidelines. No rehabilitation, upgrade, or assessment is necessary.

16 300 series lift stations were inherited from the U.S Air Force and are located on Lackland A.F.B. and the former Kelly A.F.B.

17 Determined to be a holding tank for aircraft waste.

18 SAWS intends to eliminate or rehabilitate the 300 series lift stations. A final determination on the appropriate action has not yet been made.

19 "QC" indicates a quick connect facility is installed for portable generation.

# APPENDIX F

### I. Overall Description of Remedial Measures

SAWS Early Action Program (EAP) Phase I consists of the following types of Remedial Measures:

- Large Diameter Condition Remedial Measures
- Large Diameter Capacity Remedial Measures
- Small Diameter Condition Remedial Measures
- Manhole Condition Remedial Measures

The projects associated with these Remedial Measures are summarized in the Table in Part II of this Appendix F. Following is a general description of the EAP Phase I Remedial Measures.

#### Large Diameter Condition Remedial Measures

Through SAWS CCTV program, SAWS has identified approximately 13.3 miles of large diameter mains for alternatives analysis. The 13.3 miles were identified due to structural defects that have caused, or may cause, structural SSOs in the future.

Prior to the establishment of Appendix C, this process was called issuing a "Design Request." After the establishment of Appendix C, this step is called a request to conduct "remedial measures alternatives analysis," which could either result in a remedial measure, monitoring, or maintenance.

Of the 13.3 miles, approximately 6.3 miles has been assessed and designed as of March 31, 2013, and approximately 7 miles awaits alternatives analysis. Of the 6.3 miles which has been designed, 4.4 miles is the San Antonio River Outfall Project Phase 1 and 2. For the remaining 1.9 miles SAWS is in the process of packaging the pipes into bid packages, or "projects," as well as prioritizing the projects over the five years of the EAP Phase I. SAWS has identified two projects for the 1.9 miles of the pipe that have been assessed and designed. For the 7 miles awaiting alternatives analysis, those pipes which result in a remedial measure will be added to these two projects (which is why the total project mileage adds up to 13.3 miles of pipe for EAP Phase I). If certain pipes from the 7 miles do not result in remedial measures, a similar mileage of higher risk pipe that has yet to be identified will be added to the EAP Phase I mileage to make up the difference. Projects may be divided into smaller projects to further prioritize projects related to SSOs, address contractor bidding constraints, or to reduce construction inspector drive-time per project, but the cumulative mileage of the projects will not be reduced. If the projects are divided into smaller projects, this will be reported in the Annual Report.

The <u>Summary of Remedial Measures for EAP Phase I</u> Table in Part II of this Appendix F shows the status of SAWS alternatives analysis and design process. The <u>Remediation Project List for</u> <u>EAP Phase I</u> table in Appendix F shows the status of Large Diameter Condition Remedial Measures projects for the EAP Phase I.

#### Large Diameter Capacity Remedial Measures

Through SAWS capacity assessment activities, SAWS has identified approximately 25 miles of large diameter mains to be constructed as Capacity Remedial Measures as part of EAP Phase I.

All 25 miles have been grouped into 4 projects outlined in the table in Part II of this Appendix F to be completed under the large diameter capacity EAP Phase I schedule as set forth in the Consent Decree.

The <u>Summary of Remedial Measures for EAP Phase I</u> Table in Part II of this Appendix F shows the status of SAWS alternatives analysis and design process. The <u>Remediation Project List for</u> <u>EAP Phase I</u> Table in Part II of this Appendix F shows the status of Large Diameter Capacity Remedial Measures projects for the EAP Phase I.

#### **Small Diameter Condition Remedial Measures**

Through SAWS CCTV program, SAWS has identified approximately 62.5 miles of small diameter mains for alternatives analysis. The 62.5 miles were identified due to structural defects that have caused, or may cause, structural SSOs in the future, as well as less significant defects on pipes that were in close proximity to the structural defect SSO pipes. While these less significant defect pipes are not required to be remediated per Appendix C, SAWS is bundling these pipes with less significant defects with higher priority pipes in order to potentially reduce unit bid costs, and diminish future disruption to its customers.

Prior to the establishment of Appendix C, this process was called issuing a "Design Request." After the establishment of Appendix C, this step is called a request to conduct "remedial measures alternatives analysis," which could either result in a remedial measure, monitoring, or maintenance.

Of the 62.5 miles, approximately 39 miles has been assessed and designed as of March 31, 2013, and approximately 23.5 miles awaits alternatives analysis. Of the 39 miles which has been designed, SAWS is in the process of packaging the pipes into bid packages, or "projects," as well as prioritizing those projects over the three year schedule for small diameter condition projects under EAP Phase I. SAWS has identified two small diameter projects (each involving several miles of pipe) per year for completion as part of Phase I. These 6 projects include the 39 miles of pipes that have been designed. For the 23.5 miles of pipe that is awaiting alternatives analysis, those pipes which result in a remedial measure will be added to these six projects (which is why the total project mileage adds up to 62.5 miles of pipe for EAP Phase I). If certain pipes from the 23.5 miles do not result in remedial measures, a similar mileage of higher risk pipe that has yet to be identified will be added to the EAP Phase I mileage to make up the difference. Projects may be divided into smaller projects to further prioritize projects related to SSOs, address contractor bidding constraints, or to reduce construction inspector drive-time per project, but the cumulative mileage of the projects will not be reduced. If the projects are divided into smaller projects will not be reduced. If the projects are

The <u>Summary of Remedial Measures for EAP Phase I</u> Table in Part II of this Appendix F shows the status of SAWS alternatives analysis and design process. The <u>Remediation Project List for</u> <u>EAP Phase I</u> Table in Part II of this Appendix F shows the status of Small Diameter Condition Remedial Measures projects for the EAP Phase I.

### Manhole Remedial Measures

The manhole project shown in the Table in Part II of this Appendix F consists of high priority manholes which have been identified through SAWS manhole condition assessment activities completed as of January 2, 2013. These are shown in the <u>Remediation Project List for EAP</u> <u>Phase I</u> Table in Part II of this Appendix F.

### II. Tables Summarizing EAP Phase I Work

#### Remediation Type Miles **Summary of Remedial Measures** 1. Small Diameter (SD) Condition Remediation SD Remediation -Identified through SAWS CCTV program that have been Design Completed 39 assessed and designed. See Project List Below. Mileage that has been identified through SAWS CCTV program, but has not gone through the alternatives analysis SD – Awaiting process. This mileage will continue through alternatives Remedial Measures analysis and has been incorporated into the EAP Phase I **Alternatives Analysis** 23.5 Project List below. Total 62.5 2. Large Diameter (LD) Condition Remediation LD Remediation -Identified through SAWS CCTV program that have been **Design Completed** 6.3 assessed and designed. See Project List Below. Mileage that has been identified through SAWS CCTV program, but has not gone through the alternatives analysis LD – Awaiting process. This mileage will continue through alternatives Remedial Measures analysis and has been incorporated into the EAP Phase I Alternatives Analysis 7 Project List below. 13.3 Total 3. LD Capacity Remediation LD Projects 25 See Project List Below. Manholes 4. MH Remediation (Number) Manholes identified through SAWS condition assessment Manholes 25 activities that have been assessed and designed.

### Summary of Remedial Measures for EAP Phase I

# Remediation Project List for EAP Phase I

Project Name	Miles	Target Project Completion
	INITES	
1. Small Diameter (SD) Condition Remediation		
EAP Phase I – Project 1 – 2013 SD Re-hab		
Program	12	1 Year from Date of Lodging
EAP Phase I – Project 2 – 2013 SD Re-hab		
Program	11	1 Year from Date of Lodging
EAP Phase I – Project 3 – 2014 SD Re-hab		
Program	12	2 Years from Date of Lodging
EAP Phase I – Project 4 – 2014 SD Re-hab		
Program	11	2 Years from Date of Lodging
EAP Phase I Project 5 – 2015 SD Re-hab		
Program	8.5	3 Years from Date of Lodging
EAP Phase I – Project 6 – 2015 SD Re-hab		
Program	8	3 Years from Date of Lodging
Total	62.5	
2. Large Diameter (LD) Condition Remediation		
EAP Phase I – Project 7 – LD Re-hab Program	4.4	5 Years from Date of Lodging
EAP Phase I – Project 8 ~ LD Re-hab Program	4.5	5 Years from Date of Lodging
San Antonio River Outfall Project Phase 1 and 2	4.4	5 Years from Date of Lodging
Total	13.3	
3. LD Capacity Remediation		
Donaldson Terrace	4.6	6 years from Date of Lodging
Broadway Corridor – Josephine to South Alamo		
Street	4	6 years from Date of Lodging
Broadway Corridor – Carnahan to Mulberry		
Streets	10	6 years from Date of Lodging
Leon Creek – Highway 90 to New Laredo Highway	6.4	6 years from Date of Lodging
Total	25	
	Manholes	
4. MH Remediation	(Number)	Manholes (Number)
Manhole Project 1	25	3 years from Date of Lodging

# APPENDIX G

.

## I. Cover

# II. Certification Declaration

[Required certification, with language specified by the Consent Decree, signed by a responsible official of SAWS]

# III. Table of Contents

[List of sections, tables, figures and appendices included in this report]

# IV. Acronyms and Abbreviations

[Definitions of abbreviations and acronyms included in this report]

# V. Introduction

### A. Purpose

This Report was prepared and submitted pursuant to Paragraph 28 of the Consent Decree.

## **B.** Regulatory Requirements

This Report summarizes Condition Assessment inspections completed by SAWS as of four years after the Date of Lodging pursuant to Paragraphs 23 through 28 of the Consent Decree. These Condition Assessment requirements include Large Diameter Gravity Main Sewer Inspections, Small Diameter Gravity Sewer Main Inspections and Manhole Inspections.

## VI. System-Wide Inspection Activities

### A. Inspection Method Overview

[Provide a brief description of each inspection method utilized by SAWS; with a reference to the Condition Assessment and Remediation Process and

*Guidelines Appendix.* Add a discussion of any new inspection technologies utilized, if applicable]

# **B.** Gravity Sewer Main Inspection Map

[Include a map showing the location of the inspections, small diameter and large diameter pipe, inspection method (CCTV, Pole Camera, Visual Inspection), and type of visual inspection (Smoke testing, mechanical proofing, cleaning, dye testing).]

# C. Gravity Sewer Main Inspection Status

### **Gravity Sewer Main Inspection Progress Summary**

Asset Description	Inspection Method	Miles of Inspections Required Under Consent Decree <sup>1,3</sup>	Miles Completed Prior to Date of Lodging <sup>2,3</sup>	Miles Completed since Date of Lodging <sup>3</sup>	Miles of Inspections Completed 3	% Complete
Small Diameter Gravity Sewer - Concrete Pipe and Clay Pipe Installed Prior to 1973	CCTV or other approved techniques	xx				
Small Diameter Gravity Sewer - Clay Pipe Installed from 1973 through 1982	Pole Camera, CCTV, or other approved techniques	хх				
	Pole Camera, CCTV or other approved techniques	N/A				
	Visual Inspection – Smoke Testing	N/A				
Small Diameter Gravity Sewer -	Visual Inspection – Mech. Proofing	N/A				
Other Pipe	Visual Inspection – Sewer Cleaning Findings	N/A				
	Visual Inspection – Dye Testing	N/A				
	Subtotal	N/A				
	Unique Subtotal <sup>4</sup>	ХХ				
Large Diameter Gravity Sewer	CCTV/other approved method	хх				

Note 1: Visual Inspection, and Large Diameter CCTV Inspection are not required under the Consent Decree to be completed prior to submittal of this report. These inspection types will be completed as part of CMOM after submittal of this report per CD Requirements.

Note 2: Includes small diameter gravity sewer inspections since January 1, 2009 and large diameter gravity sewer inspections since inception of the large diameter program in 2005.

Note 3: Full pipe length is included in mileages.

Note 4: Since some gravity sewer mains may be inspected with multiple visual inspection techniques, this subtotal includes unique miles of small diameter gravity sewer main inspections in order demonstrate compliance for visual inspection.

# D. Manhole Inspection Map

[Include a map showing the location of the inspections.]

# E. Manhole Inspection Status

### **Manhole Inspection Summary**

	spection Aethod	Manhole in System <sup>1</sup>	Prior to Date of Lodging <sup>2</sup>	Inspected Since Date of Lodging	Inspections Completed	% Complete <sup>1</sup>			
l Manholes	Visual spection	xx							
Note 1: Manhole Inspection is not required under the Consent Decree to be completed prior to submittal of this report. Manhole inspections will be completed as part of CMOM after submittal of this report per CD Requirements. Note 2: Includes manhole inspections since January 1, 2009.									

# VII. Categorization of Sewer Main and Manhole Condition

### A. Guidelines

[Provide a brief description of the guidelines used for categorizing condition; consistent with the Condition Assessment and Remediation Process and Guidelines Appendix]

## B. Condition Categorization Summary

Condition Category	Miles of Small Diameter Sewer Mains	Miles of Large Diameter Sewer Mains	Number of Manholes
Category A – Very Good	XX	XX	XX
Category B – Good	XX	XX	XX
Category C – Fair Condition	XX	XX	XX
Category D – Poor	XX	XX	XX
Category E Very Poor	XX	XX	XX
Note 1: Full pipe length is inclu	ided in mileages.		

### **Condition Categorization Summary**

Appendix G Condition Assessment Report Template

### C. Maps of Condition Categories

[Include one map for small diameter pipe, one map for large diameter pipe, and one map for manholes showing the location of the assets and the Condition Category.]

## VIII. Condition Assessment Results

## A. Condition Assessment Guidelines

[Provide a brief description of the guidelines used for condition assessment activities; consistent with the Condition Assessment and Remediation Process and Guidelines Appendix. Provide a brief description of how SAWS applied the guidelines to develop the quantities of structural defects selected for Remedial Measures Alternative Analysis, Monitoring (CMOM) and Maintenance Analysis (CMOM).]

## B. Condition Assessment Results

Condition Assessment Result	Miles of Small Diameter Sewer Mains <sup>1</sup>	Miles of Large Diameter Sewer Mains <sup>1</sup>	Number of Manholes
Remedial Measures Alternatives Analysis	xx	XX ·	xx
Monitoring (CMOM)	XX	XX	XX
Maintenance Analysis (CMOM)	xx	xx	ХХ
Note 1: Full pipe length	is included in milea	ges.	

## C. Maps of Condition Assessment Results

[Include one map for small diameter pipe, one map for large diameter pipe, and one map for manholes showing the location of the assets and the Condition Assessment Result.]

## I. Cover

## II. Certification Declaration

[Required certification, with language specified by the Consent Decree, signed by a responsible official of SAWS]

## III. Table of Contents

[List of sections, tables, figures and appendices included in this report]

## IV. Acronyms and Abbreviations

[Definitions of abbreviations and acronyms included in this report]

## V. Introduction

## A. Purpose

This Plan was prepared and submitted pursuant to Paragraph 30 of the Consent Decree.

## **B.** Regulatory Requirements

This Plan summarizes SAWS recommended Condition Remedial Measures that have been prioritized and selected in accordance with Appendix C to address verified structural defects in the SAWS WCTS that cause or significantly contribute to Condition-related SSOs. This Plan describes SAWS plans to implement the selected Condition Remedial Measures on a balanced annual basis during the remaining term of this Decree. SAWS has prioritized and selected these Condition Remedial Measures based on appropriate factors reflected in Paragraph 30 and in Appendix C of the Consent Decree and in accordance with the requirements of Paragraph 8 of the Decree. The implementation time-frames in this Plan reflect practical planning requirements such as those stated in Paragraph 30 of the Consent Decree.

## VI. Summary of Condition Assessment Summary Report

[Brief summary of the Condition Assessment Summary Report and how it relates to this Plan.

## VII. Remedial Measures Alternatives Analysis

## A. Guidelines for Alternatives Analysis

The Plan for Condition Remedial Measures follows SAWS completion of the Condition Remedial Measures Alternatives Analysis as described in Paragraph 29 and in Appendix C of the Consent Decree.

## B. Remedial Measures Alternatives Analyses Results

[Provide a brief description of the guidelines used for performing alternatives analysis; consistent with Condition Assessment and Remediation Process and Guidelines Appendix. Include a description of guidelines used to select monitoring or maintenance results.]

Result	Miles of Gravity Main Sewer <sup>1</sup>	Number of Gravity Sewer Main Pipe Segments	Number of Manholes
Replace <sup>2</sup>	Х	x	X
Rehabilitate <sup>2,3</sup>	x	X	X
Repair <sup>2,3</sup>	X	X	X
Monitoring	Х	X	X
Maintenance Analysis	X	X	X
Other (Specify)	X	X	X
Totals:	x	x	X
Note 1: Full pipe length is inc	luded in mileage	·	

#### Results of Completed Remedial Measures Alternatives Analyses

Note 2: Approach for actual implementation may be different than alternatives analysis result per Paragraph 31 of the Consent Decree and Appendix C (Condition Assessment and Remediation Process and Guidelines Appendix)

Note 3: Repairs include spot repairs or remediation of a short section of the pipe segment using trenchless or open-trench remediation. Rehabilitation includes trenchless sewer remediation from manhole to manhole such as CIPP lining or slip-lining.

## C. Maps of Alternatives Analyses Results

[Include one map for small diameter pipe and large diameter pipe and one map for manholes showing the location of the assets and the Remedial Measures Alternatives Analysis Results.]

## *VIII.* Remediation Completed

## A. Remedial Measures Progress

[Summarize the mileage and number of manholes for which Condition Remedial Measures have been completed prior to submittal of this report.]

	Remedial Measure Technique	Early Action Program - Phase I	Early Action Program - Phase II	Other	Total
Large Diameter	Replace				
Sewer Mains (miles) <sup>1,2</sup>	Rehabilitate				
(miles)	Repair				
Small	Replace				
Diameter Sewer Mains	Rehabilitate				
(miles) <sup>1,2</sup>	Repair				
Manholes (number)	Replace				
	Rehabilitate		<u>+</u>		
	Repair				
	e length is inclu				ine segment using

Note 2: Repairs include spot repairs or remediation of a short section of the pipe segment using trenchless or open-trench remediation. Rehabilitation includes trenchless sewer remediation from manhole to manhole such as CIPP lining or slip-lining.

## B. Maps of Remedial Measures Completed

[Include a color coded map for Phase I, a map for Phase II, and another map for Other completed remediation by remediation method and asset type (small

diameter pipe, large diameter pipe, and manholes that identifies and distinguishes between replaced and repaired manholes in Phase I and Phase II of the Early Action Program.]

## IX. Remedial Measures Plan

## A. Anticipated Remediation Timeframes

[Summarize target remediation quantities for completion each year.]

	Remedial Measure Technique	Calendar Year X	Total				
 Large Diameter	Replace	   					
Sewer Mains	Rehabilitate						
(miles) <sup>1</sup>	Repair						
Small	Replace						
Diameter Sewer	Rehabilitate						
Mains (miles) <sup>1</sup>	Repair						
Manholes (number)	Replace		ļ				
(number)	Rehabilitate						
	Repair		+				

Note 2: SAWS may make day-to-day operational changes to Remedial Measures consistent with the Consent Decree, including Appendices C and D of the Consent Decree.

## B. Maps of Anticipated Remediation Timeframe

[Include a color coded map for each year identifying the small diameter pipes, large diameter pipes, and manholes that will be Replaced, Rehabilitated, or Repaired.]

## C. Remediation Project List

## **Remediation Project List**

Project Name	Project Miles	Completion Date	For large diameter pipes, schedule Justification for Completion Date After 4.5 years from EPA Approval of Remedial Measures Plan (Pursuant to Paragraph 31 of the Consent Decree}
	l		·

## I. Cover

## II. Certification Declaration

[Required certification, with language specified by the Consent Decree, signed by a responsible official of SAWS]

## III. Table of Contents

[List of sections, tables, figures and appendices included in this report]

## **IV.** Acronyms and Abbreviations

[Definitions of abbreviations and acronyms included in this report]

## V. Introduction

#### A. Purpose

This Report was prepared and submitted pursuant to Paragraph 39 of the Consent Decree.

## **B. Regulatory Requirements**

This Report summarizes Capacity Assessment activities pursuant to Paragraph 33 through 38 of the Consent Decree. These Capacity Assessment requirements include Wet Weather SSO Verification, Hydraulic Modeling Evaluation and Field Investigation activities.

## VI. Wet-Weather Related SSO Categorization

## A. Guidelines

[Provide a brief description of the guidelines used; with a reference to the Capacity Assessment and Remediation Process and Guidelines Appendix. Include the range of dates for historical SSOs that this section covers. Include a summary of the activities performed to address Category C SSOs.]

## B. Wet-Weather SSO Categorization Summary

Category	Number of SSOs
Category A – Most likely a capacity-related SSO	Х
Category B – Most likely maintenance-related	Х
Category C Clearly not a capacity related SSO	Х
Total	X

#### Wet Weather SSO Categorization

## C. Map of Wet-Weather SSOs

[Include a map showing the location of Category A, B, and C Wet-Weather SSOs, a map showing the location of Category A Wet-Weather SSOs, a map showing the location of Category B Wet-Weather SSOs, and a map showing the location of Category C Wet-Weather SSOs.]

## VII. System-wide Hydraulic Modeling Evaluation

## A. Model Overview

[Provide a brief description of the model including software and existing population scenario, consistent with the Capacity Assessment and Remediation Process and Guidelines Appendix.]

## B. Model Maps

[Include a map showing the location of pipes in the model.]

## C. Model Calibration and Updates

[Provide a summary of any model updates and calibration performed after Date of Lodging of the Consent Decree (e.g. weather permitting) and prior to submittal of the Capacity Assessment Report consistent with the Capacity Assessment and Remediation Process and Guidelines Appendix.

## D. Prioritization of Potential Capacity Constraints

[Provide a brief description of the guidelines used to prioritize potential capacity constraints; consistent with the Capacity Assessment and Remediation Process and Guidelines Appendix].

Category	Number of Potential Capacity Constraints
Priority 1 – Category A SSO per Wet-Weather SSO Categorization	x
and where model also predicts a SSO	
Priority 2 – Where model predicts SSO, but with no observed SSO. Or a Category A SSO per Wet-Weather SSO Categorization, but model does not predict a SSO.	X
Priority 3 – Where model predicts Hydraulic Grade Line (HGL) near ground elevation	X
Priority 4 – Category 8 SSO per Wet-Weather SSO Categorization	Х
Priority 5 – Where pipe design capacity is exceeded for sustained	X
60 minutes or more but the HGL is not near the ground elevation	
Total	х

#### Potential Capacity Constraints Summary

## E. Map of Potential Capacity Constraints

[Include a map showing potential Capacity Constraints for all Priority Categories. Include separate maps for each Priority Category showing the location of Potential Capacity Constraints.]

## VIII. Field Investigations of Potential Capacity Constraints

## A. Guidelines

[Provide a brief description of the guidelines used for selecting the type of field investigation technique for each potential capacity constraint; consistent with Capacity Assessment and Remediation Process and Guidelines Appendix.]

## B. Field Investigation Status

Technique	Number of Potential Capacity Constraints					
	Priority 1	Priority 2	Priority 3	Priority 4	Priority 5	
Flow Metering	x	X	х —	X	x	
Smart Covers	Х	x	Х	X	X	
Chalking	Х	Х	X	x	X	
Visual Inspection – Smoke Testing	x	X	Х	X	x	
Visual Inspection – Mechanical Proofing	Х	X	x	Х	x	
Visual Inspection – Sewer Cleaning Findings	х	x	Х	x	x	
Visual Inspection – Dye Testing	х	x	x	X	X	
Other (if applicable)	x	X	Х	X	X	
Monitor in Future per Capacity Assessment and Remediation Process and Guidelines Appendix (CMOM)	X	X	X	X	x	
Total	x	X	Х	X	x	

#### **Completed Field Investigations**

Technique	Number of Potential Capacity Constraints						
rechnique	Priority 1	Priority 2	Priority 3	Priority 4	Priority 5		
Flow Metering	X	x	Х	x	x		
Smart Covers	x	X	Х	X	X		
Chalking	x	X	X	x	X		
Visual Inspection – Smoke Testing	X	X	X	х	x		
Visual Inspection – Mechanical Proofing	x	x	x	X	x		
Visual Inspection – Sewer Cleaning Findings	x	X	x	X	x		
Visual Inspection – Dye Testing	x	x	x	x	x		
Other (if applicable)	x	Х	x	Х	x		
Total	х	X	X	x	X		

#### In-Progress Field Investigations

## C. Map of Completed Field Investigations

[Include a map for each Priority Category showing the location of each field investigation by technique.]

## D. Map of In-Progress Field Investigations

[Include a map for each Priority Category showing the location of each field investigation by technique.]

## IX. Capacity Assessment Results

## A. Capacity Assessment Guidelines

[Provide a brief description of the guidelines used for assessing field investigation results; consistent with Capacity Assessment and Remediation Process and Guidelines Appendix.

## B. Capacity Assessment Results

Capacity Assessment Result	Number of Potential Capacity Constraints
Remedial Measures Alternatives Analysis	X
Monitor in the Future per Capacity Assessment and Remediation Process and Guidelines Appendix (CMOM)	x
Not a Capacity Constraint	X
Total	х

## C. Map of Capacity Assessment Results

[Include a color coded map showing the location of the Capacity Assessment Results.]

## I. Cover

## II. Certification Declaration

[Required certification, with language specified by the Consent Decree, signed by a responsible official of SAWS]

## III. Table of Contents

[List of sections, tables, figures and appendices included in this report]

## IV. Acronyms and Abbreviations

[Definitions of abbreviations and acronyms included in this report]

## V. Introduction

#### A. Purpose

This Plan was prepared and submitted pursuant to Paragraph 41 of the Consent Decree.

## B. Regulatory Requirements

This Plan summarizes SAWS recommended Capacity Remedial Measures that have been prioritized and selected in accordance with Appendix D to address verified Capacity Constraints in the SAWS WCTS that cause or significantly contribute to Capacity-related SSOs. This Plan describes SAWS plans to implement the selected Capacity Remedial Measures on a balanced annual basis during the remaining term of this Decree. SAWS has prioritized and selected these Capacity Remedial Measures based on appropriate factors reflected in Paragraph 41 and in Appendix D of the Consent Decree and in accordance with the requirements of Paragraph 8 of the Decree. The implementation time-frames in this Plan reflect practical planning requirements such as those stated in Paragraph 41 of the Consent Decree.

## VI. Summary of Capacity Assessment Summary Report

[Brief summary of the Capacity Assessment Summary Report and how it relates to this Plan.

## VII. Remedial Measures Alternatives Analysis

## A. Guidelines for Alternative Analysis

The Plan for Capacity Remedial Measures follows SAWS completion of the Capacity Remedial Measures Alternatives Analysis as described in Paragraph 40 and in Appendix D of the Consent Decree

## B. Remedial Measures Alternatives Analysis Results

[Provide a brief description of the guidelines used for performing alternatives analysis; consistent with Capacity Assessment and Remediation Process and Guidelines Appendix. Include a description of guidelines used to select continued monitoring results.]

Remedial Measures Alternatives Analysis Result *	Number of Potentia Capacity Constraint		
Re-route a portion of upstream wastewater flows	X		
Reduce flows entering the WCTS	×		
Reduce inflow	X		
Reduce infiltration	Х		
Increase conveyance capacity	X		
Upstream flow detention facilities	X		
Continued monitoring	x		
Other (Specify)	X		
Totals:	x		

#### Results of Remedial Measures Alternatives Analyses

\* Note: Approach for actual implementation may be different than alternatives analyses result pursuant to Paragraph 42 and Appendix D of the Consent Decree. Some Capacity Constraints may require more than one remedial measure technique. The predominant remedial measure technique will prevail for reporting purposes.

## C. Map of Alternatives Analysis Results

[Include a color coded map showing the location of each type of result.]

## **VIII.** Remediation Completed

#### A. **Remedial Measures Progress**

[Summarize the mileage for which Capacity Remedial Measures have been completed prior to submittal of this report.]

	Remedial Measure Technique	Phase I	Phase II	Other	Total
Large	Re-route a portion of upstream wastewater flows	-			
Diameter	Reduce flow entering WCTS				
Sewer Mains	Reduce inflow				
(miles) <sup>1</sup>	Reduce infiltration				
	Increase conveyance capacity				
	Upstream flow detention facilities				
	Other (specify)				
Small Diameter	Re-route a portion of upstream wastewater flows				
Sewer Mains	Reduce flow entering WCTS				
(miles) <sup>1</sup>	Reduce inflow				
	Reduce infiltration				
	Increase conveyance capacity				
	Upstream flow detention facilities				
	Other (specify)				
Manholes	Replace	1			
(number)	Rehabilitate				
	Repair				
Note 1: Full pi	pe length is included in mileage		•		
•	Capacity Constraints may require r	nore than	one remedi	al measure	technique.

#### **Completed Remedial Measures**

The predominant remedial measure technique will prevail for reporting purposes.

#### **Map of Remedial Measures Completed** В.

[Include a color coded map for Phase I, a map for Phase II, and another map for Other completed remediation by remediation method and asset type (small diameter pipe, large diameter pipe, and manholes) that identifies and distinguishes between replaced and repaired manholes in Phase I and Phase II of the Early Action Program.]

## IX. Remedial Measures Plan

## A. Anticipated Remediation Timeframes

[Summarize target remediation quantities for completion each year. Include a list of Lift Stations that require capacity upgrades per the Remedial Measures Plan.]

	Remedial Measure	Calendar	Calendar	Calendar	Calendar	Total
	Technique	Year X	Year X	Year X	Year X	
	Re-route a portion of					
Large Diameter	upstream wastewater					
Sewer Mains	flows					
(Number of	Reduce flow entering					
constraints	WCTS					
addressed)	Reduce inflow					
	Reduce infiltration					
	Increase conveyance					
	capacity					
	Upstream flow					
	detention facilities					
	Other (specify)					
Small Diameter	Re-route a portion of					
Sewer Mains	upstream wastewater					
(Number of	flows					
constraints	Reduce flow entering					
addressed)	WCTS					
	Reduce inflow					
	Reduce infiltration					
	Increase conveyance					
	capacity					
	Upstream flow					
	detention facilities					
	Other (specify)					
Manholes	Replace					
(number)	Rehabilitate					
	Repair					
Note 1: SAWS m	ay make day-to-day op	erational cl	nanges to Re	emedial Me	asures consi	stent with
	cree, including Append					
	pacity Constraints may					nique.
The predominar	nt remedial measure te	chnique wi	ll nrevail for	reporting r	urnoses	

#### **Anticipated Remediation Timeframes**

## B. Maps of Anticipated Remediation Timeframe

[Include a color coded map for each year identifying the capacity constraints and the remedial measure method that will be utilized to address each capacity constraint.]

## C. Remediation Project List

#### **Remediation Project List**

Project Name	Project Miles	Completion Date	For Large Diameter Pipes, Schedule Justification for Completion Date After 4. Years from EPA Approval of Remedial Measures Plan (Pursuant to Paragraph 42 of the Consent Decree)	

## I. Cover

## II. Certification Declaration

[Required certification, with language specified by the Consent Decree, signed by a responsible official of SAWS]

## III. Table of Contents

[List of sections, tables, figures and appendices included in this report]

## IV. Acronyms and Abbreviations

[Definitions of abbreviations and acronyms included in this report]

## V. Introduction

## A. Purpose

This Report was prepared and submitted pursuant to Paragraph 52 of the Consent Decree.

## B. Regulatory Requirements

This Report summarizes activities completed during the previous calendar year for the following requirements in Section V of the Consent Decree: Early Action Program, Condition Assessment, Condition Remedial Measures, Capacity Assessment, Capacity Remedial Measures, Lift Station Rehabilitation and Elimination Program, Force Main Assessment Program, CMOM Program (including Private Laterals) and Water Quality Program.

## VI. Early Action Program

#### Phase I Early Action Program Remediation

Asset Description	Completed in Calendar Year X	Cumulative Completed <sup>2</sup>			
Small Diameter Gravity Sewer (Miles) <sup>1</sup>	x	X			
Large Diameter Gravity Sewer (Miles) <sup>1</sup>	X	x			
Manholes (Number)	x	x			
Note 1: Full pipe length is included in mileages.					
Note 2: Includes all work completed since xx/xx/xx.					

#### Status of Phase I Multi-Year Large Diameter Projects

Project Name	Description of Status

#### Phase II Early Action Program Remediation

Asset Description	Completed in Calendar Year X	Cumulative Completed <sup>2</sup>				
Small Diameter Gravity Sewer (Miles) <sup>1</sup>	x	X				
Large Diameter Gravity Sewer (Miles) <sup>1</sup>	X	X				
Manholes (Number)	x	X				
Note 1: Full pipe length is included in mileages.						
Note 2: Includes all work completed since xx/xx/xx.						

#### Status of Phase II Multi-Year Large Diameter Projects

Project Name	Description of Status			

## VII. CMOM

## A. SSO Reporting

[Reference attached SSO documentation pursuant to Paragraph 12.c and 12.d of the Consent Decree]

## B. Fats, Oils, and Grease Program

[Report pursuant to Paragraph 52.b.ii of the Consent Decree]

Inspections and Enforcements Actions in Calendar Year X

Number of Permitted Food Service	Number of Inspections	Number of Enforcement or Compliance
Establishments		Assistance Actions
XX	XX	XX

## C. Sewer Cleaning

[Report pursuant to Paragraph 52.b.iii of the Consent Decree]

## Small Diameter System-Wide Cleaning Program Status in Calendar Year X

[This mileage includes Repeat Cleaning Program pursuant to Paragraph 14.b of the Consent Decree.]

Total Small Diameter Miles Miles		% Cleaned in Calendar Year X	% Required per Calendar Year	
xx	XX	XX	12%	

Small Diameter System-Wide Cleaning Program Cumulative Status

Unique Small Diameter Cleaning Completed – Year X Through Year X

	Unique Small Diameter Cumulative Percent Completed
January 1, 2009 through Date of Lodging	x
January 1, 2009 through Year 1	x
···	x
January 1, 2009 through Year 10	x

#### Large Diameter Cleaning Program Status

Total Large Diameter	Miles Cleaned in Calendar	% Cleaned in Calendar	
Miles	Year X	Year X	
XX	xx	XX	

#### Large Diameter Cleaning Program Cumulative Status

#### Unique Large Diameter Cleaning Completed – Year X Through Year X

	Unique Large Diameter Cumulative Percent Completed
January 1, 2009 through Date of Lodging	×
January 1, 2009 through Year 1	×
•••	x
January 1, 2009 through Year 10	×

## D. Private Laterals

[Report pursuant to Paragraphs 12.d,17, and 52 of the Consent Decree]

## VIII. Condition Assessment

## A. Gravity Sewer Main Inspection Map

[Include a map showing the location of the inspections. The map will differentiate between inspections completed during the calendar year reported in the annual report and inspections completed prior to the calendar year reported in the annual report. Inspections completed prior to the calendar year reported in the annual report will include inspections after January 1, 2009 for small diameter pipe and after inception of the large diameter inspection program in 2005 for large diameter pipe.]

## B. Gravity Sewer Main Inspection Status

## Gravity Sewer Main Inspection Completed Through Calendar Year X

Asset Description	Method	Miles of Inspections Required Under Consent Decree <sup>2</sup>	Miles Completed Prior to Date of Lodging <sup>1,2</sup>	Miles Completed in Calendar Year X <sup>1</sup>	Miles Completed since Date of Lodging <sup>2</sup>	Cumulative Miles of Inspections Completed	Cumulative % Complete
Small Diameter Gravity Sewer - Concrete Pipe and Clay Pipe Installed Prior to 1973	CCTV or other approved techniques	xx	xx	xx	xx	xx	xx
Small Diameter Gravity Sewer - Clay Pipe Installed from 1973 through 1982	Pole Camera, CCTV, or other approved techniques	xx	xx	XX	XX	xx	xx
Small Diameter Gravity Sewer - Other Pipe	Visual Inspection, Pole Camera, CCTV, or other approved techniques	xx	хх	XX	XX	xx	xx
Large Diameter Gravity Sewer	CCTV and other approved techniques	хх	xx	xx	xx	xx	xx
Note 1: Includes sma since inception of th Note 2: Full pipe len	e large diamete	r program in 20		nuary 1, 2009 a	ind large diame	ter gravity sew	er inspections

## C. Manhole Inspection Map

[Include a map showing the location of the inspections. The map will differentiate between inspections completed during the calendar year reported in the annual report and inspections completed prior to the calendar year reported in the annual report. Inspections completed prior to the calendar year reported in the annual report will include inspections after January 1, 2009.]

## D. Manhole Inspection Status

Inspection Method	Manhole Inspections to be Completed Under Consent Decree	Inspected Prior to Date of Lodging <sup>1</sup>	inspected in Calendar Year X	Inspected Since Date of Lodging	Cumulative Inspections Completed <sup>1</sup>	Cumulative % Complete <sup>1</sup>
Visual Inspection	хх	xx	xx	хх	xx	xx

#### Manhole Inspection Summary

## E. Condition Categorization Summary

#### **Condition Categorization Summary**

Condition Category	Miles of Small Diameter Sewer Mains <sup>1</sup>	Miles of Large Diameter Sewer Mains <sup>1</sup>	Number of Manholes
Category A – Very Good	XX	XX	XX
Category B – Good	XX	XX	XX
Category C - Fair Condition	XX	XX	xx
Category D – Poor	XX	XX	XX
Category E – Very Poor	XX	XX	XX
Note 1: Full pipe length is included	in mileages.	<u> </u>	

## F. Map of Condition Categories

[Include a map showing the location of the categorized assets for assets categorized during the calendar year reported in the annual report.]

## G. Condition Assessment Guidelines

[Reference Consent Decree Appendix C, Condition Assessment and Remediation Process and Guidelines Appendix. Brief description of how SAWS applied these guidelines to develop the quantities of structural defects selected for Remedial Measures Alternative Analysis, Monitoring (CMOM) and Maintenance Analysis (CMOM).]

## H. Condition Assessment Results During Calendar Year X

Miles of Small Diameter Sewer Mains <sup>1</sup>	Miles of Large Diameter Sewer Mains <sup>1</sup>	Number of Manholes
xx	xx	xx
XX	XX	XX
XX	XX	XX
	Diameter Sewer Mains <sup>1</sup> XX XX	Diameter Sewer Mains <sup>1</sup> Diameter Sewer Mains <sup>1</sup> XX     XX       XX     XX       XX     XX

## I. Map of Condition Assessment Results

[Include a map showing the location of the results for results determined during the calendar year reported in the annual report.]

## IX. Condition Remedial Measures

## A. Status of Multi-Year Large Diameter Condition Remediation

Project Name	Description of Status

## **B.** Condition Remediation Completed

[Summarize the mileage of gravity sewer mains and number of manholes for which Condition Remedial Measures have been completed (Not including Early Action Program work)]

	Miles of Small Diameter Gravity Sewer Main <sup>1</sup>	Miles of Large Diameter Gravity Sewer Main <sup>1</sup>	Number of Manholes	
Completed in Calendar Year X	х	x	x	
Note 1: Full pipe length is	included in mileage	••••••••••••••••••••••••••••••••••••••		

#### **Remediation Completed**

[After EPA approval of the Condition Remedial Measures Plan, include a description of day-to-day operational changes to Remedial Measures consistent with of the Consent Decree and Appendices C and D of the Consent Decree.]

## C. Map of Condition Remedial Measures Completed

[Include an overview map of remedial measures completed. The map will differentiate between remedial measures completed during the calendar year reported in the annual report and remedial measures completed pursuant to the consent decree prior to the calendar year reported in the annual report.]

## D. Asset Information for Condition Remedial Measures Completed During Calendar Year X

[Attach the following information to this report:

- a. The asset identification number and type of asset;
- b. Whether the asset was rehabilitated, repaired or replaced;
- c. The length of the sewer line at issue, if applicable;
- d. The pipe material, if applicable;
- e. The diameter of the pipe, if applicable;
- f. The manhole type, if applicable;
- g. The original installation date of the asset;
- h. Project name]

## X. Capacity Assessment

## A. Wet-Weather Related SSO Categorization

1. Guidelines

[Reference Consent Decree Appendix D, Capacity Assessment and Remediation Process and Guidelines Appendix. Include the range of dates for historical SSOs that this section of the Annual Report covers. Include a summary of the activities performed to address Category C SSOs.]

#### 2. Wet-Weather SSO Categorization Summary

#### Wet Weather SSO Categorization for Calendar Year X

Category	Number of SSOs
Category A Most likely a capacity-related SSO	X
Category B – Most likely maintenance-related	X
Category C – Clearly not a capacity related SSO	Х
Total	Х

#### 3. Wet-Weather SSO Categorization Summary Map

[Include a map showing the location of the wet-weather SSO categories for SSOs categorized during the calendar year reported in the annual report.]

## B. System-wide Hydraulic Modeling Evaluation

#### 1. Model Maps

[Include a map showing the location of pipes in the model.]

#### 2. Model results identifying potential Capacity Constraints

[Provide a summary of any model results that identify potential Capacity Constraints, including any lift station results]

## C. Prioritization of Potential Capacity Constraints

[Provide a brief description of how SAWS used Consent Decree Appendix D to prioritize potential Capacity Constraints, consistent with the Capacity Assessment and Remediation Process and Guidelines Appendix].

Category	Number of Potential Capacity Constraints Identified in Calendar Year X
Priority 1 – Category A SSO per Wet-Weather	Х
SSO Categorization and where model also predicts a SSO	
Priority 2 – Where model predicts SSO, but with no observed SSO. Or a Category A SSO per Wet- Weather SSO Categorization, but model does not predict a SSO.	X
Priority 3 – Where model predicts Hydraulic Grade Line (HGL) near ground elevation	X
Priority 4 – Category B SSO per Wet-Weather SSO Categorization	X
Priority 5 – Where pipe design capacity is exceeded for sustained 60 minutes or more but the HGL is not near the ground elevation	X
Total	x

#### **Potential Capacity Constraints Summary**

#### 1. Map of Potential Capacity Constraints

[Include a map showing the location of potential capacity constraints identified during the calendar year reported in the annual report.]

## XI. Field Investigations of Potential Capacity Constraints

## A. Field Investigation Status

Technique	Number of Completed Field Investigations in Calendar Year X				
	Priority 1	Priority 2	Priority 3	Priority 4	Priority 5
Flow Metering	X	х	X	X	X
Smart Covers	x	x	x	X	x
Chalking	x	x	X	<u> </u>	x
Visual inspection	X	x	X	X	x –
Other (if applicable)	X	x	x	X	х —
Monitor in Future per Capacity Assessment and Remediation Process and Guidelines Appendix (CMOM)	×	X	x	×	x
Total	X	x	x	x	X

#### **Completed Field Investigations**

## B. Map of Completed Field Investigations

[Include a map showing the location of each field investigation.]

## XII. Capacity Remediation

## A. Status of Multi-Year Large Diameter Capacity Remediation

Project Name	Description of Status	

## B. Capacity Remediation Completed

[Summarize the mileage for which Capacity Remedial Measures have been completed (Not including Early Action Program work)]

	Miles of Small Diameter Gravity Sewer Main <sup>1</sup>	Miles of Large Diameter Gravity Sewer Main <sup>1</sup>
Completed in Calendar Year X	х	x
Note 1: Full pipe length is included in	mileage	

[After EPA approval of the Condition Remedial Measures Plan, include a description of day-to-day operational changes to Remedial Measures consistent with of the Consent Decree and Appendices C and D of the Consent Decree.]

## C. Map of Capacity Remedial Measures Completed

[Include an overview map of remedial measures completed. The map will differentiate between remedial measures completed during the calendar year reported in the annual report and remedial measures completed pursuant to the consent decree prior to the calendar year reported in the annual report.]

## D. Asset Information for Completed Capacity Remedial Measures

[Attach the following information to this report:

- a. The asset identification number and type of asset;
- b. Whether SAWS addressed the Capacity Constraint through pipe rehabilitation/replacement, increased conveyance capacity, increased storage, or other Capacity Remedial Measures;
- c. The length of the sewer line at issue, if applicable;
- d. The pipe material, if applicable;
- e. The diameter of the pipe, if applicable;
- f. The original installation date of the asset at issue;
- g. Project name]

# E. Potential Capacity Constraints Removed from Field Investigation Program

[Report pursuant to Consent Decree paragraph 52.f.viii.]

## XIII. Remedial Measures Coordinated Between Capacity and Condition Remedial Measures

[Description of Remedial Measures that were coordinated between Condition and Capacity Remedial Measures]

## XIV. Lift Station Rehabilitation and Elimination Program

[Report updates to Consent Decree Appendix E pursuant to paragraphs 44 and 52.g of the Consent Decree.]

## XV. Force Main Assessment Program

[Report pursuant to requirements of paragraphs 46 and 52.h of the Consent Decree.]

	Inspections to be Completed Under Consent Decree	Inspections Completed in Year X	Cumulative Inspections Completed	Cumulative % Complete
Number of Force Mains Visually Inspected	ХХ	хх	ХХ	хх

#### Force Main Inspection Progress Summary

#### Force Main Condition Assessment Summary

Condition Assessment Result	Miles of Force Mains
Remedial Measures Alternatives Analysis	XX
Monitoring (CMOM)	XX
Maintenance Analysis (CMOM)	xx

#### Force Main Remedial Measures Completed in Calendar Year X

Miles Completed in Calendar Year X XX

## XVI. Water Quality Program

[Report pursuant to Consent Decree paragraph 52.i]

## XVII. Work Completed in Low Income Areas

[Report pursuant to Consent Decree paragraph 52.]. Include the following:

- a. Narrative summary of miles of gravity sewer main inspected, cleaned or remediated in low income areas per summaries in Sections VI, VII.C, VIII.B, IX.B, and XII.B herein;
- b. All maps required by this Annual Report Template shall show the low income areas in which work was completed using a map consistent with Attachment 1 hereto for the work categories specified in Consent Decree paragraph 52.j.]

## **XVIII.Modifications**

[Include a summary of written agreements pursuant to Consent Decree paragraph 110 and other changes made pursuant to Consent Decree paragraph 111.]

## Appendix for

## **SSO Documentation**

## Appendix for Updated


## Lift Station Table (Consent Decree Appendix E)

## Appendix for

## Asset Information for Completed Condition Remedial Measures

## Appendix for

## Asset Information for Completed Capacity Remedial Measures



## APPENDIX H

#### APPENDIX H

#### WWTP AND MITCHELL LAKE EFFLUENT VIOLATIONS SUMMARY (2003-DECEMBER 31, 2012)

#### SAN ANTONIO WATER SYSTEM

#### EFFLUENT LIMIT VIOLATIONS

#### Leon Creek Waste Water Treatment Plant (TX0052639)-Major

DATE	OUTFALL	PARAMETER	VIOLATION	PERMIT	NO. OF
				LIMIT V	<b>IOLATIONS</b>
10/03	001	DO, min.	4.1 mg/l	5.0 mg/l	1
10/03	001	NH3-N, max.	17.64 mg/l	7 mg/l	2
10/03	001	CBOD, max.	53.0 mg/l	17 mg/l	1
10/05	001	NH3-N, max.	7.42 mg/l	7 mg/l	1
12/05	001	NH3-N, avg.	2.03 mg/l	2 mg/l	31
12/05	001	NH3-N, max.	7.25 mg/l	7 mg/l	1
09/08	002	pH, min.	5.9 s.u.	6.0 mg/l	1
02/09	002	pH, min.	5.7 s.u.	6.0 mg/l	1
12/09	001	NH3-N, avg.	2.37 mg/l	2 mg/Ī	31
12/09	001	NH3-N, max.	9.39 mg/l	7 mg/l	1
06/11	001	NH3-N, max	8.18 mg/l	7 mg/l	1
06/11	002	NH3-N, max.	8.18 mg/1	7 mg/l	1
12/11	001	E.Coli, max	1160 CFU/100	394 CFU/	100 1

#### Salado Creek Waste Water Treatment Plant (TX0052647)-Major

DATE	OUTFALL	PARAMETER	VIOLATION	PERMIT LIMIT	NO. OF VIOLATIONS
03/03	001	TRC, min.	0.95 mg/l	1.0 mg/l	1
03/03	004	TRC, min.	0.95 mg/l	1.0 mg/l	1
05/03	004	TRC, min.	0.60 mg/l	1.0 mg/l	1
07/06	001	NH3-N, avg.	3.24 mg/l	2 mg/l	31
07/06	001	NH3-N, max.	8.18 mg/1	7 mg/l	1
07/06	002	NH3-N, avg.	3.24 mg/l	2 mg/l	31
07/06	002	NH3-N, max.	8.18 mg/l	7 mg/l	1
07/06	002	TRC, max.	1.10 mg/l	.099 mg/l	31
07/06	004	NH3-N, avg.	3.24 mg/l	2 mg/l	31
07/06	004	NH3-N, max.	8.18 mg/l	7 mg/l	1

### Medio Creek Waste Water Treatment Plant (TX0055689)

DATE ,	OUTFALL	PARAMETER	VIOLATION	PERMIT LIMIT V	NO. OF IOLATIONS
07/07	001	Flow, avg.	15,573 gpm	14,757 gpm	1
08/07	001	Flow, avg.	16,506 gpm	14,757 gpm	1
03/09	001	CBOD, max.	> 10 mg/l	25 mg/l	1
03/09	001	NH3-N, avg.	2.28 mg/l	2 mg/l	31
03/09	001	TSS, max.	119 mg/l	40 mg/l	1

#### Dos Rios Waste Water Treatment Plant (TX0077801)

DATE	OUTFALL	PARAMETER	VIOLATION	PERMIT	NO. OF
				LIMIT V	/IOLATIONS
10/07	004		10 1	<b>#</b> 0 (1	
12/06	004	DO, min.	4.9 mg/l	5.0 mg/l	1
12/06	005	pH, min.	5.9 s.u.	6.0 s.u.	1
01/07	002	pH, min.	5.9 s.u.	6.0 s.u.	1
01/07	005	pH, min.	5.9 s.u.	6.0 s.u.	1
08/07	001	Flow, avg.	202,431 gpm	173,611 gpn	n 31
12/07	004	TRC, max.	.79 mg/l	.099 mg/l	1
3/08	001	TRC, max.	1.4 mg/l	.099 mg/l	1
1/09	002	TRC, max.	.5 mg/l	.099 mg/l	1
1/09	006	TRC, max.	.8 mg/l	.099 mg/l	1
09/09	001	NH3-N, max.	11 mg/l	7 mg/l	1
09/09	002	TRC, max.	.099 mg/l	.16 mg/l	1
09/09	004	NH3N, max.	11 mg/l	7 mg/Ī	1
09/09	005	NH3-N, max.	11 mg/1	7 mg/l	1
01/10	001	CBOD,max.	20 mg/1	9 mg/l	1
01/10	001	TSS, max.	93 mg//l	40mg/1	1
01/10	002	COB, max	25 mg/l	9 mg/l	1
01/10	002	TSS, max	93 mg/l	40 mg/l	1
01/10	004	CBOD, max	25 mg/l	9 mg/l	1
01/10	004	TSS, max	40 mg/l	93 mg/l	1
01/10	005	COB, max.	25 mg/l	9 mg/l	1
01/10	005	TSS, max.	93 mg/l	40 mg/l	1
01/11	001	CBOD, avg.	11988 lb/d	5213 lb/d	31
01/11	001	NH3-N, avg.	2.35 mg/l	2 mg/l	1
01/11	001	NH3-N, max.	7.62 mg/l	7 mg/l	- 1
01/11	002	NH3-N, max.	2.84 mg/l	2  mg/l	1
		,		0	-

#### Dos Rios Waste Water Treatment Plant (TX0077801)

DATE	OUTFALL	PARAMETER	VIOLATION	PERMIT LIMIT	NO. OF VIOLATIONS
01/11	002	NH3-N, max.	7.62 mg/l	7 mg/l	1
01/11	004	NH3-N, avg.	2.35 mg/l	2 mg/l	31
01/11	004	NH3-N, max.	7.62 mg/L	7 mg/L	1
01/11	005	NH3-N, avg	3.06 mg/L	2 mg/L	31
01/11	005	NH3-N, max.	7.62 mg/L	7 mg/L	1
09/11	001	NH3-N, max.	7.41 mg/L	7 mg/L	1
09/11	002	NH3-N, max.	7.41 mg/L	7 mg/L	1
09/11	004	NH3-N, max.	7.41 mg/L	7 mg/L	1
09/11	005	NH3-N, max.	7.41 mg/L	7 mg/L	1
10/11	001	NH3-N, avg.	2.21 mg/L	2 mg/L	31
10/11	001	NH3-N, max.	7.35 mg/L	7 mg/L	1
10/11	002	NH3-N, max.	7.35 mg/L	7 mg/L	1
10/11	004	NH3-N, max.	7.35 mg/L	7 mg/L	1
10/11	005	NH3-N, max.	7.35 mg/L	7 mg/L	1
01/12	001	NH3-N, avg	2.31 mg/L	2 mg/L	31
01/12	001	NH-N, max.	13 mg/L	7 mg/L	1
01/12	005	NH-N, max.	13 mg/L	7 mg/L	1
03/12	001	E.Coli, max.	680CFU/100	394 CFU/100	1
05/12	001	TRC, max.	.12 mg/L	.1 mg/L	1
05/12	001	TRC, min.	.8 mg/L	1 mg/L	1
05/12	002	TRC, min.	.8 mg/L	1 mg/1	1
05/12	004	TRC, min.	.8 mg/L	1 mg/L	1
10/12	001	E.Coli, max.	770 CFU/100	394 CFU/10	0 1
10/12	002	E.Coli, max.	770 CFU/100	394 CFU/10	01
10/12	005	E.Coli., max.	770 CFU/100	394 CFU/10	0 1

#### Mitchell Lake (TX0065641)-Minor

DATE	OUTFALL	PARAMETER	VIOLATION	PERMIT LIMIT	NO. OF VIOLATIONS
01/05	001	ph, max.	9.6 s.u.	9.0 s.u.	1
02/05	001	ph, max.	9.6 s.u.	9.0 s.u.	1
03/05	001	ph, max.	9.5 s.u.	9.0 s.u.	1
01/07	001	ph, max.	9.1 s.u.	9.1 s.u.	1
01/07	001	tss, avg.	114 mg/l	90 mg/l	31
03/07	001	ph, max.	9.6 s.u.	9.0 s.u.	1
03/07	001	tss, avg.	97 mg/l	90 mg/l	31
04/07	001	DO, min.	3.8 mg/l	4.0 mg/l	1

#### Case 5:13-cv-00666-DAE Document 8-1 Filed 10/15/13 Page 74 of 74

.

Mitchell Lake (TX0065641)

DATE	OUTFALL	PARAMETER	VIOLATION	PERMIT LIMIT	NO. OF VIOLATIONS
04/07	001	ph, max.	9.8 s.u.	9.0 s.u.	1
04/0 <b>7</b>	001	tss, avg.	103 mg/l	90 mg/l	31
05/07	001	DO, min.	.2 mg/l	4 mg/l	1
05/07	001	ph, max.	9.7 s.u.	9.0 s.u.	1
05/07	001	tss, avg.	104.5 mg/l	90 mg/l	31
06/07	001	ph, max.	10.2 s.u.	9 s.u.	1
06/07	001	tss, avg.	109.6 mg/l	90 mg/l	31
07/07	001	DO, min.	2.2 mg/l	4 g/l	1
07/07	001	ph, max.	9.8 s.u.	9 s.u.	1
08/07	001	DO, min.	3.2 mg/l	4 mg/l	1
08/07	001	ph, max.	9.5 s.u.	9.0 mg/l	1
09/07	001	DO, min	1 mg/l	4 mg/l	1
09/0 <b>7</b>	001	ph, max.	9.9 s.u.	9.0 s.u.	1
10/07	001	DO, min.	.5 mg/l	4 mg/l	1
02/10	001	ph, max.	9.1 s.u.	9.0 mg/l	1
03/10	001	ph, max.	9.8 s.u.	9.0 s.u.	1
04/10	001	DO, min.	1.4 mg/l	4 mg/l	1
04/10	001	ph, max.	9.7 s.u.	9.0 s.u.	1
04/10	001	tss, avg.	92 mg/l	90 mg/l	31
04/10	001	DO.min.	1.91 mg/l	4 mg/l	1
05/10	001	ph, max.	9.2 s.u.	9.0 s.u.	1
09/10	001	ph, max.	10.8 s.u.	9.0 s.u.	1
10/10	001	ph, max.	10.84 s.u.	9.0 s.u.	1
10/10	001	tss, avg.	128.1 mg/l	90 mg/l	31
06/11	001	ph, max.	9.78 s.u.	9.0 s.u.	1
06/11	001	tss, avg.	127 mg/l	90 mg/l	31
07/11	001	BOD, avg.	33.25 mg/l	30 mg/l	31
07/11	001	DO, min.	2 mg/l	4 mg/l	1
07/11	001	ph, max.	9.46 s.u.	9.0 s.u.	1
07/11	001	tss, avg.	225 mg/l	90 mg/l	31

#### UNITED STATES DISTRICT COURT WESTERN DISTRICT OF TEXAS SAN ANTONIO DIVISION

UNITED STATES OF AMERICA, and STATE OF TEXAS Plaintiffs, v. SAN ANTONIO WATER SYSTEM, Defendants.

Civil Action No. 5:13-cy-00666-DAE

#### MODIFIED CONSENT DECREE

#### 

WHEREAS, on October 15, 2013, the United States District Court for the Western District of Texas approved and entered a Consent Decree between Plaintiffs, the United States of America and the State of Texas, and Defendant San Antonio Water System ("SAWS"). (Doc. No. 8).

WHEREAS, the objective of the Consent Decree is for SAWS to achieve and maintain compliance with the Clean Water Act and the Texas Water Quality Control Act and the regulations promulgated thereunder, including the elimination of Sanitary System Overflows ("SSOs").

WHEREAS, Section V of the Consent Decree (Compliance Requirements) requires SAWS to conduct a system-wide Condition Assessment to inspect and assess the structural condition of its sewer mains system for the purpose of identifying structural defects that have caused SSOs or may significantly contribute to the future occurrence of SSOs. SAWS is then required to prepare a Condition Remedial Measures Plan and implement remedial measures to remedy the identified structural defects. Section V also requires SAWS to conduct a system-wide Capacity Assessment to identify capacity constraint issues within its sewer system that have caused SSOs, or may significantly contribute to future SSOs. SAWS is required to prepare a Capacity Remedial Measures Plan and implement remedial to prepare a Capacity Remedial Measures Plan and implement remedial measures consistent with the objectives of the Consent Decree.

WHEREAS, SAWS completed the Condition Assessment program on July 23, 2017, inspecting over 76,000 manholes and hundreds of miles of sewer lines and is on schedule to implement the Condition Remedial Measures Plan in accordance with the Consent Decree.

#### Case 5:13-cv-00666-DAE Document 16 Filed 08/02/21 Page 3 of 12

WHEREAS, SAWS has completed the system-wide Capacity Assessment and is actively working on implementing the Capacity Remedial Measures Plan, submitted in January 2019, in accordance with the Consent Decree.

WHEREAS, the Capacity Remedial Measures Plan requires SAWS to complete construction projects to alleviate capacity constraints in the system. SAWS developed a Remediation Project List, which includes the W6, W9, and W52 construction projects. The W6 Project consists of six phases of work to replace existing sewer pipeline with approximately 8.8 miles of new or upsized pipes. Phases one to four of the W6 Project have been constructed. Phases five and six of the W6 Project were designed to cross Lackland Air Force Base (or Joint Base San Antonio), replacing existing 54-inch diameter sewer pipes with a new 104-inch diameter sewer main. The W9 and W52 construction projects are located upstream of the final phases of the W6 constructed upstream sewer pipelines, SAWS represents that good engineering practice dictates that construction begin at the lowest elevation and proceed upstream. Therefore, the final phases of the W6 construction projects.

WHEREAS, SAWS represents that construction of the W9 and W52 construction projects has been delayed due to SAWS' inability to secure an easement from the United States Air Force ("USAF") necessary for the final phases of the W6 construction project, which was designed to route the W6 sewer line through the Lackland Air Force Base.

WHEREAS, SAWS represents that it has engaged in negotiations with the USAF to obtain an easement for the W6 construction project since 2008, prior to the approval of the Consent Decree, but has not secured the easement.

#### Case 5:13-cv-00666-DAE Document 16 Filed 08/02/21 Page 4 of 12

WHEREAS, SAWS represents that it has reviewed more than fifteen alternative routes to achieve the objectives of the final phases of the W6 construction project, without routing the W6 sewer line through the Lackland Air Force Base, with only one alternative route being feasible from an engineering perspective.

WHEREAS, SAWS estimates that its selected alternative route (around Lackland Air Force Base) and new design of the final phases of the W6 construction project will require SAWS to invest approximately \$100 million in additional construction costs.

WHEREAS, SAWS represents that the original route for the W6 sewer line through Lackland Air Force Base was approximately 3.5 miles and would have allowed significant stretches of open-trench excavation for the new piping.

WHEREAS, SAWS represents that the new design of the W6 construction project, requiring the W6 sewer line to be constructed around Lackland Air Force Base, requires approximately 5.3 miles of piping, most of it being installed by tunneling at depths of up to 140 feet.

WHEREAS, SAWS represents that the new design of the W6 sewer line is approximately 1.8 miles longer than the original route through Lackland Air Force Base with significantly more complicated construction.

WHEREAS, SAWS represents that the new design of the W6 sewer line will further alleviate capacity issues within the system and help minimize wet weather SSOs.

WHEREAS, SAWS represents that the new design and route of the final phases of the W6 construction project will require SAWS to obtain over 2,500 linear feet of additional easements.

#### Case 5:13-cv-00666-DAE Document 16 Filed 08/02/21 Page 5 of 12

WHEREAS, the Consent Decree requires that Capacity Remedial Measures Plan projects that require the acquisition of easements or property be completed within 6 ½ years after EPA's written approval of the Capacity Remedial Measures Plan.

WHEREAS, EPA approved the Capacity Remedial Measure Plan on March 25, 2020 thereby requiring all Capacity Remedial Plan projects that require the acquisition of easements or property to be completed by September 25, 2026.

WHEREAS, SAWS has requested a modification of the Consent Decree to extend the deadline for the completion of the W9 and W52 construction projects to July 22, 2027.

WHEREAS, the modified deadline to complete the W9 and W52 construction projects will not increase the likelihood of SSOs because SAWS will continue to use and operate the existing sewer pipelines while constructing the replacement sewer pipelines.

WHEREAS, SAWS has met all Consent Decree deadlines, and is projected to complete 99% of all Remedial Plan projects no later than the original September 25, 2026 deadline.

WHEREAS, The Parties agree that the requested modification is fair, reasonable, and in the public interest.

WHEREAS, Paragraph 110 of the Consent Decree requires that any material modification of the Consent Decree, and any attached appendices, be effective only upon the approval of the Court. The Parties have determined that a modification to the implementation deadlines of the Capacity Remedial Measure Plan is a material modification.

NOW THEREFORE, upon the consent and agreement of the Parties IT IS HEREBY ADJUDGED, ORDERED, AND DECREED as follows:

Paragraph 42 of the Consent Decree is now replaced as follows:

42. Capacity Remedial Measures Implementation. In general, SAWS shall plan and implement the approved Capacity Remedial Measures in accordance with the process and guidelines identified in Appendix D. Following receipt of EPA's written approval, SAWS shall begin implementation of the Capacity Remedial Measures Plan on a balanced annual basis. SAWS shall complete all approved Small Diameter and Large Diameter Gravity Sewer Main Capacity Remedial Measures within four (4) and a half (1/2) years of receipt of EPA's written approval of the Capacity Remedial Measures Plan. Should a specific Large Diameter Capacity Remedial Measure project require SAWS to obtain new easements and/or acquire land for more than twenty-five (25) percent of the length of that project or more than 2,500 feet, whichever is less, SAWS may at its option elect to complete that Large Diameter Capacity Remedial Measures project within six (6) and a half (1/2) years of receipt of EPA's written approval of the Condition Remedial Measures Plan by no later than July 22, 2027. SAWS shall has advised EPA in the Capacity Remedial Measures Plan of any Large Diameter Capacity Remedial Measures projects that SAWS wishes to complete in a maximum of six (6) and a half (1/2) years instead of four (4) and a half (1/2) years by no later than July 22, 2027. For those projects that SAWS wishes to complete within six (6) and a half (1/2) years by no later than July 22, 2027, SAWS has advised in the Capacity Remedial Measures Plan the reasons why the need for new easements or land acquisition could not be avoided. Any modifications to the

#### Case 5:13-cv-00666-DAE Document 16 Filed 08/02/21 Page 7 of 12

approved Capacity Remedial measures Plan shall be in accordance with Section

XVIII (Modification).

SO ORDERED this 2nd day of August 2021.

David Alan Ézra Senior United States District Judge

Signature Page for Amended Consent Decree in the matter of <u>United States and State of Texas v.</u> <u>San Antonio Water System</u>

#### FOR THE UNITED STATES OF AMERICA:

JEAN E. WILLIAMS Acting Assistant Attorney General Environment and Natural Resources Division United States Department of Justice

/s/ Asia A. McNeil-Womack ASIA MCNEIL-WOMACK (Ga Bar #821002) Trial Attorney Environmental Enforcement Section Environment and Natural Resources Division United States Department of Justice P.O. Box 7611 Washington, D.C. 20044-7611 (202) 305-0544

ASHLEY C. HOFF United States Attorney Western District of Texas

Liane Noble Assistant United States Attorney Western District of Texas 903 San Jacinto Blvd., Suite 334 Austin, Texas 78701 Phone: (512) 370-1252 Signature Page for Amended Consent Decree in the matter of <u>United States and State of Texas v.</u> San Antonio Water System

## FOR THE UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Dated: 11-16-2020

MARK POLLINS, Director Water Enforcement Division Enforcement and Compliance Assurance Division U.S. Environmental Protection Agency 1200 Pennsylvania Ave., N.W. Washington, DC 20460 Signature Page for Amended Consent Decree in the matter of <u>United States and State of Texas v.</u> <u>San Antonio Water System</u>

## FOR THE UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Dated: <u>February 1</u> 1, 2021	Charge J. S. Logo - Development of the second secon
	CHERYL T. SEAGER
	Division Director
	Enforcement and Compliance Assurance Division
	U.S. EPA, Region 6
	1201 Elm Street, Suite 500
	Dallas, Texas 75270
Dated:	EFREN ORDONEZ Digitally signed by EFREN ORDONEZ Date: 2021.02.09 i 1:55:03 -06'00'
	EFREN ORDÓÑEZ
	Office of Regional Counsel
	U.S. EPA, Region 6
	1201 Elm Street, Suite 500
	Dallas, Texas 75270

Signature Page for Amended Consent Decree in the matter of <u>United States and State of Texas v.</u> <u>San Antonio Water System</u>

# FOR THE STATE OF TEXAS ON BEHALF OF THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY:

Dated: March 8, 2021

KEN PAXTON Attorney General of Texas

BRENT WEBSTER First Assistant Attorney General

GRANT DORFMAN Deputy First Assistant Attorney General

SHAWN COLES Deputy Attorney General for Civil Litigation

PRISCILLA M. HUBENAK Chief, Environmental Protection Division

/s/ Phillip Ledbetter PHILLIP LEDBETTER Assistant Attorney General State Bar No. 24041316 Phillip.Ledbetter@oag.texas.gov OFFICE OF THE ATTORNEY GENERAL ENVIRONMENTAL PROTECTION DIVISION P.O. Box 12548, MC-066 Austin, Texas 78711-2548 (512) 475-4152 | Fax: (512) 320-0911

ATTORNEYS FOR THE STATE OF TEXAS

Signature Page for Amended Consent Decree in the matter of <u>United States and State of Texas v.</u> San Antonio Water System

Dated: \_\_\_\_\_

FOR SAN ANTONIO WATER SYSTEM

ROBERT R. PUENTE President and Chief Executive Officer San Antonio Water System 2800 U.S. Highway 281 North San Antonio, TX 78212



# 2021 SWAS Consent Decree ToqeA IsunnA

June 30, 2022





#### II. CERTIFICATION DECLARATION

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering such information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Vice President, Production & Treatment

6-24-2022

(Date)

June 30, 2022



# 2021 Annual Report

Ш.:	TABLE OF CONTENTS	
I.	COVER	i
П.	CERTIFICATION DECLARATION	i
III.	TABLE OF CONTENTS	ii
IV.	ACRONYMS AND ABBREVIATIONS	i
v.	INTRODUCTION	V-1
A.	Purpose	
В.	Regulatory Requirements	V-1
VI.	EARLY ACTION PROGRAM	VI-1
VII.	СМОМ	VII-1
A.	SSO Reporting	VII-1
В.	Fats, Oils and Grease Program	VII-1
C.	Sewer Cleaning	VII-1
D.	Private Laterals	VII-4
E.	Condition Monitoring – Small Diameter Gravity Sewer – Other Pipe	VII-5
F.	Gravity Sewer Main Inspection Map	VII-6
G.	Gravity Sewer Main Inspection - CMOM	VII-7
Н.	Manhole Inspection Map	VII-8
I.	Manhole Inspection Status	VII-9
J.	Condition Categorization Summary	VII-10
К.	Map of Condition Categories	VII-11
L.	Condition Assessment Results	VII-13
М.	Map of Condition Assessment Results	VII-14
VIII.	CONDITION ASSESSMENT	VIII-1
IX.	CONDITION REMEDIAL MEASURES	IX-1
A.	Status of Multi-Year Large Diameter Condition Remediation	IX-1
В.	Condition Remediation Completed	IX-3



C.	Map of Condition Remedial Measures CompletedIX-4
D.	Asset Information for Condition Remedial Measures Completed During Calendar Year 2021 IX-5
Х.	CAPACITY ASSESSMENT
A.	Wet-Weather Related SSO CategorizationX-1
-	1. GuidelinesX-1
Ĩ	2. Wet-Weather SSO Categorization SummaryX-2
3	<ol> <li>Wet-Weather SSO Categorization Summary MapX-2</li> </ol>
В.	System-Wide Hydraulic Modeling EvaluationX-3
-	1. Model MapsX-3
2	2. Model Results Identifying Potential Capacity ConstraintsX-3
С.	Prioritization of Potential Capacity ConstraintsX-5
-	1. Map of Potential Capacity ConstraintsX-6
XI.	FIELD INVESTIGATIONS OF POTENTIAL CAPACITY CONSTRAINTS
Α.	Field Investigation StatusXI-1
В.	Map of Completed Field InvestigationsXI-2
XII.	CAPACITY REMEDIATION
A.	Status of Multi-Year Large Diameter Capacity RemediationXII-1
В.	Capacity Remediation CompletedXII-3
C.	Map of Capacity Remedial Measures CompletedXII-4
D.	Asset Information for Completed Capacity Remedial MeasuresXII-5
E.	Potential Capacity Constraints Removed from Field Investigation ProgramXII-5
XIII.	REMEDIAL MEASURES COORDINATED BETWEEN CAPACITY AND CONDITION REMEDIAL MEASURES
xıv.	LIFT STATION REHABILITATION AND ELIMINATION PROGRAMXIV-1
XV.	FORCE MAIN ASSESSMENT PROGRAMXV-1
XVI.	WATER QUALITY PROGRAMXVI-1
XVII.	WORK COMPLETED IN LOW INCOME AREASXVII-1
xviii	MODIFICATIONSXVIII-1

June 30, 2022



Table XI-1: Completed Field InvestigationsXI-1
Table XII-1: Status of Multi-Year Large Diameter Capacity RemediationXII-1
Table XII-2: Capacity Remedial Measures Completed in Calendar Year 2021XII-3
Table XIV-1: Lift Station Rehabilitation or Elimination Projects XIV-1
Table XV-1: Force Main Inspection Progress Summary         XV-1
Table XV-2: Force Main Condition Assessment Cumulative Summary         XV-2
Table XV-3: Force Main Remedial Measures Completed in Calendar Year 2021 XV-2

June 30, 2022



#### APPENDICES & ATTACHMENTS

- Appendix A Section VII.A SSO Documentation
- Appendix B-1 Section VII.D SAWS Information Regarding Private Lateral Discharges
- Appendix B-2 Section VII.D City of San Antonio Information Regarding Private Lateral Notifications
- Appendix C Section IX.D Asset Information for Condition Remedial Measures
- Appendix D Section XII.D Asset Information for Capacity Remedial Measures
- Appendix E Section XIV Lift Station Rehabilitation & Elimination Program Table

Attachment 1 SAWS Census Tracts Estimated Below Poverty Level



IV. ACR	ONYMIS AND ABBREVIATIONS
ССТУ	Closed-Circuit Television
CD	Consent Decree
CI	Cast Iron
COSA	City of San Antonio
СМОМ	Capacity, Management, Operation, and Maintenance
СТ	Clay Tile
СР	Concrete Pipe
EARZ	Edwards Aquifer Recharge Zone
EAA	Edwards Aquifer Authority
EPA	Environmental Protection Agency
FFAC	Final Field Acceptance Checklist
FOG	Fats, Oils and Grease
FRP	Fiberglass Reinforced Plastic
HDPE	High-Density Polyethylene
HGL	Hydraulic Grade Line
LD	Large Diameter
LS	Lift Station
NOV	Notice of Violation
NTP	Notice to Proceed
РАСР	Pipeline Assessment Certification Program
PVC	Polyvinyl Chloride
RCP	Reinforced Concrete Pipe
SAWS	San Antonio Water System
SSO	Sanitary Sewer Overflow
TCEQ	Texas Commission on Environmental Quality
VCP	Vitrified Clay Pipe



LIST OF TABLES
Table VI-1: Phase I Early Action Program Remediation VI-1
Table VI-2: Status of Phase I Early Action Program Multi-Year Large Diameter Projects VI-2
Table VI-3: Phase II Early Action Program Remediation VI-3
Table VI-4: Status of Phase II Multi-Year Large Diameter Projects VI-3
Table VII-1: Inspections and Enforcements Actions in Calendar Year 2021 VII-1
Table VII-2: Small Diameter System-Wide Cleaning Program Status in Calendar Year 2021 VII-1
Table VII-3: Small Diameter System-Wide Cleaning Program Cumulative Status Unique SmallDiameter Cleaning Completed January 1, 2009 through Calendar Year 2021 VII-2
Table VII-4: Large Diameter Cleaning Program Status         VII-2
Table VII-5: Large Diameter Cleaning Program Cumulative Status Unique Large Diameter Cleaning Completed – January 1, 2009 through Calendar Year 2021 VII-3
Table VII-6: City of San Antonio Action VII-4
Table VII-7:       Small Diameter Gravity Sewer Main – Other Pipe Inspection Completed through         December 31, 2021       VII-5
Table VII-8: Gravity Sewer Main Inspections January 1, 2021 through December 31, 2021 VII-7
Table VII-9: Manhole Inspection Summary July 24, 2017 through December 31, 2021 VII-9
Table VII-10: Condition and Categorization Summary - January 1, 2021 through December 31,2021
Table VII-11: Condition Assessment Results January 1, 2021 through December 31, 2021 VII-13
Table IX-1: Status of Multi-Year Large Diameter Condition Remediation         IX-1
Table IX-2: Condition Remedial Measures Completed in Calendar Year 2021 Excluding Early         Action Program       IX-3
Table X-1: Wet Weather SSO Categorization for Calendar Year 2021
Table X-2: Potential Capacity Constraints SummaryX-6

June 30, 2022



#### V. INTRODUCTION

#### A. Purpose

On October 15, 2013 a Consent Decree (CD) between the San Antonio Water System (SAWS) and the United States of America and the State of Texas was entered in Civil Action No. 5:13-cv-00666-DAE in the United States District Court for the Western District of Texas, San Antonio Division.

This Report was prepared and submitted pursuant to Paragraph 52 of the Consent Decree and documents the Work, as defined in the Consent Decree, which was completed during Calendar Year 2021. Note: Capitalized terms, like Work or Calendar Year, are defined in the Consent Decree.

#### B. Regulatory Requirements

This Report summarizes activities completed during the previous Calendar Year, 2021, for the following requirements in Section V of the Consent Decree: Early Action Program, Condition Assessment, Condition Remedial Measures, Capacity Assessment, Capacity Remedial Measures, Lift Station Rehabilitation and Elimination Program, Force Main Assessment Program, Capacity, Management, Operation, and Maintenance (CMOM) Program (including private laterals) and Water Quality Program.

June 30, 2022

#### VI. EARLY ACTION PROGRAM

Consent Decree Appendix F defines the Phase I Early Action Program. The following tables provide the status of projects and work being conducted under the Phase I Early Action Program. Table VI-1 shows the length of the rehabilitation work completed. Table VI-2 shows the status of the multi-year large diameter pipe projects.

As shown in tables VI-1 through VI-4, all Early Action Program projects have been completed.

Table VI-1: Phase I Early Action Program Remediation		
Asset Description	Completed in Calendar Year 2021	Cumulative Completed <sup>2</sup>
Small Diameter Gravity Sewer (Miles) <sup>1,3</sup>	0.00	66.37
Large Diameter Gravity Sewer (Miles) <sup>1,3</sup>	0.00	38.74
Manholes (Number) <sup>3</sup>	0	1,664
Note 1: Full pipe length is included in milea	ges.	
Note 2: Includes all work completed prior to	o January 1, 2022.	
Note 3: Individual Asset IDs were reported Sections IX.D and XII.D.	in Appendices C and	D as noted in

June 30, 2022



Table VI-2: Status of Phase I Early Action Program Multi-Year Large Diameter Projects			
Project Name	Description of Status		
Phase I EAP – Project 7 – Large	Project 7 completed prior to 2015. Assets reported in		
Diameter (LD) Rehab Program	2013 and 2014 Annual Reports.		
Phase I EAP – Project 8 – LD Rehab	Project 8 is complete. Assets reported in 2017 and		
Program	prior Annual Report.		
San Antonio River Outfall Project Phase 1 and 2	All phases completed in calendar year 2017.		
Donaldson Terrace	Donaldson Terrace construction was completed on 3/28/2019. Seeling Channel improvements were constructed in two phases. Phase I construction completed 02/26/2016. Phase II construction was completed 10/9/2018.		
Broadway Corridor – Josephine to South Alamo Street	Construction package A completed 4/29/2016. Construction package B completed 6/11/2020; a minor modification request was submitted on 5/10/2019. Construction packages C1 and C3 were completed 5/26/2017. Construction Packages C2 and C4 were completed 11/7/2017.		
Broadway Corridor – Carnahan to Mulberry Streets	Construction package 1 completed in 2015 and reported in the 2015 Annual Report. Construction package 2 completed in 2016. Construction package 3 completed 9/1/2017. Construction Package 5 was completed 11/14/2018.		
Leon Creek – Highway 90 to New Laredo Highway	Phase 1 construction was completed in 2014. Phase 2 construction was completed 10/07/2015. Phases 3 and 4 assets were placed in service on 11/30/2018 and project completed 6/3/2020.		
C-5/C-28 – S Laredo/W Houston	Construction package 1A assets are in service 12/22/2017. Package 1B assets are in service 7/3/2019. Package 2 completed 3/15/2019.		
W-1 Leon Creek Emergency	Project is complete. Reported in 2013 Annual Report.		
W-31 IH 10 Western Extension B	Assets placed in service 11/07/2018 and project completed 7/28/2019.		
	Il close out activities related to the project are complete. that all sewer assets are in service, but project close out		